

The cosmology of Cosmological Relativity: the expansion history from causal reassignment on a de Sitter background, the cosmogenesis branch point, and the scalar perturbation sector

Daryl Janzen

Department of Physics and Engineering Physics
University of Saskatchewan

Abstract

Cosmological Relativity (CR) obtains the observed cosmological expansion by a causal reassignment on a de Sitter background at the cosmogenesis branch point, with the Einstein field equations unchanged. This paper develops that cosmology and completes it with its scalar perturbation sector. The reassignment selects the Nariai member [37] of Schwarzschild–de Sitter, whose proper frame is a homogeneous, observationally isotropic, *non-synchronous* cosmology with areal radius $r(\tilde{\tau}) \propto \sinh^{2/3}$ —exactly the flat- Λ CDM scale factor—its rate fixed by the cosmological constant alone, with radiation and matter inherited content read off the cosmic clock rather than terms that source the expansion. The cosmic beginning is the branch point $r = 0$ —a genuine curvature singularity of the SdS metric read over the r -chart [36], and *not* a singularity of the underlying substrate, whose throat is the defining constant α ; the divergence of the r -chart invariants there is the areal coordinate degenerating; the constant-proper-time slices are exactly Euclidean ($\Omega_k = 0$) while the cosmological layers are a closed S^3 —spatial curvature and dark energy one Λ read on two slicings. The acoustic scale follows from that rate rather than calibrating it: with the plasma handed over at the branch point there is no early-universe parameter to carry the angle, so the angle is computed, and it and the baryon-acoustic distances fix H_0 together at $\simeq 68.6$. The light-element composition is produced on the same footing: the infalling matter heats above the deuterium bottleneck and the expanding leg cools back through it, so that leg is a standard big-bang nucleosynthesis run from free nucleons, fixing the composition with the inherited baryon-to-photon ratio η —the one boundary datum of that handover. Helium-4 and deuterium sit at their observed values—the freeze-out temperature the data demands being the bottleneck the standard rate delivers, un-tuned; the near-zero metallicity of the oldest systems follows from the handover; and because the run is standard, lithium-7 carries the standard threefold over-prediction, the lithium problem shared with flat Λ CDM rather than dissolved.

On this cosmology the primordial scalar spectrum *factorizes*. The de Sitter substrate *determines* its structure—the geometric coherence of the acoustic phases on the null boundary (not a super-horizon freeze-out), the classical non-vacuum character of the fluctuations (the substrate vacuum lies some 10^{113} below the observed A_s), the throat’s isotropization, a parameter-free low-multipole discreteness floor, and the faithful transmission of the spectral shape—while the progenitor collapse *supplies* its content, the amplitude A_s and tilt n_s , inherited as boundary data exactly as flat Λ CDM inherits the baryon-to-photon ratio. *The transmission is supported by a mechanism rather than by the absence of a scale alone* (§3): on the contracting leg aH grows without bound as the branch point is approached, so the comoving horizon shrinks to zero and every mode *exits* it and freezes before the crossing; the imaginary-time segment’s Euclidean kernel damps oscillatory content and has nothing to act on in a frozen mode, so amplitude and tilt cross unaltered while the collapse-leg acoustic phase does not—which the observed peak positions independently require, excluding a transmitted leg phase by a factor of 21–41 in the required distance [9].

The decisive result is a *transmission dichotomy*: a non-degenerate horizon’s exponential near-horizon approach imprints a scale-invariant spectrum (the inflationary de Sitter-horizon

mechanism), whereas the degenerate Nariai double root’s power-law approach carries no scale, and the branch point where the modes cross—a third case, f diverging so that the tortoise coordinate stays finite—accumulates no phase at all; the super-horizon transfer across it is computed and scale-invariant, so the progenitor spectrum is transmitted unaltered and CR has no inflationary scale-invariant attractor, no consistency relation, and no substrate-sourced primordial B -modes.

Because the distance slicing is flat, the discrete closed- S^3 source projects through the flat transfer to a parameter-free low-multipole deficit ($\ell \lesssim 8$)—mild, and on a genuine Boltzmann transfer a dip whose *minimum falls at* $\ell = 4$ (0.36 of the Λ CDM expectation there, 0.487 and 0.435 at $\ell = 2$ and 3; *the shape and the depth both cross-validated between two independent transfers*, which agree to three per cent at worst once the post-recombination source is carried to the present), and non-discriminating in sum: scored against the measured multipoles with cosmic variance carried, *the quadrupole favours this construction and $\ell = 3$ to 5 favour the standard model*, the two nearly cancelling at $\Delta(-2 \ln L) = +1.6$ over $2 \leq \ell \leq 10$.

Taken together, these results carry a reckoning the paper draws in full: what flat Λ CDM assembles from added, tunable apparatus—inflation for the horizon, flatness, coherence, and near-scale-invariance, a dark-energy component for the late-time acceleration, added early-universe physics for the tensions—this cosmology recovers from the cosmological constant alone, each feature required by structure already present rather than produced by a sector introduced to yield it. By the economy of assumption that distinguishes a required structure from a merely permitted one, that comparison is settled on the theory-choice axis in this cosmology’s favour; and on the data axis it is split: the expansion history fits the low-redshift distance ladder on the SDSS DR12 consensus and, at the current state of the art, the DESI DR2 dataset (thirteen measurements across seven tracers) at $\chi^2/\text{dof} \simeq 1$, which fixes $\Omega_m \simeq 0.30$ and $H_0 \simeq 68.6$ and leaves the discrepancy with the local distance ladder where the standard model leaves it; the light-element abundances are confirmed within 1σ at the microwave-background baryon density (the cosmogenesis paper [19]); and the acoustic peak structure, computed from that same background with nothing fitted to it, reproduces the comb to a part in six hundred and is still rejected on shape—at 2.57 times the control’s distance from the data as computed, and 1.57 times once both arms’ parameters are refitted; what it leaves is about one multipole at each peak.

The cosmology’s exposed edges are named: a signature in the diffusion *scale*, the two rates differing by the radiation term alone so that the plasma’s Silk scale and the foliation’s distances do not share a rate [27]—a computed effect, non-reabsorbable by the baryon density, whose size is fixed by the handover, read with both lengths carried to the peak of the visibility function, and which the joint fit locates as a Gaussian residual in ℓ that no tilt removes, a refit absorbing a Gaussian only window-locally (the low multipoles being a mild, non-discriminating deficit rather than a sharp edge either way); and the acoustic peak structure. *The full-spectrum likelihood is run on the computed spectrum*: scored against Planck 2018 `plik_lite` over the full-range lensed configuration, with one amplitude fitted so that what is compared is shape, this arm sits at 2.57 times the control’s distance from the data (§4.7). *That is a spectrum computed on a background fitted to the distances and then confronted*, which is a different statement from a refit of the spectrum’s own parameters to the microwave data; the second is the comparison the standard model is usually judged by, and it is reported in §4.7 beside the first.

We mark maturity throughout. *Established*: the cosmological derivation, the transmission dichotomy, the amplitude floor, the throat, the flat slice, the flat-projection transfer, the data confrontation, and the time-reversal driving equality as a Fourier theorem. *Argued*: the coherence mechanism. *Measured*: the peak *heights*, which this arm’s own instrument returns within a few per cent of the sky’s first two ratios on the polarisation path and above them on the fluid path, so the heights are the path’s and the positions are the construction’s.

Run, and returning a partial agreement: the end-to-end branch-point-to-recombination transfer, the standard line-of-sight integral across a visibility of finite width, validated on its control to 0.23% in the first-to-second height ratio in the configuration this construction’s arm is read in, and carried through to that arm, which returns the peak spacing to one part in six hundred and the first three peaks within a grid step of the measured ones, with the fourth not resolved against the sky once the likelihood’s own covariance is propagated; the likelihood rejects the arm’s spectrum on TT shape nonetheless. *Open*: the *derivation*—as

against the measurement—of A_s and n_s . *The cosmology carries no early-universe parameter, and what it does carry should be stated plainly:* the plasma is handed over at the branch point, where every acoustic mode is outside the horizon and the potential sits at its regular value, so the sound-horizon integral has no lower endpoint to fit and the acoustic angle is an output of the rate rather than a calibration of it. The background is fixed by the late-time data alone—the epoch x_0 (equivalently $\Omega_m = 2/(x_0^3 + 2)$) and H_0 , from the baryon-acoustic distances together with that angle, which agree with one another within a twentieth of a unit at $H_0 \simeq 68.6$. *Matter–radiation equality is then fixed by the same epoch*, $1 + z_{\text{eq}} = \omega_m/\omega_r$ with ω_r measured, so one quantity carries the expansion history and the acoustic driving together and the computed spectrum is a test of the background rather than a further fit to it. The substrate’s single Λ is shown to govern both the global expansion and, per structure, the local scale at which structure resists it—the Hubble–Eddington radius—one constant read at two ranges.

1 Introduction: the cosmological theory and its scalar perturbation sector

Cosmological Relativity (CR) recovers the flat- Λ CDM expansion history by a causal reassignment on a de Sitter background at the cosmogenesis branch point: the expansion rate is fixed by the cosmological constant alone, radiation carries no term in it, and the present matter density is a reading of the cosmic epoch rather than an independent quantity [9, 11]. The cosmic beginning is the branch point $r = 0$ —a genuine curvature singularity of the SdS metric read over the r -chart, and *not* a singularity of the substrate, whose throat is the defining constant α , and the construction makes the constant-proper-time slices exactly flat while the cosmological layers are a closed S^3 . This paper develops that cosmological theory in the form its observational tests require (§2) and completes it with the scalar perturbation sector the framework paper’s outlook named open—“perturbations within the Schwarzschild–de Sitter representation”—the primordial density perturbations and their imprint on the microwave background (§§4–8), closing on the open frontier the construction sets up (§10). Across these sections one comparison recurs and is drawn together at the close (§9): the causal contact, flatness, coherence, isotropy, and near-scale-invariance that the standard picture obtains from an added, tunable inflationary sector are here read off structure already present and fixed by Λ alone—an economy-of-assumption difference the paper argues is decidable on the theory-choice axis, where it falls to this cosmology—and on the data axis the expansion history fits the low-redshift distance ladder, which fixes H_0 alongside the epoch, and the light-element abundances are confirmed against the data (§2.4), while the exposed edge is the acoustic peak structure—where the transfer, run on that background with nothing fitted to it, reproduces the comb to a part in six hundred and is still rejected on TT shape (§4.7)—and the damping-*scale* signature, a computed, non-reabsorbable effect whose size the handover fixes, read with both lengths carried to the peak of the visibility function, and which the joint fit locates as a Gaussian residual no tilt removes, the low multipoles a mild, non-discriminating deficit rather than a sharp edge either way. The companion dynamics paper develops the perturbation sector’s *tensor* half—the propagating graviton as the leaf’s shear, a massless de Sitter mode on the cosmic foliation [10]; the scalar half is here.

The result is organized by one thesis, which we state at the outset because it controls everything below.

The CR primordial scalar spectrum factorizes: the de Sitter substrate geometry determines its structure, the progenitor collapse supplies its content, and the branch point’s null geometry assigns each its job.

Substrate-determined, and developed here: the coherence of the acoustic phases (§4); the classical, non-vacuum character of the fluctuations (§5); the isotropizing throat (§6); a parameter-

free low-multipole discreteness floor (§7); and the faithful transmission of the spectral shape (§8). Progenitor-supplied, and inherited rather than derived: the amplitude A_s and tilt n_s . This is the same division of labour by which flat Λ CDM carries the baryon-to-photon ratio η as a measured datum from a baryogenesis it does not model; this cosmology carries that same η from the hot handover of the progenitor collapse, and the transmission result of §8 routes A_s and n_s through the *same* handover. There is one boundary-condition supplier, not two.

A word on what is settled before the spectrum. The acoustic *scale* (the peak spacing) is settled in the cosmological development above (§2.3): it is computed from the rate, with the sound speed the ordinary baryon-loaded value of pressureless branch-point matter, and the Hubble constant is fixed alongside it by the baryon-acoustic distances. *The sky’s own side of that comparison is measured here rather than quoted. Locating the acoustic peaks of the Planck 2018 `plik_lite` binned TT spectrum [24] by parabolic fit to each hump above $\ell = 100$ returns $\ell = 220.4, 537.7, 817.3$ and 1123.9 , which reproduce the standard quoted values to better than one per cent without having been fitted to them. Fitting $\ell_n = \ell_A(n + \phi/\pi)$ to the first three gives the sky $\phi/\pi = -0.2404$ against -0.2361 for a Λ CDM control measured by the identical procedure—an offset of 0.0043 , so the control stands in for the sky on this quantity to within seven parts in a thousand.* The move has a name and the name is worth stating, because it is what licenses the comparison: *this is matched-procedure differencing—the control is passed through the identical extraction, so whatever bias the procedure itself carries appears in both arms and cancels in their difference, and what survives is attributable to the physics rather than to the instrument.* The same discipline governs every control in this sector: *a residual is credited against CR only once the control, run through the same machinery, has been shown not to produce it.* What this construction’s own arm returns against that measured comparison is reported in §4.7, *the two-arm transfer being validated on the control and carried to convergence on both arms.* These are settled there and are not reopened in the perturbation sector; in particular, the standard radiation-governed sound horizon laid on this cosmology’s rate is a calculation belonging to neither framework, and any “tension” it produces is an artifact, not a CR result. What is genuinely downstream is the *spectrum*—the peak heights, measured below against this arm’s own transfer (§4), and the full oscillating-medium transfer, run on both arms in §4.7—which is where this paper’s substance lives.

The register is the programme’s [14, 9]: the field equations are Einstein’s, unchanged; the existing object is the evolving three-dimensional layer; “the substrate determines” and “the branch point transmits” are statements about a real geometry and its real boundary [17, 16], not about a modification of the dynamics.

2 The cosmological theory the perturbations complete

This paper develops the cosmology of Cosmological Relativity from first principles and carries it to its empirical confrontation, completing it with the scalar perturbation sector. It takes from the companion framework paper [9] the *general* primitives—the layered ontology, the projection principle, and the representational freedom by which one fixed manifold admits distinct Lorentzian metrics—together with the Null–Boundary Correspondence theorem, the structural result (grounded in the metric-singularity causal structure of gravitational collapse [4]) that a collapse event-of-events and a de Sitter cosmic-entry slice are one ontological layer under two causal assignments. The cosmology proper is built here: the causal reassignment that selects the Nariai member, the proper-frame expansion law, the branch point at which the collapse leg becomes the expansion leg—the beginning, reached a lap on from the horizon the Correspondence anchors—and the computation of the acoustic scale and the confrontation with the distance data; the perturbation sector (§4–§8) is its completion.

2.1 The causal reassignment and the Nariai member

The vacuum solution of $R_{\mu\nu} = \Lambda g_{\mu\nu}$ with a localized source is Schwarzschild–de Sitter (SdS),

$$ds^2 = -\frac{r}{\frac{\Lambda}{3}r^3 + \frac{2GM}{c^2} - r} dr^2 + \frac{\frac{\Lambda}{3}r^3 + \frac{2GM}{c^2} - r}{r} dt^2 + r^2 d\Omega^2, \quad (1)$$

whose areal radius r is timelike in the cosmological regime $\Lambda G^2 M^2 / c^4 \geq 1/9$. Building the cosmology, we reassign causal roles on the de Sitter substrate—a move licensed by the representational freedom of the framework, distinct Lorentzian metrics on one fixed manifold sharing its foliation [9]: the de Sitter null rulings whose causal sense matches a collapse horizon’s generators are promoted to the timelike fundamental congruence, the at-rest comoving worldlines become the null photon congruence, and the foliation by expanding 3-spheres is preserved. This selects the *Nariai* member $\Lambda G^2 M^2 / c^4 = 1/9$, $M = c^2 / (3\sqrt{\Lambda}G)$ —the unique non-pivoting tilt, fixed by Λ alone—at which the two positive horizons merge at $r_N = \alpha/\sqrt{3}$, $\alpha = \sqrt{3/\Lambda}$ the de Sitter 3-sphere size (a scale distinct from the merged-horizon radius $\alpha/\sqrt{3}$ and from the areal-radius amplitude below; we keep the three apart throughout). The selection is geometric—the fixed point of the slicing curve’s root-exchange involution, equivalently the limiting tangent orientation a collapse selects—not a fitted mass [5]. That the selection is moreover *unique* is a structural fact about the description groupoid rather than a fitting: the generic vantages fall into two-cycles of the involution, the Nariai member is its one fixed point, and the reassignment promoting a null direction to the fundamental congruence is forbidden at every generic vantage, so it selects Nariai and no other [6].

2.2 The proper-frame cosmology, derived

In the proper frame of the fundamental observers the SdS metric is a homogeneous, non-synchronous cosmology. The derivation [15] proceeds from (1) in five steps. (i) A timelike radial geodesic has a conserved energy E (the metric being independent of t); eliminating $dt/d\tau$ in the normalization $L = -1$ gives the radial equation $(dr/d\tau)^2 = E^2 - V_{\text{eff}}(r)$, with $V_{\text{eff}} = (r - 2GM/c^2 - \frac{\Lambda}{3}r^3)/r$. (ii) The fundamental congruence is the worldlines whose motion in r is produced purely by the field—those at rest exactly where $V_{\text{eff}} \equiv 1$ and the metric reduces to Minkowski—which is $E = 1$; this fixes the rest frame by the field rather than by stipulation, *and it is worth saying where that locus is*: $V_{\text{eff}} = 1$ is $r^3 = -2GM\alpha^2/c^2$, so the rest frame is defined at $r = -(6GM/c^2\Lambda)^{1/3}$ —a *negative* areal radius, on the conjugate branch of the lap, between the progenitor’s horizon and the branch point [9]. *An earlier derivation carried that locus as a formal one*—“a negative mathematical abstraction that lies beyond a singularity at $r = 0 \dots$ simply a matter of algebraic consistency” [2, App.]—*and on the lap it is a place*. The same locus fixes the sign, since $t = \tau$ there if and only if $E = +1$. (iii) With $E = 1$, integrating the radial equation gives, along one worldline, $r(\tau) \propto \sinh^{2/3}(\frac{3}{2}\sqrt{\Lambda c^2/3}\tau)$. *That this integration closes at all is a second thing the same condition buys*. Writing the radial equation as $(dr/d\tau)^2 = 2GM/c^2r + r^2/\alpha^2 - k$ with $k = 1 - E^2$, the quadrature $\int dr/\sqrt{\cdot}$ is elementary at $k = 0$ —it is $\frac{2\alpha}{3} \text{arcsinh}(r^{3/2}/\sqrt{2GM\alpha^2/c^2})$, which inverts to the $\sinh^{2/3}$ above—while for $k \neq 0$ the substitution $r = u^2$ carries it to a sextic under the root and it is not elementary. *So $E = 1$ fixes the rest frame by the field and, by the same stroke, is the one non-degenerate energy at which the cosmology integrates in closed form*; the only other elementary cases are the degenerate ones, $\Lambda = 0$ giving the dust cycloid and $M = 0$ giving pure de Sitter^{L14}. (iv) Labelling the congruence by a comoving coordinate χ through the integration constant $r(0)$, the areal radius across the congruence depends on τ, χ only through their sum, $r(\tau, \chi) = r(\tau + \chi)$, with $\partial_\chi r = \partial_\tau r$. (v) Fixing the transformation $t(\tau, \chi)$ by requiring the comoving coordinate orthogonal to proper time, $g_{\chi\tau} = 0$, forces the integration function to be χ itself, and the remaining components follow ($g_{\tau\tau} = -1$, $g_{\chi\chi} = (\partial_\chi r)^2$). The result is the proper-frame line element

$$ds^2 = -d\tau^2 + (\partial_\chi r)^2 d\chi^2 + r^2 d\Omega^2, \quad (2)$$



Figure 1: The scale factor (3) as one analytic curve $r(\tilde{\tau})$ in $(\tilde{\tau}, \text{Re } r, \text{Im } r)$. The expanding cosmology is the real leg $\tilde{\tau} > 0$, lying in the real plane; the branch point $\tilde{\tau} = 0, r \rightarrow 0$ —*not* a seam—is where the curve leaves the real plane onto a conjugate branch at constant phase $2\pi/3$ for $\tilde{\tau} < 0$. The beginning is this analytic branch point, not a real $r = 0$ boundary. Forcing r real (dashed) projects the conjugate branch onto the negative axis and manufactures a cusp the smooth curve does not carry.

with cosmic time $\tilde{\tau} \equiv \tau + \chi$ (by Weyl’s principle the congruence issues from a common origin and the constant-cosmic-time slices are those of constant $\tilde{\tau}$), areal radius

$$r(\tilde{\tau}) = \left(\frac{6GM}{\Lambda c^2} \right)^{1/3} \sinh^{2/3} \left(\frac{3}{2} \sqrt{\frac{\Lambda c^2}{3}} \tilde{\tau} \right), \quad (3)$$

and redshift $1 + z = r(\tilde{\tau}_0)/r(\tilde{\tau}_e)$. The constant- $\tilde{\tau}$ slices sit at 45° to the fundamental rest frame: the cosmology is homogeneous and observationally isotropic, yet *non-synchronous*—the constant- τ slices are exactly Euclidean (§7) but are not the cosmological ones. Of the FLRW kinematic assumptions—(i) a geodesic congruence, (ii) hypersurface orthogonality, (iii) homogeneity, (iv) isotropy—this construction keeps (i) and drops (ii); Lemaître’s reading [30] of the Euclidean slices as “space ejected from $r = 0$ ” is causally incoherent and is not the physics. Equation (3) is moreover a single analytic function of $\tilde{\tau}$ (Fig. 1): the expanding cosmology is its real branch $\tilde{\tau} > 0$, and the cosmogenesis *branch point* at $\tilde{\tau} = 0$, where $r \rightarrow 0$, is the branch point of the scale factor rather than a real $r = 0$ boundary—and it is *not* a seam: the seams are the two unit-speed loci of the lap, $r = -2\alpha/\sqrt{3}$ and $r = +\alpha/\sqrt{3}$ [9], and $r = 0$ lies strictly between them, at the close of the lift—the analytic counterpart of the beginning at the branch point, where the substrate’s curvature stays finite while the geometry read over the r -chart diverges [4], and the cosmological reading of the slicing curve’s closed lap—the *cosmogenetic bead* the framework establishes as one closed object [5, 9], of which this scale factor’s real branch $\tilde{\tau} > 0$ is the expansion leg and its analytic continuation the prior universe’s collapse—on which $r = 0$ is a branch point and not a barrier, the substrate smooth across the locus the chart so labels [5].

2.3 Exact recovery of flat Λ CDM, and the amplitude fixed by Λ

What fixes this rate is worth stating before what it recovers, and the count is smaller than it looks. The rate this cosmology computes on is set by the substrate’s geometry and by nothing else. *It has one parameter*—the substrate curvature radius $\alpha = \sqrt{3/\Lambda}$, an invariant length—and *one epoch*. At the Nariai member the mass is no longer free (5), so the amplitude and the rate

of the expansion law are both set by Λ and the scale factor is one function of it; what remains is where the present sits on that one curve. *The quantity x_0 carries that:* it is the present areal radius in units of the Nariai radius, $x_0 = r(\tilde{\tau}_0)/r_N$, and since $r_N = \alpha/\sqrt{3}$ is fixed by Λ the number is a clock reading and not a second geometric datum^{P15R14}. *The geometry's own offset is fixed twice over:* it is the double root of the horizon cubic at the Nariai mass, and it is the constant ledger's $2M = \alpha((r_0/\alpha) - (r_0/\alpha)^3)$ with M at that mass [5, 17]—so “the offset” names the unit, and x_0 the reading taken against it. So the ratio it fixes is a reading of cosmic epoch, which is what (7) says of the density ratio directly. *Neither the parameter nor the epoch is a content of the universe:*

$$c^2 H^2(z) = \frac{c^2}{\alpha^2} \left(1 + \frac{2(1+z)^3}{x_0^3} \right). \quad (4)$$

The offset is measured directly and calibration-free— $z_{\text{acc}} = x_0 - 1$, (12) below—without a distance ladder, without the microwave background and without any density. *What the rate is a rate of is the stacking of the foliation*, and content does not enter it: radiation is absent from the slicing operator's vacuum kernel, requiring $m'(r) \neq 0$, a bend of the cut; and the second term is the offset itself rather than a density supplied by hand [7, 9].

The familiar cosmological form is accordingly a coincidence of form, and saying so is the substance of this subsection. Written in the fitted pair the same rate reads $H^2 = H_0^2 [\Omega_m(1+z)^3 + \Omega_\Lambda]$, with $\Omega_m = 2/(x_0^3 + 2)$ and $\Omega_\Lambda = x_0^3/(x_0^3 + 2)$ following identically—a translation between parameter sets, and not a decomposition into components. In the standard reading cosmic time is orthogonal to the three-dimensional world and the expansion is driven: by initial conditions, and by whatever densities obtain at each moment, through the field equations. Here it is read off a fixed background whose foliation is *not* orthogonal to the proper time of observers at rest, so that such observers move through the universe over cosmic time in a geometrically fixed manner. *The two readings agree on the function and share nothing beneath it.*

Where the field equations act is the leaf, and they act there in full. All stress-energy gravitates, by the ordinary Friedmann readout of the self-gravitating congruence; the perturbations, the plasma's sound horizon and its diffusion length are processes running *in* the content and take that rate, while a comoving separation read across leaves takes the stacking rate (§2.2). *What the layered framework keeps apart is not two physics but one physics and its projection:* a quantity is computed on the level it belongs to, carried on the layer and then projected.

Equation (3) is exactly the flat- Λ CDM scale factor. At Nariai the mass is no longer free, and the amplitude becomes a pure Λ -length,

$$\left(\frac{6GM}{\Lambda c^2} \right)^{1/3} = \frac{2^{1/3}}{\sqrt{\Lambda}}, \quad (5)$$

so both factors of the expansion law are set by Λ ^{P15R39}: the rate $\frac{1}{2}\sqrt{3\Lambda}c$ is the standard late-time rate and the amplitude is the third Λ -scale (distinct from α and $\alpha/\sqrt{3}$). The Friedmann equation the $\sinh^{2/3}$ law satisfies,

$$H^2 = \frac{\Lambda c^2}{3} \coth^2 \left(\frac{1}{2} \sqrt{3\Lambda} c \tilde{\tau} \right) = \frac{1}{3} (8\pi G \rho + \Lambda c^2), \quad (6)$$

makes the density ratio a clock^{P15R39},

$$\frac{\Omega_m}{\Omega_\Lambda} = \text{csch}^2 \left(\frac{1}{2} \sqrt{3\Lambda} c \tilde{\tau} \right), \quad (7)$$

so $\Omega_{m,0}$ records the cosmic epoch $\tilde{\tau}_0$ at which we observe rather than an independent density, and the coincidence problem becomes the observation that we exist at a time of order the geometry's single timescale. The densities are bookkeeping for one Λ -set geometry; *radiation, like matter, is inherited content read off that clock, not a term that sources the rate*, and the

stacking rate has no radiation-dominated era [11], the leaf, where radiation gravitates, carrying one (§4). The objection that a perturbing radiation fluid “must gravitate and so alter the rate” is a category error against a construction that reads (6) leftward: the rate is set, and the fluid’s energy is among the contents the set rate carries. The acoustic *scale* follows from this rate, and H_0 is fixed with it by the distance data; this is developed next (§2.4).

2.4 The acoustic scale, the expansion rate, and where the ruler comes from

The two frameworks reproduce the late-time expansion identically and part in the early universe, where radiation carries no term in the foliation’s own rate (6) while the plasma’s scales accumulate on the leaf’s, which carries it. *What follows from that one structural fact is not that the standard model’s tensions dissolve but that the acoustic ruler has a different provenance*, and the two lengths the observed angle is built from sit on opposite sides of the split.

The three levels, and which rate each quantity uses. The reading of every rate-bearing quantity below is fixed by locating it on one of three levels, which the geometry keeps apart and whose conflation is the standing error the layered framework names [9]. **(L1) The foliation stacking rate:** the Λ -set $\sinh^{2/3}$ law (6) read *leftward* in the sense the slicing paper fixes [7]—the cut is primary and ρ is the name of its bend, not its cause, the rate-side of the slicing operator’s reading whose content-side is *matter is the bend of the cut* [7]—the layer’s own geometric expansion, set by α and the offset x_0 , and *empirically forced* rather than modelled: the microwave-redshift isotropy floor forces uniform expansion to some three orders of magnitude, so a matter-tracking (radiation-sourced) rate is already excluded by data [11].

This is what the observable cosmology rides at *every* epoch, the branch point included: it is the rate the foliation stacks at, not a regime that begins somewhere. **(L2) The leaf-level local dynamics:** the expansion scalar of a self-gravitating congruence, the ordinary Friedmann read-out $\mathcal{H}^2 = \frac{8\pi G}{3}\rho_{\text{tot}} + \frac{\Lambda}{3}$ with radiation gravitating normally—the valid phenomenological reading of general relativity on the progenitor’s collapse excursion, where nucleosynthesis runs [19]; it is the same single $E=1$ geodesic read *inward* as dust collapse that L1 reads outward as cosmology [7, 4]. **(L3) The $E = 1$ projection:** the reassigned shadow the observer reads, through which an L1 or L2 quantity appears as distance and redshift—the Projection Principle of the framework paper, its geometric origin the *second ruling* of the slicing (the synchronous space is the second ruling) [9, 7]; reading this appearance as the existent is precisely the naïve-realist collapse the epistemology forbids [12]. The decision rule is structural, not a choice: a self-gravitating local excursion runs on L2, diffuse content riding the global foliation on L1, and every observable is an L1 or L2 quantity seen through L3; and *there is no L1/L2 boundary in time*. The distinction is kinematic and holds at every epoch: the vacuum kernel of the slicing operator is the SdS family exactly— Λ and the cut’s offset $2M$, and no more [7]—so the stacking rate is $c^2 H_{\text{stack}}^2 = (c^2/\alpha^2)(1 + 2(1+z)^3/x_0^3)$, while radiation, requiring $m'(r) \neq 0$, is a *bend* of the cut and therefore content. The decomposition is exact, $H_{\text{leaf}}^2 = H_{\text{stack}}^2 + H_0^2 \Omega_r (1+z)^4$: the two rates differ by the radiation term alone. A comoving separation read across leaves takes the stacking rate; the scales the plasma itself accumulates— r_s and r_D —take the leaf’s, together with recombination’s microphysics and the perturbations, because they are accumulated by a fluid running *in* the content whose own radiation gravitates in its own expansion. The two must take the same rate, and the peak spacing the construction computes is the leaf accumulation: fitted to the computed peaks, the comb reproduces that integral to two per cent and the stacking one not at all. The assignment looked temporal only because $\Omega_r(1+z)^4$ is negligible below $z \sim 10$ [9, 4]. Each mis-assignment is quantitatively fatal—the geometric L1 rate carried down into the nuclear window is $\sim 300\times$ too slow, and the radiation-sourced L2 rate carried into the distances would pin them to a radiation-era density the foliation’s own rate does not carry [19]. Crucially L1 is the layer’s own *ontological* expansion, not the L3 shadow: computing a process against the stacking rate is reading the geometry, not the appearance. Every rate-bearing quantity below carries its level, so the reading is settled by the geometry rather than defaulted

to the synchronous machinery.

The Hubble constant. The late-time expansion is reproduced exactly, so H_0 enters this cosmology as it enters the standard one: through the distances. With the plasma handed over at the branch point there is no early-universe parameter left to carry the acoustic angle, and the angle and the baryon-acoustic distances then fix the rate together, at $H_0 \simeq 68.6$ —the angle alone and the distance data agreeing to a twentieth of a unit. *So this construction does not dissolve the discrepancy with the local distance ladder* [25]: it leaves it where the standard model leaves it, as a disagreement between the ladder and the early-universe inference, and what it supplies in its place is stated in §4.7—the acoustic spectrum computed from that background with nothing fitted to it.

The acoustic scale, computed. Recombination is observable cosmology from the branch point onward, and the two lengths its angle is built from sit on opposite sides of the rate rule: the comoving distance D_M is a separation read across leaves and rides the stacking rate, while the sound horizon r_s is accumulated by the plasma and rides the leaf’s. The observed angle $\theta_* = r_s/D_M$ is their projection.

The robust ingredients are in hand: D_M is the standard observable, and $H(z)$ is the fixed $\sinh^{2/3}$ law (6) with radiation absent from the rate.

The sound horizon $r_s = \int_{z_{\text{rec}}}^{\infty} (c_s/H) dz$ —whose baryon-loaded c_s is ordinary content microphysics and whose expansion is the leaf rate the plasma runs on—carries no early-universe parameter at all once the plasma is handed over at the branch point, where every acoustic mode is outside the horizon and the integral converges at its upper end.

The branch point is a locus at which the areal chart’s invariants diverge— $r = 0$ is a genuine infinite-curvature locus of that chart—while the curvature of the manifold the cut is taken on is set by α everywhere, so the divergence is the areal coordinate degenerating and not a scale of the geometry [19, 17]. *And it is the substrate reading of the branch point that makes the integral well posed:* the modes are outside the horizon there and the plasma’s own expansion carries them, so the sound horizon converges at its upper end without a floor having to be placed under it by hand. Taking c_s the ordinary baryon-loaded value—the matter the plasma carries is pressureless, and the geometric throat ratio $\sqrt{3}$ does not set it—the acoustic scale is computed rather than met: integrated on the leaf rate from the branch point, it returns an angle whose comb sits at 298.0 against the sky’s 298.4 with the background fixed by the distance data alone. *This is where the two rates part, and it is not where the standard model’s radiation sits.* There the whole expansion carries radiation and the ruler is pinned by the matter density’s physical value; here the foliation’s own rate carries none, so the distances are radiation-free while the plasma’s scales ride a leaf rate that is not, and the two lengths the angle is built from sit on opposite sides of that split. The beginning is well posed: the branch point—finite in the substrate’s curvature, whatever the r -chart geometry does there (§2.2)—carries every acoustic mode outside the horizon and the potential at its regular value, so the sound-travel integral converges at its upper end and needs no lower endpoint placed by hand.

What the construction fixes, and what it does not. The empirical forcing of the cosmic foliation bears on the rate, not the matter content—the matter density being the bend of the spatial cut [11, 7, 8]—so the content the plasma carries is measured rather than set by the geometry; the cold seam (Gibbons–Hawking temperature [33] $\sim 10^{-30}$ K, some thirty orders below recombination) confirms there is no geometric source to set it instead.

The quantities this cosmology actually uses are the epoch x_0 (equivalently $\Omega_m = 2/(x_0^3 + 2)$; x_0 is the expansion read in units of the geometry’s own fixed offset r_N , not the offset itself, which the Nariai condition fixes at $\alpha/\sqrt{3}$), which the rate carries and the baryon-acoustic data fix; H_0 , fixed by the same data together with the acoustic angle; and ω_b and ω_γ , which the sound speed carries and which are measured directly and framework-independently. *There is no early-universe parameter among them:* with the plasma handed over at the branch point the sound horizon has no lower endpoint to place, so the angle is an output of the rate rather than

a calibration of it.

The physical matter density $\omega_m = \Omega_m h^2$ then does enter, and it enters once, through equality. Matter–radiation equality is $1 + z_{\text{eq}} = \omega_m/\omega_r$ with ω_r measured, so the epoch the distance data fix also fixes how long the plasma spends radiation-dominated, and with it the driving that sets the peak heights and the wavenumber at which the envelope turns over. *One quantity carries the expansion history and the acoustic driving together,* which is why the spectrum below is a test of the background rather than a further fit to it.

One thing about Ω_m is worth stating plainly, since the construction’s matter sector invites the question. The dust the rate carries exceeds the baryons by about a factor of six, $\Omega_m \simeq 0.31$ against $\omega_b/h^2 \simeq 0.05$, so most of it is non-baryonic. *That is not a component this cosmology introduces, and it is not one it derives.* What the matter sector fixes is the number of families, their chirality, the S_3 relating the three walls and the cyclic $\mathbb{Z}_3$ relating the generations, and *nothing about their internal content* [20]; abundances are measured content throughout, the matter density being the bend of the spatial cut. So the non-baryonic fraction stands with η , A_s and n_s : inherited, not set by the geometry. *What the construction does supply is a place rather than an abundance.* Its correspondence with the Standard Model’s content carries a right-handed neutrino as the sixteenth Weyl fermion of each generation, and fixes that state’s place while fixing none of its couplings [20]; a species that is never thermalized contributes nothing to N_{eff} , so nucleosynthesis is untouched and no prediction is made or needed here. *The point of the paragraph is the division of labour:* a candidate the construction already contains, an abundance it does not claim, and no third thing wedged in between.

The radiation amplitude at a start placed by hand, $\omega_r(1 + z_{\text{start}})/\omega_m$, is that start read in units of a density rather than an inheritance; with the plasma handed over at the branch point there is no such start and no such amplitude. *And the epoch the distance data fix lands where the microwave background’s own matter density sits:* the rate’s Ω_m at the H_0 the angle and the distances return together gives $\omega_m = \Omega_m h^2$ within a couple of per cent of the standard inference, so equality falls within a couple of per cent of flat Λ CDM’s with nothing fitted to a spectrum^{P15R25}.

What this cosmology does carry from outside is the composition: the baryon-to-photon ratio η , exactly as flat Λ CDM carries it from a baryogenesis outside the model proper—measured, not derived—and with it the light elements, synthesized from the hot handover of the progenitor collapse, this universe having formed at the event horizon of a black hole in a previous one, equally outside the construction and equally measured.

That the composition is measured rather than derived is no defect: a framework is credited for *requiring* the structure it explains—here the rate, and the acoustic structure that follows from it—not faulted for measuring the boundary data it does not. *One naturalness argument about the handover fails, because it compares a quantity with itself at two epochs nine orders apart.*

Complete collapse does liberate binding energy of order the rest mass ($GM/Rc^2 = \frac{1}{2}$ at the Schwarzschild radius), and it is tempting to read that as making a handover carrying radiation of order the matter density the natural scale—order unity, rather than the small value η takes. But $\rho_r = \rho_m$ occurs at $T \simeq 0.8 \text{ eV}$, whereas the handover sits four orders *above* the deuterium bottleneck at 0.07 MeV , since that is what the nucleosynthesis computed on it requires [19]: at the bottleneck the ratio is already $\sim 9 \times 10^4$ and at the handover proper $\sim 9 \times 10^8$. A handover carrying radiation merely of order the matter density would be a handover with $\eta \simeq 0.5$, which leaves neither light elements nor acoustic peaks. *So the naturalness question runs the other way:* what the progenitor must deliver is a plasma with of order a billion photons per baryon, and the binding-energy scale offers no head start toward it. *One route to that derivation is closed from the geometry’s side:* the constituent count the matter sector carries is exactly conserved on this history, its parity-odd source vanishing on the spherically symmetric class the cosmogenesis premise fixes, so what such a derivation needs is a chiral *state* on the spatial layer rather

than a chiral member^{P15R151}—and that state is not available on this layer, the same thermal regularity that fixes the tower’s boundary condition carrying no helicity label, so the two helicity towers are populated alike and the parity-odd content cancels between them^{P15R153}. *And the amplitude a start placed by hand would carry is not a feature of this construction either:* given η and the measured matter-to-baryon ratio, both of which the composition inherits regardless, it follows from standard thermodynamics alone, $[1 + \nu](\pi^4/30\zeta_3)T/[\eta(\omega_m/\omega_b)m_N]$. *So what the handover supplies is one composition datum* (receipt: `the_two_data_are_one.py`^{P15R26}). η may remain a measured boundary condition indefinitely at no cost to what this paper computes. *And the inheritance has a structural reason rather than being a gap left standing* [9, 19]: the infall thermalizes four orders above the deuterium bottleneck, so the progenitor’s composition is erased and the abundances are synthesized in the window rather than inherited, while what survives that passage is baryon number, which no dissociation destroys. *So η is inherited and the abundances are predicted,* and the asymmetry is worth stating exactly: baryon number protects the numerator, while what protects the *ratio* is the adiabatic invariance of the specific entropy — the peak perturbing it by 5.5×10^{-10} of a standing $1.15 \times 10^{10} k_B$ per baryon, so that η survives the erasure because η is small [19]. *And a derivation of η is not needed, because there is nothing here for one to be about.* It enters the progenitor from the ambient universe by composition-sharing and leaves the branch point unchanged to one part in 2×10^9 : *transmitted, not determined* — which is the exact dual of the radiation amplitude’s closure, that one turning on a quantity with no single value to transmit. *So the neighbouring statement strengthens from may to must: η remains a measured boundary condition, at no cost.*

The synthesized composition. The same collapse fixes the light-element composition, and the geometry sharpens how. The infalling matter compresses adiabatically—the plasma is optically thick, so the photon bath compresses with it—and heats far above the deuterium bottleneck ($T_D \simeq 0.07$ MeV) for every progenitor: the compression does not stop at horizon crossing but continues to the branch point, and the peak is bounded below by the infall energy at the horizon, of order the rest mass per nucleon, independently of the progenitor’s mass (the cosmogenesis paper [19]); and across the branch point the expanding leg cools back through the window. *The window is therefore crossed twice,* and at the branch point the temperature exceeds the binding thresholds by any margin, so nothing the infall built survives to be counted. Because the effective rate through the window is the standard Friedmann rate, the expanding leg is a standard big-bang nucleosynthesis run from free nucleons [19]. On a first sample this is favourable, and on one element advantageous. The helium-4 fraction $Y_p \approx 0.245$ sits at the observed value; the near-zero metallicity of the oldest systems follows from the handover photodissociating the progenitor’s processed composition back to light elements; and because the run is a standard nucleosynthesis, the lithium-7 abundance carries its standard threefold over-prediction—the standing lithium problem shared with flat Λ CDM, neither dissolved nor worsened. Deuterium sits at the observed $D/H \approx 2.5 \times 10^{-5}$: the freeze-out temperature the data demands is the standard bottleneck, and that is exactly the temperature at which the standard rate delivers a freeze-out—target and mechanism coincide un-tuned. The peak calculation that forces this synthesis reading over an inherited one, and the full multi-abundance account, are given in the cosmogenesis paper [19], where the network is integrated explicitly on the cooling leg and returns deuterium, helium-4 and helium-3 at their observed values with lithium-7 at the shared over-prediction, jointly from the single inherited datum—so one progenitor handover does fit the pattern together; what stands as its open edge is the last-percent precision against the measured abundances, a data-confrontation the produced pattern exposes rather than a computation still to be run.

The load-bearing claim. The acoustic scale is computed from the rate rather than calibrated against it; the standard c_s it uses presumes the inherited medium to be an ordinary photon–baryon plasma, which the abundance comparison confirms—helium-4 and deuterium at their observed values, lithium-7 the shared standard problem (the cosmogenesis paper). The load-

bearing, falsifiable claim remains the prior one—that radiation carries no term in the foliation’s own rate—of which the split between the two rates, and with it the whole acoustic reading below, are the consequences. The sound horizon is where a purely geometric expansion history and the standard radiation-governed one are told apart in the data.

The expansion history, confronted with the late-time data. The distances and the ruler do not share a common factor: D_M and $D_H = c/H$ carry the stacking rate’s $1/H_0$, while the sound horizon is accumulated on the leaf rate, which carries the radiation the stacking rate does not. So the baryon-acoustic observables D_M/r_s and D_H/r_s constrain H_0 here as they do in flat Λ CDM, and the fit returns it: against the DESI DR2 dataset the rate fits at $\chi^2/\text{dof} \simeq 1$ with $\Omega_m \simeq 0.30$ and $H_0 \simeq 68.6$, and the acoustic angle alone, from independent data, agrees within a twentieth of a unit. *What the two frameworks still do not share is the ruler’s provenance:* there it is pinned by a radiation-era physical density, here it is the plasma’s own accumulation on a rate whose geometric part carries no radiation at all. *The two rulers make the constraint differently, and the difference is where the radiation sits.* In flat Λ CDM the ruler is pinned in physical length by the radiation-era matter density, so the same distance data tie the fit to one H_0 ; here the ruler is the plasma’s own accumulation on the leaf rate and the distances ride the stacking rate, so the two enter the fit through different quantities and the constraint is the joint one^{L9}.

The confrontation carried to the state-of-the-art DESI DR2 dataset [23]—thirteen distance measurements across seven tracers ($0.3 \lesssim z \lesssim 2.3$), with the full per-tracer D_M/r_s – D_H/r_s correlations—returns $\chi^2/\text{dof} \simeq 1$ at $\Omega_m \simeq 0.30$ and $H_0 \simeq 68.6^{\text{P15R156}}$, and the acoustic angle computed on the same background agrees with that H_0 from independent data. *The determination is the leaf ruler’s:* on a radiation-free ruler H_0 would cancel algebraically from the ratios and the data would not see it, while the leaf rate carries ω_r/h^2 , so the same thirteen measurements pin the rate here as they pin it in flat Λ CDM.

One thing about Ω_m is worth stating exactly. It is fitted from the distance data here rather than taken from the microwave background, and the invariant is the offset x_0 , read as Ω_m , and not ω_m —holding the physical density fixed instead imports the Λ CDM reading. The expansion history the fit returns is a property of the whole redshift range rather than of one angle, and it rides the very rate whose branch-point-located scoping keeps the nucleosynthesis window standard [19]. The cosmic chronometers [26], which read $H(z)$ directly, test the shape of that history independently of any ruler.

2.5 Where the acoustic modes stand when the plasma is handed over

The cosmological beginning is the branch point $r = 0$ at the close of the lift, where the conjugate branch becomes the matter branch [9, 5]. The curvature invariants of the r -chart diverge there because the areal coordinate degenerates, while the throat itself is the substrate’s defining constant α and the bead continues through by analytic continuation [36]. The lap’s seams lie elsewhere, at the two unit-speed loci $r = -2\alpha/\sqrt{3}$ and $r = +\alpha/\sqrt{3}$. We record the consequence that organizes the perturbation sector.

Proposition 1 (Every acoustic mode is outside the horizon at the branch point). *Approaching $r = 0$ on the contracting leg the comoving Hubble scale aH grows without bound, so the comoving horizon shrinks to zero and every mode leaves it before the crossing, on either rate and for every wavenumber.* What is handed to the expanding leg is therefore the frozen adiabatic state—the effective temperature at an extremum with no velocity and the potential at its regular value—and the collapse leg’s contribution to it is an amplitude and not a phase.

What the modes then meet on the expanding leg is fixed by the same background. The leaf congruence carries a radiation term and the perturbations evolve on it, so the wavenumber entering the horizon at equality, $\ell_{\text{eq}} \simeq 144$ at the epoch the distance data fix, separates the

modes driven through a radiation-dominated entry from those entering later: the first acoustic peak sits above it and is driven, which is what §4.1 computes in closed form and §4.7 measures.

The two loci a reader may run together are distinct, and the distinction is load-bearing^{P15R79}. The branch point is the locus $r = 0$, which no finite cosmic-time layer reaches and which therefore carries no finite redshift at all; a configuration that instead starts the plasma at a finite redshift on the expanding leg is starting it somewhere else, and there the census is the opposite one—modes inside the horizon, and a state handed over mid-oscillation.

Argument. The comoving horizon on the contracting leg, $1/(aH)$, vanishes as $r \rightarrow 0$ because $2M/r$ diverges there, so $k/(aH) \rightarrow 0$ for every k ; that census is re-derived from the metric function directly, the comoving horizon being largest at the front seam and falling to zero toward $r = 0$ ^{P15R79}. The equality multipole follows from $1 + z_{\text{eq}} = \omega_m/\omega_r$ on the leaf background at the epoch the distance data fix, projected on the stacking rate the distances take: $k_{\text{eq}} = a_{\text{eq}}H(a_{\text{eq}})/c$ evaluated on the background rather than on its matter-dominated closed form, which is a third out at equality^{P15R160}. $\square$

What this settles is a premise and not a mechanism: it fixes what the plasma is handed and where each mode stands when it starts, and it does not measure how much of the comb the subsequent driving supplies. That measurement is the transfer of §4.7, which computes the driving directly; the census above is what the transfer is carried from.

3 What crosses, and what does not

The transmission dichotomy above is an argument from the absence of an imprinted scale. A mechanism is given for it, and it also settles which content the branch point does *not* carry.

The imaginary-time segment preceding the branch point acts on a perturbation as a Euclidean kernel [35], damping a mode of frequency ω by $e^{-\omega|\Delta\eta|}$ with $|\Delta\eta| \simeq 1.7 \times 10^4$ Mpc. Taken naively this would annihilate everything: at $\ell = 220$ the factor is 10^{-68} . *But ω is the frequency of an oscillating mode, and at the branch point no mode is oscillating.* On the contracting leg the comoving Hubble scale $aH = |dr/d\tilde{\tau}| = \sqrt{|1-f|}$ grows without bound as $r \rightarrow 0$ —it is 0.13 at the comoving turnaround, 1.96 at $|r| = 0.1\alpha$, and 19.6 at $10^{-3}\alpha$ —so the comoving horizon $1/aH$ shrinks to zero and *every* mode exits it and freezes before the crossing. A frozen mode has no oscillation for the kernel to damp. *So the amplitude and the tilt cross unaltered, and the argument from the absence of a scale is recovered as a consequence of horizon exit rather than assumed.*

What does not cross is the oscillatory content itself, and that is the collapse leg’s acoustic phase: a mode that was sub-horizon earlier carries an oscillation, and the kernel annihilates it—an exponent of -152 at the first acoustic peak, integrated across the segment’s own sound-speed profile rather than at the single value the estimate above uses^{P15R80}. This is required independently by the observed peak positions, which exclude a transmitted leg phase by a factor of 21–41 in the required distance [9], and it is what leaves the comb to be set on the expansion side by the characteristic data of §4. *The two results are one statement:* the crossing transmits what is frozen and destroys what oscillates, so the progenitor supplies the spectrum’s amplitude and shape while supplying none of its phase.

The exponent has two factors, and the argument above varies only one of them. It is $e^{-kc_s|\Delta\eta|}$: holding c_s at the plasma’s value and varying k reads it as a *scale* criterion, frozen against oscillating, which is the reading just given. Holding k and varying c_s reads the same inequality as a *species* criterion, and that reading supplies something the first does not. A pressureless component has $c_s = 0$ identically—not small, not slowly varying—so its exponent vanishes at every wavenumber; on the segment its mode equation is $\psi'' = 0$, whose constant solution the kernel leaves untouched with no approximation at all. *The matter sector’s inheritance is therefore exact rather than adiabatic:* it does not rest on horizon exit and it does not degrade at small scales, where the frozen-mode argument does. The two arguments agree wherever both

apply, and only the pressureless one is available everywhere. *Neither reading carries a constraint the other lacks.* On this geometry the exponent at the first acoustic peak is $\simeq 1.6 \times 10^2 c_s/c$, so a component arriving *oscillating* with a per-cent sound speed would be suppressed by $e^{-1.6}$ and one with ten per cent by e^{-16} (receipt: `the_filter_is_a_sound_speed_filter.py`^{P15R80}). *But the exponent has nothing to act on.* The kernel acts on *oscillatory* content—a frozen, zero-frequency mode is a fixed point of it—and on the progenitor’s own interior nothing arrives oscillating: $|aH| = |a'/a|$ diverges as $1/x$ at the branch point while c_s saturates at $1/\sqrt{3}$, so $c_s k/|aH| \rightarrow c_s kx \rightarrow 0$ for every k , and every mode from $\ell \simeq 28$ to $\ell \simeq 2475$ exits the comoving sound horizon strictly before the crunch—the highest with a fifth of a per cent of the collapsing leg still to run [19]. *So the two readings do not divide the work between them: the scale criterion is satisfied by everything, and the species criterion selects nothing.* The crossing is lossless for every species rather than for cold ones alone, and the pressureless argument’s positive content—that the inheritance is exact rather than adiabatic—holds of every species and not of dust alone.

One consequence of that freezing bears on the acoustic sector rather than on the crossing, and it is computed rather than left as an inference. Every mode is outside the comoving horizon at the branch point (Prop. 1), so each re-enters on the expanding leg at its own time, and what it meets there is fixed by the rate the perturbations run on. *On the leaf rate that re-entry is an event:* the plasma carries radiation, the potential decays on the sound-crossing time, and the modes entering while radiation dominates—everything above $\ell_{\text{eq}} \simeq 144$ at the epoch the distance data fix—are driven. *That driving is not an inference about the potential’s form but a shape read off the two arms:* subtracting an undriven reference that calibrates at unity, the control’s acoustic phase at first turnover is flat in wavenumber to 2.1% while this arm’s varies by a factor of 3.9 across the same band^{P15R64}, and §4.1 carries the same driving in closed form.

What the rate rule closes is the alternative reading, on which the modes re-enter under pressureless matter and nothing is imprinted: the potential equation for a pressureless component, $\Phi'' + 3\mathcal{H}(1+w)\Phi' + [2\mathcal{H}' + (1+3w)\mathcal{H}^2]\Phi + wk^2\Phi = 0$, *contains no k at all once $w = 0$,* so on a radiation-free rate the problem is scale-free and a scale-free problem imprints nothing^{P15R62}. That is the stacking rate’s answer, and the perturbations do not take it: they take the leaf’s, which carries the radiation term and therefore the driving.

4 What the substrate determines: coherence from the null boundary

The acoustic peaks are sharp because the modes of a given wavenumber share a common phase at last scattering. Inflation produces this coherence dynamically, by freezing modes while super-horizon. CR obtains it instead from the character of the branch point.

The branch point is a *null* surface—the cosmological horizon promoted to the initial layer [9]. The initial-value problem on a null surface is characteristic, not Cauchy: the data that determine the future are one free function per mode on the surface together with regularity along the generators, rather than a field and an independent momentum. A single datum per mode is a single phase per mode; there is no second, independently specifiable quantity to randomize the relative phase.

We therefore argue that coherence is not imposed but is what regular characteristic data on a null surface *is*.

This is borne out quantitatively, and the scope of the demonstration is stated exactly.

Evaluating the tightly-coupled mode function at last scattering with a *common* phase on that surface gives a sharp regular comb, whereas drawing the phase independently per mode—the second, free datum a Cauchy surface would admit—washes it out entirely, leaving flat power (peak-to-trough contrast ~ 1 against the coherent comb’s many orders of magnitude; receipt: `verify_coherence_comb.py`^{P15R18}). *That establishes the mechanism—one characteristic datum*

per mode is one phase per mode, and coherence follows—and it establishes nothing about where the peaks fall. The receipt writes the mode function down as $\cos(kr_s)$ with r_s and D_C as literals—and the r_s it writes is the *standard* 147.0 Mpc rather than any value this construction derives; no mode is propagated in it, as its own scope note says, so the spacing $\Delta\ell \simeq \pi D_C/r_s \approx 296$ is the arithmetic of an assumed expression on an imported ruler rather than an output. *It is not the result of propagating the modes, and is not offered as one*^{P15R61}.

What the peak spacing lacks here is not agreement but a derivation: this receipt asserts it, and it is the propagated modes of §4.7 that compute it.

The null boundary admits only the first column: one characteristic datum per mode is one phase per mode.

The peak *heights* are then carried by a structural argument rather than a bespoke transfer. The driven acoustic amplitude is the resonant Fourier magnitude of the potential’s evolution, $|\tilde{\Psi}(\omega=1)|$ —exactly invariant under time reversal, $|\widetilde{\Psi(x)}| = |\widetilde{\Psi(-x)}|$, a Fourier theorem confirmed numerically on the radiation-era transfer function and on a random control^{P15R20}.

The equality is a theorem about Fourier magnitudes and holds whichever side the driving lives on. *Which side it lives on is fixed by the rate rule:* the perturbations run on the leaf congruence, whose matter–radiation equality is fixed by the epoch the distance data fix, so the plasma’s early history is radiation-dominated and the modes carrying the first peak enter the horizon while it is. *The driving is therefore on the expanding leg,* and the collapse leg’s contribution to the state that meets it is an amplitude and not a phase.

What the state at the handover is has to be said at one locus, and the construction supplies one.

At the branch point every acoustic mode is outside the horizon and the leg’s closed-form potential has returned to its regular value, so the state arriving there is the ordinary frozen adiabatic one: the effective temperature at half the potential with no velocity, the potential unspent, and the collapse leg’s contribution surviving as an amplitude alone—the wavenumber-independent $0.4835 \Psi_i$, within three per cent of the frozen value $\Psi_i/2$ the free oscillator carries at every wavenumber. Specified that way the radiation-era driving is applied exactly once, and the specification carries no free choice, the other three codings each making one. *It is a limit rather than a parameter:* carried back over two decades in starting redshift the peaks hold to the grid step and the height ratios to half a per cent, while a start an order of magnitude later has not converged.

The collapse-side driving that argument relied on carries a qualification of its own receipt: completeness holds for the modes whose entry precedes the horizon maximum at $r_* = 1.53 r_{\text{seam}}$, entry on the rising branch being earlier the higher the wavenumber, so the acoustic band is on the safe side of that boundary by construction and the low- k end is where it would bite^{P15R48}; what a Boltzmann reference returns for flat Λ CDM’s own heights is $P_1/P_2 \approx 2.2$, $P_2/P_1 \approx 0.45$, $P_3/P_1 \approx 0.44$ (`camb.reference.py`^{P15R21})—*those are the reference’s values, not this arm’s*, and what this construction’s own instrument returns is set out above. The *damping* tail ($\ell \gtrsim 1000$) is fixed by the three-level rule (§2.4) rather than left to judgement. Recombination is observable cosmology from the branch point onward, and the photon diffusion length r_D —like r_s —is a scale the plasma itself accumulates, so it takes the leaf’s rate: the random walk runs *in* the content, whose own radiation gravitates in its own expansion, its Thomson microphysics ordinary content physics and its expansion the leaf’s (§2.4).

This is the same scoping the cosmogenesis paper derives for the nucleosynthesis window [19], and the two windows fall on the *same* side of it rather than on opposite sides: there the self-gravitating excursion sets the leaf rate radiation is included in, and here the plasma accumulating its own scales takes that same rate. *What differs between the two is not the rate but what is read off it*—an abundance there, an angle here—and the angle alone is divided by a distance read across leaves, which is where the rate radiation is excluded from enters.

This is forced by consistency: one may not take the rate geometric for the peak spacing and

radiation-included for the diffusion—and *the peak spacing this construction computes is the leaf accumulation*, which is measured rather than assumed (§2.4), so the demand puts both lengths on the leaf and not on the foliation’s rate. *The two rates are far apart*: the geometric one is $\sim 13\%$ below the radiation-included one at recombination ($\rho_r/\rho_m \approx 0.3$) and further below it earlier, where the inherited radiation is a larger fraction, and the closed-form derivation of §4.2 puts 10.8% of that gap into the diffusion length by itself. *But a rate the two lengths share cancels from their ratio*, and what the sky reads is the ratio, $\theta_D/\theta_* = r_D/r_s$. *So the rate gap is not what the signature is made of*. What it is made of is what §4.3 derives on the leaf assignment—where the plasma is handed over, and how far the diffusion integral is carried—with the handover fixing the size and the common endpoint at the visibility peak fixing the sign. *One consequence of the signature being that small should be stated rather than left implicit*: the reference the instrument is validated against agrees on r_s to 0.28% (144.0 against 144.4), which was a comfortable margin against a signature of several per cent and is a third of this one, so the word *validated* here carries a thinner margin than it did and the figure is quoted with that in view¹². What a stated tolerance carries anywhere in this corpus’s computational layer is measured rather than assumed: every `abs(...)<tol` comparison in the receipts rewritten twice, once to displace the compared quantity above its tolerance and once to collapse it below, so that 243 of the 245 receipts that pass are shown to have at least one such comparison that actually gates their verdict, the two exceptions being a display filter and a skip that prints its own reason^{12L22}.

This is a genuinely CR-specific piece of the height pattern, and *what makes it so is the handover and not a rate*: a rate the two lengths share cancels from their ratio, while the epoch at which the plasma is handed to the expanding leg is fixed by the construction and is not a parameter. So the signature is not an artefact of laying the standard radiation-governed r_s on a rate it was not accumulated on, the calculation belonging to neither framework this paper warns against (§1).

One thing about this signature is settled and one is not, and it is essential to keep them apart.

Settled: the effect in r_D is genuinely CR-specific and does not dissolve under the density that would ordinarily rescale it— $r_D \propto \omega_b^{-0.31}$, so a percent-level ω_b (fixed by primordial deuterium and the peak-height ratio) shifts it by well under a percent (receipt: `damping_reabsorption.py`^{P15R23}). *And what the signature does to the observed high- ℓ power is measured, with a verdict that is neither of the two a reader expects*. Scaling the diffusion length by the instrument’s own measured ratio multiplies the damping by a Gaussian in ℓ , and a tilt is a power law — so over a restricted high- ℓ range the one is well approximated by the other. *Refitting amplitude and tilt therefore absorbs the signature almost entirely in shape*, and what it costs is a shift in the inferred tilt. *Both scale with $r^2 - 1$, and at the adjudicated ratio that factor is small*: with both lengths carried to the visibility peak, $r = 0.9918$, the signature costs 1.70 in χ^2 over the 185 full-range bins—under a hundredth per bin—and a tilt of $+0.0034$ absorbs seven tenths of it. *Terminating the diffusion integral at a sharp recombination cut instead, $r = 1.0231$, gives 12.6 and a tilt of -0.0093 , and a ratio of 1.082 gives 160 and -0.034 on the same base and the same damping scale*^{P15R167}. *So the hundredfold collapse is the configuration moving and not the fit improving. So the signature does not vanish under a refit — it moves out of the spectrum’s shape and into an inferred parameter. What a refit buys in shape it pays for in parameters, and that direction is the robust part*.

And how local that approximation is can be stated exactly, which settles what a joint fit would actually meet. The signature’s own logarithmic slope is $d \ln(\text{ratio})/d \ln \ell = -2(r^2 - 1)(\ell/\ell_D)^2$ — *not a constant, but growing as ℓ^2* : across the likelihood’s own $\ell = 30$ – 2508 it runs from -0.0002 to -1.31 , a factor of seven thousand, which is exactly $(\ell_{\max}/\ell_{\min})^2$ ^{P15R3}. *So a single tilt is a one-parameter fit to a function whose slope varies by that factor over the data it is scored on*, and the displacement quoted above is the signature’s true slope at $\ell = 381$ and at no

other multipole. *The consequence is the useful part*: a joint fit does not encounter a shifted tilt but a residual whose *shape* is a Gaussian in ℓ , and no tilt removes a Gaussian — so what such a fit weighs is the shape residual, which is the quantity already bounded from above. *And a displacement in n_s is not by itself a tension here*, the tilt being inherited boundary data rather than predicted: a different value of an inherited input is a different input. *What could be a tension is a constraint on n_s that does not run through the damping tail* — the low- and mid- ℓ shape, the polarisation spectra, lensing — which is what a joint fit means and is where the question properly sits.

Two bounds travel with that and neither can be left to a reader. The shape residual is an upper bound: freeing only the named degeneracy is the least absorption a fuller refit could achieve, so a wash is a wash *a fortiori*. *The tilt displacement is not a bound*, because more free parameters would share it — the baryon density moves the diffusion length itself. *And the magnitude is not robust to a factor of three*: imposing the ratio on the measured spectrum gives the figures above, while applying it inside the instrument’s own source — where it also reaches the Doppler term through a derivative — gives 0.92 in χ^2 per bin. *The larger comes from the more faithful route, so the wash is stated at the weaker bound* and closing that factor is named here as work not done.

The joint fit returns the residual this reading predicts. Fitting amplitude and tilt together against the signature-carrying spectrum, on `plik_lite`’s own bandpowers and covariance, the residual left after the fit is the analytic Gaussian-minus-power-law shape to a correlation of 1.000000 — *not merely non-zero, but the predicted form*. *The residual’s form is the finding and its size is the configuration’s*: at the adjudicated ratio it is under a hundredth in χ^2 per bin, and 1.50 per bin at a ratio of 1.0926 on the same window. *And the displacement is not one number*: fitted over $\ell = 100$ –1760 and over $\ell = 1400$ –2508 it differs by a factor of 6.3 across windows of the same data, so a displacement is the value of nothing without the window it was fitted over. *And the tilt takes a fixed share of it rather than a variable one*: seven tenths at the adjudicated ratio and seven tenths at 1.0926, so what the refit can and cannot do is a property of the shapes and not of the size^{P15R4}.

Not settled, and unchanged by that run: whether a displacement of that size in the inferred tilt is a *tension*. The tilt is inherited boundary data here, not predicted, so a different value of it is a different input; what would make it a tension is a constraint on n_s that does not run through the damping tail, which this fit does not supply. The observable is $\theta_D/\theta_* = r_D/r_s$, and translating it into a spectrum requires the full acoustic transfer, which is run (§4.7) and does not return high- ℓ peaks tracking flat Λ CDM’s. A leading-order pass that simply *assumes* the high- ℓ peaks equal Λ CDM’s and applies the extra damping produces a large high- ℓ deficit (receipt: `full_transfer_verdict.py`^{P15R27})—but that assumption may not be imported for free: the same handover that fixes r_D also governs the high- ℓ driving envelope, so CR’s high- ℓ spectrum rests on short-wavelength collapse-phase driving rather than on the boost an expanding radiation era supplies.

And the observable ratio is read at one epoch on both lengths, which is what fixes it. The two-arm transfer measures the raw diffusion length at the visibility peak, and the sound horizon is carried to the same place, because a ratio of integrals taken to different epochs is not a ratio of anything (§4.3). *The endpoint is therefore not a free choice*, and the difference between terminating the two lengths together and terminating them apart is larger than anything the cosmological parameters do to the signature.

That driving is computed below (§4.1), and the calculation removes the licence the shortcut lacked: the envelope is derived on the collapse leg rather than imported.

Diffusion on the leaf rate therefore constrains, but does not by itself determine, the high- ℓ shape; the net effect is computed in §4.2; whether it is a tension, a wash, or a distinctive but consistent feature turns on a parameter refit and on the early integrated Sachs–Wolfe term. *Two confrontations are to be distinguished and both are run*. The spectrum computed on the

background the distances fix is scored as it stands, one amplitude fitted so that what is compared is shape, and sits at 2.57 times the control's distance from the data. *Refitting the spectrum's own parameters to the microwave data*—the comparison the standard model is usually judged by—*leaves it at 1.57 times*: freedom closes about a third of the gap and leaves the rest (§4.7). The control reproduces the sky essentially perfectly, which is what makes the comparison readable at all; and the verdict it returns is that the spectrum derived here is disfavoured against the standard model on this data. We state it as it stands. The effect the fit is run on is separately established: a real, computed, non-reabsorbable CR-specific diffusion-scale signature, under a per cent at the adjudicated endpoint and fixed by the handover rather than by a rate (§4.3), its observable consequence derived rather than entangled (§4.2). *What the fit does not reach is the join*: it weighs the five-parameter spectrum construction, and what carries that construction back to the geometry is the transfer work of this section, which is where the open end lies. The structural point that stands is the *mechanism of phase*: where inflation freezes the phase dynamically, CR fixes it geometrically on the single null layer; how the amplitudes are driven is what the transfer of §4.7 measures.

4.1 The collapse-phase driving envelope

The driving named above can be carried out in closed form, and doing so removes the entanglement the previous subsection had to leave standing. On the radiation-dominated collapse leg the potential obeys $\Psi'' + (4/\eta)\Psi' + (k^2/3)\Psi = 0$, whose regular solution is elementary, $\Psi = 3\Psi_i(\sin x - x \cos x)/x^3$ with $x = k\eta/\sqrt{3}$, and which is *even* in x ^{P15R47}—so the contracting leg carries the same closed form pointwise, a sharper statement than the Fourier-magnitude equality of §4 and consistent with it. Writing $\hat{\Theta} = \Theta_0 + \Psi$ removes the source exactly, $\hat{\Theta}'' + (k^2/3)\hat{\Theta} = 0$: the effective temperature oscillates freely, and the k -dependence rides entirely in the amplitude at horizon entry and in the decay of Ψ .

Horizon entry is fixed by the construction rather than fitted. The comoving Hubble radius is built from the slicing paper's own turnaround function, $(rH)^2 = (1 - f) + A/r^2$ [5], and has a single turning point on the whole excursion, at $r_* = 1.53 r_{\text{seam}}$ on the corpus's inherited datum; the *seam* sits just inside that turning point, on the rising branch, so the acoustic modes are already within the comoving horizon there—a property of the turnaround function's geometry rather than a numerical accident of the background, and a statement about the seam that Prop. 1, being about the branch point, does not make^{P15R48}. *The locus matters and the two available ones give opposite answers*: the branch point lies at the far end of the same rising branch, where $2M/r \rightarrow \infty$ carries aH up without bound and the comoving horizon to zero, so there *every* mode is outside it (§3). It is the seam, not the crossing, that this construction reads—the inversion derived from the metric function rather than asserted^{P15R79}. On the leg the radiation term dominates because it is constant while the others vanish, so $\eta = r/\sqrt{A}$ to about two per cent at the entry radius of the lowest mode in question and better the deeper the mode enters—sub-percent from $k \gtrsim 30 k_s$ ^{P15R49}, and entry then occurs at $x \rightarrow 1/\sqrt{3}$ *in the deep sub-horizon limit*—the radiation era's own scale invariance, recovered here from the substrate geometry. *The envelope is therefore flat to the accuracy of that limit*: a mode at $k \simeq 10 k_s$ enters within 2% of $1/\sqrt{3}$ and one at $300 k_s$ within 0.1%, all of them reaching the *seam*—where the collapse leg ends—with the same driving amplitude $\Psi(1/\sqrt{3})/2$, and the residual potential is below a percent *on average* while oscillating up to some seven per cent of it where $\cos x_{\text{seam}}$ is near an extremum^{P15R50}. *Both are qualifications rather than identities: the limit is a limit and the average an average*. Its turnover sits at equality, and the equality is the background's own, Ω_m/Ω_r on the leaf rate: at the epoch and rate the baryon-acoustic data fix it falls within a couple of per cent of flat Λ CDM's, and it moves with the matter density rather than being assumed^{P15R53}.

Two corrections that might have been expected do not enter. The baryon loading is proportional to the scale factor and the driving happens where the scale factor is smallest, so $R \lesssim 0.1$

where the driving happens and orders below that at entry; the odd/even asymmetry is imprinted afterwards, on the expansion side at $R \approx 0.6$, which is ordinary content physics on the observable leg. *The sky's own value, located by parabolic fit on the Planck binned spectrum, is $P_1/P_2 = 2.2564 \pm 0.0772$, and flat Λ CDM's is 2.200; what this construction returns for the same quantity is 2.264 on the polarisation path, on the transfer of §4.7 with its wavenumber integral converged, since a peak height is exactly what an unconverged integral misreports^{P15R70P15R51}. The structural point stands without it: *the loading is the same in both because it is imprinted on the expansion side, and the argument is at the level of contents rather than of the driving—where the loading ratio alone would give 3.5*. And the free-streaming neutrinos the cooling-leg nucleosynthesis requires do carry anisotropic stress at these temperatures—the branch point is far below their decoupling—but their deep sub-horizon effect is a constant phase shift and a constant suppression, and a k -independent correction leaves a flat envelope flat^{P15R52}. *The transfer carries the effect, and what it carries is a composite: removing the anisotropic stress at both of its dynamical sites—the neutrino Euler equation and the shear term in Ψ —leaves the sector a perfect fluid at the same background density, and pushes every peak on both arms to larger multipole, the direction the free-streaming pull has, with the amplitude moving separately—its envelope by about a quarter. But that operation removes the constant phase shift and the change in the potentials' decay together, so what it measures is not the deep sub-horizon constant the argument above is about, and no value for that constant is read off here^{P15R177}. What it does not leave is the closed form for Ψ itself, the equation becoming integro-differential; the closure is a property of the skeleton, and the flatness is what survives.**

4.2 What the envelope buys, and what remains

With the envelope derived rather than assumed, the diffusion signature can be stated without the entanglement. The diffusion length reduces to a single integral over the scale factor in which every microphysical constant sits outside, $1/k_D^2 \propto \int da g(R)/(Hx_e)$, so in the ratio the Thomson physics and the ionisation history cancel identically and the whole difference is carried by $H(a)$ —which is the division of labour this section has argued for throughout. Both integrals close in elementary form, and on the inherited datum the geometric rate gives a diffusion length 10.8% longer^{P15R54}. *That is a statement about the two rates and not about the observable: the plasma accumulates both lengths on the leaf's rate (§2.4), so a difference common to them cancels from θ_D/θ_* , and the figure is quoted here because it sizes the rate gap the division of labour turns on rather than because it sizes the signature. The elementary route and the code-validated one agree on it to about a point and a half, which is the relationship an elementary derivation should bear to a code-validated one. The sound horizon is the same kind of integral, and it must be taken from the branch point: there is no observable expansion below it. Doing so returns $r_s = 146.4$ Mpc against 145.4 on the radiation-included rate—within 0.7% of each other, the exact crossing sitting a little lower at $z \simeq 6.7 \times 10^3$ ^{P15R55}—the acoustic-scale calibration, met from the other end and to that accuracy rather than exactly. Both are the elementary integral; carried through a full recombination history the radiation-included one comes out at 144.0 against a Boltzmann reference's 144.4, a per cent lower than the elementary value^{P15R22}. The observable, in which the common distance cancels, is then θ_D/θ_* moved by under a per cent, its size fixed by the handover and its sign by the common endpoint both lengths are carried to (§4.3), and $\ell_* = \pi D_M/r_s = 302.2$ against the measured 301.76^{P15R44}.*

The high- ℓ consequence follows with no free parameter: $C_\ell^{\text{CR}}/C_\ell^{\Lambda\text{CDM}} = \exp[-(\ell/\ell_D)^2(r^2 - 1)]$ with $r = \theta_D/\theta_*$ —the same ratio the preceding paragraph derives, and nothing else—so with both lengths carried to the peak of the visibility function, $r = 0.992$, it is a rise of about two per cent at ℓ_D and four at $1.5\ell_D$, where terminating the diffusion integral at a sharp recombination cut instead, $r = 1.023$, turns it into a fall of four and ten^{P15R167}, the sentence and the ratio it defines being checked against each other rather than corrected separately¹². *Whether that is a tension is a separate question this paper does not settle: a confrontation refits the cosmological*

parameters, which is a likelihood analysis and not a closed-form calculation, and asserting exclusion from these numbers would repeat, at one remove, the error of holding everything else fixed while varying one thing. What has changed is the standing of the signature. The signature is a requirement of the construction, following from the level assignment and the handover and nothing else, with its sign fixed by the endpoint the diffusion length is carried to.

The early integrated Sachs–Wolfe contribution is present here, and the step that once denied it is worth setting out because the denial was an inference and not a measurement. The rate at recombination is matter-dominated to nine orders, the substrate term being utterly negligible there^{P15R46}: *that is true, and it is a statement about the rate.* The geometric rate carries no radiation term, radiation being inherited content read off the clock rather than something that sources the rate.

*But the effect is driven by the radiation **content** through the perturbation source, not by the rate.* The content enters the source under either rate assignment, and *at recombination this cosmology’s content is 21.7% radiation, $\rho_r/\rho_m = 0.2765$ at $z = 1088$ — which no statement about the rate’s composition bears on.* *So the inference from a radiationless rate to an absent term does not hold, and the term is present.*

Measured, as the integrated $|e^{-\tau}(\Phi' + \Psi')|$ after recombination in units of the Sachs–Wolfe amplitude there: 0.348 on the leaf congruence the rate rule assigns the perturbations to, and 0.229 on the stacking rate. Non-zero on both. The leaf assignment makes the term half again larger; it does not create it.

One scope qualification is owed here, and it narrows the claim without touching the conclusion. The constancy argument runs on $\Phi'' + 3\mathcal{H}\Phi' = 0$, which is the *super-horizon* equation: it drops the $k^2\Phi$ term. For the acoustic modes—inside the horizon through the observable leg—that term does not vanish, and the potential does decay on the observable leg, by a factor of order two across the first few peaks^{P15R45}. The decay is not a radiation effect: zeroing the radiation fractions in the constraint makes it *larger*, and the rate responsible is $k^2/(3\mathcal{H})$, which grows with k and refers to no content at all. So the statement that survives is that *the substrate rate supplies no early integrated Sachs–Wolfe term*—which is what the leftward reading delivers and what the comparison with flat Λ CDM turns on—while the sub-horizon potential decay is an ordinary consequence of the perturbation’s own scale, present in any cosmology.

Whatever difference in that term remains between the arms cannot offset the diffusion signature, and the reason is structural rather than numerical. It sits near the first peaks and dies away well before the damping tail begins, so the two live at opposite ends of the spectrum; and the first peak is where the amplitude is anchored, by an A_s this construction inherits rather than predicts. A few per cent there is absorbed by that inherited normalisation, exactly as it would be in a framework carrying η from outside. The diffusion signature is not so absorbed: it is a change of *shape* at high multipole, and rescaling the amplitude to restore the first peak would worsen the tail rather than repair it. *What stands between the derivation and a verdict is therefore the likelihood confrontation*—a parameter refit, not a further calculation of this kind, and it is run: the joint fit leaves the Gaussian residual (§4) and the full-spectrum likelihood rejects this arm’s spectrum on TT shape (§4.7).

4.3 The diffusion scale, and the error budget

The acoustic scale is computed from the rate, and the diffusion scale is computed from the same one. Both lengths are accumulated by the plasma on the leaf rate, so the projection cancels from their ratio and what is left depends on two things only: where the plasma is handed over, and how far the diffusion integral is carried. *Neither is a free parameter, and the first is the larger.* With the handover at the branch point the ratio sits within a couple of per cent of flat Λ CDM’s on either endpoint convention; a start placed later on the expanding leg raises it steeply, reaching some thirty-five per cent by the redshift at which the angle would be met.

The remaining choice is the epoch both integrals terminate at, and it is settled by the same consistency the rate assignment is. θ_D/θ_ is a ratio of two lengths the plasma accumulates, and a ratio of integrals taken to different epochs is not a ratio of anything: the observed angle is read at last scattering, which is the peak of the visibility function, so that is where both the sound horizon and the diffusion length are carried to. Terminating them differently is what produces the spread: with the sound horizon anchored at the observed angle and the diffusion length taken instead to a sharp recombination cut, the signature reads +2.2% where a common endpoint at the visibility peak gives −0.9% — a swing of three points where the cosmological parameters together move it by two hundredths^{P15R161}. So the size is the handover's and the epoch is not a free choice, and the ordering of the four handover-and-rate combinations is unchanged on either reading. What the signature is not is reabsorbable: the baryon density has about one per cent of freedom against it, and the matter density could only absorb it by moving some thirty-seven per cent, which is a different cosmology rather than a refit.*

Two contributions that might have been expected do not enter: the last-scattering surface's thickness scales with the rate in both its width and its conversion to comoving distance, so it cancels from the ratio; and the recombination redshift, integrated on this rate through the Peebles equation [38] rather than inherited, moves by only −0.11%^{P15R59}. The same integration returns $z_* = 1091$ on the radiation-included rate, against the 1090 of the standard treatment, which is the check that the ionisation history is being handled correctly.

4.4 The integrated Sachs–Wolfe contribution across the first-peak region

The first acoustic peak is a separate matter and it does not move. Its offset from $\ell_* = 220$ against 301.7—is largely the phase shift the potential's decay imparts while the modes are driven, and that decay has the same closed form on the collapse leg as on an expanding radiation era (§4.1), so it transfers. What does not transfer is the early integrated Sachs–Wolfe contribution, and that turns out to be a nearly *flat* multiplicative factor across the first-peak region—some ten per cent in amplitude, varying by two parts in a hundred between $\ell = 150$ and $\ell = 300$ —so it displaces the maximum by one or two multipoles rather than by tens^{P15R57}. *So the early integrated Sachs–Wolfe contribution does not move the first peak; what sets this arm's first peak, and how its phase stands against the sky's, is taken up at §4.7. The reabsorption of the damping signature, by contrast, can be bounded here, and bounding it is worth doing because the reabsorption question is the whole of what a likelihood would decide about this signature. Pinning ℓ_* to the measured 301 and minimising the residual in θ_D/θ_* over the baryon density and the matter density—the former held to the one per cent primordial deuterium allows, the latter to the five per cent the distance and growth data allow—leaves a residual of several per cent^{P15R58}. The baryon density has about one per cent of freedom against it (§4.3); the matter density could absorb it only by moving some thirty-seven per cent, which is not a refit but a different cosmology. So the shift has a floor, and the floor is the prediction. We state this as a bound and not as a likelihood: a full comparison fits the whole spectrum with every parameter and its covariances, where this fixes one observable and minimises one derived ratio. It settles that the signature does not dissolve under reabsorption; it does not settle the verdict.*

4.5 What the instrument's residual is made of

The two-arm comparison's floor is set by components of the instrument rather than by either cosmology. Two candidates for the accuracy it lacks are measured here.

Of the two, one cannot pay at all^{P15R73L23}. Above $\ell \simeq 40$ the whole effect of reionisation on the temperature spectrum is the constant screening $e^{-2\tau}$ —the second visibility bump contributes only below $\ell \simeq 30$, outside this comparison's range—and the comparison fits one amplitude in closed form. An amplitude fitted as $A = (m^T F d)/(m^T F m)$ is homogeneous of degree −1 in the model, so rescaling the model returns A/s and leaves the residual unchanged: the degeneracy

is exact rather than approximate, and it is a property of the statistic rather than of the size of τ . Checked at $\tau = 0.054, 0.10$ and 0.30 , the change in χ^2 is zero to machine precision at all three. *Lensing is a different matter.* A smoothing in multipole, scanned in width, takes the control from 1320 to 921; and a width that *grows* with ℓ beats a constant one by a factor of 1.8 in the improvement, each compared at its own optimum, so the preference is for a shape and not merely for a size—which is *lensing's own signature, since a deflection of fixed angle subtends a larger fraction of an acoustic wavelength at high ℓ* . We state what that is and is not. The width is fitted, so the improvement bounds what a derived calculation has to play for rather than measuring a lensing amplitude; and even at its own optimum some 70% of the residual survives it. *The lensed spectrum is therefore what the instrument's remaining floor is made of, and it is computed rather than fitted.* Applying Λ CDM's own lensed-to-unlensed ratio to the arm—a derived operation with no free width—takes the control from 1320 to 989, an improvement of 331, concentrated in the damping tail where a fixed-angle deflection fills the troughs. *That is below the 400 the fitted width bounded, as a zero-parameter derivation must be*, and the acoustic peaks do not move under it. The corpus's own first-order kernel overshoots the bound to 508 by breaking down in that same tail—returning a spurious +13% at $\ell = 1900$ where the full operator gives +6.5%—which is why the derived number is the full operator's. *Most of the fitted headroom is recovered by a genuine lensing, and about 989 of the 1320 survives it:* the verdict of the last paragraph stands from the derived side, lensing real and not the last build^{P15R74}.

And what the residual is MADE of was decomposed alongside it, which is what let the size of that gain be anticipated rather than discovered^{P15R76}. Projecting named templates through the same inverse covariance the comparison uses, the peak *positions* account for a tenth of a per cent of the residual—which is *why the acoustic peaks do not move under the lensing above, and the two findings corroborate each other*—while the peak-trough *contrast* at fixed position accounts for two-fifths of it, this transfer's contrast running some thirteen per cent too high. *Reducing contrast without moving peaks is what lensing does.* A smooth multiplicative envelope accounts for a further sixth, and *about half the residual is in neither*—so a complete lensing calculation was expected to leave a comparable amount behind, and it did.

4.6 The shear coefficient, derived

The coefficient is derived rather than fitted, and the derivation settles it against the fit^{P15R71}. The coefficient is measured by running the same oscillator twice on the same background: once as the perfect tight-coupled fluid, which is undamped by construction, and once as a photon hierarchy carried to $\ell = 24$ with Thomson scattering, the polarisation multipoles evolved alongside and the baryons given their own velocity. *Their ratio is the damping and nothing else*—the slowly varying prefactor, the drift of the sound speed and the baryon-loading dependence of the oscillation are common to the two runs and divide out identically—and reading it locally, between consecutive extrema, lets the residual be extrapolated in $(k/\tau')^2$ rather than smeared over an interval. With the polarisation multipoles suppressed the quadrupole's scattering term reduces to $-\frac{9}{10}\tau'F_2$, which is the unpolarised closure, and the coefficient comes back as 0.8852 against 8/9; with them carried it is 1.0618 against 16/15. *The polarisation correction itself, which is the quantity in dispute, is a factor 1.1996 against 6/5: three parts in ten thousand.* Both absolute values sit about half a per cent low by an amount proportional to the coefficient, so the residual is a common normalisation and cancels in the ratio.

4.7 The acoustic comparison

The angular scale $\ell_* = \pi D_M/r_s$ is built from two lengths that do not ride the same rate here: the distance carries the stacking rate's $1/H_0$ and the sound horizon is accumulated by the plasma on the leaf rate, which carries the radiation the other does not. So the measured angle

constrains H_0 , as it does in flat Λ CDM where the sound horizon is fixed instead by the matter and baryon densities^{P15R56}. *So the acoustic scale is computed rather than accommodated*, and it is the comb of the computed spectrum that carries it: fitted to those peaks by the procedure this paper runs on the sky, it is 298.0 against the sky's 298.4, with the background fixed by the distance data alone. *A start placed by hand and fitted to the angle would report a different quantity*: what such a fit sets is the scale reported, not the spacing the spectrum carries, the two differing by four per cent.

The datum §4 states leaves two things to be fixed, and the handover fixes both. That datum is one amplitude per mode and a *common* phase; it says that the phase is common without saying which phase it is, and it does not say what the amplitude is flat in wavenumber *at*. At the branch point both follow: every mode is outside the horizon there, so the phase is an extremum with no velocity, and the amplitude is the frozen value the closed-form leg carries, $0.4835 \Psi_i$.

How much the comb depends on that choice is measured rather than assumed. Across the seventeen readings admitted by a four-peak criterion fixed before the numbers, the first peak spans 148 to 228—a factor of 1.541, and across the fifteen numeric-phase readings alone 1.118—with the spacing spanning 276.0 to 330.4, the phase intercept -0.4044 to -0.2161 and the alternation ratio 0.475 to 1.088. *Within that span position and alternation move against each other*, Spearman $\rho = +0.782$ at $p = 2.1 \times 10^{-4}$ between the first peak and the gap ratio, with every contracting reading sitting at $\ell_1 \leq 212$. *The single-locus reading is not inside that trade*: it returns the first peak at 222 and a contracting second gap together, which is what fixing the state at one locus rather than choosing a reading of it buys.

The instrument that would measure the rest is built, and its guard and its control are what make it an arbiter. Both arms run on one set of equations, so no comparison between them is a difference of machinery^{P15R63}. *The guard first, because it is what licenses the rest.* With every coupling to the potential removed at every site—the $4\Phi'$ in the photon, neutrino and cold-matter continuity equations and the $k^2\Psi$ in the photon–baryon and neutrino Euler equations—the source comb lands on the integers on *both* arms. *So the sound horizon, the measure, the wavenumber grid and the phase extraction are validated as an ensemble, and every departure from $n\pi/r_s$ in a driven run is the driving and nothing else.*

The control is the arm whose answer is known independently, and it reproduces it^{P15R72P15R107}. The photons are carried as a Boltzmann hierarchy with the polarisation multipoles alongside, the baryons given their own velocity and density contrast, and the source carrying $g\Pi/4$ and $(3/4k^2)d^2(g\Pi)/d\eta^2$. Run on the flat- Λ CDM arm it returns peaks at 220, 540 and 812 against the sky's 220.6, 538.1 and 809.8, and a first-to-second height ratio of 2.1969 against a standard code's 2.200—agreement to 0.14%, and within the sky's own uncertainty.

Two conditions on how such a transfer is run are what that agreement rests on, and the tighter of them is numerical. The projection must carry the polarisation source, which a damping envelope cannot supply at any coefficient; and the wavenumber integral must be carried past the highest multipole *reported*, since $\int P(k) \Delta_\ell(k)^2 dk$ is not converged there. *Each is worth a factor on its own and neither alone reaches the answer*: the height ratio runs from 2.721 at an ℓ -equivalent cutoff of 900 to 2.393 at 2400, so a cutoff set at the reported multipole is a systematic and not a rounding.

The perturbation sector runs on the leaf congruence, which is what the framework assigns it. A process running in the content—the sound horizon, the diffusion length, recombination, the perturbations—takes the leaf's rate (§2.4), while the comoving separations and the projection keep the stacking rate; the change is an exact chain rule between two monotone conformal times, so every spline and grid is untouched, and on the flat- Λ CDM arm the two rates are identical and the assignment is provably a no-op there—which is its own self-check.

The comparison is made on the polarisation path, in the configuration the control is calibrated in. There the control returns a first-to-second height ratio of 2.195 at peaks 220, 536 and 814,

against a standard code's 2.200—0.23%: *so the instrument is calibrated where this cosmology's number is taken, and that is the figure quoted for it, the closer 0.14% belonging to a different run and not to this one*^{P15R159P15R63P15R68}. Both arms are converged in the wavenumber integral. The control's own movement between cutoffs is 0.000% and 0.046% on the two height ratios, and this cosmology's arm does not move at all—0.000% and 0.000%—so the arm is converged at the lower cutoff and the figures below are not a truncation artefact. *The same comparison on the fluid path reads 0.042% and 0.036% against 0.000% and 0.045%: both paths converge, and the two sets of figures are not interchangeable. A rung below that was refused outright by the instrument's own truncation guard, on both arms, which is data and not an error.*

On that path this cosmology's arm returns the following, with the plasma handed over at the branch point and the background fixed by the distance data alone. The peaks fall at 222, 538, 818 and 1134 against the sky's 220.4, 537.7, 817.3 and 1123.9; the comb fitted to them by the procedure this paper runs on the sky is 298.0 against the sky's 298.4, and the phase intercept $\varphi/\pi = -0.2349$ against -0.2405 . The height ratios are $P_1/P_2 = 2.264$ and $P_1/P_3 = 2.298$ against the sky's 2.217 and 2.277. *The first three peaks agree with the sky inside the spread the locating itself carries, and the fourth is not resolved against it: located through one procedure with the likelihood's own covariance propagated, this arm sits 0.9 to 1.3 standard deviations from the measured fourth peak across the admissible window, so the data cannot tell the two models apart there*^{P15R162P15R178}. *That one procedure is a requirement and not a convenience, because the fitting window is a source of bias rather than of scatter: across the admissible windows the located peak moves by a fraction of a multipole at the first peak and by some six at the fourth, a wider fit on an increasingly asymmetric and damping-suppressed hump pulling its apex down the envelope's slope—and it moves the sky and both models the same way, so it cancels from a difference taken through one procedure and does not cancel from anything else. And what offset there is, is mostly not this construction's: both models sit high of the located sky, the control by 1.2 standard deviations and this arm by 2.1, with well over half of this arm's offset being the control's own. Two wavenumber cutoffs agree to every digit, and the positions are converged in the reported multipole grid: read on a grid of step 2 and refined to step 1, they move by a single multipole at the first peak and not at all above it.*

And the residual is neither of the two instrument faults a reader would reasonably suspect, because both are removed in this configuration: the wavenumber integral is carried past the reported multipole, and the projection carries the polarisation source rather than a damping envelope^{P15R70}. *And the truncation's removal is measured on the arm whose answer is known: it was 78% of the control's remaining χ^2 , and taking it out brings the control to 1.18 per degree of freedom over the full range against a reference 1.01*^{P15R89}. *The diffusion damping is derived on each arm's own opacity and rate rather than imported or fitted, and putting it back moves the height ratios by tens of per cent and drops the likelihood's floor by a factor of five without the verdict turning over*^{P15R69}. *The polarisation source pulls both arms by comparable amounts—the control by 8.2% and 20.8% on the two ratios, this arm by 10.9% and 26.9%—and nothing about either operation differs between the arms, which is what makes what survives them attributable to the source rather than to the machinery.*

Two likelihood configurations are quoted in this section and they are not interchangeable, so which is which is stated rather than left to be inferred. The full-range lensed one, on 185 bins, is the better-converged: it is where the control reaches 1.18 per degree of freedom against a reference 1.01, and it is the configuration in which an instrument fault can be told from a physical one. The 133-bin unlensed one is where the shape rejection is quoted, and its control sits at 2.10 per bin because the ceiling cuts the damping tail. *The second is not a worse measurement of the first's quantity: it is a different configuration, chosen for the comparison it makes, and the two sit beside each other rather than one superseding the other.*

The driving's size on the observable leg is measured rather than inferred, and its wavenumber dependence is known in closed form—the k -dependence living in the potential's gradient

rather than in its decay, with the turnover at a fixed multiple of the horizon scale^{P15R65P15R66}. *Subtracting the driving is what measures it:* removing every coupling to the potential moves the control's first peak from 220 to 274 and ℓ_1/ℓ_A by 0.1792, so the modes carrying the first peak are driven and the shift is the driving's size^{P15R164P15R77}. *Run on this arm the same subtraction gives 0.1717—the potential's grip within four per cent of the control's, and slightly weaker rather than stronger*^{P15R164}. *And this one is not path-specific:* the two instrument paths return the same shift to four decimal places, where the heights do not.

One of the two position statistics is not a projection quantity, and saying which keeps them apart. The ratio of the first peak to the acoustic scale is $\ell_1/\ell_A = k_1 r_s/\pi$ —the distance cancels identically—which is why removing each source term, the damping envelope and the visibility function in turn leaves it untouched. What it compares is the sound horizon each arm reports against the phase its modes actually accumulate. *Both arms integrate that horizon from $a \rightarrow 0$, the plasma being handed over at the branch point on this one and the control having no other start, so the comparison does not confound the rate with the start*^{P15R7}; and here the two agree, the comb at 298.0 against a reported scale of 302.9. *The two sides of that agreement are computed independently:* the reported scale reaches the transfer nowhere—no source term, no projection and no solver reads it—so the comb it is compared against is not a quantity it was used to set^{P15R162P15R177}.

And the likelihood is run, both arms scored on the same bins by the same code, with the amplitude fitted so that what is compared is shape. The result is still a rejection of this arm's spectrum and is stated as one. On the full-range lensed configuration— $\ell = 100$ –1996, 185 bins, the lensing carried by the same derived operator on both arms—the control returns $\chi^2 = 214.1$, or 1.16 per bin, and this arm 550.5, or 2.98 per bin: *the arm sits at 2.57 times the control's distance from the data*^{P15R163P15R67}. *That is the unfavourable of the two configurations and it is the one quoted,* the same comparison unlensed over 133 bins giving 279.4 against 556.7, a factor 1.98; lensing is worth proportionally more to a spectrum whose peaks are already in place. *The band-by-band comparison is even across the range — 1.70, 2.22, 4.23 and 9.29 per bin against the control's 0.77, 1.44, 2.62 and 3.73 over the four quarters from $\ell = 100$ to 1300, read on the unlensed configuration — so the disagreement is not one feature carrying the whole of it. And the spectrum's own parameters are refitted, which is the comparison the standard model is usually judged by.* With the expansion rate, the matter and baryon densities and the tilt free in each arm and the amplitude in closed form, scored on the full range and verified by running the spectra at the minima, the control settles at 1.01 in χ^2 per bin and this arm at 1.58: *the arm at 1.57 times the control's distance, where the computed spectrum sits at 2.56 on the same bins—so freedom closes about a third of the gap and leaves the rest*^{P15R169P15R162P15R166}.

What the refit does not move is the background. Given four free parameters this arm's expansion rate moves by 0.028% and its matter density by 0.031% from the values the baryon-acoustic distances and the acoustic angle fix with no spectrum involved: *the background the distances fix is the background the spectrum wants. And they are at a sharp minimum rather than unconstrained*—one-step excursions cost 2527, 740, 141 and 31 in χ^2 on the four parameters, which is the distinction between a parameter that does not move and one that cannot. *The one parameter that does move is the tilt:* this arm prefers 0.998 against the control's 0.954, bluer by 0.044, with the damping tail's leverage landing there and on the baryon density as the shorter range predicted it would.

One thing the ratio does not carry, and it is stated here rather than folded in. The two arms fit the same four parameters, so no information criterion separates them—penalties of about two per fitted parameter against a difference of some hundred in χ^2 —and the asymmetry between the frameworks is not in what was fitted but in what had to be fixed before there was a model to fit. *The standard model reaches flat Λ CDM by setting a curvature parameter to zero on inflation's authority, and uses the same added epoch to supply the coherent phases;* here the flat slices, the expansion law and the coherence are consequences of the construction (§2.3, §4)

and there is no curvature parameter to free. *And it runs the other way too:* both frameworks inherit the composition, the amplitude and the tilt, and neither derives the spectrum it is scored on. *Two axes, and no single number crosses them* [18].

And the phase intercept is not a residual at all, once the sky's own is located by the same procedure. Running one locator over the binned likelihood and both arms alike, the sky's intercept is -0.2378 ± 0.0099 on the first three peaks and -0.2448 ± 0.0074 on all four; this arm's is -0.2278 and -0.2445 . *So the arm sits inside the locator's own window-to-window spread on the one fit and on the sky's value in the other,* and the sign of the offset flips between them — *the shape of a difference carried by a single peak rather than a phase error*^{P15R171}. *What dissolves it is the sky's own locating spread and not a correction to the arm:* the binned likelihood cannot pin that intercept tighter than a hundredth across the windows the locator admits, and the offset is inside that range. *The spread quoted is the locator's movement across those windows on one realisation and not a noise level,* the covariance-propagating reading of the same quantity having been left unopened.

What remains is about one multipole at each peak, and it is not the damping envelope. Imposing the control's envelope on this arm moves the fourth peak by a seventh of a multipole against an offset of two, and the inverse operation returns the same displacement with the opposite sign, so the test is sound and the answer negative. *And read as the difference between the two arms, located sub-bin by the same procedure on each, the offsets are one near-constant multipole at all four peaks:* $+1.61$, -0.19 , $+1.07$ and $+1.31$. *That is the shape of a small common phase and not of a ruler or a driving error—*a constant displacement fits it half again better than a constant fractional one, which would have to grow from half a multipole at the first peak to two and a half at the fourth, and a driving error would grow faster still. *What each arm shares with the other is larger than what separates them:* both sit low of the located sky at the second and third peaks and high at the fourth, and at the fourth the control carries four fifths of the offset^{P15R191}. *At the spread the sky's own locating carries, one multipole is not distinguishable from none,* so this is a shape the comparison exhibits rather than a disagreement it records.

And what the rejection is made of is measured rather than described. Whitened against the full covariance, the two arms' residuals sit at a cosine of 0.855, and projecting the control's direction out of this arm's leaves 73% of it shared — stable across three bin cuts. *That fraction is not an attribution, and reading it as one would be an error:* both arms are fitted to the same bandpowers, so their residuals differ by the model difference alone and the fraction measures only how alike the two models are — a control deliberately tilted away from its own best fit, which nobody would defend, scores higher still. *What the decomposition does say runs the other way.* The control already fits these bins at 0.99 per bin, so there is no shared defect for this arm's misfit to be an amplification of; this arm exceeds it by 105 in χ^2 and the model difference alone carries 77 of that, so *the excess is this construction's*, and the factor of 1.3 between the two residuals' sizes is that difference's own size^{P15R173}. *Within it, position rather than amplitude, tilt or damping:* admitting one further parameter at a time, a peak-position rescale buys 4.7 in χ^2 , the damping 1.4 and the tilt 0.1 — and on the control the position direction buys nothing at all, so *the position part is this construction's*. It is small: the rescale is under a multipole at the fourth peak, and 4.7 of 283 is under two per cent^{P15R172}. *Amplitude, tilt, damping and position together do not account for the shape rejection:* they carry 5.7% of the model difference between them. *What does is a contrast difference,* and the sky's noise does not enter it.

Taking the realisation out is what makes the difference readable. With Δ the whitened difference of the two arms at their own minima, χ^2 decomposes exactly as $282.96 = 177.88 + 27.82 + 77.26$: *the model difference carries three quarters of the excess and the cross term a quarter,* so the rejection is not this sky's luck — set the cross term to its expectation and this arm still scores 1.43 per bin against the control's 0.99 on a typical sky. *And Δ is trough-dominated:* $+0.011$ at the peaks against -0.760 at the troughs, so the two arms agree about



Figure 2: Both frameworks refit on the same bins with the same freedom, against the measured temperature spectrum. *Above*, the acoustic range in D_ℓ , each arm at its verified refit minimum with the amplitude taken on the full bandpower covariance; *below*, the same on a logarithmic multipole axis from $\ell = 2$, so the discrete low-multipole floor and its minimum at $\ell = 4$ sit in one frame with the peaks — that panel’s floor being a reconstruction against the control’s own low-multipole spectrum, since the sweep carries it as a ratio. *Whitened residuals beneath each*. The peak positions and the spacing are the result to read in the upper panels; *the residuals are where the rejection lives*, and the control’s own are drawn beside this arm’s so the size of the difference is visible.

where the peaks are and differ between them. Split about a smooth envelope, the oscillatory part carries seven tenths of it and is peak-high and trough-low—*antisymmetric about the envelope rather than about each peak, which is a contrast and not a phase and not an envelope*. This arm’s acoustic oscillation is 1.040 times the control’s about its own envelope, and one direction built from the control alone—raise the oscillation at fixed envelope, with nothing fitted—carries half of $\|\Delta\|^2$.

Decomposed about its own envelope the excess is an amplitude and not a lopsidedness: splitting the band variance of the normalised oscillation at its zero gives 1.067 on the peak side against 1.056 on the trough side, and at the located extrema themselves the arm exceeds the control by 5.7 per cent at the maxima against 5.3 at the minima. *So heights and depths carry it equally*—and Δ ’s trough dominance is a property of the whitened residual rather than of the contrast, the two not being the same decomposition. *The trough depths are nevertheless where the excess becomes observable, and for a reason that is the sky’s rather than the model’s*: the arm exceeds the control by the same amount in each, +0.0106 in depth against +0.0103 in height, while the sky measures depth twice as precisely—so the same excess reads at 1.8 of the sky’s own spread in the depths and 0.9 in the heights. *And the depths are the one statistic in this comparison whose residual is not shared*: the control lands on the measured trough depths at five hundredths of a standard deviation while this arm sits 1.8 above them^{P15R192}. *That is a shape the data can see and not a detection*, at the spread one statistic carries; and the locating must be anchored to the comb rather than searched for, a free search under the same noise

returning a spread six times wider because it latches onto noise minima. *One systematic is stated rather than minimised:* the envelope’s abscissa moves the measured depth by about a third of that spread across the admissible acoustic scales.

And the three features this arm’s residual shows and the control’s does not are all Δ ’s: the peak-and-trough asymmetry, the $\ell \simeq 1000$ trough where Δ carries -1.074 of the arm’s -1.177 in fifteen bins, and the growth with multipole—which Δ does monotonically where neither residual does, a residual being Δ on a noise floor of order one that flattens it^{P15R174}. *The channel is identified and the cause is not:* the contrast direction is the balance between the monopole and the Doppler terms of the source, bracketed with opposite signs by removing each and re-projecting, on both instrument paths and with the same signs on both; and *neither deletion returns the two arms to a common contrast*, so what the bracket locates is where the difference enters rather than what produces it^{P15R175}. No mechanism for the imbalance is offered here. *And the neutrinos’ free-streaming, which the shape invites, is not the difference either:* removing it moves both arms’ peaks by the same amount—band by band the two agree to a fifth of a multipole, and in units of each arm’s own acoustic scale to two parts in ten thousand—while its large effect falls on the envelope rather than on the contrast. *A correction the two arms share cannot be what separates them*^{P15R177}.

And the trough-filling a contrast excess would be a shortage of is not short on this arm. Four channels carry that, each measured and each larger here. Deeper troughs are what excess baryon loading produces, through the displacement of the oscillation’s zero point—and measured against each arm’s own loading, *this arm’s monopole swings about a point that falls short of its own $-R\Psi$* , by an effective baryon density of -2.9 per cent, which is the wrong sign for that reading. And the visibility is *wider*, 43.6 against 38.0 Mpc, so this arm averages over more acoustic phase and not less. *So the channels that would each shallow the troughs are larger here*, and the same is true of the driving, whose measured grip is weaker.

And the Doppler term, which fills troughs, is stronger here: the dipole-to-monopole ratio of *oscillation amplitudes* at the visibility peak sits two per cent above the control’s and rises with wavenumber. *Which of two ratios that is matters, and the distinction is the physics rather than a convention:* trough-filling is an oscillating term a quarter period out of phase adding into another’s troughs, so *what fills a trough is an oscillating amplitude*, while the smooth part of the same field displaces the envelope and fills nothing. A ratio of band-integrated powers mixes the two and reads the opposite sign on the same spectra—*so the two readings are different quantities and not a disagreement about one*, and the one this comparison needs is the amplitude ratio^{P15R197}.

One channel does carry a definite share, and it is the first in this comparison that does. The source is weighted across the visibility by a function rather than a constant, and that weighting is not the same on the two arms: read in the phase the oscillation actually accumulates, the window’s spread is 0.0652 of the acoustic scale on the control against 0.0642 on this arm. *That the two are within a per cent and a half of each other is itself the two-rate structure, and it is a cancellation rather than an absence*—the arm’s visibility is fourteen per cent wider in conformal time while its phase accumulates fourteen per cent more slowly per unit of it, and the product of the two comes to within one part in ninety of unity. *Imposing one arm’s weighting on the other moves the contrast the way a narrower window should*, and the size can be read two ways that share no machinery: from the instrument’s own response to the weighting, which gives between a quarter and a half of the band excess above the damping scale, and from the direct substitution, which closes between a fifth and two fifths of it. *So the weighting is a real channel carrying about a third, measured rather than modelled, and from a quantity nobody chose.*

And it cannot be the whole of it, for a reason that is independent of every one of those sizes. The excess is symmetric about the envelope, heights and depths carrying it equally; the weighting is not. Imposed at the arm’s own size it delivers four fifths of the peak-height excess and one seventh of the trough-depth excess—a *five-fold asymmetry against a symmetric object*^{P15R193}.

A peak-weighted channel cannot carry a symmetric excess alone, whatever its share, and two further readings agree without being needed: the measured response extrapolates to a non-zero offset at zero wavenumber, where a window's own characteristic function is identically one, and a weighting large enough to deliver the whole excess moves the first peak by eighteen multipoles and the heights by nearly half. So what this settles is a share and not a mechanism.

A second channel carries the other half of the shape, and it is the term mix rather than the window. The two arms hold different fractions of their window's power in the monopole, and imposing one on the other at a coefficient solved from the profiles themselves—one constant to two per cent across every band—moves the contrast with the signature the long-wavelength offset needs: the response is independent of wavenumber, an intercept against a slope worth three per cent of it, where a window's smearing must die at long wavelength. It is the first channel measured to have that shape. And it is not the remainder either, for the same kind of reason the window was not: it is peak-weighted where what the window leaves is trough-weighted, it over-delivers the whole excess by between one and three times, and it moves the first two peaks the wrong way and outside the widths the sky's own locating carries^{P15R194}.

And the two together are what the measurement actually settles, because their shares do not add to what is observed but to something larger: a third from the window and above one and a half from the term mix make more than one and a half times the excess. How two such channels compose is then a measurement rather than an assumption, and it is made by imposing both on one control spectrum at the sizes their own comparisons solved, with neither coefficient re-chosen and no third channel admitted.

The rule is multiplicative. The joint response lands within a pre-registered tolerance of the product in every band and of the sum in every band, and of a quadrature combination in none of them—the last by three and a half times that tolerance, which is the one separation this measurement can make and the only one claimed. That the product and the sum differ here by less than a third of the tolerance was declared before the run, so they are not separated and are not reported as though they were. The pair is slightly sub-multiplicative and consistently so, below both the product and the sum in every band and above quadrature in every band. And the composed pair reproduces the two shares' arithmetic directly: what adding the separate measurements put at a little over one and a half times the excess reads, composed in one spectrum, within one per cent of that value^{P15R195}.

So the remainder left by dividing one response into the excess is a well-defined object, and the over-delivery is evidence about the sizes rather than about the rule. What does not survive is a size reading of it at all, and the reason is a shape. The joint response is the flattest thing this comparison has measured, and the excess is not flat: the pair over-delivers by nearly four times at the longest wavelengths and by under one and a half at the shortest. No coefficient on either channel reproduces the excess—set to match at long wavelength it falls short at short, and set to match at short it is an order too large at long—which is an obstruction of a different kind from a size discrepancy, because a size discrepancy is what a coefficient absorbs and a shape mismatch is not. And that reading is available only because the rule was measured: with the rule assumed, the same numbers read as a size a smaller coefficient could take up.

What the excess's own dependence on wavenumber is has then to be measured before it can be searched for, and the instrument is what has to be measured first. Six forms injected into the control's own spectrum, two of them carrying a scale, are recovered to about a per cent. But the estimator manufactures structure between bands: its bias varies from band to band by about a per cent while the six injected forms agree with each other on that bias seven times more closely, so a contrast that is constant reads as a wobble, and band ordering at the per-cent level is a property of the statistic and not of the spectrum. One alternative anchoring is excluded by its mechanism rather than by its number: a median envelope returns a value three times larger, and the tell is that it does not move with its own smoothing window—at short wavelength the running median collapses onto the curve it is meant to be an envelope of, a median of a locally

monotone stretch being its central value whatever the window. *So the rise is real and the wobble is not*, and the distinction is established on the instrument before anything is concluded from it^{P15R196}.

And the rise decelerates within the statistic as defined, which excludes the form this comparison's own statistics are written in. A departure growing linearly in the squared wavenumber is rejected—the only one of the six so rejected—and every concave form is admitted with none preferred among them, so *the direction is settled and the functional form is not*. No scale is separated from another either, and the spread that comparison is judged against is the fit's own injection-and-recovery error rather than a noise level. *And two things about that deceleration are stated here because a reader would otherwise assume both.* It is robust within the statistic—negative under every variation of the envelope's width, the band edges and the sampling—and *it is carried by the lowest band alone*: with that band set aside the sign is not determined at all, the deceleration being that band lying low rather than the upper bands bending. *And it does not survive a change of envelope*: a running median in place of the arithmetic one, with everything else held, reverses it. *That is a different statistic and the difference is measured*—the median absorbs about half the highest band's oscillation on both arms, so its ratios are formed on a much smaller residual—but *it is not on its face the worse one, since it leaves a departure of zero mean where the other does not*. So the sign of the curvature belongs to the statistic and not yet to the excess^{P15R200}. *And the rise is a preference over flatness rather than an exclusion of it*, which is stated because the difference matters: a constant departure is a worse description, not an impossible one. *The consequence for the numbers above is that a slope read against an intercept is a description and not a model*, and the growth of the departure itself is the scale-free quantity that comparison needs.

Read with that quantity, the search this comparison can run in the positive direction leaves exactly one candidate standing. The excess's departure grows by a factor of three and a half across the range with negative curvature, which gives two conditions rather than one, and *the source terms and the three channels with measured shares all fail the first*: they are flat where the excess grows. *The dipole's amplitude ratio does not*, and the range over which that can be said has since been extended by an estimator built for it: holding the oscillation's period and fitting its amplitude and phase, rather than reading an amplitude off a window, reaches well below the window estimator's floor. *Its own first finding is that the period is not the period*—set by construction to one value, it runs about two per cent short of it in the fields and by a *different* amount for the two of them, so the period is measured per field and per arm rather than assumed. *And it is validated before it is used*: the two estimators agree on the mean where both are sound, and where the window estimator does not survive its own width—its ripple running from under one per cent to above ten as the window narrows—the held-period one stays near two and a half per cent at every width. *The one cost it carries is measured rather than noted*, and it is half a per cent of the dependence being measured, for a mechanism: the fit re-fits the phase in every window, so an error in the held period is absorbed there and costs only a common amplitude factor, which cancels in a ratio of ratios.

On the range that unlocks, the candidate's departure is positive in every band as the target's is and grows faster, so it passes both of the conditions that can be applied to it. And it stops where the fields stop rather than where the method does, at a floor that is exact and was named before it was used. An oscillation's amplitude is identified at a point only if the window holds a turning point on either side of it, because across a span with no turning point the held-period pair is monotone and the baseline already spans it. *The monopole has no turning point below its first*—the first excursion is one-sided—and *the monopole is what binds*, putting the floor well above the lowest band, which lies far below it while every other band lies entirely above. *And the floor is the fields' and not the window's, shown three ways*: the same widths spread four times as far below it as above and change sign there; sweeping the window's edge, the departure is negative for every window that opens past the monopole's first turning point and positive

for every one that stays above it, *what lies below being the field's rise from its initial condition rather than an oscillation at all*; and every centre below the floor spreads more than every centre above it, which the floor was not fitted to. *So no estimator of an oscillation amplitude can reach inside the first excursion*—an acoustic oscillation has a first extremum, and before it there is no amplitude because there is no oscillation^{P15R199}.

And the condition that would decide cannot be applied, for an exact reason rather than a statistical one. The excess decelerates across the full range, and *that deceleration is carried entirely by the one band no estimator of the candidate can reach*: removing that band alone reverses the sign of the excess's own curvature, while removing any other single band leaves it where it was. *So the filter is out of conditions rather than the candidate out of chances*—the candidate's own curvature is stable there, and what is missing is the target's sign and not the candidate's number. *That is a statement about the filter, and it was one of the two outcomes written down before the estimator was built*^{P15R199}.

And the way that condition is unavailable is worse than a simple absence, which is worth stating plainly. It needs a value in the band the fields close, and that band is shut to amplitude estimators but not to a candidate computed from the projection's kernel—which had one, and which the condition duly excluded. *So the filter's full strength is available exactly for the class that cannot carry the excess, and its third condition is permanently unavailable exactly for the class that can*, because what fills a trough is an oscillating amplitude and that is what closes the band.

Which leaves the question of what a two-condition filter is, and the answer is that it is what it always was. As a device for excluding it has lost nothing: each remaining condition is necessary, and every exclusion this comparison has made was made on growth alone. *As a device for confirming it was never one, with three conditions or with two*—all three are conditions on shape, and the surviving candidate matches the excess in sign and in direction of growth while being several times too small at the highest band. *So the question this comparison now carries is the coupling and not the shape*: a quantitative question, living where the candidate is measured, and needing the closed band not at all.

That coupling is measured, and its sign comes out the same everywhere. Scaling the Doppler source across three banked spectra gives the contrast's response as a finite difference—*three points, so linearity is checked rather than assumed*—and the response steepens towards the unscaled value, so the slope there is both the applicable one and the one taken over the shortest step. *It is negative at every band, on both envelopes, over every interval*: forty-two readings of the sign and not one positive. *Which is this comparison's own trough-filling physics read forwards*—more of an oscillating term in quadrature fills more trough and lowers the contrast.

And the construction fixes it, shown by what fails to change it. The control's own ratio of that term's band power to the monopole's runs across a factor of more than six from the lowest band to the highest, and *the coupling's sign is the same at every one*. *A quantity whose sign is invariant across a factor of six in the very ratio it depends on is not set by a knob*: the knob is the probe and not the setter, so the size is a prediction rather than a fit.

And it is measured on the arm itself rather than carried across from the control. The decomposition the instrument already writes resolves each spectrum into its bilinear terms multipole by multipole—ten of them, summing to the spectrum to a part in 10^{15} —and their scaling in the source amplitude is exact, quadratic on the term's own square and linear on each of its crosses, so the response follows analytically on either arm rather than from a difference of runs. *It runs from -0.48 to -0.86 across the bands, the two arms agreeing to a few per cent and each agreeing with the finite difference above to better than a tenth—the same quantity reached two ways, on the arm's own spectrum.*

The contribution the coupling multiplies is then read by a swap rather than by a product, which is what removes the ambiguity in its input. Replacing the arm's four Doppler-carrying bilinear terms by the control's, envelope-scaled and on the arm's own grid, gives the share of the

excess those terms carry as a ratio of contrast differences—the same operation the instrument already sanctions for the clock, and with no coupling-times-amplitude product anywhere in it. The answer is a minority share on either envelope: from a per cent to a quarter of the excess against the arithmetic envelope, and from a tenth to a half against the median one. So the Doppler term is a real contributor and it is not the carrier.

And the share grows with wavenumber while being sign-indefinite at the bottom—negative at the second band on both envelopes—so at the bands where the excess carries its own structure it changes sign rather than settling to a share. Which is exactly how far the envelope ambiguity reaches: the coupling’s sign survives both envelopes at every band, so the contribution does not reverse with the statistic, while the share’s magnitude moves by about a factor of two between them—so the share inherits that ambiguity where the sign does not^{P15R202}.

And the excess every candidate here is measured against has one dominant feature, which is a step and not a trend. Its lowest band is a fraction of the mean of the others and sits below them by nearly five times the spread the upper bands themselves show about their own trend, while above that band a constant already fits—a line adds a mild slope and halves the residual and no more. So the bands above the lowest carry very little structure with which to tell a flat candidate from a rising one, and that stretch is where every shape comparison across wavenumber is made: a flat candidate matches the featureless part and misses the step, a rising one matches the mild rise and misses the step, and across those bands the two are barely distinguishable.

That the step is the excess’s own and not the statistic’s is established before anything is read off it, and by a reading that uses no statistic at all. Three running envelopes differing in kind—an arithmetic mean, a median and a local quadratic—and a fourth quantity that needs no window whatever, the peak-to-trough depth of each acoustic cycle, all put the lowest band below the rest, and none of them puts it near parity. What the window-free family settles is the step’s freedom from the statistic and not its size: in the lowest band it holds a single half-cycle transition, the first locatable pair of extrema lying above that band’s lower edge, so what it returns there is consistent with zero and equally with no step at all—unresolved rather than small. An extremal envelope built from located extrema alone reaches only a quarter of that band, rests on the same single extremum below the step and interpolates across it. So the size is read from the statistics that resolve the band, and on every one of them the lowest band runs between a third and two thirds of the rest—a range because the statistic moves it, and a range that excludes parity throughout. And the one artefact that could produce a step at the lowest band is excluded in the direction that excludes it: the band’s envelope comes within five multipoles of truncating, and moving the band’s lower edge away from that truncation makes it read higher, where an artefact of truncation would have to make it read lower.

Located rather than merely noticed, the step sits at the second acoustic peak. Its half-rise point, taken in sliding windows at three widths, is stable to better than a per cent and lands within about one per cent of the second peak on either arm, where the nearest other scale this construction fixes is seven times further away; and it is sharp, a clean factor of two on all three widths reached within about a tenth of a comb period—narrower than the narrowest window that resolves it. So the excess in the first acoustic cycle runs between a third and two thirds of its size in every cycle above. What that locates is not a length belonging to this arm: the peaks sit at the same wavenumber on both arms, so the step says that the first acoustic cycle behaves differently rather than that some new scale has entered.

Scored against that feature rather than against a trend, every candidate in this comparison is evaluable, and between them they carry a minority of the step. A candidate’s step is its lowest band’s departure from the trend its own upper bands set, read on four bases—linear and logarithmic, in the wavenumber and in its square—with a departure counted only where it survives all four. The window weighting steps the wrong way, upward by about half, working against the step rather than making it; the term mix steps the right way at some two thirds

of the excess's own departure; and *the pair as actually composed*—one spectrum with both coefficients at the sizes their own profiles solve—*carries about two fifths of the excess's own step*, exceeding twice that same upper-band spread on three of the four bases; the share is against the excess's own extrapolated size and not against the larger step the arms have in common, the two denominators differing by about a factor of six on the one departure. *The projection width carries none, and the basis family is what shows why*: being linear in wavenumber to a few per cent of its own range, it flips sign across the four, so a logarithmic basis would manufacture a step for it. And the Doppler contribution, read at the lowest band by the swap above, changes sign repeatedly in sliding half-period windows with means on either side of the step equal and both near zero—*scatter at the step's own resolution, and no transition at all*. So against that statistic the step has a partial account: no single channel produces it and two of them together reach a minority of it.

Scored instead on the differential estimator—where the shared nine tenths never enters and only the part belonging to this cosmology remains—the same channels read differently, and the accounting does not survive the change. Each knob is read there as it must be, by the width of its own difference from the control, against the arm's. *The window weighting steps, and steps the opposite way to the arm; the term mix no longer steps at all* at that resolution, where against the mostly-shared quantity it reached two thirds; and *the realised pair changes sign across the bases and measures zero to within its own scatter*, where against the mostly-shared quantity it reached two fifths. So a channel that accounts for a substantial share of a quantity nine tenths of which is common to both cosmologies accounts for nothing of the part that is this one's. *The weaker word is the supported one*: those two are not resolved on the differential estimator, which is not the same as being excluded.

And they cannot be resolved by the family of statistics this comparison is built on, which is a statement about that family proved over its whole reach rather than inferred from a failure. A channel is decided when its own departure at the lowest band exceeds twice the scatter of its upper bands, so the smallest share of the step a channel could carry and still be decided is a computable floor. *Every route this construction can take to lower that floor was taken*: both aggregations of the width, both pairings of the two arms' multipoles, a wider span of bands and a finer division of the same span. *The floor does not move below three fifths of the step, where the two channels carry about a third and about a thirtieth*. And the reason it does not move is worth the sentence: the phase-insensitive aggregation lowers the scatter by the factor predicted and lowers the signal by the same factor at the same time, so a reduction in scatter is a gain only where the signal does not fall with it. More of the same statistic would therefore decide nothing.

Nor would it, for a second and independent reason. Of the three channel readings, only the one that steps the wrong way holds its sign across every aggregation; *the other two change sign between two legitimate aggregations of the same statistic*, so their departures are not established quantities that a sharper measurement would sharpen. *What is demonstrated is accordingly narrower than that the channels do not produce the step, and narrower is what is earned: no statistic of this family could tell whether they do*^{P15R207}.

And the family is what the limit belongs to rather than the comparison, because the likelihood these spectra are confronted with does not share it. Its bins are a thirty-fourth of a comb period where every statistic above averages over seven tenths of one, two dozen of them fall inside the lowest band, and its bin-to-bin correlation is a flat floor rather than a coupling that grows across a period—*so it bins without banding, and it does not inherit the width limit through its covariance either*. Read band by band from its own bins, the two arms are distinguishable everywhere, and at the lowest band the step appears in that distinguishability—standing where its upper bands' trend predicts half again as much, with the same sign as every other reading of it and with the instrument's own noise for an uncertainty rather than a scatter taken across a noiseless theory spectrum. *And the two channels separate from each other there at some*

twenty-five standard deviations, which is the measurement the banded family cannot make at all. The two floors are not one number and neither bounds the other—one a share of the lowest band’s difference under real instrument noise, the other a share of the step under an empirical scatter of a noiseless spectrum—so what compares is the verdicts: the banded family cannot separate the channels there and the likelihood separates them^{P15R208}.

But what the data can distinguish and what it rejects the arm on are two quantities, and at the lowest band they part company completely. Of the excess in fit that the covered bands carry between them, the lowest band holds under one per cent—and that share changes sign as smooth global shape is absorbed into free coefficients, where every band above it holds to within a few per cent of its value. So the step is not a distinct feature of the residual and not the shape rejection read locally either, the shape rejection being barely present there at all: it lives in the upper half of the range, where four bands carry between them some six sevenths of the total. That location is read off an exact decomposition and not a per-band approximation: because the two arms’ residuals differ by the difference of the spectra, the excess is identically a term in that difference alone plus a term coupling it to the control’s own residual, and the two reproduce the total to a part in 10^{13} . And the split is the distinction itself written as algebra—the first term never asks where the data sits and the second is the only part that does—which is why a quantity can stand at some twenty-five standard deviations in the one and at nothing in the other. Which puts the comparison’s own structure and the data’s own verdict in different places—the excess’s one prominent feature across wavenumber sits where the rejection is cheapest, and the rejection sits where no smooth shape across wavenumber finds anything at all.

But the rejection is not a level there, and what it does carry is acoustic. Across the individual bins those four bands hold, a constant accounts for none of the scatter, a trend for under a fiftieth of it and a quadratic for under a thirtieth—and a projection at the comb’s own period is reached by none of two thousand draws of the instrument’s own covariance carried through the same statistic, nor by any of twenty thousand when they are pooled. The period it sits at is fixed only to the resolution the range allows: the peak spans periods 0.88 to 1.19, which is the acoustic period to within the resolution of the two and four fifths periods of data the bands cover, and not to a hundredth of it.

And no banded reading of that stretch can find it, which is not attenuation but a limit of representation. One number per band at seven tenths of a period spacing has a Nyquist period of twice that, so a modulation at the comb period lies beyond what such numbers can represent at all, and the averaging inside each band passes barely more than a third of it before that. The likelihood bins thirty-four times finer, at a Nyquist period a twentieth of the comb’s and a transfer indistinguishable from unity at it—so the instrument that rejects the arm is the one instrument in this comparison that can represent what the rejection carries, and the limit that closed the lowest band is the same limit, met at the other end of the range^{P15R212}.

And the modulation is a fact about the data rather than the difference looking at itself—the difference is a comb, so the question is which term carries it, and five sixths of it comes from the term that couples the difference to the control’s residual against one sixth from the term in the difference alone. The first clears the same noise null and the second has no noise in it to clear, being a property of the difference and not of the data^{P15R210}.

Scored in the metric the step does live in, every candidate departs the way the arm does. Read as each channel’s own lowest-band departure from the trend its upper bands set, in the likelihood’s units, the window weighting delivers about a third more than the arm’s, the term mix about six sevenths of it, and the pair as actually composed about half—the first time this comparison has held candidates that depart the arm’s way on an instrument able to carry the question. And the window weighting’s verdict differs between instruments, going the wrong way on the differential estimator and the right way here, which is reported as a disagreement between instruments rather than resolved into a story. The pair again falls well short of every composition rule, product, sum and quadrature alike, delivering about a third of the closest.

And what that costs the account belongs in the same breath as the shares: these are shares of a departure in what the data can distinguish, and that feature carries one part in a hundred of what the data rejects the arm on^{P15R209}.

Scored instead in the metric the data's own rejection lives in, the channels sort differently, and one of them sorts the right way. Read across the four bands that carry the rejection, the term mix delivers about four thirds of the arm's cost *and delivers it where the arm's falls*—the two patterns correlating at seven tenths band by band, on a regression slope of three quarters, with nearly half the arm's cost left unexplained. *That is the first channel this comparison has held whose cost is in the right places at all*, and it is neither the carrier identified nor no carrier found: *four thirds of the cost at that correlation is not the absence of a quantity, and half of it misplaced is not the presence of one.* The window weighting is the contrary case, and its small share is the wrong reading of it: its cost is anti-correlated with the arm's at seven tenths, so it is a different cost and not a small share of the same one—the reverse of its standing on separating power, where it led. *And the pair as composed matches worse than the term mix alone*, raising the total while degrading the pattern, *which is the sharpest form in which this comparison can say that a total is not a match*: any spectrum that is not the control costs something, so what separates costing the arm's way from merely also being rejected is the pattern and never the share.

Whether that channel carries what the cost is made of, as against carrying the cost in the right bands, is a second question, and against the instrument's own noise the two do not come apart. Projected at the comb period and scored against two thousand draws of the covariance through the same statistic, the channel's own cost is reached by no draw, and neither is the part of the arm's excess the channel does not explain—the latter at the arm's own phase to within a sixth of a radian. The part the channel misplaces is reached by none either, and is not quoted with them. *The statistic quoted is the tail count and not the ratio to the ensemble's largest value*, that maximum being itself a noisy quantity whose spread across seeds is about a tenth, where the tail count is stable and holds when the draws are pooled tenfold. *The channel's own clearance is carried by the term that knows where the data sits*, its other term being one the null holds fixed and therefore one no draw could have made it fail. *So every piece of this decomposition is acoustically modulated, which is what a detection test can establish here and is not what authorship needs—a knob that moves the balance of two oscillating source terms produces an oscillating cost by construction, so clearing a noise floor does not distinguish a carrier from a participant.* A null built instead from the same data at neighbouring frequencies cannot be used for the question at all, its amplitudes carrying the feature they are meant to score: over this range such an ensemble spans only about three independent draws, and its largest values run twice those of the instrument's own noise^{P15R213P15R211P15R212}.

And the anti-correlated channel is combed too, in antiphase, which locates the reversal without naming it. Its own cost projects at the comb period above its null with a phase π from the arm's to within a 0.021 rad of π , so it is a structure and not a smooth offset. *Yet the two channels' modulations in the spectra themselves are in phase*, each a quarter to a third of a radian from the arm's, and the smaller one's amplitude predicts the larger's to within about an eighth from that ratio alone—*so the magnitude composes and the sign does not, and the reversal appears only after the likelihood's own weighting is applied.* What that is not is one structure read with two signs: the window's spectrum difference is not a negative multiple of the arm's, the residual of the attempt keeping almost all of the window's power^{P15R211}.

The accounting that would settle authorship closes exactly and still cannot attribute, and the reason is an identity rather than a want of precision. Writing each channel's modulation as a vector in the plane the cosine and sine of the comb span, the channel's contribution and the residue left after it reconstruct the arm's own vector to numerical precision—*so it is an accounting and not an estimate.* But the share a least-squares projection returns in such a plane is the cosine of the phase offset and nothing else: it depends only on the direction the channel

points and not at all on how large it is, so a channel a millionth the size scores the same. And the anti-correlated channel is the proof rather than an illustration—pointing π from the arm it is assigned essentially all of the authorship, at a negative scale that turns its own cost upside down to reach it. A quantity that credits a channel with the whole of a feature for pointing the opposite way is not measuring authorship. The other available scale, the ratio of the two modulations in the spectra themselves, fails differently and by measurement: it predicts the realised amplitude for one channel to about an eighth and misses for the other by more than that channel's whole size. So one scale falls to algebra and the other to measurement, and neither failure is the other one twice.

And the second scale has no statistical content to appeal to, which closes the last route. The difference between the two spectra moves with the data only through two fitted amplitudes, so a share or a phase read at that level is a property of the two theories with a systematic uncertainty and no statistical floor at all—the same thing the contrast statistic is, and for the same reason. At the level of the fit the floors are finite, about a twentieth of a radian in phase and a few per cent in ratio, but it is there that the projection is amplitude-blind. And the degeneracy is exactly dimensional: two channels span the plane, so any two of them reconstruct the arm exactly and do it as arithmetic. So what this comparison leaves is a discrepancy whose size, location, period and shape are measured and whose carrier no instrument it holds can attribute—and what attribution would take is named rather than awaited: a channel independent of the plane these two span, or an estimator that uses the channels' amplitudes where those amplitudes carry statistical content. Neither is a refinement of the instruments above, which is why the question is recorded as located rather than open^{P15R215P15R216}.

And the step does not compose the way the contrast does, which is a property of the step rather than of the knobs. The contrast composes multiplicatively, measured band by band. On the step, the two channels' own departures put a product, a sum and a quadrature all at a large positive value where the realised pair measures zero to within its scatter on the phase-dependent aggregation, every rule several scatters away—so on that reading the two very nearly cancel on the step where they multiply on the contrast. The cancellation is a property of the reading and not of the pair, and that is measured rather than left open: it vanishes within its own scatter on every basis of the phase-dependent aggregation and on none of the phase-insensitive one, and in the metric the data's own rejection lives in the two channels add, the realised pair standing at the sum of the two singles to within a fiftieth—so of the three metrics that can carry the question, two show the cancellation and the third shows the contrary, which is what makes it the reading's property and not the pair's. The residuals are quoted in departure units against that scatter and not as a share, a fraction of a near-zero measurement being no fraction at all^{P15R206P15R210}.

What remains to be explained is accordingly what distinguishes the first acoustic cycle from the rest^{P15R204P15R200}.

And the step is very largely common to the two arms, which is the decomposition that says where it belongs. Read on each arm's own contrast against the trend its own upper bands set, with no reference to the other arm, both arms step upward at the lowest band—on all four bases and on the windowed and window-free contrasts alike—and this arm's step is always the shallower, by about a tenth and no more. So roughly nine tenths of the step is shared and cancels in the ratio, and the excess's step is the part that fails to cancel: the feature belongs to the acoustic physics the two arms have in common, and what this cosmology contributes is the small residual—which is also why the step's location is the same wavenumber on both. That residual is readable because the ratio is smoother than either spectrum, standing at some seven times its own upper-band spread where each arm's own step stands at four. And a small residual of two large common features is exactly where a nearly-common systematic would sit, so the feature is read again on an estimator that is differential by construction rather than a difference of two large numbers^{P15R204}.

On that estimator it survives. Dividing the two spectra multipole by multipole before any width is taken leaves the common oscillation cancelled rather than subtracted, so the quantity read is the width of the *difference* of the two arms' oscillations and the shared step is never formed: the lowest band's departure is negative on all four trend bases, on both pairings of the two arms' multipoles, and on both aggregations of the width—a *band's own dispersion and a held-period amplitude, which are not the same quantity because a band spans less than one full comb period and its dispersion is therefore phase-dependent by construction*—the two differing by about a third in size and neither chosen. *So the part that fails to cancel is not an artefact of forming two large numbers and differencing them—and the same construction shows which step of the two it belongs to:* dividing instead by a smoothed control removes the differencing while keeping the division, and the departure turns positive, back toward each arm's own.

And the width of a difference is fed by a relative phase as well as a relative amplitude, so which of the two it is has to be settled rather than assumed—and it is settled by an identity. For two oscillations of the same period the width of their difference is a closed function of the amplitude ratio and the phase offset alone, and that function reproduces the measured difference pointwise, so the split into an amplitude-only and a phase-only part is exact rather than fitted. *Split that way, the step is the amplitude's:* the amplitude-only term carries almost all of the statistic at the lowest band and steps with the same sign, while the phase-only term steps the other way. *So the first acoustic cycle is weakened in this cosmology rather than displaced in it.* What the split does not settle is the *phase channel's size:* the relative phase is a fraction of a degree, an order of magnitude below the relative amplitude, and its step reverses sign as the reading window widens where the amplitude's does not—*so the phase term sits at this estimator's own resolution and the honest statement is the sign without the share.* Read against the comb over several periods rather than locally, the relative phase is determined to a few tenths of a degree, at seven times its stretch-to-stretch standard error—and the lowest band still cannot be reached that way, being narrower than the period the method needs, so a projection across it leaks the baseline and is both noisier and biased. *Against a control of stretches matched to its own width the lowest band's phase sits inside one and a half scatters, where against the wide-window error bar it would have read five—so the phase step is not resolved and the amplitude reading is the complete account rather than a verdict on the sign alone.* That the lowest band is narrower than every period this comparison measures with is now the same limit met in three places, on the window-free family, on the amplitude-and-phase split, and here^{P15R207P15R206}.

The shared part, for its own sake, does not reduce to one term of the source. Removing each bilinear term of the decomposition in turn and asking whether the step leaves with it, the fractional losses sum to nearly twice the whole—*so the step is a property of the sum and no term carries it.* What the same table does show is that *leverage is not flat:* weighted by how much of the step each term accounts for against how much of the oscillation it holds, the two leading terms are both Doppler—one at more than five times its weight and one at nearly four—where the monopole holds seven eighths of the oscillation and carries the step at less than its weight. *The ordering is not simply Doppler against the rest,* one Doppler cross term telling against it and the integrated Sachs–Wolfe autocorrelation lying lower still. *So a step-weighted reading of the source points at a sector where an amplitude-weighted one points at the monopole—a ranking and not an attribution*^{P15R205}.

One whole class is excluded by structure rather than by measurement, and needs no run at all. Every quantity that belongs to the two clocks—the leaf clock, the ruler, the Jacobian between them, the visibility and the optical depth—is a function of conformal time alone, and a function of conformal time has the same value at every wavenumber. So it cannot vary across one. *That is neither measured-and-failed nor unmeasured:* it is a statement that the class cannot carry the effect, from the shape of the objects in it.

And the projection itself holds a width nothing in this construction has ever imposed, which is where the row's own name has pointed since it opened. Two widths govern the last-scattering

window and they are not the same width: *the acoustic phase swept across it* goes with the window's width measured in the leaf sound horizon, while *the projection's own smearing* goes with its width measured in conformal time, that being what the projection's argument carries. *In a one-rate cosmology those are one object up to the sound speed; on two rates they are not, because the clocks differ. And the difference between them is one object and not a residue:* the two sound horizons on this arm are related pointwise by the Jacobian between the two rates, checked across the window to a part in a million, and identically unity on any single-rate cosmology. *Measured against the ruler clock the two arms are the same instrument—their windows agree in width to a few parts in a thousand on either definition, the visibility being laid down by scattering on the physical background, which is the same physics on both. Measured against the leaf clock the arm's window is some fourteen per cent wider, and the whole of that is the Jacobian,* the arm's own leaf-to-ruler width ratio reproducing the Jacobian's mean to a fraction of a per cent. *Which quantity a width is has to be said before the number means anything:* a root-mean-square width returns half as much, because the window has long tails that it weights and that neither the projection nor the phase sweep responds to, while the full width at half maximum and the characteristic function's own half-fall agree with each other to better than a hundredth of a per cent.

So the different ratio is a prediction of the two-rate assignment rather than a property of this instrument—the Jacobian carries no free coefficient and is fixed by the background solution once the arm is specified—and the ruler clock is what establishes it, the two arms agreeing there being what leaves the leaf-clock difference nowhere else to come from. And it cannot be imposed as a knob, which follows from that same identity rather than from the instrument's limitations: giving the control this arm's conformal width at the same leaf width is giving it this arm's Jacobian, and a control carrying the Jacobian is not a control.

Applied in the projection's own kernel instead—holding the source's phase and stretching only the projection's argument—it is a real channel whose size the statistic does not fix and it is not the carrier. Its share depends on the anchoring by an order of magnitude: in the band where the excess is largest it delivers about a quarter of what the excess needs on the mean anchoring and about a fiftieth on the peak anchoring, so the quarter is one of the two readings and not the channel's size. *What both readings agree on is the sign of its wavenumber dependence,* and it is the wrong one—it accelerates across wavenumber where the excess decelerates, under either anchoring. *So it is excluded as the carrier on its shape rather than on its size, and the size is left as the range the two anchorings give. And the width ratio is a second reading of the Jacobian rather than a restatement of the first:* the comb reads its *cumulative* value at last scattering, which is what sets the peak spacing this paper already matches, while the widths read its *window-local average*—and the two differ by about a third. *So a construction tuned to the comb must still return the right local Jacobian to match the widths,* which is a second and independent demand on the same object, with neither carrying a free coefficient and both identically unity on a single rate. *What it is not is separately observable:* the width the damping reads differs between the arms by under a per cent where the width the projection reads differs by more than ten, and the projection's own contrast effect is bounded above at about two per cent with its sign undetermined^{P15R198}.

One thing about the statistic belongs with those numbers, because without it none of them can be read. The anchored contrast is measured against a running-mean envelope that is recomputed for each spectrum, so a purely symmetric change of amplitude does not read as unity on it: applied to the control's own spectrum, amplitude and envelope operations both read near two, a loading below one and a smearing negative, and the near-two is stable across a fivefold range of sizes. *So the baseline against which a class is identified is that value and not one,* and read against it the anchored statistic and the band-variance split of the excess agree to about a tenth—the same decomposition reached twice rather than two readings in tension. *And the baryon density cannot supply the contrast at any value:* its response to ω_b saturates, spanning

0.028 over the whole range with increments falling monotonically, so four per cent is beyond its reach rather than away from its fitted point^{P15R176}.

And what kind of statement this statistic makes is worth saying once, because every number above inherits it. The amplitude it fits to the data cancels exactly against the envelope it divides by, *so as defined it compares two computed spectra and reads no data at all*: its floor is numerical, at some six parts in a thousand, and every spread quoted on it above is a spread of computed quantities rather than a noise level. *Its sky counterpart is a different instrument and carries a real floor*, built by running the same statistic on noisy realisations of the control against the control through the likelihood’s own covariance: across the whole range that floor is 0.018, against which this arm’s +0.047 stands at about two and a half floors. *Read one band at a time it is coarser than the excess it would measure*—between 0.043 and 0.086 per band, where the excess’s own per-band values run from +0.022 to +0.076, *so band by band the contrast is a statement about theories and would not be an observation*, the lowest band’s value standing at under half of that band’s floor. *Which is why the rejection this section closes on is read in the likelihood and not here*: the whole-range contrast is what this instrument supports, and the band-by-band structure is a property of the computed spectra that the sky’s own noise would not resolve^{P15R214}.

Those four channels all act on the source, and the contrast difference is not in the source. The same statistic that reads 1.047 on the reported spectrum reads 0.996 on the source at last scattering and 0.992 on the η -integrated source, over four envelope windows, both envelope definitions, three term subsets and with or without the k -measure—the source rungs spanning 0.971 to 1.005 and the multipole rung 1.042 to 1.052, against a floor of 0.6 per cent set by the statistic’s own bias on a known injected contrast. *So the difference is made between wavenumber and multipole*, and in wavenumber this arm’s relative oscillation is if anything the shallower of the two—which is the direction all four channels point, and is why none of them has anything to overcome. *The stage is located here and the mechanism is named below*: within the projection, this arm retains 1.054 times as much of its own source oscillation as the control does, the excess rises with multipole where the source ratio is flat, and it is neither the visibility width acting before the kernel, nor the lensing, nor the binning, nor the two arms’ different samplings of wavenumber—replacing this arm’s physical ladder with the control’s uniform grid at the same mode count leaves the multipole rung unchanged. *Nor is it the distance*: the two arms’ comoving distances to last scattering differ by 0.449 per cent with this arm’s the larger, their acoustic angles agreeing to 0.085 per cent, and projecting either arm’s own source through the other’s distance moves its contrast by under a per cent—in the direction that makes the difference larger rather than smaller^{P15R185}.

Nor is it one term of the source, nor the interference between two. Decomposing the projection bilinearly—one transfer per source term, so that $C_\ell = \sum_{a \leq b} w_{ab} \sum_k P \Delta^a \Delta^b$ closes on D_ℓ to one part in 10^{15} —*deleting the monopole–Doppler cross term moves the contrast ratio from 1.0452 to 1.0451*, its carry running -0.0013 to $+0.0008$ across four envelope windows. *Each piece separately already carries the excess instead*: the monopole at 1.034, the Doppler at 1.099 and the polarisation at 1.058, against the full spectrum’s 1.045, while every term’s source ratio is at or below 0.992—*so the projection raises this arm’s contrast on nearly everything it projects, and no single term is the channel*. Of the difference, about two fifths is this arm weighting the terms differently and the rest is each term’s own response, two reweightings run in opposite directions agreeing to 0.001. *And the fraction of the source’s oscillation the projection retains rises with wavenumber*: its arm-to-control ratio goes from 1.030 in the lowest acoustic band to 1.089 in the highest, with a slope of $+0.0139$ per acoustic period, the twelve envelope settings spanning 0.0021 about it and none of them returning a negative value. *The intercept of that rise covers one across the same twelve settings*, 1.017 with a spread of 0.010, so what is established is the growth with wavenumber and not a constant offset: *whatever the projection does differently here, it does nothing at the longest acoustic wavelengths and more of it at each*

shorter one^{P15R187}. That slope's size is not all retention, and the part that is not is measured rather than allowed for. Fed one comb on both arms—no difference to retain—the statistic still returns a rise at the real comb's phase, 36 to 39 per cent of the reported slope and in its direction, because the two arms' own source combs sit at periods 1.0170 and 1.0160 and so drift apart by between 0.013 and 0.042 of a radian across the range, which a band root-mean-square taken over seven tenths of a period reads as a difference in retention. Replacing the two combs by one removes it, the null slope falling to a sixth or less, while flattening the envelope leaves most of it—so the carrier is the source's phase and not the envelope. The rise survives and its size does not: about two thirds of the quoted slope is retention and the rest is that drift. The step at the lowest band is the sounder of the two readings, its false value at the real phase running a quarter to two fifths of the measured step. And the statistic's phase systematic is what limits both, carrying three to three and a half independent modes across the seven bands where its noise response carries nearly seven—the slope's own effective count being between five and nine, so a wavenumber slope read across these bands rests on fewer independent points than its regression error assumes^{P15R219}.

And it is not in the source at all. Replacing the source with a pure oscillation on the visibility—no transfer, no terms, no weights, carrying $k^{(1-n_s)/2}$ so that the smooth part of the projected integrand is the same on both arms—and projecting it through each arm's own kernel, visibility and wavenumber grid gives an arm-to-control retained ratio of 1.066 at a slope of +0.023 per acoustic period, exceeding what the real source gives; the injection's phase does not change it. So the projection's geometry accounts for the whole of the difference and the source is irrelevant to it. And the two factors left in that integral are not separable: the comoving distance the kernel reads is $\eta_0 - \eta$ on both arms, so there is nothing to exchange there, while the visibility's width and the clock the acoustic phase accumulates on close the gap only together—forcing both arms onto one clock moves the comb rather than isolating a factor, and exchanging the widths amplifies the wavenumber dependence eightfold instead of removing it. What they close on is one ratio. Across the visibility's full width at half maximum the sound horizon this plasma accumulates agrees between the arms to 0.08 per cent, 17.307 against 17.294 Mpc, while the comoving distance across that same window differs by 14.6 per cent, 38.04 against 43.59—because the scales accumulate on the leaf rate while conformal time, and so that distance, is the stacking rate's. The sound speed the kernel sees is therefore 0.455 on the control and 0.397 here, and a difference in that ratio is term-independent by construction, grows with wavenumber, and vanishes for a window narrower than one acoustic period—which is the signature above^{P15R188}. That places the residual on the rate assignment of §2.4 rather than on the projection: what is open is whether that assignment is right, not whether the transfer implements it.

And the retention is not merely located at that acceptance; it is a law, and there is nothing in the law to fit. For a standing oscillation the line-of-sight integral factorises with no approximation at all, $\Delta_\ell(k) = \cos(kr_s^*) k^{(1-n_s)/2} G_\ell(k)$ with $G_\ell(k) = \int g j_\ell(k\chi) d\eta$, and the factorisation holds to a relative 3×10^{-15} on multipoles spread across the reported range—so the comb reaches the transfer undamped, and the only thing left that can damp it is the sum over k at fixed ℓ . That sum's weight is $W_\ell(k) = P(k) k^{1-n_s} G_\ell(k)^2 = G_\ell(k)^2 dk/k$, the tilt cancelling identically, and since $C_\ell = \int W_\ell \cos^2(kr_s^*) dk = \frac{1}{2} \int W_\ell dk + \frac{1}{2} \text{Re} \int W_\ell e^{2ikr_s^*} dk$, the comb's fractional amplitude in C_ℓ is

$$A_\ell = \frac{\left| \int W_\ell(k) e^{2ikr_s^*} dk \right|}{\int W_\ell(k) dk}, \quad (8)$$

built from the window the kernel reads and the comb's period, both of them the background's own. There is no coefficient in it, so it predicts an absolute amplitude and one measurement can kill it—and against the amplitude measured band by band it holds to within ten per cent everywhere, worst deviation 6.7 per cent. What that comparison is worth turns on the measuring statistic's own error, which is not a single number: fed a comb of known amplitude the statistic

is accurate to 3.74 per cent at one injection phase and to ten or eleven per cent at the worst phase, *so the smaller figure is one phase's error and not a floor. But the phase is measured rather than assumed, and the real comb sits at that phase to 0.03 of a radian*, where the statistic is wrong by about four per cent in the lowest band and by under one per cent in the other six. *Divided out, the law holds at every band on both arms to better than four per cent—worst 3.4 and 3.6—and the lowest band's apparent six-and-a-half per cent departure is around two thirds the statistic's own. And the two arms are one test of it rather than two: their deviation patterns correlate at 0.998, as do the statistic's errors at the two arms' phases. Within an arm the seven bands are close to independent under the instrument's noise response, 6.9 effective of seven across four hundred draws of the whole instrument, while the instrument's phase systematic carries only some two and a half independent modes across the same seven—so the comparison is seven measurements against noise and nearer two against that systematic. The acceptance the law integrates over is the narrower on this arm, spanning 4.47 of acoustic phase against the control's 5.14—13.03 per cent narrower, and by that same amount at every one of twelve numerical settings, the spread across them being five thousandths of a percentage point, where the sound-speed ratio above independently gives 12.8: two routes to one quantity, and the agreement is built in nowhere. Read physically the law says one thing: a wider χ -extent narrows the kernel's acceptance in wavenumber, so less of an acoustic period is averaged over and more of the comb survives; this arm's visibility is the 14.6 per cent wider in χ while accumulating the same sound horizon to 0.08 per cent, and that is why it retains more*^{P15R217P15R220P15R218}. *Three things the law does not do, and they are stated because it would otherwise be read as doing them. The acceptance itself does not move under refinement: across every numerical axis that can move it—the wavenumber ceiling over a near-doubling, the conformal-time resolution, the visibility's half-width and its split—the largest excursion at any single multipole is 0.008 per cent, inside the statistic's own 0.6 per cent floor by two orders of magnitude, with the worst axis carrying only two points and so not read as having turned over. Three of the twelve axis-arm pairs cannot move it at all and are reported as such rather than as converged: the reported multipole grid, because A_ℓ is read at the same multipoles by construction, and this arm's mode count, because its wavenumber ladder never reaches the decimation cap—the two refinements writing a wavenumber axis, measure, conformal time, kernel argument and visibility identical to the base run to the byte, and the spectrum with them, where the same two settings move the control outright. What none of that settles is the sum the spectrum is made of: the retention and the peak heights are measured on spectra rather than on the window, and §10 keeps that as its own open reading—a converged acceptance beside an unconverged retention would itself be a finding, which is why the two are not reported together. The oscillation it is checked against is a known input transferred through the projection, so that the law over-delivers is sufficiency and not identity with the real source. And naming A_ℓ does not say why the construction puts its scales and its distances on different rates, which is where the residual sits and is untouched by anything here.*

And the rule as stated does not reach the object that difference lives in. The visibility $g = \tau' e^{-\tau}$ is neither a separation read across leaves nor a scale the plasma accumulates: the optical depth is the plasma's, but it is differentiated per unit conformal time, and conformal time is the stacking rate's. *The transfer already resolves that ambiguity twice and in opposite senses—the diffusion length is accumulated on the leaf rate where the scales are, while the optical depth is accumulated on the stacking rate, with nothing stating the choice. Resolving it the other way, so that the optical depth is accumulated exactly as the diffusion length already is, leaves the ratio alone: $dr_s/d\chi$ moves by 0.06 per cent, because it is a ratio of two accumulations across the same window and re-weighting that window re-weights both. So the visibility is not where the freedom is; the freedom is in the assignment of r_s itself. And the two readings that could have chosen between the assignments disagree: the alternative moves the retained oscillation toward what the real source gives, but it moves this arm's first peak from $\ell = 221.95$*

to 226.16 and ℓ_1/ℓ_A from 0.7354 to 0.7494 against the sky's 0.7312, leaving the control's comb untouched—and its apparent improvement in the contrast is in part the same shift read by a statistic that assumes the two combs aligned^{P15R190P15R189}. *The peak positions are the only one of the three readings with an external referent, and they support the assignment the transfer already makes.*

What that support is worth is then measured, because a reading promoted to arbiter needs its resolution stated before it decides anything. Letting the weighting on the optical depth run continuously from one clock to the other through the one-parameter family $1 + f(d\eta_{\text{leaf}}/d\eta_{\text{stack}} - 1)$, every reading is linear in f : the first peak runs $\ell_1 = 221.93 + 4.21f$ to three hundredths of a multipole. *So the whole span between the two admissible assignments is four multipoles—0.01395 in ℓ_1/ℓ_A , which is 4.2 times a one-multipole locating width and 2.1 times a two-multipole one—and the peak positions therefore pin the assignment to about a quarter of that family and no further.* *Those two widths are assumed rather than measured here:* the only locating uncertainty this comparison propagates through the sky's own covariance is the fourth peak's, at 2.19 multipoles, *so whether the first three locate to one multipole is not settled by anything above and the span is quoted against a stated assumption.* The retained oscillation's level is the shallower reading, at 1.75 of its own band spread across the family, and its wavenumber slope reaches 3.80 of its own regression error over that family. *Those two are not the peak positions' statistical equals and are not quoted as such:* the comb's width is a locating width assumed of the sky where both of the others are spreads taken across a family of computed curves, *so what the comparison supports is which reading moves and which does not—the contrast's spread grows about fivefold across the family while the comb's locating width does not move at all.* *And the decisive result is not about the choice between the clocks.* The sky's 0.7312 lies at $f = -0.304$ on that same straight line—outside the family, on the far side of the clock the transfer already uses—so no intermediate weighting fits the peak positions better than the endpoint in use, there is no fitted clock to declare, and *the residual first-peak disagreement cannot be absorbed by the clock assignment at all, because the direction it would need is not admissible.* The height ratio P_1/P_2 agrees independently, moving $2.141 \rightarrow 2.017$ away from the sky's 2.217. *And the motion the alternative produces is separable into its causes,* the projection of an analytic oscillating source with no plasma dynamics in it isolating them: about a third is the visibility peak relocating, so that the sound horizon at last scattering is read at a slightly different time, a tenth is the visibility's re-weighting of the projection kernel, and three fifths is the plasma's own acoustic phase responding to the re-weighted optical depth^{P15R190}.

The comparison between the arms is taken as a distance between the two models rather than as a difference of two numbers each read against the sky, which is what makes it independent of the configuration's own floor^{P15R92}.

The instrument's own accuracy is measured rather than assumed. On the full range its control sits at 1.16 per bin lensed, within about a seventh of what a standard code returns on the same bins, so the ratio above is a statement about the arm and not about the machinery. *What the comb does not carry is the disagreement:* at 298.0 against 298.4 the spacing is right to a part in six hundred, on both instrument paths, so what remains is about one multipole at each peak.

The result is reproduced independently on a second instrument. A separate implementation—the hierarchy path rather than the line-of-sight one, 185 covered bins rather than 133, its own wavenumber grid—returns peaks at 221.96, 536.11, 815.40 and 1130.53, located sub-bin on a grid refined to unit step and recovered there to a few hundredths of a multipole, against this path's 222, 538, 818 and 1134; height ratios 2.273 and 2.319 against 2.264 and 2.298; and 4.02 per bin in the band from $\ell = 700$ to 1000 against 4.23: *within a multipole on every peak and within one per cent on the heights.* *The fourth peak's excess reproduces there too,* so it is a property of the spectrum rather than of either implementation—and on that path, where the sub-bin location is available on both arms, it is a property the control carries with it^{P15R165P15R191}.

The heights are the polarisation path's and the positions are not. Both paths return the same comb to four figures; the height ratios differ between them by more than either differs from the sky — 2.264 and 2.298 on the polarisation path against 2.448 and 2.934 on the fluid one — so every height quoted here is the polarisation path's and is stated as such, while the position, the phase and the alternation are the construction's.

Where the plasma starts moves the scale and not the peak, which is why the start is not free. Scanning a hand-placed start over a factor of 3.6 runs ℓ_A from 360.6 down to 239.3 while the first peak sits between 206 and 210 throughout^{P15R6}: it moves the denominator of ℓ_1/ℓ_A and leaves the numerator where it is^{P15R24}, so the spacing such a start reports is not the spacing its spectrum carries.

What that leaves is the equality, and it is measured rather than supposed. Holding everything else fixed and moving matter–radiation equality alone carries the third peak and the band it sits in with it: the height ratio P_1/P_3 tracks equality on both routes to it — through the radiation density and through the matter density, which move the projection in opposite directions — agreeing to within a per cent across a 12 to 24% change in the matter density, so what the band responds to is the equality and not the route. *And the epoch the distance data fix is what sets it:* equality is ω_m/ω_r with the radiation density measured, so the background that meets the baryon-acoustic distances is the same background that drives the peaks.

Two things this section does not claim, and they are separated because a reader would otherwise supply them. The alternation figures are read on a multipole grid whose step is the same size as the sky's own gap contraction is large, so *a contraction of the sky's size is resolved while the smaller ones at lower ℓ are not*^{P15R78}; a finer grid is what would settle those. And the equality result accounts for the band it moves and not for the phase residual: *what the phase is to be read against is the driving subtraction on this arm, and §10 carries it as such.*

5 What the substrate determines: the amplitude floor and the classical character

One might ask whether the observed fluctuation amplitude is the substrate's own de Sitter vacuum—the natural CR analogue of the inflationary spectrum-is-the-stretched-vacuum story. It is not, by a decisive margin.

Proposition 2 (The substrate vacuum is negligible against the observed amplitude). *The substrate curvature scale is the cosmological-constant scale: in Planck units $\Lambda\ell_P^2 \approx 3 \times 10^{-122}$, and the de Sitter vacuum metric-fluctuation power is of the same order, $(H_\Lambda/M_{\text{Pl}})^2 \sim 10^{-122}$. Against the observed $A_s \approx 2 \times 10^{-9}$ this is smaller by $\sim 10^{113}$.*

Argument. $\Lambda = 3(H_0/c)^2\Omega_\Lambda$ gives $\Lambda\ell_P^2$ directly; $H_\Lambda = c\sqrt{\Lambda/3}$ and $(\hbar H_\Lambda/E_P)^2$ give the vacuum power (receipts: `verify_numeric.py`, anchor 5^{P15R17}). The prefactor ($\sim 10^{-122}$ versus $\sim 10^{-123}$) is a 2π and reduced-versus-full Planck-mass convention; the conclusion is robust to it. $\square$

One scope qualification is owed immediately, and closing it is what makes the classical reading a result rather than an inference. Proposition 2 rules out the *substrate's* vacuum. But the reading it supports locates the fluctuations in the *progenitor*, and the progenitor's own vacuum is a different quantity: it is normalised at the collapse leg's curvature scale, not at H_Λ , and it is amplified on its way here by the branch point's mode mixing. Neither effect is small, and neither is addressed above. Both can be computed, because the collapse-side background is a single function: with $A = 2M$ and $\rho = 2\sqrt{B}/A$ the exact closed dust-plus-radiation interior gives $a = M(\rho|\sigma| + \sigma^2/2)$ near the crunch, whose Mukhanov–Sasaki potential $z''/z = 2/(|\sigma|(|\sigma| + 2\rho))$ is *independent of the mass*—so M enters only through the final division $\zeta = v/a$. The passage then has exactly three stages, and each contributes one factor of $1/\rho$. A mode leaves the sound horizon on the $\beta = 2$ leg and freezes as $v \rightarrow D_k/|\sigma|$ with the scale-invariant $D_k = \sqrt{\hbar/2}k^{-3/2}$;

the connection through equality is elementary, since $v = a \int d\sigma/a^2$ solves the $k = 0$ problem in closed form and carries $D_k/|\sigma|$ to the constant $(3/2\rho)D_k$ at the crunch; the crunch monodromy then leaks that constant into the survivor with coefficient $4\pi/\rho$ —twice the tensor value, because the true hydrodynamical $z_S = a(a + \frac{4B}{3A})/a'$ has $z_S''/z_S \rightarrow 2/(\rho x)$ where $a''/a \rightarrow 1/(\rho x)$ —the companion paper’s numerically obtained $-2\pi i/\rho$ [19] being the *tensor* value of the same object, recovered here in closed form as the continuation of the $(\sigma/\rho) \ln \sigma$ term the $(0, 1)$ resonance forces; and the survivor’s curvature is $\zeta = C/(M\rho)$, the last $1/\rho$ being the crunch’s own slope $a'(\eta_c) = -M\rho$. The result is a transfer law with no free constant,

$$\mathcal{P}_\zeta = \frac{18 k^3 D_k^2}{M^2 \rho^6}, \quad (9)$$

which is *exactly* scale-invariant on vacuum data—the k^3 cancels the k^{-3} identically—and which therefore delivers, for the vacuum, $A_s = 9(\ell_P/M)^2 \rho^{-6}$ (receipt: `P15_the_progenitor_vacuum_is_negligible_t`) the connection coefficient confirmed against integration from vacuum data to 0.1% over a decade in ρ . *One check is owed here and is not optional, because the hydrodynamical variable differs from a in three places and not one: $z_S \propto a^{3/2}$ in the matter era, so the exponents there are $(-2, 3)$ against a ’s $(-1, 2)$; the crunch residue doubles; and the final division is by z_S rather than by a . Propagating the same physical initial condition under each potential returns a ratio of exactly 2 in amplitude at every composition tested—the matter-era exponents and the change of divisor cancel, and the crunch residue alone survives. So the $z \propto a$ chain is corrected by one factor rather than rebuilt, and Eq. (9) is the true-variable law.*

Proposition 3 (The progenitor vacuum is negligible too). *With the mass capped at the recollapse threshold $M \leq \alpha/3\sqrt{3}$ and the radiation fraction at the largest value the observed spectrum permits, Eq. (9) on vacuum data returns $A_s \sim 1 \times 10^{-112}$, short of the observed 2×10^{-9} by $\sim 10^{103}$. The figure is read on the potential’s scale-free branch; on the observed band, which lies above the break the radiation content sets, the residue is some thousands larger in power, which moves the shortfall by a few orders out of a hundred and three and leaves the conclusion where it is.*

Argument. $(\ell_P/M)^2 \geq 27(\ell_P/\alpha)^2 \approx 2.6 \times 10^{-121}$ at the cap, and the companion paper determines $\rho \simeq 5.45 \times 10^{-2}$ [19]; $9 \times 2.6 \times 10^{-121} \times \rho^{-6}$ then gives the figure. Running it backwards, the vacuum would reach the observed amplitude only at $\rho \sim 3 \times 10^{-19}$, thirteen orders below what nucleosynthesis on the same leg permits. $\square$

So ten orders separate the substrate’s vacuum from the progenitor’s amplified one—Eq. (9) carries the crunch mixing already, so the amplification is the ρ^{-6} and is not a second factor on top of it—and it is still short by a hundred and three, and the classical character of the primordial statistics is established for the source that actually supplies them rather than only for the one that does not. Two consequences of character, not of number, follow.

First, the observed amplitude is inherited classical content—boundary data from the progenitor, not a quantum fluctuation generated within the Schwarzschild–de Sitter era, nor one generated in the progenitor’s collapse.

Second, there is no inflationary consistency relation: $r = -8n_t$ presupposes that scalar and tensor spectra are one vacuum stretched by one expansion, and with the amplitude not vacuum-sourced that link is absent; the substrate tensor floor is the same $\sim 10^{-122}$, so there are no substrate-sourced primordial B -modes, and any observed tensors would themselves be inherited content rather than a measure of a substrate inflationary scale. *And the tensor statement can be made unconditionally, which the scalar one cannot.* The scalar law, Eq. (9), is the true-variable law only through the hydrodynamical z_S of the progenitor’s own fluid, which carries that fluid’s equation of state and sound speed—and across the progenitor’s own equality neither w nor c_s is constant.

For tensors that restriction is absent: $z_T = aM_{\text{Pl}}/2$ exactly, for any content, any equation of state and any sound speed, so $z_T''/z_T = a''/a$ identically and the entire passage—background, connection, monodromy—applies verbatim with nothing assumed. It returns

$$\mathcal{P}_T = 144\pi (\ell_P/M)^2 \rho^{-6} \simeq 5 \times 10^{-11}, \quad (10)$$

evaluated at the recollapse cap and the largest composition the spectrum permits, against an observational ceiling of $\sim 7 \times 10^{-11}$: *below it by a hundred orders* (receipt: `P15_no_primordial_B_modes_uncondition`). So the absence of primordial B-modes is a prediction of this construction at any conceivable sensitivity, and it does not rest on the substrate's own floor—the floor argument, like its scalar twin, ruled out the substrate's vacuum and said nothing about the progenitor's. What the crossing does to the ratio is likewise fixed and free of k : every factor of the passage is shared by the two sectors, so $r_{\text{out}} = 6 r_{\text{in}}$: the passage alone would carry the ratio by 24, and the scalar mixing being twice the tensor's divides that by four in the power, and the observed bound becomes a statement about the parent, namely that its own tensor-to-scalar ratio was below 5×10^{-3} . An observed tensor signal would therefore not falsify the construction but measure the previous generation, which is the same reading the amplitude receives. The substrate fixes that the fluctuations are classical, inherited, and not governed by a vacuum consistency relation, and leaves their size to the handover. What it does fix is the multiplier. Eq. (9) holds for any incoming growing-mode amplitude, quantum or classical, so the crossing determines how much an amplitude is magnified without determining the amplitude—which is this construction's one-constant character read at the level of the perturbations rather than of the couplings. Two corollaries follow and are worth stating because each closes a natural hope in one direction and opens a statement in the other. A_s does not measure the progenitor's mass: with D_k free, the relation cannot be inverted, and the mass must be reached, if at all, by a route that does not run through the amplitude. And the classical datum has a size: since $A_s \propto D_k^2$, the parent's growing-mode amplitude must have exceeded its own vacuum's by $\sim 10^{47}$ at the top of the permitted composition window—so this cosmology does not merely decline to predict A_s , it says the previous generation's perturbations were enormously super-vacuum, which is a claim about the parent and not about us.

6 What the substrate determines: the throat and isotropization

At the branch point the near-horizon geometry is fixed, and what the perturbations cross is fixed with it.

Proposition 4 (Equal-radii $\text{dS}_2 \times S^2$ throat). *At the Nariai locus $\Lambda G^2 M^2/c^4 = 1/9$ the two positive horizon roots of $f(r) = 1 - 2GM/c^2 r - r^2/\alpha^2$, $\alpha = \sqrt{3/\Lambda}$, merge at the Nariai radius $r_N = \alpha/\sqrt{3} = 1/\sqrt{\Lambda}$ (the symbol is the algebroid paper's [3]; it is written r_N and not r_* because r_* is the tortoise coordinate used below), where $f(r_N) = f'(r_N) = 0$ and $f''(r_N) = -2\Lambda$ (the cosmology selects this $M > 0$ member of the parity-conjugate Nariai pair; the $M < 0$ member has instead one positive and two negative roots, the two exchanged by $r \mapsto -r$ [5, 6]). The near-horizon geometry is $\text{dS}_2 \times S^2$ with both curvature radii equal to $1/\sqrt{\Lambda}$: the S^2 has two-Ricci $R_2 = 2/r_N^2 = 2\Lambda$, and the dS_2 has radius² $= -2/f''(r_N) = 1/\Lambda$.*

Argument. Direct from f at the Nariai mass (receipts: `verify_geometry.py`, anchor `2P15R16`; this is the Ginsparg–Perry near-horizon limit [29]). $\square$

A field on $\text{dS}_2 \times S^2$ (Fig. 3) decomposes in S^2 harmonics; the degree- ℓ harmonic becomes a dS_2 field of effective mass $m^2 = \ell(\ell+1)/r_N^2$, i.e. $m^2/H_{\text{dS}_2}^2 = \ell(\ell+1)$. With the dS_2 index $\nu^2 = \frac{1}{4} - m^2/H^2$, the monopole $\ell = 0$ has $\nu = \frac{1}{2}$ —a scale-invariant base—while every $\ell \geq 1$ has $\ell(\ell+1) \geq 2$, hence $\nu^2 < 0$: the heavy principal series, which oscillate and decay through the throat. We read this as an angular no-hair, and the reading is grounded rather than asserted:




Figure 3: The Schwarzschild–de Sitter metric function $f(r) = 1 - 2GM/c^2 r - r^2/\alpha^2$ across the three regimes. Under-critical masses ($\Lambda G^2 M^2/c^4 < \frac{1}{9}$) give two distinct positive horizons; over-critical masses give none. The cosmogenesis branch point is carried on the *Nariai* member ($= \frac{1}{9}$), where the two horizons merge into a single *degenerate* double root at $r_N = \alpha/\sqrt{3} = 1/\sqrt{\Lambda}$ with $f(r_N) = f'(r_N) = 0$ and hence vanishing surface gravity $\kappa = 0$. The degeneracy of this root is what the throat geometry (Proposition 4) and the transmission dichotomy (§8) turn on.

the dS_2 factor of the throat is a positive- Λ epoch, and the de Sitter no-hair theorem [21] damps exactly the anisotropic content—every $\ell \geq 1$ harmonic is heavy principal-series, oscillating and decaying, while only the isotropic monopole $\ell = 0$ survives as the $\nu = \frac{1}{2}$ base—so the throat isotropizes what passes through it (receipts: `verify_throat_tower.py`^{P15R40}). The geometry is established (Proposition 4) and the mode tower follows from it; the no-hair reading is the standard theorem read on the throat, and we flag one guard as load-bearing: the index ℓ of this throat tower is the S^2 -harmonic degree of the *near-horizon* geometry at areal radius $1/\sqrt{\Lambda}$, and is *not* the observable microwave-background multipole, which lives on the last-scattering sphere of radius D_C . The map between them is §7, not an identity; conflating them would manufacture a prediction the geometry does not make. *A second guard belongs beside it, and it bounds what the tower damps.* The computation above is a statement about propagating field modes—degrees of freedom carrying a mass on the dS_2 factor, which is what being heavy principal-series means. *The low multipoles of a perturbation about a spherically symmetric background are not such modes:* $\ell = 0$ carries the mass and the axial $\ell = 1$ carries the angular momentum, the latter a stationary slow-rotation configuration rather than an oscillation, with the radiative content beginning at $\ell \geq 2$ —the multipole face of the non-radiative skeleton the range paper describes [8]. *So what the throat isotropises is the radiative content, and a conserved charge sitting in a constrained sector is not among the modes this argument is about*^{P15R8}. *This is a bound on the claim and not a claim in the other direction:* that the angular momentum is not removed *by this mechanism* says nothing about whether it is carried off by matter or torqued on the way, which this paper does not settle. *And the geometry the tower is computed on is itself a non-rotating one,* Proposition 4 following directly from f at the Nariai mass. *So it is worth measuring how much the conclusion rests on that.* Writing λ for the ratio of the dS_2 curvature radius squared to the S^2 one, the index generalises to $\nu^2 = \frac{1}{4} - \lambda \ell(\ell + 1)$, with $\lambda = 1$ the equal-radii case above. *The monopole is untouched:* $\nu^2 = \frac{1}{4}$ for every λ , so the scale-invariant base does not depend on the radii being equal. *And the damping persists*

well away from it: every $\ell \geq 1$ remains heavy principal-series for $\lambda > 1/4\ell(\ell + 1)$, which at $\ell = 1$ is $\lambda > 1/8$ —the dS_2 radius would have to fall below 0.354 of the S^2 radius, a factor near three, before the dipole ceased to decay, with the higher multipoles safer still^{P15R9}. *What ratio a rotating progenitor would produce is not computed here*, and a rotating near-horizon geometry is generally warped rather than a direct product, so a single ratio may not describe it; what the margin establishes is that the conclusion does not turn on the equal-radii point itself. *The ratio can in fact be computed on the rotating family, and it runs the helpful way.* Kerr–de Sitter’s radial function $\Delta_r = (r^2 + a^2)(1 - r^2/\alpha^2) - 2Mr$ reduces at $a = 0$ to $r^2 f(r)$, and its degenerate locus $\Delta_r = \Delta'_r = 0$ gives $a^2 = r^2(\alpha^2 - 3r^2)/(\alpha^2 + r^2)$, which returns $r_N = \alpha/\sqrt{3}$ and the Nariai mass at $a = 0$ rather than presupposing them. *The family is bounded: a reaches $(2 - \sqrt{3})\alpha$ at $r/\alpha = 0.3933$, where Δ''_r vanishes and the double root becomes triple—the ultracold member.* *Along it the ratio begins at unity and rises: $\lambda = 1$ exactly in the static case and $\lambda > 1$ monotonically with a , so rotation carries the throat away from the $1/8$ threshold rather than toward it^{P15R10}.* *That ratio is read at the pole, where the sphere’s radius is r_N ;* the rotating near-horizon sphere is warped through $r_N^2 + a^2 \cos^2 \theta$ and a single ratio does not describe it, so what the calculation establishes is the direction and its size at one well-defined point, with a factor of eight in hand at the outset.

The warped problem is done directly, and does not need the proxy. The near-horizon limit of the degenerate family, taken as a limit rather than posited, is a warped product and not a direct one: $\rho_0^2 = r_0^2 + a^2 \cos^2 \theta$ multiplies the dS_2 and polar directions alike, and the dS_2 is fibred over the sphere by $\tilde{k} = 2r_0 a \Xi / (r_0^2 + a^2)$, which vanishes only at $a = 0$. A massless field still separates on it, the warp cancelling from the relation between the transverse eigenvalue and the dS_2 operator because it multiplies both. *For the axisymmetric modes it cancels altogether:* the transverse problem is $(\Delta_\theta \sin \theta Y')' + E \sin \theta Y = 0$ with $\Delta_\theta = 1 + (a/\alpha)^2 \cos^2 \theta$ —a spheroidal deformation of Legendre in which ρ_0 does not appear at all, so the harmonic label survives the warping rather than being spoiled by it. *The decay condition generalises to $\nu^2 = \frac{1}{4} - L^2 E - L^4 m^2 \tilde{k}^2$, the last term the rotation’s own fibration, which is non-negative and so can only deepen the damping.* *Two exact bounds then settle the family without a scan: $L^2 \geq 1$ on the physical branch and $E \geq 2$ above the monopole, each with equality only at $a = 0$, so $L^2 E \geq 2$ against the threshold $\frac{1}{4}$.* *The monopole keeps $\nu^2 = \frac{1}{4}$ exactly on the warped sphere too. So the conclusion holds across the whole family $0 \leq a < a_{\max}$ with the same factor of eight, and the marginal member is the non-rotating one—rotation strictly improves the case rather than threatening it^{P15R11}.*

7 Large scales: the flat/discrete decoupling and the low-multipole floor

Here the construction makes its sharpest large-scale statement, and the load-bearing piece is established.

Proposition 5 (The fundamental-observer slice is flat). *In the fundamental-observer frame (2), a surface of constant τ has induced three-metric $dr^2 + r^2 d\Omega^2$ (since $(\partial_\chi r)^2 d\chi^2 = dr^2$ along the slice), whose Riemann tensor vanishes identically. The constant- τ slice is exactly flat $\mathbb{R}^3$.*

Argument. The substitution is immediate from the line element; the curvature of $dr^2 + r^2 d\Omega^2$ is zero by direct computation (receipts: `verify_geometry.py`, anchor 1^{P15R16}). This is the framework paper’s own stated property that constant- τ slices are Euclidean. $\square$

The decoupling follows. The distance slicing is the flat constant- τ one— $\Omega_k = 0$, no curvature term in the redshift–distance relation—while the *cosmological* layers are the closed S^3 of constant $\tilde{\tau} = \tau + \chi$ (§2.2). The non-synchrony $\tilde{\tau} = \tau + \chi$ is the decoupling itself: flat distances and a closed S^3 of comoving worldlines coexist because they are different slicings of one geometry. A literal closed-Friedmann reading would put $\Omega_k = -\Omega_\Lambda \approx -0.685$ into the distance relation and be excluded; CR avoids that not by tuning but because its distance slicing is the

flat one, the curvature living on the orthogonal layers. Spatial curvature and dark energy are one Λ read on two slicings—the corpus identity, here at the observational rung.

The low-multipole floor. The closed S^3 carries a discrete mode spectrum, labelled by integer degree L , with comoving wavenumber $k_L = \sqrt{L(L+2)}/r_0$ and the lowest physical mode the quadrupole $L = 2$ (the monopole $L = 0$ is the background, the dipole $L = 1$ pure gauge). The decoupling fixes how these project to the sky, and the fixing is the whole point. Because the distance slicing is flat (Proposition 5), the photons are projected through the *flat* geometry—the comoving angular-diameter distance is $D_M = D_C$, the same flat- Λ CDM observable that places the acoustic scale at $\ell_A \approx 301$ —while only the *source* modes carry the closed- S^3 quantization. The transfer is therefore the discrete closed- S^3 spectrum projected through the flat spherical Bessel $j_\ell(k_L D_C)$, *not* the hyperspherical transfer of a literal closed universe: that transfer carries the closed *distance* relation, which CR does not have, and would (wrongly, here) deliver the lowest mode to the quadrupole and no deficit. The flat projection places the discrete modes at

$$\ell_L \simeq \sqrt{L(L+2)} \frac{D_C}{r_0}, \quad (11)$$

with r_0 the present S^3 areal radius and D_C the comoving distance to last scattering, both fixed without new parameters: $D_C \approx 1.395 \times 10^4$ Mpc is the comoving distance to last scattering and $r_0 \approx 5051$ Mpc is the Narai amplitude $2^{1/3}/\sqrt{\Lambda}$ carried to the present epoch $u = \operatorname{arcsinh} \sqrt{\Omega_\Lambda/\Omega_m} \approx 1.22$, both on the background the distance data fix. The stretch factor $D_C/r_0 \approx 2.76$ —the ratio of the flat projection distance to the curvature radius, the decoupling made numerical—carries the lowest mode to $\ell_2 \approx 7.8$, with no source below it.

The full flat-projection transfer confirms the estimate and sharpens it into a prediction. Carrying the discrete spectrum through $j_\ell(k_L D_C)$ with the scale-invariant measure—the first-principles closed- S^3 Harrison–Zel’dovich weight [31, 32] $w_L = (L+1)/(L(L+2))$, fixed as the mode degeneracy β^2 (with $\beta = L+1$) times the per-mode power $1/(\beta(\beta^2-1))$ that equal power per logarithmic interval in k requires, and reducing to the continuum dk/k at large L so that $\ell(\ell+1)C_\ell$ returns to the flat plateau as $D_C/r_0 \rightarrow 0$ (receipt: `verify_lowell_exact_measure.py`^{P15R29})—yields a low-multipole *deficit*: $\ell(\ell+1)C_\ell$ falls below its high- ℓ plateau for $\ell \lesssim 7$ and recovers by $\ell \approx 8$, because the flat projection of a discrete source with a hard lowest mode at k_2 leaves the lowest multipoles starved (receipts: `verify_closedS3_nonsync.py`^{P15R28}).

The one effect that partly fills it is the late integrated Sachs–Wolfe term [28], sourced near the observer where small line-of-sight distances send wavenumbers $k \gtrsim k_2$ —*above* the floor—down to $\ell \sim 2$.

By the decomposition of the empirical-forcing paper [11] the cumulative term is the standard Sachs–Wolfe and integrated Sachs–Wolfe—CR’s own differential-expansion floor being zero under uniform expansion—so this late boost rides the same modes the discrete source keeps, and the deficit is milder than the bare Sachs–Wolfe starvation alone.

The depth is a matter for a *genuine Boltzmann transfer* rather than for the geometry, *and the reason is that the deficit is two effects and not one*. In the pure Sachs–Wolfe limit the suppression splits exactly into a *floor*—the projection integral truncated below k_2 —and a *ladder coarseness*, the discrete sum minus that same truncated integral. At $\ell = 5$ and 6 the two are comparable and pull opposite ways: the ladder puts back power a pure cut-off removes. And they respond to the fitted parameter with opposite signs—under $\pm 2\%$ in r_0 the floor moves by a few per cent while the full result moves by tens—so the location is the floor and is robust for that reason, and the depth is the ladder and is volatile for that reason¹². The recovery multipole is the ladder’s too: with it the spectrum recovers by $\ell \approx 8$, on the floor alone not until $\ell \approx 10$. Because the only CR modifications are the discrete source and the flat projection—every transfer ingredient (Sachs–Wolfe, early and late integrated Sachs–Wolfe, Doppler) shared with flat- Λ CDM [11]—the exact CMB temperature transfer $\Delta_\ell(k)$ of a standard Boltzmann code




Figure 4: The low-multipole discreteness floor. The closed- S^3 source spectrum is discrete ($k_L = \sqrt{L(L+2)}/r_0$, lowest physical mode $L = 2$), but the flat distance slicing (Proposition 5) projects it through the *flat* transfer $j_\ell(k_L D_C)$, not the hyperspherical transfer of a literal closed universe. With $D_C \approx 1.395 \times 10^4$ Mpc and $r_0 \approx 5051$ Mpc fixed parameter-free by Λ , the stretch $D_C/r_0 \approx 2.76$ carries the lowest mode to $\ell_2 \approx 7.8$, with no source below it. The full flat-projection transfer turns this into a low-multipole power deficit ($\ell \lesssim 8$); on a genuine Boltzmann transfer (the late integrated Sachs–Wolfe sourced above the floor and so retained by the discrete source) it sits at 0.487, 0.435, 0.359, 0.666 of the flat- Λ CDM expectation at $\ell = 2, 3, 4, 5$, recovering by $\ell \approx 8$ —a deficit whose minimum falls at $\ell = 4$, so that the quadrupole and octopole are its shoulders and not its floor. Those figures are read through the exact transfer, and the photon hierarchy built for this programme (§9.1), carried to the present, agrees with them to three per cent at every multipole (§10): *the shape and the depth are both cross-validated*. This is a mild deficit, non-discriminating against the observed large-angle power within the lowest multipoles’ cosmic variance (shaded). *What the branch-point filter does to this prediction at these multipoles—and what it does not do—is taken up in the text below rather than here.*

is CR’s transfer, and the discrete spectrum is read off it: $C_\ell^{\text{CR}} = \sum_{L \geq 2} w_L \Delta_\ell(k_L)^2$ against the continuum $\int d \ln k \Delta_\ell(k)^2$, the measure w_L being exactly $d \ln k_L / dL$ so the CR sum is the $L=2$ -floored Riemann sum of the very integral Λ CDM does continuously.

Carried out with the exact transfer (gate-validated: the continuum reproduces the code’s own C_ℓ to four figures; and the r_0 sensitivity is measured rather than assumed: the *shape* is stable—the minimum stays at $\ell = 4$ and the recovery multipole moves by 0.1%—while the *depths* drift by up to 15% at $\ell = 4$ under $\pm 2\%$ in r_0), the deficit is *milder* than a Sachs–Wolfe-only estimate suggests, and it has a shape: $\ell(\ell+1)C_\ell$ sits at $\approx 0.487, 0.435, 0.359$ and 0.666 of the flat- Λ CDM expectation at $\ell = 2, 3, 4, 5$, recovering by $\ell \approx 8$ (receipts: `verify_lowell_boltzmann.py`^{P15R31} for the transfer, and the depths with the late integrated Sachs–Wolfe term carried to the present^{P15R170}). *The prediction is therefore not a monotone recovery from the quadrupole but a dip whose minimum falls at $\ell = 4$* ^{P15R34}—and the quadrupole and octopole, the two multipoles a large-angle discussion reaches for first, are its two *shallowest* points.

The shape is not one code’s, and that was checked here by running it rather than by comparing tables^{P15R36}.

Driving the photon hierarchy built for this programme (§9.1) through the same discrete projection puts the minimum at the same multipole, $\ell = 4$, and recovers at the same place, $\ell \approx 7$ –8. *The two independent Boltzmann treatments cross-validate the depth as well as the*

shape once each carries the late integrated Sachs–Wolfe term to the present: on the exact transfer the deficit is 0.487, 0.435, 0.359, 0.666 of the flat expectation at $\ell = 2$ to 5, and the hierarchy agrees to three per cent at every multipole and one per cent above $\ell = 5$ (§10)^{P15R170}.

The reason is the late integrated Sachs–Wolfe: it is sourced near the observer at wavenumbers $k \gtrsim k_2$ (small line-of-sight distances), *above* the floor, so the discrete source *retains* it rather than losing it, and the deficit is milder than a Sachs–Wolfe-only treatment of the same source would give.

This is a parameter-free deficit, set by Λ through r_0 and D_C , and what is robust is its existence, its location ($\ell \lesssim 8$, geometric, set by $k_2 D_C$), its minimum at $\ell = 4$, and that the single floor k_2 starves $\ell = 2$ and $\ell = 3$ *together*: the exact discrete measure and the Doppler term (super-horizon velocity through j'_ℓ) each leave the $\ell = 2$ -to- $\ell = 3$ ratio near unity, if anything suppressing the octopole slightly more (receipts: `verify_lowell_exact_measure.py`^{P15R29}, `verify_doppler_lo`). Whether this predicted deficit matches the observed sky is the data test, against the large cosmic variance of the lowest multipoles. Confronted with the measured low multipoles, the verdict is a *wash*. CR predicts a smooth modest deficit bottoming at $\ell = 4$; the observed sky has a sharp quadrupole-only dip (~ 0.2) with a near- Λ CDM octopole (~ 0.6 – 1.0), so CR sits *above* the observed quadrupole and *below* the observed octopole, matching neither sharply. Under the exact cosmic-variance likelihood the net over $2 \leq \ell \leq 10$ is $\Delta(-2 \ln L) \approx +1.6$ (range $+0.2$ to $+3.4$ across the octopole estimator), a small residual well inside cosmic variance (receipts: `confront_lowell_data.py`^{P15R32P15R170}). *Broken up by multipole, the sector's weight does not lie where its name suggests*: the quadrupole *rewards* this cosmology (-2.5 , its milder dip nearer the observed low power than flat Λ CDM's), the octopole penalises it at $+1.0$, and the largest single-multipole penalty is the $+2.0$ at $\ell = 4$ —the prediction's own minimum, and the one multipole of the four that the large-angle literature does not treat as anomalous. The low multipoles are thus a genuine but *non-discriminating* sector: neither a parameter-free correspondence success nor a sharp falsification edge, but a mild deficit consistent with Λ CDM within the lowest multipoles' cosmic variance.

One further question belongs with this prediction, and it is a located one. The branch-point filter that sets what crosses into the expansion leg is, in its quantum reading, a Euclidean kernel whose action on a mode is controlled by an adiabaticity parameter C/μ_n , with μ_n the harmonic index of the layer's S^3 tower [35]. That parameter is small for all but the lowest harmonics and reaches order unity only at $n = 2$ and $n = 3$, where it takes the values 0.70 and 0.47. *Three independent routes put the approximations at their limit on the same scale*: the transmission calculation's boundary at $\ell \approx 2.5$, the projection's incompleteness below $k \sim 2 \times 10^{-4} \text{ Mpc}^{-1}$ ($\ell \approx 3$), and this parameter's reaching order unity at $n = 2, 3$. Whether that is a loss of control is decided by computing the filter rather than estimating it.

The transmitted amplitude at low multipoles can be computed rather than estimated, and doing so settles what the estimates left open. The branch-point filter's action on a mode is, in the quantum reading, a Euclidean kernel [35]. The exponential-of-an-integral form $e^{-\int \omega d\eta}$ is a WKB approximation whose adiabaticity parameter is of order unity at $\ell \lesssim 5$; but the underlying mode equation $d^2\psi/d\eta^2 = \omega^2\psi$, with $\omega = kc_s$ and $d\eta = ds/a$ along the segment, is well posed at every k , and integrating it is a matter of numerics rather than of approximation. Composing exact constant- ω transfer matrices in the stable direction over the segment ($|\Delta\eta| = 3.32$ in units $\alpha = 1$) gives exact/WKB ratios of 0.926, 0.913, 0.901, 0.891 and 0.889 at $\ell = 2, 3, 5, 15, 40$: *the WKB form is accurate to 7–11% at every multipole from 2 to 40*, with the exact transmission slightly smaller, so the filter is marginally stronger than the approximation gives.

Two readings suggested by the adiabaticity parameter alone are thereby excluded. The first is that the treatment is uncontrolled at $\ell = 2$ – 5 : it is not, and the parameter was the wrong figure of merit, measuring as it does the fractional error in an exponent that is itself small at low ℓ . *The residual's own behaviour settles this independently of any argument about the parameter*: the ratio *decreases* monotonically with ℓ —0.926, 0.913, 0.901, 0.891, 0.889—so the discrepancy

is smallest at $\ell = 2$, where the adiabaticity parameter is of order unity, and largest at $\ell = 40$, where it is small. An error of adiabatic origin runs the other way, WKB being an expansion *in* that parameter, so such an error is largest where the parameter is $O(1)$ and vanishes as it does. *What the numbers show is therefore a systematic offset rather than an adiabatic breakdown*—the WKB form is uniformly slightly generous and the exact filter uniformly slightly stronger, which is a correction of known sign and bounded size and not a loss of control^{L19}. The second concerns the comparison with the observed sky. The correction is very nearly ℓ -independent—varying by 4% across a factor of twenty in ℓ —so between $\ell = 2$ and $\ell = 3$ it alters their ratio by 1.4%. *The structural expectation that a single floor starves $\ell = 2$ and $\ell = 3$ together is therefore not relieved by the exact treatment*, and the observed sky’s selective suppression of $\ell = 2$ alone, by a factor of order three, remains unaccounted for. The low-multipole prediction of this section therefore stands as stated, and so does the discrepancy it faces.

Finally, the two Boltzmann treatments above agree, on the depth as well as on the shape, the minimum and the recovery, once both carry the late integrated Sachs–Wolfe term to the present (§10). What both supersede is the Sachs–Wolfe-analytic estimate (0.22 and 0.20 at $\ell = 2, 3$), which takes the Sachs–Wolfe source as the matter-domination value $\frac{1}{3}\Phi$, whereas at recombination $\rho_r/\rho_m = 0.317$ and the source is 0.4006Ψ —a 20% error in the very ratio of Sachs–Wolfe to integrated Sachs–Wolfe that fixes how much the latter fills the bare deficit.

8 What the progenitor supplies: the transmission proof

The decomposition’s decisive proof is here: *why* the substrate transmits the spectral shape rather than imprinting one of its own. It turns on how a mode approaches the locus it meets. Two horizon cases bound the question: a non-degenerate horizon, and the degenerate *Nariai double root*—the Nariai seam, at $r = +\alpha/\sqrt{3} \equiv -2\alpha/\sqrt{3}$, where f and f' vanish together so that $\kappa = 0$. *The locus the modes cross is neither*: the branch point sits at $r = 0$, carries no surface gravity because f diverges there rather than vanishing, and is not a Killing horizon at all.

Proposition 6 (Transmission dichotomy). *For a mode approaching a horizon where the metric function behaves as $f \sim (r - r_h)^p$, the tortoise coordinate $r_* = \int dr/f$ controls the approach. At a non-degenerate horizon ($p = 1$, $f \sim 2\kappa(r - r_h)$, surface gravity $\kappa > 0$) the integral is logarithmic and the approach exponential, $(r - r_h) \sim e^{2\kappa r_*}$. At the degenerate Nariai double root ($p = 2$, $f \sim -\Lambda(r - r_N)^2$, $\kappa = 0$) the integral is $r_* \sim +1/[\Lambda(r - r_N)]$ and the approach power-law, $(r - r_N) \sim +1/(\Lambda r_*)$.*

Argument. The two tortoise integrals directly (receipts: `verify_geometry.py`, anchor 4^{P15R16}).
□

Remark 1 (The leg does not tilt it either). The proposition shows that a degenerate Killing horizon carries no scale, so it cannot imprint one, and Proposition 7 shows the same of the branch point. The collapse leg supplies the other half of the same conclusion, by an independent route. Horizon entry on that leg occurs at $x = k\eta/\sqrt{3} = 1/\sqrt{3}$ for every k —the radiation era’s own scale invariance, which §4.1 recovers from the substrate geometry—so every mode leaves the leg carrying the same free-oscillation amplitude $\Psi(1/\sqrt{3})/2 = 0.4835\Psi_i$, a single k -independent number^{P15R41}. *So the leg multiplies the spectrum by a constant and the branch point imprints nothing*: neither carries a scale, and a spectrum can only be tilted by something that does. The tilt observed is therefore the progenitor’s, established from both sides of the branch point rather than one.

“Carries a scale” has an operational form, and it is worth recording because it is what makes the dichotomy testable rather than descriptive: a kernel carries a scale exactly when the tilt one fits to it *depends on which band one fits*. Fitted on four disjoint bands, the degenerate ($p = 2$) kernel returns one tilt to sixteen decimal places while the non-degenerate ($p = 1$) kernel spreads

by several units, and that spread shrinks as κ grows—a larger scale pushing its knee past the range. Restoring a scale to the degenerate kernel by hand destroys the agreement, so the scale-freedom is doing the work and not the arithmetic^{P15R150L21}. *This restates Proposition 6 and proves nothing further*; what it adds is a test one can run on a kernel without knowing where it came from.

Remark 2 (What the branch point does not fix). Both halves of the dichotomy are statements about the spectrum’s *shape*: a degenerate horizon carries no scale, and neither does horizon entry on the leg, so neither can tilt what passes. *Neither is a pointwise condition on the perturbation state at the branch point*, and the distinction matters for anyone computing the handover. The single free function per mode is the freedom of the *spectrum*—the progenitor’s amplitude and tilt—not a claim that the branch point fixes the state component by component. The state itself is whatever the leg’s evolution produces, and §4.1 supplies it in closed form: the potential from the leg’s own equation, the effective temperature oscillating freely from horizon entry, and the density contrast as their difference.

The Hamiltonian constraint is not an additional condition to impose there. In this framework it *is* the anchor—the map from a cut to its stress-energy, whose energy sector reads the Friedmann equation off the geometry [7, 8]. It is a definition, not a restriction: on the leftward reading the rate is set by the substrate and the content is read from it, so the perturbed constraint likewise *defines* the density contrast a given geometry carries rather than restricting which geometries are allowed. Imposing it at the branch point alongside the leg’s own solution therefore over-determines the handover, and the same geometric state answering to different stress-energy on the two sides is not a failure of matching but the branch point doing what the level assignment says it does.

Remark 3 (What the branch point’s degeneracy does not settle). It is tempting to read Proposition 6 as settling the phase as well as the shape: the tortoise coordinate diverges at the degenerate root, so a mode’s accumulated phase would be unbounded and nothing finite could be inherited. *That reading does not survive its own arithmetic*. The divergence is geometric and carries no k , so an unbounded kr_* is a divergent term *linear* in k ; a linear phase renormalizes the sound horizon rather than shifting the comb, and an unbounded one would send the comb spacing to zero and erase the acoustic peaks altogether—excluded by observation, not supported by it. And the modes never meet the divergence in any case: they cross the branch point at finite conformal time, whereas r_* diverges along a static slicing’s approach to the horizon, which is not the collapse trajectory.

What the leg does contribute is finite and, as it happens, invisible in the peak positions. Horizon entry at $x = 1/\sqrt{3}$ for every k makes the accumulated leg phase $k\eta_{\text{bp}}/\sqrt{3} - 1/\sqrt{3}$: linear in k with a mode-independent offset. So carrying it across rescales the effective sound horizon by $1 + \eta_{\text{bp}}/(\sqrt{3}r_s)$ and adds a constant, and changes the comb in no other way. *The comb therefore cannot distinguish a transmitted phase from a reset one*, because a rescaling of r_s is absorbed by the angle it is read against. Any discriminant must be a quantity that does not take the same factor—the diffusion scale is one, since r_D does not—and that is the discriminant of principle. *The comparison is made, and it does not require r_D* . The leg’s accumulated conformal time is fixed by the geometry rather than fitted: the collapse branch $r = -(2M\alpha^2)^{1/3} \cosh^{2/3}(3\text{Re}\tilde{\tau}/2\alpha)$ has $\cosh \geq 1$, so $|r| \geq (2M\alpha^2)^{1/3} \simeq 3792$ Mpc and the branch point is reached only across the lift, along which $\text{Re}\tilde{\tau}$ does not advance and no conformal time accumulates. Hence $\eta_{\text{bp}} \approx 5 \times 10^3\text{--}10^4$ Mpc, and $r_s^{\text{eff}} = r_s + \eta_{\text{bp}}/\sqrt{3}$ is *dominated* by the leg term— $3.0\text{--}5.9 \times 10^3$ Mpc against $r_s = 144$ Mpc. The absorption that takes a small rescaling cannot take this one: reproducing the measured $\ell_A = 301.8$ would require $D \approx 2.9\text{--}5.7 \times 10^5$ Mpc against the actual 1.4×10^4 Mpc, a factor of 21–41. *The acoustic phase is therefore reset at the branch point and not carried across it*—established on the peak positions alone^{P15R42}. The result is robust to the open account of the lift: any conformal contribution the lift is found to carry only adds to an already-excluded total.

The transmission dichotomy: a horizon imprints a thermal scale; a degenerate seam does not




Figure 5: The transmission dichotomy (Proposition 6). *Left:* the approach to the horizon in the tortoise coordinate $r_* = \int dr/f$, on a logarithmic vertical axis. At a non-degenerate horizon ($\kappa > 0$) the approach is exponential, $(r - r_h) \sim e^{2\kappa r_*}$ (a straight line); at the Nariai double root ($\kappa = 0$) it is power-law, $(r - r_N) \sim 1/|r_*|$. *Right:* the logarithmic approach rate $d \ln(r - r_h)/dr_*$ is the local scale. The non-degenerate horizon carries a fixed thermal scale 2κ —the mechanism by which a de Sitter horizon imprints a scale-invariant spectrum ($n_s \rightarrow 1$); at the Nariai double root the rate falls to zero, carrying *no* scale. The branch point, where the modes cross, is a third case: f diverges there, the tortoise coordinate is finite, and the crossing accumulates no phase at all (Proposition 7).

The amplitude separates from the tilt in the same statement. What the progenitor supplies is the potential power P_Ψ ; what the construction contributes is the factor $(0.4835)^2 = 0.2338$ carrying it to the observed A_s . That factor is computed rather than fitted: the inherited quantity is P_Ψ and the map from it to A_s is derived, so what the construction takes from the progenitor here is the potential power and nothing about the map [9].

The physical reading is the result (Fig. 5). The exponential, non-degenerate approach is the thermal (Hawking) law—the mechanism by which a de Sitter horizon *imprints* a scale-invariant spectrum ($n_s \rightarrow 1$): the exponential redshift erases the infaller’s spectral information and stamps the horizon’s own thermal scale. The power-law, degenerate approach carries no thermal scale; it is scale-free, and the infalling spectrum is transmitted faithfully. CR’s transmission locus is the branch point $r = 0$, where f *diverges* as $-2M/r$ so the tortoise coordinate is *finite*—the crossing accumulates no divergent phase and stamps no scale, a third case beyond the dichotomy’s two^{P15R42}. The Nariai double root (Proposition 4, $f''(r_N) = -2\Lambda$, $\kappa = 0$) is *the Nariai seam*—one point of the substrate, which the bead meets on the way in and again one full lap later, the two chart values $r = -2\alpha/\sqrt{3}$ and $r = +\alpha/\sqrt{3}$ being the same φ modulo 2π in the phase $\varphi = 2\pi r/\sqrt{3}\alpha$. The branch point sits two thirds of the lap in from it (240° , with 120° remaining), so the crossing at $r = 0$ and the seam are distinct loci on the lap without the seam being an endpoint of anything. Hence:

Proposition 7 (The branch point transmits). *The cosmogenesis branch point is a faithful scale-free transmitter—not because it is the degenerate Nariai horizon, which it is not (that is the Nariai seam, met at $r = -2\alpha/\sqrt{3}$ and again one lap later at $r = +\alpha/\sqrt{3}$), but because f there diverges as $-2M/r$, so r_* is finite and the crossing accumulates no divergent phase at all: the amplitude A_s and tilt n_s are the progenitor collapse’s spectrum carried across unaltered, not imprinted by the branch point. Equivalently, CR has no inflationary scale-invariant attractor,*

because the non-degenerate exponential approach that would drive $n_s \rightarrow 1$ is exactly the approach neither the branch point nor the Nariai seam has.

The absence of any scale where the modes cross is thus the proven reason CR carries the primordial tilt rather than manufacturing it. What the transmitter carries is, from the Schwarzschild–de Sitter side, open: n_s and A_s are inherited, fixed by the progenitor collapse—the same handover that fixes ρ_r/ρ_m and the light-element abundances—and not derived here. *Naming them together is convenient and has concealed that they are not the same kind of quantity*^{P15R85}. The vacuum normalisation is the only place a quantum constant enters the spectrum, so $P(k) = \hbar A_0 k^{n_s-1}$ and $\hbar$ is an overall multiplicative factor: *it survives in the amplitude and cancels in every logarithmic derivative*. An amplitude is the spectrum at one wavenumber; a tilt is its ratio to itself at two. *So the construction's inability to force a dimensionless magnitude bears on A_s and not on n_s —the first is permanently inherited, the second need not be. And read backwards the same statement is useful rather than limiting:* a quantity fixed by the moduli rather than the invariants is one the observation *measures* rather than one the construction must predict, so the observed A_s is a measurement of the progenitor's boundary data. *It does not isolate the mass:* the parent's growing-mode amplitude D_k enters alongside it, which is the corollary recorded above, so the mass must be reached by a route that does not run through the amplitude and checked against the independent requirement that it lie below the Nariai value. *And it is worth saying precisely what that openness is, because a count settles its kind.*^{P15R84} The progenitor family described here is parametrised by M alone— α is the one invariant and $E = 1$ a choice of geodesic—so the geometry is one-dimensional; and the Kretschmann along the bead is mass-free in the faller's own proper time, so that one parameter does not survive the approach either. *A quantity identical for every member carries no information about which member it was,* and the collapse geometry therefore transmits not one parameter but none. Against that stand at least four independent inherited numbers. *So 'inherited from the progenitor collapse' cannot mean inherited from the collapse geometry:* what is inherited is inherited from the progenitor's matter content—its composition, its entropy per baryon, its perturbation spectrum—and none of that is carried by M , the exterior here being exactly vacuum and the marginally-bound interior dust without composition. *The frontier is accordingly not a derivation awaiting a cleverer argument but a modelling task awaiting a progenitor interior,* and what the geometry supplies in its place is a cutoff rather than a content: the segment's conformal length $|\Delta\eta| = 3.32\alpha$ is fixed by Λ alone *on the Nariai member*—below it $|\Delta\eta|$ runs as $M^{-1/3}$, reaching 4.19α at $M/2$ and 15.4α at $M/100$ —and says which modes survive without saying how large they were.

9 Predictions, and the progenitor boundary

The signatures, with their maturity marked:

1. Classical, non-vacuum primordial statistics; no inflationary consistency relation; no substrate-sourced primordial B -modes (established, §5).
2. The transmission character: the branch point carries the progenitor tilt and does not drive $n_s \rightarrow 1$ by any *inflationary* attractor (established, §8). *Nor does the construction lack a scale-invariant attractor—it has one, and it is not the inflationary root.*^{P15R81} Scale invariance for a background $a \propto (-\eta)^\beta$ with $z \propto a$ requires $\beta(\beta - 1) = 2$, a quadratic with *two* roots: $\beta = -1$, de Sitter inflation, and $\beta = +2$, a matter-dominated contraction. *The collapse leg of this construction is the second root exactly:* near the branch point $f \rightarrow -2M/r$, so the leg is pressureless there and the banked law $r^3 = \frac{9}{2}M\tau^2$ with $a = |r|$ gives $a \propto \tau^{2/3} \propto \eta^2$; the mode equation integrated from vacuum data returns a flat spectrum to a part in 10^4 . *The mode-selection question that shadows this in the literature was accordingly put to the construction directly, and it answers in the negative.*^{P15R82}

The scale-invariant spectrum sits in the mode that *dominates* the contraction, whose curvature perturbation goes as η^{-3} ; the mode that survives on the expanding side is the constant one, and from vacuum data its spectrum is $n_s - 1 = 6$.

Whether the first reaches the second is a connection problem at the branch point, and here it is settled rather than assumed: the exponents 2 and -1 differ by an integer, so a logarithm could mix them, but the $\sinh^{2/3}$ law is *even* in τ , which in conformal time places its correction at η^6 and steps the Frobenius recursion in sixes past a resonance sitting at three. *No logarithm is generated, the continuation acts diagonally, and the scale-invariant spectrum does not reach the observer*—confirmed independently by continuing the dominant solution numerically around the branch point, where the admixture it produces is what the claim turns on, where the admixture falls as $\delta^{2/3}$ and the diagonal entry goes to unity. *What survives is therefore narrower than it first appeared and sharper than what it replaced*: the construction *has* a scale-invariant background, the spectrum that background freezes is confined to the contracting side, and the obstruction is a parity property of the construction’s own solution rather than a missing mechanism. *Mixing would require a background correction odd in τ , and that question is settled here too, in the negative.*^{P15R83}

Writing the law as $r = Au^{2/3}g(u)$ with $g = [\sinh u/u]^{2/3}$ places every branched factor in $u^{2/3}$ and leaves g even, analytic and non-vanishing at the origin—exactly, since $\log(\sinh u/u)$ is analytic in u^2 there and the exponential of a series in u^2 is one. The three sheets differ by a constant cube root of unity, and a constant multiplier cannot change a parity; the conjugate branch is even as well, and carries no branch point at all. *So the evenness is unavoidable, and what it says is not a technical fact but a symmetry*: $r(-\tau) = r(\tau)$, the cosmogenesis is time-symmetric about the branch point, and a time-symmetric background cannot mix a growing mode with a decaying one, since mixing would distinguish a direction of time the background does not. *The same invariance appears one observable over*: the driven acoustic amplitude of §4 is a resonant Fourier magnitude exactly invariant under time reversal, a theorem about the driving, though what it carries about the peak heights is what that section’s instrument does not return. *One symmetry, read at two places. And it locates rather than forecloses what would be needed*: this leg is exactly even because it is the marginally-bound geodesic of an exactly vacuum exterior, so a progenitor carrying real matter content—pressure, dissipation, anything with an arrow—would not be, which returns the question to what the progenitor was.

3. Flat distances ($\Omega_k \simeq 0$) coexisting with a closed- S^3 low-multipole *deficit* below $\ell \approx 8$, set parameter-free by Λ —mild, and on a genuine Boltzmann transfer a dip bottoming at $\ell = 4$ ($\approx 0.49, 0.44, 0.36, 0.67$ of the flat- Λ CDM expectation at $\ell = 2, 3, 4, 5$), its shape and depth cross-validated between two independent transfers (*established* for the existence, the location, the minimum and the depth (§10); *non-discriminating* as a test, the deficit sitting inside the largest multipoles’ cosmic variance). Confronted with data it is non-discriminating: it starves $\ell = 2$ and $\ell = 3$ together, matching neither the sharp observed quadrupole-only dip nor the near- Λ CDM octopole, and sits consistent with Λ CDM within the lowest multipoles’ cosmic variance (§7).
4. Coherent acoustic peaks from geometric (null-boundary) phase-fixing rather than super-horizon freeze-out (argued, §4).
5. The acoustic scale is resolved in the cosmological development above (§2.3), and the geometric rate (4) is the standing CR-versus- Λ CDM discriminator on data in hand (*established*, §2.3)—a strength established before the spectrum, not this section’s to re-assert.

The boundary is principled. The substrate carries everything the branch point’s null geometry lets it carry—coherence, isotropization, the discreteness floor, the classical character, the faithful transmission—and the scale-free crossing proves precisely where it stops: the spectrum’s amplitude and tilt are not the substrate’s to set. This is the shape inflation has when it parametrizes its observables through an unknown inflaton potential; CR routes them through an unknown progenitor collapse, with the arrival constrained—whatever the collapse supplies must reach the branch point coherent, isotropized, scale-freely transmitted, and classical.

The symmetry between the two unknown suppliers is only apparent, and the asymmetry is the substance. Inflation is not structure the standard cosmology already contains; it is an added sector—a scalar field with a freely specified potential—introduced to produce features that cosmology was known to lack: the causal contact the horizon problem denies, the flatness the dynamics do not single out, and, once these were in view, a near-scale-invariant spectrum. The potential is then chosen to deliver the observed amplitude and tilt. A model built to be tunable, and tuned to a target known in advance to require tuning, earns precisely what such a model can earn—it establishes that the features are *possible*, that an apparatus permitting them exists. It does not establish that they were *required*, and the routine elevation of the spectral fit into a vindication of inflation conflates the two: that a freely chosen potential can be set to match n_s and A_s is not evidence that inflation occurred, but the statement that a model with enough adjustable structure to fit has been fit. This is the distinction between a world that *requires* a phenomenon and one that merely *permits* it through adjustable parameters—the same distinction the programme draws in reading the cosmic foliation as forced rather than chosen [11]—and it places the inflationary spectrum on the permitting side.

The present cosmology adds no such apparatus. Causal contact, isotropy, flatness, phase coherence, and scale-free transmission are not produced by a field introduced to produce them; they are read off structure the construction already contains—the de Sitter throat that isotropizes by the no-hair theorem (§6), the null boundary on which coherence *is* the characteristic-data condition (§4), the exactly Euclidean constant-time slice (§2.3), and the degenerate horizon whose vanishing surface gravity transmits rather than imprints (§8)—each fixed by Λ alone, with no parameter free to do the producing. The one quantity it does not derive, the amplitude and tilt, it inherits in exactly the sense flat Λ CDM inherits the baryon-to-photon ratio; on that single datum the two frameworks stand level, and on everything the inflationary sector is invoked to supply they do not. The verdict this licenses is not symmetric, and it does not await a future measurement. On the data in hand the two align; on the structure each must assume in order to align, one introduces an entire tunable sector and tunes it while the other introduces none—and makes, in its place, falsifiable commitments where inflation keeps its freedom: no scale-invariant attractor *reaching the observer*, no consistency relation, no substrate-sourced B -modes (§5, §8)^{P15R82}. By the economy of assumption that distinguishes a required structure from a permitted one, that comparison is settled by what each theory must presuppose, and it is settled in this cosmology’s favour. The bound on that verdict is stated in the same breath: it is a verdict on what each theory must presuppose, and the data axis is split. The expansion history fits the distance ladder and fixes H_0 with the acoustic angle (§2.4); the abundances are confirmed within 1σ [19]; the spectrum’s content remains inherited; and the acoustic peak structure, computed from that background with nothing fitted to it, reproduces the comb to a part in six hundred and is still rejected on TT shape (§4.7)—the sharpest datum against the construction.

9.1 The acoustic instrument: what it is validated against, and to what accuracy

The low-multipole prediction above and the ratio statements below are carried by a Boltzmann transfer built for this programme, and its standing should be stated plainly rather than assumed. It is a full photon hierarchy with polarisation, second-order tight coupling, massless neutrinos,

and a Peebles recombination history; the line-of-sight source carries the monopole with the potential, the Doppler term, the integrated Sachs–Wolfe term, and the quadrupole with its own projection kernel ($j_\ell + 3j_\ell''$).

Against a like-for-like reference—an independent Boltzmann code run at identical parameters, unlensed and with reionisation off—it reproduces the *acoustic peak and trough positions* to $\leq 0.5\%$ across P_1 – P_4 , the *ionisation history* $x_e(z)$ and its derivative to $\sim 1\%$ through the visibility peak, matter–radiation equality to 0.02% , and the *transfer function* to better than 1% for $k < 0.02 \text{ Mpc}^{-1}$. Above that wavenumber it agrees to 1 – 2% , with the residual scatter in both directions and no trend across the range^{P15R43}.

Two construction details are worth stating, because both are easy to omit and both have signatures that read as physics.

The first is the reach of the mode ladder. The angular spectrum at multipole ℓ is an integral over wavenumber, and the projection kernel $j_\ell(k(\eta_0 - \eta))$ has substantial support *above* $k = \ell/D_M$, not merely at it; a ladder cut at k_{max} therefore truncates the integral, and does so more severely as ℓ rises toward $k_{\text{max}}D_M$. Quantitatively, truncating an exact transfer at $k_{\text{max}}D_M = 900$ retains 99.2% of C_ℓ at $\ell = 200$ but only 61% at $\ell = 800$ and nothing at all at $\ell = 1150$; carrying the ladder to $k_{\text{max}} \geq 2\ell_{\text{max}}/D_M$ recovers every multipole to better than half a per cent. *The tell is unmistakable once known:* the highest peak simply fails to appear, so a spectrum that should show four acoustic peaks shows three, and the peaks that do appear are displaced downward by an amount that grows with ℓ . *Increasing the ladder’s density at fixed reach does not help*—the loss is the range, not the sampling, which is worth checking explicitly because the two are easily confused.

The second is the seeding of the conformal time. It is a cumulative integral, $\eta(a) = \int_0^a da'/(a'^2 H)$, and a numerical grid necessarily begins at some finite a_{min} ; the interval already elapsed below that point must be carried as a seed rather than set to zero. In radiation domination $H \propto a^{-2}$ makes the integrand constant, so the omitted piece is $a_{\text{min}}/(H_0\sqrt{\Omega_r})$ exactly—for $a_{\text{min}} = 10^{-5}$ it is 4.6 Mpc . *It is a fixed offset at every epoch*, and therefore 0.03% of η_0 but 12% of η at $z = 10^4$: the acoustic scale, the peak positions and the peak ratios are insensitive to it, while any early-time quantity or any comparison against a second code is not. Its signature is instructive—because the potential decays more steeply at larger k , a fixed error in the time coordinate reads out as a *smooth, monotone, k-growing* error in amplitude, which is the shape one would otherwise attribute to a physical suppression. The grid must also extend below the intended starting redshift, so that the initial epoch is interpolated rather than clamped.

That residual does not enter the claims made here. The Cosmological Relativity and flat- Λ CDM spectra are computed through the *same* machinery, so an instrumental transfer error afflicts both arms identically and cancels in their ratio—and every prediction stated in this paper is a ratio. The low-multipole deficit in particular lives at $\ell \lesssim 8$, i.e. $k \ll 0.02 \text{ Mpc}^{-1}$, where the two agree to better than 1% . What the residual does forbid is an *absolute* amplitude claim: this instrument should not be read as reproducing the observed small-angle power to better than a few per cent, and no such claim is made.

10 The open frontier: the pieces this cosmology is built to close

The result stands on what the substrate determines. What it does *not* yet claim has been carried to a sharp, gradable edge rather than left vague—and those edges are the most interesting part of the programme from here, each a gap to be closed, not papered over.

We hold them to the criterion of necessity the programme’s epistemology names—that a structure is credited for *requiring* a phenomenon, not for *permitting* a value that fits it [12]—and sort them by it: a gap that is *buildable* is a debt owed, to be built before the claim it bears on is a proof rather than a coherent proposition, while a genuinely external unknown may stay open at no cost, exactly as flat Λ CDM leaves its own inherited data open.

The buildable ones below are named as debts, not softened into frontiers. *Of the four, three are run and one is a frontier*: the end-to-end branch-point-to-recombination transfer, the large-angle depth and the likelihood are built and confronted below, what the transfer leaves being a difference in the acoustic contrast rather than in the phase (§4.7); and the derivation of the progenitor spectrum is the genuine frontier rather than a debt. Four stand out:

1. the sufficiency of the null-boundary characteristic data for the observed acoustic coherence (§4), argued from the structure of the characteristic initial-value problem, with the time-reversal driving equality established there as a Fourier theorem and the handover at the branch point fixing the phase and the amplitude the datum leaves open. *The end-to-end branch-point-to-recombination transfer is run* (§4.7): a two-arm line-of-sight Boltzmann integral, $\Delta_\ell(k) = \int S j_\ell(k(\eta_0 - \eta)) d\eta$, carried on this cosmology's own background with the perturbations on the leaf congruence the framework assigns them, and validated on its control to 0.23% in the first-to-second height ratio in the configuration the arm's own numbers are taken in ^{P15R159P15R107}. On this arm it returns a comb of 298.0 against the sky's 298.4 and height ratios 2.264 and 2.298 against 2.217 and 2.277, with the likelihood still rejecting this arm's spectrum on shape; the diffusion-scale signature it carries is located by the joint fit as a Gaussian residual in ℓ that no tilt removes (§4). *What the transfer leaves is about one multipole at each peak, and the sky cannot resolve it*: the comb is right to a part in six hundred, the phase intercept sits inside the sky's own locating spread, and the fourth peak is 0.9 to 1.3 standard deviations out with most of that offset shared with the control. *What remains is not a position at all*: the difference between this arm and the control is a *contrast* about the acoustic envelope—not a phase and not an envelope—it carries three quarters of the likelihood's excess, and its channel is the balance between the monopole and the Doppler terms of the source, bracketed with opposite signs on both instrument paths, and the difference itself is made *between wavenumber and multipole*—in wavenumber the two arms' relative oscillations agree to the measuring statistic's own floor—and not by any one source term nor by the interference between two, the projection raising this arm's contrast on nearly everything it projects and increasingly with wavenumber, the mechanism being the kernel's own acceptance in wavenumber and stated as a law with nothing fitted in it (§4.7). *Two things about that excess are measured rather than left to the frontier*: the Doppler channel's coupling to the contrast is negative at every band on the arm's own spectrum and the share of the excess that channel carries is a minority on either envelope, growing with wavenumber and sign-indefinite at the lowest bands; and *the excess's own structure across wavenumber is a step at its lowest band rather than a trend*, the bands above it fitted by a constant, so the discriminating power of every shape comparison across wavenumber sits where the excess carries least structure. *The step survives three running envelopes differing in kind and sits at the second acoustic peak to about a per cent*—sharper than the window that resolves it—with the lowest band running between a third and two thirds of the rest on every statistic that resolves it. *Every candidate this comparison holds is evaluable against that step, and between them they carry a minority of it*: the window weighting steps the wrong way, the term mix the right way, the pair as actually composed about two fifths, and the projection width and the Doppler none. *And the step is very largely shared*—both arms step upward at the lowest band and this arm's is shallower by about a tenth and no more, *so the feature belongs to the acoustic physics the arms have in common and the excess's step is the part that fails to cancel*. *That part survives an estimator that is differential by construction*, the two spectra divided before any width is taken so the shared step is never formed—negative on all four bases, both pairings and both aggregations—and it is an *amplitude difference and not a phase one*, the split being exact rather than fitted, so the first acoustic cycle is weakened in this cosmology rather than displaced in it. *The shared part reduces to no single term of the source*, the removal losses summing

to nearly twice the whole, though a step-weighted reading of the decomposition is led by the Doppler where an amplitude-weighted one is led by the monopole. *And scored on the differential estimator the candidate list accounts for none of the step:* one channel steps the opposite way to the arm and the other two are not resolved there, where against the mostly-shared quantity they reached two thirds and two fifths—and *they cannot be resolved by the banded family of statistics*, the smallest decidable share standing at three fifths of the step against carried shares of about a third and a thirtieth, with every route to a lower floor taken and the phase-insensitive aggregation lowering scatter and signal by the same factor. *But that limit belongs to the family and not to this comparison:* the likelihood these spectra are confronted with bins at a thirty-fourth of a comb period rather than banding at seven tenths of one, and in its metric the two channels separate from each other at some twenty-five standard deviations, with every candidate departing the arm's way at that band. *What that metric measures is what the data can distinguish, and the data's own rejection of this arm lies elsewhere:* the lowest band carries under one per cent of the excess in fit and changes sign as smooth shape is absorbed, while four bands in the upper half carry some six sevenths of it on an exact decomposition—*so the excess's one prominent feature across wavenumber sits where the rejection is cheapest, and the rejection sits where no smooth shape finds anything. But the rejection there is not a level:* bin by bin it is modulated at the comb's own period, reached by none of twenty thousand pooled draws of the instrument's own covariance through the same statistic, with five sixths of it carried by the term that couples the two arms' difference to the control's residual—*so the rejection carries acoustic structure*, the period fixed to the range's own resolution and not finer. *And no banded reading can find it, which is a limit of representation and not attenuation:* one number per band at seven tenths of a period spacing has a Nyquist period of twice that, so eight of the eleven instruments this comparison has used cannot represent a comb-period feature at all, where the likelihood bins at a Nyquist period a twentieth of it and passes it whole. *And across those bands one candidate channel costs the arm's way:* the term mix delivers about four thirds of the arm's cost with the two patterns correlating at seven tenths and nearly half of it misplaced, where the window weighting's cost is *anti-correlated* and the pair as composed matches worse than the term mix alone—*so a total is not a match, and on this metric the two channels add rather than cancel. But whether that channel carries what the cost is made of is a question no instrument this comparison holds can settle, and that is established rather than left open:* against two thousand draws of the covariance the channel's own cost, the part of the excess it leaves unexplained and the part it misplaces all clear, *so every piece of the decomposition is acoustically modulated*—a knob moving the balance of two oscillating source terms producing an oscillating cost by construction, which is what a detection test establishes and is not what authorship needs. *And the accounting that would settle it closes exactly and still cannot attribute:* the least-squares share in the plane the comb's cosine and sine span *is the cosine of the phase offset identically*, so it is blind to the channel's amplitude—the *anti-correlated channel being credited with essentially all of the authorship for pointing π away*—while the one scale that is not amplitude-blind fails by measurement and carries no statistical floor, the spectra's difference moving with the data only through two fitted amplitudes. *So the acoustic contrast excess is a measured discrepancy of known size, location, period and shape whose carrier is not attributable from here*, the degeneracy being exactly dimensional in that two channels span the plane; *and what attribution would take is a channel independent of that plane or an estimator using amplitudes where those amplitudes carry statistical content*, neither of which is a refinement of the instruments above. *And the stage at which the excess is made is located, and so now is the mechanism, which is where this sector's open work now sits:* the difference is not in the source—the same statistic reads 1.047 on the projected spectrum against 0.996 and

0.992 on the source, and in wavenumber this arm's relative oscillation is if anything the shallower of the two—*so it is made between wavenumber and multipole*, this arm retaining 1.054 times as much of its own source oscillation as the control does and increasingly with multipole, *and not by the wavenumber sampling, the distance, the visibility width before the kernel, the lensing or the binning*, each of which is excluded by direct substitution. *And the mechanism is the kernel's own acceptance in wavenumber, stated as a law rather than as an account*: for a standing oscillation the line-of-sight integral factorises with no approximation, so the comb reaches the transfer undamped and only the sum over k at fixed ℓ can damp it, and what survives is that comb averaged over the window the sum carries— $A_\ell = |\int W_\ell e^{2ikr_s^*} dk| / \int W_\ell dk$, with no coefficient in it to fit, holding to within ten per cent of the measured amplitude on both arms at every band, and narrower here because this arm's visibility is the 14.6 per cent wider in χ while accumulating the same sound horizon to 0.08 per cent. *What that leaves is a question about the line-of-sight integral on this background rather than about the statistics above*: whether the extra retention is required by the construction or is an artefact of how the integral is carried—and *the sector's standing against the sky is not settled until it is answered, since on the first reading the excess is this cosmology's own prediction and on the second the comparison has not yet been made*^{P15R185P15R215P15R216P15R213P15R211P15R212P15R210P15R205P15R204P15R202P15R217};

2. the exact large-angle *depth* (§7): the flat-projection transfer of the discrete closed- S^3 source is built with a *genuine Boltzmann transfer*—the exact CMB temperature transfer $\Delta_\ell(k)$ (Sachs–Wolfe, early and late integrated Sachs–Wolfe, and Doppler, all common to CR and flat- Λ CDM) sampled at the discrete modes k_L , gate-validated (the continuum reproduces the reference C_ℓ to four figures) with the r_0 sensitivity measured rather than asserted—shape stable, depths drifting up to 15% at $\ell = 4$ (receipt: `verify_lowell_boltzmann.py`^{P15R31}).

It gives a *mild* deficit, $\approx 0.487, 0.435, 0.359$ and 0.666 of the Λ CDM expectation at $\ell = 2, 3, 4, 5$ —*a dip whose minimum falls at $\ell = 4$, not at the quadrupole*, the shape and the depth both reproduced by the programme's own photon hierarchy to three per cent—recovering by $\ell \approx 8$: the late integrated Sachs–Wolfe term is sourced above the floor and is therefore retained by the discrete source, leaving the deficit shallower than the bare Sachs–Wolfe starvation.

The mechanism is robust—parameter-free, located at $\ell \lesssim 8$, bottoming at $\ell = 4$, with $\ell = 2$ and $\ell = 3$ starved *together* (the exact discrete measure and the Doppler term each leave the $\ell = 2$ -to- $\ell = 3$ ratio near unity: receipts `verify_lowell_exact_measure.py`^{P15R29}, `verify_doppler_lowell.py`^{P15R30}).

Confronted with the sky the sector is a *wash*: CR's smooth ~ 0.4 – 0.5 deficit sits above the sharp observed quadrupole (~ 0.2) and below the near- Λ CDM octopole (~ 0.6 – 1.0), matching neither, and the exact cosmic-variance likelihood returns $\Delta(-2 \ln L) = +1.58$ over $2 \leq \ell \leq 8$ and the same to the digit over $2 \leq \ell \leq 10$, both arms being at unity by $\ell = 8$ (range $+0.2$ to $+3.4$ across the octopole estimator), a small residual inside cosmic variance — *and it is a near-cancellation rather than a uniform cost*: per multipole the quadrupole rewards the construction by -2.5 and $\ell = 3$ to 5 penalise it by $+1.0, +2.0$ and $+1.0$, with nothing above^{P15R170}. So the low multipoles are a genuine but *non-discriminating* sector, neither a parameter-free correspondence success nor a sharp falsification edge; the deficit's existence and location stand as a real parameter-free feature, but its depth places it consistent with Λ CDM within the lowest multipoles' cosmic variance.

The location is robust and the depth is not, and the difference between them is now measured rather than estimated. On the background the distance data fix, the discrete scale moves by a quarter of a per cent and the lowest mode lands at $\ell \simeq 7.8$, so *where* the deficit sits is not a background choice. *The two Boltzmann treatments still differ by a factor of two at $\ell = 4$* — and that factor is not the geometry: moving the discrete scale alone buys

three per cent against a gap of a hundred. *It is the late integrated Sachs–Wolfe term*, which at these multipoles is sourced above the discrete floor and is therefore retained by the sum, filling the deficit; the treatment that truncated its line-of-sight integration earlier was deeper at exactly the multipoles where the two disagreed. *Carried to the present instead, the two treatments agree*: on the exact transfer the deficits are 0.487, 0.435, 0.359, 0.666, 0.911, 0.983 and 0.998 of the flat expectation at $\ell = 2$ through 8 — *the exact transfer being the one carried here, with the hierarchy agreeing* to within three per cent at every multipole and one per cent above $\ell = 5$ ^{P15R168}. *The factor of two was the missing term and not a difference between the constructions*, and the agreement is stable: it does not move under a doubled opacity grid, a halved late step count, or a further-extended continuum. *So the shape and the depth both cross-validate* — minimum at $\ell = 4$, recovery by $\ell = 8$ — and the sector is ready to be scored against the measured multipoles with cosmic variance carried.

The exposed edges lie elsewhere—the acoustic contrast difference of the first item and the damping signature it carries;

3. the progenitor spectrum itself— n_s and A_s (§8)—inherited boundary data fixed by the progenitor collapse, the baryogenesis-analogue computation belonging to the matter sector [7, 8], with the target a consistency between the inherited composition and spectrum and the measured primordial abundances and tilt, not a derivation from the geometry alone—the most ambitious reach of the four, the one that would close the decomposition from both ends and give CR a derivation where the standard model keeps a measured datum. *And the target is now a number rather than a direction*: refitting both arms on this construction’s own background prefers a tilt of 0.995 here against 0.956 on the standard one (§4.7), *so a derivation has to land near the bluer value and not near the one the standard model infers*. *And what supplies it is the progenitor’s vacuum and not the collapse leg*: on the leg both the potential and the effective temperature are functions of the single variable $k\eta/\sqrt{3}$, so a handover at a fixed phase is exactly scale-free—the ratio of amplitudes at two wavenumbers is one—and a handover at a fixed time would contribute not a tilt but a running, red in both channels and growing as k^2 , which no amplitude choice makes look like a constant. *At the branch point it vanishes quadratically*, so the leg is a wavenumber-independent amplitude and nothing else. *And what the substrate alone fixes is $n_s = 1$ exactly*: in conformal time the mode equation carries no length, so the curvature radius enters only as the prefactor that sets the amplitude and reaches the tilt for no value of it; and on the forced member the progenitor’s mass is that same radius up to a pure number, so the two candidate scales are one and fall together. *But the fluctuations are not generated on the substrate*, and the interior they are generated in carries a scale the substrate does not. *Solved there*, the mode potential interpolates between the scale-free matter form and a radiation form that is not, so the generated spectrum *breaks* at the wavenumber the radiation content sets: its log-slope runs from +0.30 to +1.98 across the observed band, tending to the radiation value +2. *So it is a running and not a tilt*, by the same band test that closes the collapse leg — and *blue at every wavenumber*, where the measured value is red by two parts in a thousand^{P15R182}. *The flattest slope goes as the radiation fraction*, so exact scale-invariance is the pure-dust limit and reaching red would need that fraction negative. *And the running is the interior’s own and not the vacuum’s*, which is what the two readings of this interior share. Measured on unit incoming amplitude, so that what comes out is the multiplier itself, the transfer’s log-slope runs from -0.866 near the bottom of the observed band to -0.010 near its top: it is *neither scale-free nor a power law*, and what it adds to any spectrum’s tilt is twice that spread. *The exact scale-invariance the vacuum shows is that same function’s low-wavenumber limit*: below the break the log-slope tends to -1 and $kT(k)$ to a con-

stant, and the vacuum's $k^3|T|^2$ is scale-invariant exactly where that slope is -1 . *So the cancellation is the vacuum normalisation meeting the transfer's low-wavenumber power law, and it holds only where that power law does.* The split is an identity rather than an argument—the tilt is $d \ln T / d \ln k + 1$, the wavenumber dependence always the transfer's and the constant always the normalisation's. *And the transfer is the same function for every input*, linear to parts in 10^{14} and reproducing its slope to parts in 10^{12} across inputs including one that is not a power law^{P15R184}. *So the question is not what the progenitor's vacuum gives but what this interior does to whatever enters it*, and the answer is that *no power-law progenitor spectrum emerges with a red, near-constant tilt*: an input that did would have to run by 1.71 to 1.72 across the band, opposite in sense to the transfer, the spread being the differencing convention rather than the measurement, and the figure moving by two per cent over the range the arm's own distance mapping allows. *That is a requirement on the progenitor and not a result about it*, and it is stated as one. *And it is bounded, because the transfer's running is a function of one variable.* In the interior's own radial variable the potential carries no radiation fraction at all—the fraction and the wavenumber enter only through their product—so the log-slope is a universal function of that product and the break sits at a fixed value of it, which places the break wavenumber inversely with the radiation fraction exactly rather than approximately. *At the other end the potential is Coulombic*: the crunch's $1/x$ against the mode's k^2 is the repulsive zero-angular-momentum Coulomb wave equation, and the expansion of its irregular solution's amplitude carries the log-slope to zero as $1/k$. *So the excursion is exactly one, from -1 to 0 ; what the transfer can add to any tilt is at most two; and no band, however wide, can ask a progenitor for a running above it*—the observed band asking 86 per cent of that maximum, which is a structural statement and not an empirical one. *The limit is derived where the integration is not trusted and only checked where it is*: past the wavenumber at which the incoming mode would start inside the radiation era rather than outside the break the construction's premise fails, and the asymptote is compared with the solved transfer only below that wavenumber, where the two agree to better than two per cent. *And what forces the requirement is the radiation fraction.* A fraction that carries the whole observed band below the break—where the transfer is a clean power law and a power-law progenitor would come through untilted—does exist, below 10^{-3} on the looser of two stated criteria for where the break is and below 1.4×10^{-4} on the stricter; but it lies fifty-five to nearly four hundred times under the determined value, so the requirement stands because the composition this construction determines elsewhere forces it. *Both runnings are then set by the same object*, the break, so a progenitor that cancels this one is not a tuning of an arbitrary function but a progenitor whose own spectrum breaks where the interior's does—a structural candidate, and nothing here shows that any progenitor does^{P15R186}. *And the substrate's power-law formula does not apply off the substrate*: its coefficient is dimensionless, which is what makes it a power law, where the interior's carries a scale—a distinction invisible to a tilt read off a background fitted to the other arm. *The figure is provisional in one respect and it is stated*: it is measured on the range below the damping tail, which is where a tilt has most of its leverage. *One route to it is closed, and closing it narrows the target rather than the ambition.* The construction is recursive—each progenitor seeds the next cosmology—so a *stationary* recursion would make A_s a fixed point and determine it. But entropy per baryon rises strictly at every branch-point crossing, the crossing being an erasure and the increment bounded below by Landauer's $k_B \ln 2$ independently of the network and of η [19]: *a map that strictly increases a coordinate has no fixed point*, and independently the chain it generates is finite, so there is no asymptotic limit for a fixed point to be the limit of^{P15R2}. *So the derivation must reach the head of a bounded genealogy rather than a stationary state*—the same terminus the inherited composition reaches, and the two are one question asked of two quantities;

4. the *likelihood-level model selection*: the parameter-free ratio comparison above is joined by the exact low-multipole cosmic-variance likelihood—each $\hat{C}_\ell$ a scaled $\chi^2_{2\ell+1}$ about the model C_ℓ , the absolute baseline cancelling in the CR/ Λ CDM ratio (`verify_lowell_likelihood.v2.py`^{P15}) the proper instrument where cosmic variance dominates.

With the genuine-Boltzmann depths ($\approx 0.49/0.44$ at $\ell = 2/3$, above) the sector is a *wash*: the low quadrupole still mildly rewards CR ($\Delta(-2 \ln L) \approx -2.5$, its milder dip nearer the observed low power than Λ CDM's), the octopole and $\ell = 4$ mildly penalise it ($\approx +1.0$ and $+2.0$)—so the sector's largest single-multipole penalty sits not at the octopole but at $\ell = 4$, the prediction's own minimum—and the net over $2 \leq \ell \leq 10$ is $\Delta(-2 \ln L) \approx +1.6$ (range $+0.2$ to $+3.4$ across the octopole estimator)—a small residual well inside cosmic variance. A Monte-Carlo over 10^4 skies puts the sector's *in-principle* discriminating power at only $\sim 3.4\sigma$ (the short multipole lever arm and cosmic variance), and the current measurement uncertainty swamps even that.

The low multipoles are therefore a genuine but *non-discriminating* test: CR and Λ CDM are statistically indistinguishable there, the mild deficit neither favouring CR nor refuting it. Decisiveness comes from outside the sector—the geometric expansion rate (4), confronted with the distance ladder (§2.4), as the standing discriminator, and the likelihood across the *full* spectrum, which is run and rejects this arm's spectrum on TT shape (§4.7), its amplitude level not established by the time-reversal driving equality (§4).

A frontier of a different kind concerns the matter itself rather than the perturbation observables above: the *dynamics of matter crossing the branch point*.

Three facts about that crossing follow from the structure already established here.

It is *well posed*—the beginning is fixed at the branch point $r = 0$, and the crossing is taken on the *substrate*, whose curvature is finite there however the geometry's own invariants behave.

The bend $\rho = m'/4\pi r^2$ that carries the matter is accordingly finite, and its data on that null surface is characteristic rather than Cauchy: a characteristic crossing with no obstruction from the substrate's curvature. *The geometry's Kretschmann scalar does diverge at that locus*, as the abstract states and the circle paper computes [36]; what makes the crossing well posed is that the divergence belongs to the chart-borne geometry and not to the substrate the cut is taken on, and that the tortoise measure converges so the crossing carries no scale.

It *isotropizes and is scale-free*—the throat's de Sitter no-hair (§6) damps the anisotropic part of the crossing stress-energy to the isotropic monopole, and the degenerate approach (§8) imprints no thermal scale: the matter counterparts of the field no-hair and faithful transmission established above. *Where each of those acts is worth stating, since one of them cannot act at the crossing at all.*

Damping is a process and requires elapsed time, and the crossing has none: the real part of the complex cosmic time is frozen along the segment reaching it [35].

The no-hair damping therefore belongs to the *approach*—the throat region, over the collapse leg's own cosmic time—while the crossing carries whatever survives it unchanged, not because a mechanism protects it but because there is no interval in which anything could act. *The isotropy is earned on the approach and preserved by the crossing*, and the two halves are of different kinds: the first is a damping calculation with a rate, a timescale and a residual, the second follows from the zero-duration structure and takes no model input. It follows that *how much anisotropy survives is fixed by the approach against the leg's duration*—a property of the progenitor's collapse history rather than of the crossing. And it obeys a *structural transition law*: because the reassignment preserves the cosmic foliation and the density is leaf-carried and lapse-independent [7], the reassignment acts on the time-stacking—fixing the Λ -set rate (6)—and not on the leaf, so the isotropic density crosses as inherited progenitor content, which is the structural reason the inherited datum of §2.4 is inherited rather than produced; *and two conditions must be met at that crossing, which a concrete model has to satisfy separately: the*

reassignment requires a degenerating Killing field whose freed null direction can be re-founded as a clock, the joining of the legs requires a branch point, and these are independent—the forced Nariai member carries the degeneracy and is not a branch point, while $r = 0$ is the branch point and carries no Killing degeneracy [10], so a model furnishing one without the other furnishes no cosmogenesis. The first of the two is settled as a uniqueness, not merely an availability: across the slicing family the reassignment that promotes a null direction to the fundamental congruence is *uniquely* the one selecting the forced Nariai member, every other vantage yielding a congruence that crosses the embedding’s symmetry structure transversally and so reading as a localised black hole [6]. A model therefore has no freedom in where the reassignment acts, and misplacing it does not fail to give a cosmology by a little—it gives a black hole instead. The scoping of the two rates this law forces—the excursion-side local readout against the observable geometric rate, their boundary—is drawn out in the cosmogenesis paper [19]. What remains open is the *detailed* worldline and field dynamics of the crossing for a concrete matter model [9, 7]—a depth left for a matter model to supply, and resting on a crossing shown well posed rather than merely postponed.

None of these unsettles the result obtained: the branch point’s null geometry decomposes the primordial scalar spectrum into a substrate-determined structure and a progenitor-supplied content, and the branch point transmits that content rather than imprinting one of its own; the super-horizon transfer across the branch point is itself computed— $\Phi \rightarrow \Phi_i$ for every k , with the expanding leg inheriting $\frac{9}{10}\Phi_i$ scale-invariantly^{P15R105}—and carrying the acoustic evolution from that datum through to recombination is the transfer of §4.7, which is run and returns the comparison recorded there. They are, rather, the map of where this cosmology goes next—what displaces the fourth peak, and the full oscillating medium downstream in the matter sector, the tensor sector’s companion in the dynamics paper [10].

11 Discussion

What this paper determines is one thing seen from several sides. A single de Sitter geometry, its scale set by the cosmological constant alone (the maximally symmetric substrate’s sole scale [17]) and read through a causal reassignment at the cosmogenesis branch point, *is* the observed cosmology: the flat- Λ CDM expansion history is its areal radius (§2.3); the acoustic scale is computed from its geometric rate, which the distance data and that angle fix together (§2.4); the primordial scalar spectrum is the characteristic data of its branch point, structure fixed by the substrate and content inherited across the branch point (§§4–8). The Einstein field equations are unchanged; what changes is the reading, and under it the quantities the standard model carries as independent inputs—the present matter density, the dark-energy fraction—are readings of one cosmic clock, not drivers of the expansion, so that the coincidence of Ω_m and Ω_Λ dissolves into our observing at a time of order the geometry’s one timescale. There is a single seed, and the observed universe is what grows from it. And the one scale reaches down as well as out: the same cosmological constant that sets this expansion sets, for every mass M , the *Hubble–Eddington radius* [34] $r_{\text{HE}} = (3GM/\Lambda c^2)^{1/3}$ —the boundary within which local structure stays bound against the cosmic flow and beyond which it is carried off. The slicing geometry reads that boundary as the flat locus of the existent slice’s own curvature, the local bend of the cut exactly cancelling the substrate’s cosmological term [5], and the slicing operator reads it as the handover from sub-marginal bound orbits to the marginally-bound $E = 1$ congruence that *is* this cosmology [7]. So the substrate’s single Λ governs both the global expansion this paper computes and the local scale at which structure resists it—one constant read at two ranges—and the Hubble–Eddington radius, proposed as a local, per-structure test of Λ from the largest bound structures [13], is an independent observational handle on the very constant the expansion history here measures. The two ranges are moreover the same length up to a pure number. The Hubble–Eddington radius—where the slicing surface’s Gaussian

curvature $K_G = 1/\alpha^2 - M/r^3$ vanishes, the local bend cancelling the substrate's cosmological curvature [5]—is $r_{\text{HE}} = (M\alpha^2)^{1/3}$; while the expansion's own amplitude, $(2M\alpha^2)^{1/3}$, is exactly the areal radius at matter- Λ equality ($\rho_m/\rho_\Lambda = \text{csch}^2(3\tilde{\tau}/2\alpha)$, unity at $\sinh = 1$). The two therefore stand in the fixed ratio $2^{1/3}$ for every M : the scale at which a bound structure's gravity balances the expansion and the scale at which the expansion's matter balances its Λ are one length read locally and cosmologically, the factor of two that of the Schwarzschild term against the surface curvature's M/r^3 and nothing else. ^{P15R35}

The comparison with the standard cosmological model is accordingly not *only* a contest of fits—though the geometric rate fits the joint acoustic-and-distance-ladder data at one H_0 (§2.4)—but also, and more deeply, a difference in what each must assume to do so. The standard model *assembles* the observed universe: a dark-energy component for the late-time acceleration, an inflationary sector for the causal contact, flatness, coherence, and near-scale-invariance the background dynamics do not themselves supply, and further early-universe physics where the sound horizon and the expansion rate come into tension. Each part is a real solution to a real problem, and each was introduced to yield the feature it produces. *This cosmology adds no such part.* Causal contact, isotropy, flatness, phase coherence, and scale-free transmission are read off structure the construction already contains—the isotropizing throat (§6), the null boundary on which coherence *is* the characteristic-data condition (§4), the exactly Euclidean constant-time slice (§7), the scale-free crossing that transmits rather than imprints (§8)—each fixed by Λ alone, with no parameter free to produce it. This is the distinction between a structure that *requires* a phenomenon and one that merely *permits* it through adjustable apparatus [12, 11], and it is the criterion by which competing frameworks are rightly weighed ahead of the measurement that will decide between them.

The dark-energy component is the plainest case of the difference: on this cosmology the acceleration is not a sector at all. Since $(dr/d\tilde{\tau})^2 = E^2 - f$ on the energy family, one has $d^2r/d\tilde{\tau}^2 = -f'/2 = rK_G$: *the comoving acceleration is the existent slice's own Gaussian curvature*, up to the positive factor r .^{P3R12} So the expansion decelerates while the slice is negatively curved, turns over exactly where it is flat—the Hubble–Eddington radius, $\rho_m = 2\rho_\Lambda$, at $\sinh(3c\tilde{\tau}/2\alpha) = 1/\sqrt{2}$ —and accelerates thereafter, with nothing added to make it do so. *And that locus is a measurement, not only a description:* the turnover sits where the areal radius reaches the front seam, $r = r_N$, so the acceleration-onset redshift is the offset parameter itself minus one,

$$z_{\text{acc}} = x_0 - 1 = 0.6648 \pm 0.0467, \quad (12)$$

against $(2\Omega_\Lambda/\Omega_m)^{1/3} - 1 = 0.632$ on Planck's parameters—the two agreeing to well within the quoted interval, and with no fit performed here. *That interval is carried as an input throughout rather than derived here*, so it is quoted as the stated uncertainty on the offset parameter and not converted into a significance. *What makes the equation worth stating is what it does not contain:* z_{acc} is a redshift, measured calibration-free, so it is untouched by the distance-ladder tension, and it fixes x_0 without H_0 , without a ladder and without the microwave background. The single dimensionful scale is where any disagreement must then live, and the age follows from the same parameter in closed form, $t_0 = (2r_N/\sqrt{3}c) \text{asinh}(x_0^{3/2}/\sqrt{2})$. The late-time acceleration is thus read off the same structure that fixes the local boundary of a bound system.

And the growth sector, written on this rate, loses its parameters entirely — which turns a known numerical curiosity into a statement about the epoch. Substituting $H = (c/\alpha) \coth u$ and the Friedmann readout's $4\pi G\rho = \frac{3}{2}(c/\alpha)^2 \text{csch}^2 u$ into the growth equation and changing to u , every factor of $(c/\alpha)^2$ divides out:

$$3D'' + 4\coth(u) D' - 2\text{csch}^2(u) D = 0. \quad (13)$$

The scale does not merely fail to appear—it cancels, because at Nariai the source is fixed by Λ and the time variable carries α too. *The decaying mode is the rate itself*, $D_- = \coth u = H\alpha/c$,

and reduction of order gives $D_+ = \coth u \int_0^u \sinh^{2/3} v \operatorname{sech}^2 v dv$. And the matter fraction is a clock reading: $\cosh^2 u = 1/\Omega_m$ exactly, so $\Omega_m = \operatorname{sech}^2 u$.

On these variables the normalisation of the standard growth factor — $J(\Omega_m) = \int_0^\infty (1+z) dz / [\Omega_m(1+z)^3 + 1 - \Omega_m]^{3/2}$, known to cross unity once near the concordance density [1] — becomes $J = \frac{2}{3} \cosh^2 u_0 (D_+/a)|_0$, whose matter-domination limit $D_+/a \rightarrow \frac{3}{5}$ returns the analytic endpoint $J \rightarrow \frac{2}{5}$. Differentiating the condition $J = 1$ gives an exact identity between the two sides' derivatives, $\propto \frac{9}{2} \Omega_m - 2$, and integrating it from the common origin leaves

$$\int_0^{u_0} a(v) \Omega_m(v) \left[\Omega_m(v) - \frac{2}{3} \right] dv = 0, \quad (14)$$

the growth-weighted history of Ω_m balanced about $\frac{2}{3}$ ^{P15R12}.

The pivot is the deceleration-to-acceleration turnover: $\Omega_m = \frac{2}{3}$ is $\rho_m/\rho_\Lambda = 2$ exactly. (14) is solved at $\Omega_m = 0.31516$, so the density at which that normalisation equals unity is fixed by an equation with nothing free in it.

Two scope statements belong with that, and both narrow it. The turnover is not this construction's property: any flat matter-and- Λ rate has it, and what is this construction's is the identification of that turnover with a geometric locus — the areal radius there being $\alpha/\sqrt{3} = r_N$, the Nariai radius and the merged double root (above). So the balance pivots on the turnover, and the geometry is what makes the turnover a place.

And the rate used is the stacking one, which is the right rate for the object but not for this construction's own growth. The published normalisation is a matter-and- Λ integral, and the stacking rate written in the fitted pair is that rate, which is why the derivation reproduces it. The rate rule assigns perturbations to the leaf (§2.2), and on the leaf rate the same integral returns 0.99940 rather than unity. So what is derived here is the root of the standard normalisation, and what remains contingent is that the present epoch lies near it.

What that figure does **not** measure is how far the root moves, and saying so matters because it invites that reading. Continuing the closed form onto the leaf rate is a closed form applied to a rate it does not solve. Solved directly, the root moves the other way and by less — the leaf root sitting at $u_0 = 1.180039$ against the stacking 1.180309, a shift of 1.1% of the gap to the measured epoch and away from it, taking the offset from 0.704 to 0.713σ ^{P15R13}. So the root's two-per-cent offset from the measured epoch — $x_0 = 1.6315$ at the leaf root against the measured 1.6648 — is not an artefact of the rate: it stands, and wants a mechanism.

The transmission dichotomy (§8) is where the distinction between requiring and permitting is sharpest, because there the two frameworks make opposite structural commitments about one object. A non-degenerate horizon's exponential approach imprints a scale-invariant spectrum — the very mechanism by which inflation produces near-scale-invariance — while the degenerate Nariai seam carries no scale and the branch point, where the modes cross, accumulates no phase at all, so the progenitor spectrum is transmitted unaltered. Inflation accommodates the observed tilt because a freely specified potential can be tuned to it; reading that fit as a confirmation mistakes a model with enough adjustable structure to match for one that required what was found (§9). This cosmology cannot tune: the finite tortoise coordinate at the branch point *requires* that the crossing not imprint a scale, so the framework has no inflationary scale-invariant attractor, no consistency relation, and no substrate-sourced primordial B -modes. The amplitude and tilt it does not derive it inherits, exactly as flat Λ CDM inherits the baryon-to-photon ratio from a baryogenesis it does not model; on that single datum, of the same kind and count the standard model already carries, the two stand level. A framework is credited for requiring the structure it explains, not faulted for measuring the boundary data it does not — and the asymmetry falls on everything else.

The verdict this licenses must be drawn on the right axis, and confined to it. On the axis of theory-choice — the requiring rather than the permitting of the phenomena, the consolidation of many results under one structure, the absence of a device added per problem — the comparison

is decidable from the structural record, and it falls to this cosmology [12]. On the axis of data-discrimination the picture is split: the geometric rate fits the acoustic scale and the baryon-acoustic distance ladder together at one H_0 (§2.4), leaving the discrepancy with the local ladder where the standard model leaves it—while on the light elements and the low multipoles the two frameworks are even. *On the microwave-background peak structure they are not*: the transfer’s likelihood comparison rejects this arm’s spectrum on TT shape (§4.7), and that is the sharpest datum against the construction that the corpus holds. So the standing is stated as it stands: favoured on the structure, level with the standard model on the light elements and the low multipoles, and carrying a spectrum computed from a background fitted to the distances alone—which reproduces the comb to a part in six hundred and is rejected on shape. The data axis is not even, and where it is uneven it runs against the construction, which is the direction a framework that has staked falsifiable commitments—no scale-invariant attractor *reaching the observer*, no consistency relation, no substrate *B*-modes—must be prepared for, precisely where the standard model keeps its freedom^{P15R82}.

The low-multipole deficit is a mild, non-discriminating feature (§§7, 10). The flat projection of the discrete closed- S^3 source gives a parameter-free deficit below $\ell \approx 8$ —real, and set by Λ through r_0 and D_C —bottoming at $\ell = 4$, at $\approx 0.49, 0.44, 0.36$ and 0.67 of the Λ CDM expectation at $\ell = 2, 3, 4, 5$. At that depth CR’s smooth deficit matches neither the sharp observed quadrupole-only dip nor the near- Λ CDM octopole, and under the exact cosmic-variance likelihood the two frameworks are statistically indistinguishable at low ℓ ($\Delta(-2 \ln L) \approx +1.6$ over $2 \leq \ell \leq 10$, inside cosmic variance). So the sector neither confirms nor refutes: it is a genuine parameter-free prediction whose depth places it consistent with Λ CDM within the lowest multipoles’ cosmic variance. The framework’s exposed edges are the acoustic peak structure, where the transfer reproduces the comb and differs from the sky in the acoustic contrast (§4.7), and the damping-*scale* signature (§4), a computed, non-reabsorbable effect whose size the handover fixes and whose sign the diffusion integral’s endpoint does. Its sharpest test is the geometric expansion rate itself, carried to the distance ladder and confronted with the DESI DR2 baryon-acoustic dataset at $\chi^2/\text{dof} \simeq 1$ (§2.4): the rate that carries the full ladder is the rate the spectrum is computed on, so the two are one commitment.

The framework’s standing includes what the standard model has genuinely built and this cosmology has not. Dark matter is inferred from multiple independent, cross-consistent lines—rotation curves, gravitational lensing, the merger offsets, the acoustic-peak structure, the growth of structure—and this cosmology carries the matter density as the bend of the spatial cut without yet removing the component or answering its particle question; that column stands at full weight. Standard nucleosynthesis derives the light-element abundances from one measured parameter, a genuine achievement this cosmology meets on the same footing rather than exceeds: the collapse’s cooling leg is a standard nucleosynthesis run on one inherited datum (§2.4; the cosmogenesis paper [19]), producing helium-4 and deuterium at their observed values—the freeze-out temperature the data demands being the bottleneck the standard rate delivers—and, because the run is standard, carrying lithium-7’s standard threefold over-prediction, the lithium problem shared rather than solved. On the light elements the two frameworks stand even: the same two successes, the same one problem, one progenitor handover fitting the pattern together, and this cosmology’s open edge the last-percent precision against the measured abundances. And the framework is young: the *detailed* dynamics of matter crossing the branch point (its crossing shown well posed and structurally governed, §10), the derivation—as against the measurement—of the inherited data, and the Standard-Model matter *content*—the gauge representations and the mass spectrum, which the framework does not supply, its geometry shown to force only the discrete flavour skeleton [20]—remain to be built (§10; [9]). These are open frontiers, not defects: a theory is not marked down for what it has not built, only for a claim it makes that fails. They are named plainly here because an economy that favours this cosmology on the structure it carries would be worth nothing bought by concealing the

structure it does not.

12 Conclusion

So, plainly, what this paper claims and what it does not. It claims that the observed expansion history, the computation of the acoustic scale, and the structure of the primordial scalar spectrum are consequences of a single de Sitter geometry read through the causal reassignment its own horizon geometry selects—one seed, grown, the field equations unchanged—and that on the economy of assumption, the criterion by which theory-choice is rightly made ahead of the deciding measurement, this reading is favoured over the assembled standard picture. On the data axis it claims a more limited thing: that the axis is split—the expansion history fitting the distance ladder, which fixes H_0 with the acoustic angle, and the abundances confirmed, while the acoustic peak structure, computed from that same background and scored by the full-spectrum likelihood, counts against it—with that structure and the damping-tail signature the edges still to be settled (the low multipoles a mild non-discriminating deficit consistent with Λ CDM within cosmic variance). It does not claim to be a complete cosmology: its matter sector, the derivation of its progenitor spectrum, and its fermion content remain to be built. It claims to have shown that the universe we observe is the reading of one geometry, and to have staked the falsifiable commitments by which that claim can be tried.

A final word on the register, because it is the thesis rather than an aside. The beginning this cosmology describes is the branch point at $r = 0$ —the locus at which the collapse leg of the cosmogenetic contour becomes the expansion leg [9]—and it is not a curvature singularity reached and left behind. *The curvature there is set by the substrate’s own scale.* The throat is α , the defining constant of the maximally symmetric manifold the cut is taken on, and the divergence of the invariants computed in the areal chart is that chart degenerating, exactly as a polar chart degenerates at a pole—not a curvature scale of the geometry [19, 17]. Two further facts stand with it: no finite cosmic-time layer ever reaches the locus, and the continuation through it carries no scale, since $f \rightarrow -2M/r$ diverges so that the tortoise coordinate $r_* = \int dr/f$ converges and what is transmitted is fixed by the analytic structure rather than by a length. *The branch point is crossed by continuation, not traversed by a worldline.* The expansion is not a space ejected from a point but the reading, on the near side of that branch point, of a spatial layer still advancing, the branch point itself a collapse that in the frame it bounds is never complete. The distinction the whole programme turns on—between what has finished happening and what is still underway—is thus the distinction the cosmology is built from: the universe is not the collapsed record of a beginning but the still-evolving layer that record represents, read here as one de Sitter geometry.

Appendix R Computational Receipts

Each computation marked ^R in the text is verified by a runnable receipt in the `receipts/` directory that ships with this work; status OK = verified (traced, run, output matches the claim). This appendix is generated from the receipt index, not maintained by hand.

P15R1 `P15_the_sky_phase_fit_and_its_uncertainty` [OK]

sec:intro (FITS the sky’s acoustic phase from the peak positions and PROPAGATES its uncertainty: $\ell_n = \ell_A(n + \phi/\pi)$ on 220.4, 537.7, 817.3 returns $\phi/\pi = 0.2405$ against the paper’s 0.2404, and the control’s 0.0043 offset is seven parts in a thousand of the 0.615 disagreement. The quoted $\sigma_{\text{simeq}0.008}$ is the TWO-multipole value; one multipole gives 0.0046 and twice the separation – so the paper’s figure is the CONSERVATIVE end, and the sentence now says which assumption it carries). *Computes:* least-squares fit; Monte-Carlo propagation at one and two multipoles *Run:* `python3 receipts/P15_CR_cosmology/P15_the_sky_phase_fit_and_`

P15R2 `P15_the_fixed_point_route_is_closed_by_the_monotone` [OK]

‘PO-31’ (register), ‘THE_WISDOM_LEDGER’ r1942 (the one route the corpus ever named for DERIVING A_s – a fixed point of a stationary recursion – is CLOSED by ‘PO-40’*’s monotone:* entropy per baryon rises strictly at every crossing, bounded below unconditionally by Landauer at $k_B \ln 2$, and a map that strictly increases a coordinate has NO fixed point; independently the chain is finite, so there is no asymptotic limit for a fixed point to be the limit OF). *Computes:* the two reasons checked and shown not to share a premise – one needs only that the increment is positive, the other only that it is bounded below; lap bounds computed on the Landauer floor (1.7e10) and on the present-day increment (1.8e9) *Bound:* bounded: PARTIAL invariance of A_s alone is not stationarity and SURVIVES, needing the lap map r1942 itself called unbuilt; and this closes a route, not the row *Run:* `python3 receipts/P15_CR_cosmology/P15_the_fixed_point_route_is_closed_by_the_m`

P15R3 `P15_the_tilt_is_the_wrong_absorber` [OK]

‘PO-24’; ‘sec:refit-bound’ (the diffusion signature’s *local* mimicked tilt is $\mathrm{d} \ln(\text{ratio}) / (r^2 - 1) (\ell / \ell_D)^2$, which runs -0.0002 to -1.31 across plik_lite’s own $\ell = 30$ – 2508 — *a factor of 6989, exactly $(\ell_{\max} / \ell_{\min})^2$* — so absorption by a SINGLE tilt is necessarily window-local and the fitted Δn_s is a range-weighted average of a quantity nowhere equal to it). *Computes:* the slope profile and its swing, asserted against the exact $(\ell_{\max} / \ell_{\min})^2$; that the \$185\$-bin ceiling truncates the steep part; and that the reported $\Delta n_s = -0.0304$ equals the true slope at $\ell = 381$ alone; CONTROL at $r=1$ vanishes identically at every ℓ *Bound:* bounded: this shows a constant tilt is the wrong absorber and the displacement is not a stable parameter shift. *It does not run the joint fit*, which remains the row’s discharge *Run:* `python3 receipts/P15_CR_cosmology/P15_the_tilt_is_the_wrong_absorber.py`

P15R4 `P15_the_joint_fit_leaves_the_gaussian_and_the_bound_was_chi2_not_sigma` [OK]

‘PO-24’; ‘sec:diffusion-scale’, continuing ‘C62’ and ‘r6409’ (*THE JOINT FIT RUN: THE RESIDUAL IS THE PREDICTED GAUSSIAN TO A CORRELATION OF \$1.000000\$, AND IT SURVIVES LARGER THAN THE BOUND IT WAS TO BE MEASURED AGAINST.* *‘r6409’ predicted a Gaussian-shaped residual no tilt removes; fitting A and Δn_s jointly against the signature-carrying spectrum on plik_lite’s own bandpowers and covariance returns exactly that — the residual correlates with the analytic $S(\ell) - A(\ell/1000)^{\Delta n}$ at \$1.000000\$. It survives at $\chi^2_{\text{bin}} = \$1.497$ over ‘P15’*’s 185-bin ceiling window ($\ell = 100$ –\$1758, 171 covered bins). AND THE BOUND WAS QUOTED IN THE WRONG UNITS:* ‘C62’ says $\chi^2_{\text{bin}} = \$0.26$ per bin and converts to σ by a square root in its own check; ‘r6409’ restated it as “\$0.26 sigma per bin” and the ‘r6521’ order inherited that — the looser bound quoted as the tighter, since $\chi^2_{\text{bin}} = \$0.26$ $\chi^2_{\text{bin}} = \$0.510$ σ_{bin} . *AND IT IS THE MORE FAVOURABLE OF ‘C62’*’s TWO**, which says in terms that the instrument route (\$0.92\$) “is the more faithful of the two and it is the LARGER, so the wash is the weaker claim and is asserted at the weaker bound”. *AND THE DISPLACEMENT IS NOT A NUMBER, NOW MEASURED:* $\Delta n_s = -0.083$ over $\ell = 100$ –\$1760\$, -0.521 over \$1400\$–\$2508\$ — a factor of \$6.3\$ across windows of the same data, with absorption rising monotonically as the window narrows upward (\$69.8\%\$ to \$97.6\%\$). *In the likelihood’s own units* the signature costs $+357.3$ χ^2 with amplitude alone and $+84.5$ over 171 bins after the tilt is refitted: the fit *improves* the comparison by \$272.8\$,*

absorbing 76% , and does not remove it.). *Computes:* C62's unit asserted from its own text and its own 'math.sqrt' conversion; r6409's restatement asserted; C62's two-route sentence asserted after stripping comment markers; ****two calibrations — a known injected tilt recovered to 10^{-11} , AND the SCALE, which the first is blind to because a tilt-recovery test is unit-free****; the pipeline asserted to reproduce 'chi2.of' on the same spectrum and window; the residual's correlation with the analytic shape; the residual asserted larger than both C62 routes; the displacement's spread across windows; monotone absorption; the sky-cost split; the red/blue sign difference between the two fits; and the $r=1$ control returning $\Delta n_s \sim 10^{-14}$ and $\chi^2 \sim 10^{-22}$ *Bound:* ****scope:** what a tilt ABSORBS, not whether CR fits the sky.**** TT only, no polarisation, no lensing, no $\ell \sim 100$ from this baseline; two parameters free, so 'C62's scoping stands unchanged — an upper bound on what survives in shape, and no bound at all on the tilt, since ω_b moves r_D itself. n_s is INHERITED boundary data here****, so a displacement is a different INPUT and not a conflict; what would be a tension is a constraint on n_s that does not run through the damping tail, which this does not supply. The baseline is the instrument's control arm, unlensed and ceiling-limited where the sky is neither — 'C62's own stated reason its routes differ by about three *Run:* python3 receipts/P15_CR.cosmology/P15.the_joint_fit_leaves_the_gaussian_and_the_bound_was_chi2_not_sigma.py

P15R5 P15.the.potential.at.the.handover.is.not.free [OK]

'PO-13'; 'sec:transmission', and 'C21'/'C19' (the potential at the handover is ****not free and not primordial****: the super-horizon join is conservation of $\mathcal{R}$, so $\Phi_{\text{rm exp}}/\Phi_{\text{coll}} = (3/2)/(5/3) = 9/10$ exactly and Φ is constant on the matter-dominated expanding leg — ****which 'P15' already states and receipts, while the instrument sets the potential to its primordial value instead****). *Computes:* the join in exact arithmetic; that the prescription is a FOURTH coding distinct from all three the row measured ($\$2.43$, $\$5.14$, dead comb); that Θ and Ψ are then read at ONE locus, which is the row's own discharge criterion; and the omission's size *Bound:* bounded hard: ****the omission is $10/9$, not 2.4 , and being scale-invariant it moves an amplitude and cannot move a ratio**** — P_1/P_2 and ℓ_1/ℓ_A are untouched, so this is NOT the cure and must not be read as one. The spectrum it yields is an instrument run, not made here *Run:* python3 receipts/P15_CR.cosmology/P15.the.potential.at.the.handover.is.not.free.py

P15R6 P15.the.one.fitted.number.moves.the.scale.and.not.the.peak [OK]

'PO-13'; 'sec:refit-bound', and the instrument's own 'LATARG' comment (****THE ONE FITTED NUMBER MOVES THE ACOUSTIC SCALE AND DOES NOT MOVE THE FIRST PEAK, SO THE DEFICIT IS NOT AN ARTEFACT OF WHERE THE PIN WAS PUT.**** 'ACOUSTIC.two_arm.py' exposed 'LATARG' at 'r2441' expressly to ask ****"GIVEN that ℓ_A is fitted, is the peak deficit an artefact of where the pin was put?"**** and ****the question had never been run****. Scanned over a factor of 3.6 in z_{onset} on the converged grid: ℓ_A runs $\$360.6$ to $\$239.3$ (51%) while ℓ_1 sits at $\$206$ – $\$210$ (2%). ****The deficit is $\ell_1 = 206$ against the sky's $\$220.6$ at every onset.** **And the trade is then an IDENTITY****: pinning ℓ_A to the measured $\$301.6$ costs $\$6.59\%$ on ℓ_1/ℓ_A , pinning ℓ_1/ℓ_A to the sky costs $\$6.59\%$ on ℓ_A — the same number twice, because it is one deficit booked against either of two observables. ****And "both pinned" is unreachable rather than skipped****: under the symmetric convention the control's scale approaches $\$301.4$ from above, so 'LATARG' $= 301.6$ lies below its floor and 'brentq' reports same-signed endpoints — the control ARRIVES where this arm SPENDS its fitted onset to get.). *Computes:* that the configuration reproduces 'P15's own quoted $\ell_1 = 206$ BEFORE its scan is read; that ℓ_A 's range exceeds $\$40\%$ and ℓ_1 's is under $\$5\%$; that ℓ_A falls monotonically; that ℓ_1 misses the sky at EVERY onset and the misses spread by under $\$3$ points; that the two pinnings agree to 10^{-3} ; that the ratio nonetheless crosses the sky, so reading it alone gives the opposite answer; and that the control's floor sits below 'LATARG' *Bound:* ****scope:** driven, 'LMAXL=520', 'LSTEP=2', each arm on its own geometry throughout.**** It does not shrink the deficit and does not say the construction is wrong — it says $\$0.6830$ and $\$-6.6\%$ are two spellings of one number, and that no choice of the one fitted number touches it. The 'LMAXL=1300' cross-check is ****run and opt-in**** ('cutoff', ****measured 1207s a point**** against the scan's $\$92$ s, $\$943$ modes against $\$376$): $\ell_1 = 206$ at both ends, while the HIGHER peaks do move — so the invariance is the first peak's and not the spectrum's *Run:* python3 receipts/P15_CR.cosmology/P15.the.one.fitted.number.moves.the.scale.and.not.the.peak.py**

P15R7 P15_the_symmetric_comparison_was_never_runnable_and_the_quarter_was_two_fifths [OK]

‘PO-13’; ‘sec:refit-bound’ (**THE SYMMETRIC UNDRIVEN COMPARISON ‘r4549’ PROMISED AND NEVER LANDED — ITS THREE CLAIMS HOLD, ITS ONE NUMBER DOES NOT.** ‘r4549’*s* own message read *“60’s receipt for this result is not yet pushed and lands next”*; **no receipt in the tree ever set ‘LZSTART’, and the sound-horizon half of the convention had NO KNOB AT ALL** until ‘LRSFROM’ was added at ‘r6476’, so its numbers were unreproducible from the tree by anyone including their author. Run now: matching the start alone *overshoots* and changes sign** ($\$+0.2249\backslash\{\}$ to-0.4719\$, the magnitude doubling); matching the convention too leaves a residue on the far side of zero ($\$-0.0865\backslash\{\}$); and *the implied mode is identical across those last two rows***, $\backslash\{\}$ ell_1=482\$ in both, while the convention moves $\backslash\{\}$ ell_A\$ from \$301.4\$ to \$397.1\$. *But the residue is \$38\backslash\{\}%\$ of the original, not the “quarter” ‘r4549’ reported** — a factor of \$1.5\$, in the direction that makes the dissolution look more complete than it is.). *Computes:* the commit’s reachability asserted FIRST, so a shallow clone cannot turn the two commit-pinned checks into a vacuous pass; that ‘r4549’ touched no file under ‘receipts/’; that no receipt at that revision set either knob; the sign change and the growth in magnitude; the residue’s sign and size; the mode’s identity across the convention change; and that the residue exceeds a third *Bound:* *scope:* undriven on both arms, ‘LMAXL=520’, ‘LSTEP=2’. *It does not* re-open ‘r4549’*s* verdict, which survives the correction — two fifths is still a minority and still on the far side of zero. *The structural finding is the shared one*: a convention moves $\backslash\{\}$ ell_A\$ and leaves $\backslash\{\}$ ell_1\$ at \$482\$; the fitted number moves $\backslash\{\}$ ell_A\$ and leaves $\backslash\{\}$ ell_1\$ at \$206\$. Both times the denominator moved and the mode did not *Run:* python3 receipts/P15_CR_cosmology/P15_the_symmetric_comparison_was_never_runnable_and_the_quarter_was_two_f*

P15R8 P15_the_angular_momentum_sector_is_not_a_propagating_mode [OK]

‘PO-31’s first computation; ‘sec:coherence’s throat tower (**the damping removes the anisotropic signature, not $\backslash\{\}$ J\$ — because $\backslash\{\}$ J\$ is not among the modes the tower is a statement about.** ‘P15’s $\backslash\{\}$ nu²= $\backslash\{\}$ tfrac14- $\backslash\{\}$ ell($\backslash\{\}$ ell+1)\$ is reproduced exactly, and it is a computation about a *propagating field mode***, one with a mass that can be heavy. But in the standard multipole decomposition $\backslash\{\}$ ell=0\$ carries $\backslash\{\}$ M\$, $\backslash\{\}$ ell=1\$ axial carries $\backslash\{\}$ J\$ — the slow-rotation limit, a STATIONARY solution, non-propagating** — and only $\backslash\{\}$ ell $\backslash\{\}$ ge2\$ radiates. $\Rightarrow$ *Applying a principal-series argument there assigns a decay rate to a conserved charge.**** And ‘P09’ already carries the concept as its *non-radiative skeleton ... the wall is where the field begins to propagate*”; it needed connecting, not inventing). *Computes:* ‘P15’s tower reproduced at $\backslash\{\}$ ell=0,1,2,3\$, the sectors by what each carries and whether it propagates, and that $\backslash\{\}$ J\$’s sector is not among the propagating ones *Bound:* *does NOT* establish that $\backslash\{\}$ J\$ survives the leg** — only that the no-hair tower is not the mechanism that would remove it. A charge can still be carried off by matter or torqued, and *the constrained-sector analysis on the throat is a computation not done here* *Run:* python3 receipts/P15_CR_cosmology/P15_the_angular_momentum_sector_is_not_a_propaga

P15R9 P15_the_tower_is_robust_to_the_throat_being_squashed [OK]

‘prop:throat’s equal radii; ‘sec:coherence’s tower (**‘prop:throat’ is a $\backslash\{\}$ J=0\$ construction** — its argument is “direct from $\backslash\{\}$ f\$ at the Nariai mass”, and $\backslash\{\}$ f=1-2GM/c²r-r²/ $\backslash\{\}$ alpha²\$ is the *non-rotating* metric. *So the charge whose survival ‘PO-31’ asks about is the one whose presence would deform the geometry the argument is conducted on****, a dependency drawn nowhere. *But the tower is robust*: generalising to $\backslash\{\}$ nu²= $\backslash\{\}$ tfrac14- $\backslash\{\}$ lambda $\backslash\{\}$, $\backslash\{\}$ ell($\backslash\{\}$ ell+1)\$ with $\backslash\{\}$ lambda=r- $\backslash\{\}$ rm dS²/r- $\backslash\{\}$ S²\$, *the* $\backslash\{\}$ ell=0\$ base is $\backslash\{\}$ tfrac14\$ for EVERY $\backslash\{\}$ lambda***, and $\backslash\{\}$ ell $\backslash\{\}$ ge1\$ stays principal series for any $\backslash\{\}$ lambda;1/(4 $\backslash\{\}$ ell($\backslash\{\}$ ell+1))\$ — \$1/8\$ at $\backslash\{\}$ ell=1\$, so the damping survives until the $\backslash\{\}$ mathrm{dS}_2\$ radius falls below \$0.354\$ of the $\backslash\{\}$ S²\$ radius, *a factor of \$2.83\$****). *Computes:* $\backslash\{\}$ lambda=1\$ reproducing ‘P15’s tower, the $\backslash\{\}$ ell=0\$ base’s independence of $\backslash\{\}$ lambda\$, and the thresholds at $\backslash\{\}$ ell=1,2,3\$ with the higher multipoles safer *Bound:* *does not show the conclusion survives rotation*** — *what* $\backslash\{\}$ lambda\$ a rotating progenitor produces is not computed**, and a rotating near-horizon geometry is generally *warped* rather than a direct product, so $\backslash\{\}$ lambda\$ may not even be the right single parameter. It measures a margin and names what would decide it *Run:* python3 receipts/P15_CR_cosmology/P15_the_tower_is_robust_to_the_thro

P15R10 P15_rotation_moves_the_throat_away_from_the_damping_threshold [OK]

the rotating Nariai locus; ‘r6497’s named computation (**rotation moves the throat AWAY from the damping threshold.** Solving the Kerr-de Sitter double root $\backslash\{\}$ Delta_r= $\backslash\{\}$ Delta_r=0\$ gives $\backslash\{\}$ a²=r²($\backslash\{\}$ alpha²-3r²)/($\backslash\{\}$ alpha²+r²)\$, which *recovers* ‘prop:throat’s

own $r_N = \alpha/\sqrt{3}$ and $M = \alpha\sqrt{3}/9$ at $a=0$ rather than assuming them^{***}. The family is bounded: $a_{\max} = (2-\sqrt{3})\alpha$ exactly^{**}, attained where $\Delta_r = 0$ — the *ultracold* point where the double root becomes triple. And $\lambda = 1$ exactly^{**} at $a=0$, rising monotonically with a , against ‘r6497’'s threshold of $1/8$). *Computes*: the $a=0$ reduction to $r^2 f(r)$, the locus recovering both corpus values, $a_{\max}$ in closed form coinciding with the triple root, and $\lambda \geq 1$ across the physical branch *Bound*: λ here is a PROXY and it is named^{**}: the ratio ^{**}at the pole^{**}. The rotating near-horizon S^2 is warped through $(r_N^2 + a^2)\cos^2\theta$, so one ratio does not describe it — ‘r6497’ warned of exactly this. ^{**}What is established is the direction and its size at one well-defined point^{**}; for the conclusion to fail the warping must reverse a trend running the right way by a factor of eight *Run*: `python3 receipts/P15_CR_cosmology/P15_rotation.moves`

P15R11 `P15_the_warped_throat_keeps_every_mode_above_the_monopole_decaying` [OK]
‘PO-31’; ‘sec:throat’ and ‘prop:throat’, continuing ‘r6497’/‘r6499’ (^{**}THE WARPED HARMONIC PROBLEM, DONE: EVERY MODE ABOVE THE MONOPOLE STAYS PRINCIPAL-SERIES ACROSS THE WHOLE ROTATING FAMILY, AND THE MARGINAL MEMBER IS THE NON-ROTATING ONE.^{**} ‘r6499’ left the ratio read at the POLE as a proxy, warning that the rotating near-horizon sphere is warped through $r_N^2 + a^2\cos^2\theta$ so one ratio may not describe it and ℓ may not be a good label. ^{**}The near-horizon limit is TAKEN rather than posited^{**} and is a warped product, not a direct one: ρ_0^2 multiplies the dS_2 and polar directions alike and the dS_2 is FIBRED over the sphere by $\tilde{k} = 2r_0 a \Xi / (r_0^2 + a^2)$, non-zero at every rotating member. A massless scalar still separates, the warp cancelling from the relation between the transverse eigenvalue and the dS_2 operator. ^{**}AND FOR THE AXISYMMETRIC MODES THE WARP CANCELS ALTOGETHER^{**}: $W \propto \sin\theta$ and $P \propto \Delta_\theta \sin\theta$ exactly, so the $m=0$ problem is $(\Delta_\theta \sin\theta)^2 + E \sin\theta = 0$ — a SPHEROIDAL deformation of Legendre in which ρ_0 never appears. ^{*}The order’s worry is answered by the structure, not by the numbers.^{*} The decay condition is $\nu^2 = \frac{14-L}{2E-L} \tilde{k}^2$, the fibration term non-negative, so rotation can only deepen the damping. ^{**}TWO EXACT BOUNDS SETTLE IT WITHOUT A SCAN^{**}: $L^2 \geq 1$ on the physical branch (from $L^2 - 1 = -(3u-1)(u+2)/(3u^2+6u-1)$) and $E_{L=1} \geq 2$ above the monopole (Rayleigh, $\Delta_\theta \geq 1$ pointwise), each with equality only at $a=0$ — so $L^2 E_{L=1} \geq 2$ against the threshold $\frac{14}{3}$, ^{**}a factor of eight, attained where the rotation vanishes^{**}. The monopole keeps $\nu^2 = \frac{14}{3}$ exactly.). *Computes*: T3 asserted symbolically ($\Delta_r(a=0) = r^2 f$, not $r f$); the locus re-derived from $\Delta_r = \Delta_r' = 0$ for BOTH a^2 and M and asserted to return ‘prop:throat’'s values at $a=0$; r_* asserted to be exactly where $\Delta_r = 0$ (T2); the near-horizon limit asserted equal to the warped ansatz coefficient by coefficient at exact members, with the τ rescaling coming out exactly $1/(r_0^2 + a^2)$ and no stray cross terms; W^2 and P^2 asserted free of ρ_0 ; ^{**}the solver calibrated against Legendre $l(l+1)$ at $a=0$ across $m=0..4$ BEFORE any warped zero is believed^{**}; every sample asserted on the physical branch (T1); the monopole asserted both numerically and EXACTLY (the $m=0$ flux matrix annihilates constants, so $E_0=0$ is not a fitted zero); and both closed-form bounds *Bound*: ^{**}scope: a massless SCALAR on the near-horizon geometry — the same proxy ‘r6497’'s $\nu^2 = \frac{14-\lambda}{\ell(\ell+1)}$ is built on.^{**} It does not decompose gravitational perturbations into axial and polar. ^{**}It is about whether the DAMPING MECHANISM reaches these modes; it is NOT about whether the J survives the leg^{**} — a charge can still be carried off by matter or torqued, and ‘r6495’'s separation of J from the propagating tower is untouched. The geometry is the throat’s exact limit, not the collapse leg’s history *Run*: `python3 receipts/P15_CR_cosmology/P15_the_warped_throat_keeps_every_mode_above_the_monopole_decaying.py`

P15R12 `P15_the_growth_root_is_a_moment_balance_pivoting_on_the_nariai_radius` [ALL PASS]
sec:discussion (^{**}THE GROWTH SECTOR IS PARAMETER-FREE AND THE NORMALISATION ROOT IS A MOMENT BALANCE PIVOTING ON THE NARIAI RADIUS.^{**} Substituting $H = (c/a)\coth u$ and $4\pi G\rho = (3/2)(c/a)^2 \cosh^2 u$ into the growth equation gives ^{**}3D^{**} + 4coth(u)D' - 2cosh^2(u)D = 0 — alpha CANCELS^{**}, because at Nariai the source is fixed by Λ and the time variable carries α too. Decaying mode is the rate itself, $D_- = \coth u$; growing mode by reduction of order. ^{**} $Om_m = \text{sech}^2(u)$ exactly^{**} — a clock reading. $J = (2/3)\cosh^2(u_0)(D+a)$, matter-domination limit $D+a \rightarrow 3/5$ giving the analytic endpoint $J \rightarrow 2/5$. The identity $G'/F' = (9/2)Om - 2$ integrates the condition to ^{**}int a Om ($Om -$

2/3) $du = 0^{**}$, solved at $Om = 0.315162424 - ^{**}$ and the pivot $Om=2/3$ is $\rho_m/\rho_L = 2$ exactly, at areal radius $\alpha/\sqrt{3} = r_N^{**}$). *Computes:* r4253 *Bound:* 61 *Run:* python3 receipts/P15_CR.cosmology/P15.the.growth.root.is.a.moment.balance.pivoting.on.the.nariai.radius.py

P15R13 P15.the.growth.root.on.the.leaf.rate.is.not.a.moment.balance.and.the.gap.stands [OK]

sec:discussion (**PO-38: THE MOMENT-BALANCE FORM DOES NOT SURVIVE ON THE LEAF RATE, THE ROOT BARELY MOVES, AND IT MOVES THE OPPOSITE WAY FROM WHAT THE CONTINUED INTEGRAL IMPLIES.** PO-38 asked for the growth normalisation root re-solved on the LEAF rate and warned that radiation may break the cancellation that made the growth equation parameter-free. ** (1) IT DOES, EXACTLY. ** The derivation rests on "the decaying mode IS the rate"; applying the growth operator to $D = H$ with radiation present gives $L[H] = (32/3) \pi G H \rho_r$, which vanishes iff $\rho_r = 0$. With that gone the reduction of order, the G'/F' identity and the balance all go. $Om_m = \text{sech}^2(u)$ fails on the leaf rate ($9.3e-4$ at $v=0.2$) and the balance integral returns $-1.71e-4$ at the leaf root where the stacking one vanishes to $1e-13$. α still cancels, so the equation stays scale-free but acquires Om_r : the loss is parameter-freedom, not scale-freedom. ** (2) WHAT REPLACES IT ** is the growth ODE solved on the rate, with the Meszaros mode $1 + (3/2)y$ as an EXACT initial condition (verified to $1.6e-12$) and the published $(2/5)a/Om$ convention calibrated against the closed form where the closed form is valid ($2e-12$). ** (3) THE ROOT: OUTCOME 3, WITH A SIGN. ** Leaf $u_0 = 1.180038880$ against the stacking 1.180309372 – a move of 1.1% of the gap, taking the offset from 0.704 to 0.713 sigma against the corpus's measured $x_0 = 1.6648 \pm 0.0467$. **The 2% is not an artefact of the rate; the gap stands and wants a mechanism** – and the shift goes FURTHER from the measurement, not closer. ** (4) THE CONTINUED INTEGRAL GETS THE DIRECTION BACKWARDS. ** The route behind the recorded 0.99934 moves the root TOWARD the measurement (0.693 sigma) where solving the equation moves it away, and by $1.7x$ the size in u_0 . **That figure does not measure how far the root moves; it measures a closed form failing on a rate it does not solve.** ** (5) THE PIVOT SPLITS RATHER THAN MOVES. ** $Om_m = 2/3$ is the acceleration turnover only when matter and Lambda are the whole content; radiation decelerates too, so $q = 0$ needs $Om_m + 2 Om_r = 2 Om_\Lambda$. On the leaf rate the two loci separate by $du = 5.08e-4$ and the Nariai radius sits BETWEEN them. ** (6) AND A FLATNESS SLIP IN THE EXISTING SCOPE-(b) CHECK: ** its leaf integrand carries $Om_\Lambda = 1 - Om$ rather than $1 - Om - Om_r$, so the fractions sum to $1 + Om_r$; kept flat its own figure reads 0.99940 and the slip alone is 10.4% of the shift it is quoted for.). *Computes:* $L[H]$ asserted symbolically equal to $(32/3) \pi G H \rho_r$ and asserted to vanish at $\rho_r = 0$; the ODE asserted to reproduce the published integral to $1e-10$ under the $(2/5)a/Om$ convention; the Meszaros form asserted EXACT to $1e-9$ with Lambda off; the stacking root asserted to reproduce the published 1.180309372 ; the leaf shift asserted under 2% of the gap; the leaf root asserted FURTHER from the measurement and the continued integral asserted CLOSER – the two signs asserted opposite; the recorded 0.99934 asserted to be the flatness-slipped value and 0.99940 the flat one, with the slip asserted comparable to the effect; $Om_m = \text{sech}^2 u$ asserted to FAIL on the leaf rate; the balance asserted to vanish on the stacking rate and NOT on the leaf; the stacking pivot asserted to be r_N exactly, the leaf pivot and turnover asserted distinct, and r_N asserted to lie between them. **CONTROL THAT FIRES: the $(2/5)$ convention and the Meszaros IC are each checked against an independently known answer before either is used** – the closed form where it is valid, and the analytic $1 + (3/2)y$ – so a normalisation error would surface before it could move the root *Bound:* ** COMPUTES A CONSEQUENCE, NOT AN ASSIGNMENT. ** It does not claim the leaf rate is the right rate for this object; the corpus's rule assigns it and this computes what follows. Om_r is held FIXED at $8.5e-5$ throughout and NOTHING is tuned. **No mechanism for the residual 2% is offered** – the row asked whether the rate explains it and the answer is that it does not. NOT CLAIMED: that the balance has any leaf-rate analogue; what is shown is that this one does not hold there *Run:* python3 receipts/P15_CR.cosmology/P15.the.growth.root.on.the.leaf.rate.is.not.a.moment.balance.and.the.gap.s

P15R14 P15.the.rate.has.one.parameter.and.one.epoch [ALL PASS]

sec:flatlcdm (**THE RATE HAS ONE PARAMETER AND ONE EPOCH, NOT TWO PARAMETERS.** Three statements in P15 could not all be true of one quantity: that its two parameters are α and "the OFFSET x_0 "; that "at Nariai the mass is no longer free" so BOTH factors of the expansion law are set by Lambda; and that the density ratio is a CLOCK. The offset is fixed twice over – the horizon cubic's DOUBLE root at the Nariai mass, and

P17's constant ledger $2M = \alpha((r_0/\alpha)-(r_0/\alpha)^3) -$ and $**x_0 = r(\tau_0)/r_N$ identically at every epoch**, the expansion read in the unit the geometry supplies. **Decisive check: if x_0 were the geometric offset ratio it would be $1/\sqrt{3}$, and P15's own dictionary would return $\Omega_m = 0.91$, not a cosmology.**). *Computes:* r4251 *Bound:* 61 *Run:* python3 receipts/P15_CR_cosmology/P15.the_rate_has_one_parameter_and_one_epoch.py

P15R15 P15_the_growth_normalisation_root_has_no_feature_at_the_physical_point [ALL PASS]

(resources) (**THE GROWTH-NORMALISATION ROOT HAS NO FEATURE AT THE PHYSICAL POINT, so the agreement is a coincidence – and it is the STANDARD MODEL'S.** Embedding J in its natural families (exponent p, equation of state w, curvature) gives a root that is smooth, monotone and feature-free through $p=3/2$, $w=-1$ and flatness, with the physical point NOT stationary in any direction. **A property of the matter-Lambda crossover would leave a mark there; there is none.** The artefact reading was never available (J is forced and dimensionless), and the crossing is steep rather than broad-band ($dJ/d\Omega_m = -2.45$). Discriminating: $J=0.99966$ at Planck's 0.3153, $J=1.02142$ at this corpus's DESI DR2 fit of 0.3066.). *Computes:* r4247 *Bound:* 61 *Run:* python3 receipts/P15_CR_cosmology/P15_the_growth_normalisation_root_has_no_feature_at_the_physical_point.py

P15R16 P15_verify_geometry [OK]

prop:flat / prop:throat / prop:transmission (three geometric props DERIVED from primitives: (a1) const-tau 3-metric $dr^2 + r^2 d\Omega^2$ has Riemann=0 (flat R^3); (a2) Nariai near-horizon $dS_2 \times S^2$, $f(r_{\text{star}})=f'(r_{\text{star}})=0$, $f''=-2\Lambda$, both radii $1/\sqrt{\Lambda}$); (a4) tortoise integrals simple- $\int \log(\exp)$ vs double- $\int \text{power-law}$). *Computes:* Riemann from Christoffels; Nariai conds from f; two tortoise integrals; checks intrinsically discriminating *Bound:* Kretschmann bonus derived too *Run:* python3 receipts/P15_CR_cosmology/P15_verify_geometry.py

P15R17 P15_verify_numeric [OK]

prop:amplitude / prop:subhorizon ((a5) substrate dS vacuum power $(\hbar H_{\text{Lam}}/E_P)^2 = 9.5e-123$ vs $A_s = 2.1e-9$ - $\int$ ~ 113 orders below, robust to $O(10)$ prefactor; (a7) comoving Hubble k at seam $0.0104/\text{Mpc}$ vs peak $\pi/r_s = 0.0217/\text{Mpc}$ - $\int$ $2.1\times$ sub-horizon). *Computes:* $\Lambda +$ vacuum power + k derived from obs inputs; matches paper; $[E]/[R]$ marked *Bound:* anchor 6 low-ell leading-order $[R]$ only *Run:* python3 receipts/P15_CR_cosmology/P15_verify_numeric.py

P15R18 P15_verify_coherence_comb [OK]

sec:coherence (coherence comb: common seam phase - $\int$ sharp comb $\Delta\ell = \pi D_C/r_s = 296$ (peaks 296,592,888), peak/trough $\sim 1e5-1e6$; random phase per mode - $\int$ washed out, contrast ~ 1 (400 realisations). Null seam's one characteristic datum/mode = one phase/mode (**SCOPE: this receipt propagates nothing – it writes down $\cos(k r_s)^2$ with r_s and D_C as hardcoded literals, exactly as its own scope note says. It establishes the COHERENCE MECHANISM and NOT the peak spacing.)). *Computes:* ACFM coherence demo on the seam; coherent-vs-incoherent control; matches paper *Bound:* mechanism only; full transfer open $[R]$ *Run:* python3 receipts/P15_CR_cosmology/P15_verify_coherence_comb.py

P15R19 P15_cr_collapse_driving [OK]

sec:coherence (acoustic driving as linear oscillator $\Theta'' + \Theta = -\Psi$: undriven ($\Psi=\text{const}$) $a_0=0.500$, driven (radiation) $a_D=0.999$, boost $a_D/a_0=2.00$ (known LCDM boost); baryon-loaded driven-equiv 1.60 vs adiabatic 1.10). *Computes:* ODE integration; undriven- $\Psi=\text{const}$ control; matches known boost *Bound:* time-symmetry of contracting phase argued (magnitude proven in next receipt) *Run:* python3 receipts/P15_CR_cosmology/P15_cr_collapse_driving.py

P15R20 P15_time_reversal_driving [OK]

sec:coherence ($|\Psi(\omega=1)|$ resonant driving magnitude is time-reversal invariant: $|\Psi(x)|=|\Psi(-x)|$ at $w=1$ on the radiation transfer (0.037049) AND a random control (1.411379); so CR's time-mirrored collapse driving = LCDM's magnitude, peak heights match by structure). *Computes:* numerical Fourier magnitude at $w=1$; radiation + random control; complex/phase-not-invariant discriminator *Bound:* built to close the paper's 'confirmed numerically ... random control' claim *Run:* python3 receipts/P15_CR_cosmology/P15_time_reversal_driving.py

P15R21 P15_camb_reference [OK]

sec:coherence (**!! MARKED c54.160: the closing annotation states the paper's anchors as $P2/P1 \sim 0.46$ and $P3/P1 \sim 0.45-0.46$ while the file itself computes 0.452 and 0.443 and the

paper now prints 0.45 and 0.44.** A stale annotation contradicting the same file's own digit-by-digit claim; both figures are now pinned). *Computes:* CAMB TT spectrum + peak-finder; matches paper *Bound:* needs camb; CR-matches-it carried by driving receipts *Run:* python3 receipts/P15_CR_cosmology/P15_camb_reference.py

P15R22 P15_damping_ratio_clean [OK]
sec:coherence (**!! CORRECTED c54.155: theta_D/theta_* CR/LCDM IS 1.0816 (+8.2%), NOT THE 1.0785 (+7.9%) THIS ROW AND THE RECEIPT'S OWN DOCSTRING RECORD** – both stale from the z_onset 6850 -i 6797 retune. The paper's 'approx 1.08' brackets the live value correctly). *Computes:* CAMB x_e(z); r_s+r_D both rates; depends on CAMB; RATIO cancels conventions *Bound:* absolute theta_D ~7% below CAMB (k_D convention), cancels in ratio *Run:* python3 receipts/P15_CR_cosmology/P15_damping_ratio_clean.py

P15R23 P15_damping_reabsorption [OK]
sec:coherence (~9% damping shift not reabsorbable: r_D ~ omega_b^{-0.305} (paper -0.31), d ln r_D/d ln omega_c=-0.295; cancelling +8.9% needs omega_b +29% vs ~1% BBN+height prior -i 29x too big; 1% omega_b shifts r_D ~0.3%; residual ~8.2%). *Computes:* finite-diff levers on CAMB thermodynamics vs BBN+height priors *Bound:* broader multi-sigma tension is conditional (full transfer open); paper takes only settled part *Run:* python3 receipts/P15_CR_cosmology/P15_damping_reabsorption.py

P15R24 P15_zonset_determinations [OK]
sec:tensions (**!! MARKED c54.160: the paper reported the rounded-l_* pinning as recovering 6873 and this receipt returns 6844 on the current integrals.** The paper now carries both numbers and notes that 6844 sits NEARER to the retired 6850, which sharpens the withdrawal rather than softening it). *Computes:* three determinations computed on one stated convention; H0-independence of (1) exact to 5 digits; rigging of (2) shown by the l_* that 6850 itself returns *Bound:* (3) recorded as a structural observation, not a refutation: the datum is inherited and order-unity either way *Run:* python3 receipts/P15_CR_cosmology/P15_zonset_determinations.py

P15R25 P15_the_ratio_is_the_onset_in_imported_units [OK]
sec:tensions (WHAT $\frac{\rho_r}{\rho_m} \approx 2$ IS, AND WHAT IT IS NOT: **NEITHER A HIDDEN KNOB NOR A SECOND MEASURED DATUM, BUT THE ONE FITTED QUANTITY z_{onset} RE-EXPRESSED IN UNITS OF A PHYSICAL MATTER DENSITY THE CONSTRUCTION DOES NOT DETERMINE.** The rate carries Ω_m (fitted to BAO); the sound speed carries ω_b and ω_γ (measured directly, framework-free); z_{onset} is the one fitted number – and the PHYSICAL $\omega_m = \Omega_m h^2$ enters NO prediction. But ρ_r/ρ_m at onset is $\omega_r(1+z_{\text{onset}})/\omega_m$ and equality is $1+z_{\text{eq}} = \omega_m/\omega_r$, so **both divide by exactly that quantity**. ** KNOB-FREENESS SURVIVES AND IS THE LOAD-BEARING HALF: $z_{\text{onset}} = 6747.3$ at $H_0 = 67.4, 70.0, 73.0$ and 74.0 , to the digit – H_0 is a common factor in r_s and D_M and cancels from θ_* , so the fitted quantity does not move between the two H_0 the tension is between and cannot be absorbing it. ** WHAT DOES NOT SURVIVE IS THE EXACTNESS OF 'ABOUT TWICE EQUALITY': at the fitted $\Omega_m = 0.3066$ the ratio is 2.01 at $H_0 = 67.4$ and 1.71 at $H_0 = 73$, the two readings crossing at $H_0 \sim 68$ where $\Omega_m h^2$ reproduces the CMB-inferred $\omega_m = 0.143$ – and the papers' headline is that the cosmology fits at the DIRECTLY measured $H_0 = 73$. ** So the datum is an order-unity BAND (1.7-2.0), not a determined number; the eta-analogy and the BAO confrontation are untouched (the latter uses distance ratios and never ω_m).). *Computes:* z_{onset} recomputed from the geometric rate at four values of H_0 by root-finding on the measured acoustic angle, its spread asserted below 1 part in 6000; the crossing H_0 asserted in 67-69; the $H_0=73$ ratio asserted at 1.71 *Bound:* ** THIS IS A UNIT ANALYSIS, NOT A NEW MEASUREMENT. ** It does not touch the rate, the fit, or the abundances; and the CMB-inferred ω_m it compares against is itself derived in a radiation-included analysis, which is the point rather than an objection – the residual measures how far the two analyses' ω_m must differ *Run:* python3 receipts/P15_CR_cosmology/P15_the_ratio_is_the_onset_in_imported_units.py

P15R26 P15_the_two_data_are_one [OK]
sec:tensions (WHAT THE 'SINGLE INHERITED DATUM' $\rho_r/\rho_m \sim 2$ ACTUALLY IS, AND WHAT THE NATURALNESS ARGUMENT OFFERED FOR IT ACTUALLY DESCRIBES. ** (1) IT IS NOT A DATUM DISTINCT FROM eta. ** On any thermal history $\rho_r/\rho_m(T) = [1+\nu](\pi^4/30 \zeta(3) T / [\eta (w_m/w_b) m_N])$, which returns **1.99 at $T = 1.6$ eV** – the quoted value to one per cent, from standard thermodynamics and NO feature of this construction.

Given η and the measured matter-to-baryon ratio, both inherited for the composition regardless, **the ratio at onset IS the onset**: the handover supplies ONE composition datum and the cosmology fits ONE parameter. **(2) AND THE NATURALNESS ARGUMENT DESCRIBES AN EPOCH NINE ORDERS FROM THE HANDOVER.** $\rho_r = \rho_m$ at $T = 0.806$ eV; the handover sits FOUR ORDERS ABOVE the deuterium bottleneck (0.07 MeV) because that is what the nucleosynthesis computed on it requires, so the ratio there is $\sim 9e8$ – and ‘a handover carrying radiation of order the matter density’ would be a handover with $\eta \sim 0.5$: no light elements, no acoustic peaks. **So the naturalness question runs the OTHER WAY:** what must be explained is a BILLION photons per baryon, which is the baryogenesis-analogue question already named as open, and the binding-energy scale ($GM/Rc^2 = 1/2$) offers no head start toward it. **P7’s ‘the frontier is two data and not one’ is corrected to one inherited datum plus one fitted parameter.** *Computes:* the identity evaluated at the onset temperature and asserted against the quoted datum to better than 5%; the equality temperature and the ratio at the bottleneck, at P7’s own handover and at the rest mass computed; the η that $O(1)$ would require at each epoch computed and contrasted with the measured $6.1e-10$; and the papers asserted to carry the withdrawal and the corrected accounting *Bound:* **THIS CORRECTS AN ACCOUNTING AND WITHDRAWS AN ARGUMENT; IT TOUCHES NO RESULT.** **The rate, the fit, the baryon-acoustic confrontation and the abundances are all untouched – and the accounting moves in the construction’s favour, from two inherited data to one** *Run:* `python3 receipts/P15_CR_cosmology/P15_the_two_data_are_one.py`

P15R27 P15_full_transfer_verdict [OK]
sec:coherence (high-ell deficit UNDER THE SHORTCUT (assume peaks=LCDM + apply +8.9% damping): C_l CR/LCDM = 0.979/0.920/0.829/0.717/0.594 at $l=500-2500$; cited to show the shortcut is illegitimate (assumption (A) is the unbuilt part)). *Computes:* exp damping on CAMB LCDM C_l ; conditional χ^2 *Bound:* verdict explicitly CONDITIONAL/open (own banner); paper honors scoping *Run:* `python3 receipts/P15_CR_cosmology/P15_full_transfer_verdict.py`

P15R28 P15_verify_closedS3_nonsync [OK]
sec:largescale (low-ell floor mechanism+location: discrete closed- S^3 source ($k_L = \sqrt{L(L+2)}/r_0$, $L_i=2$) through FLAT $j_{ell}(k_L D_C)$, stretch $D_C/r_0=2.75$ pushes $L=2$ to $ell \sim 7.8$; $ell(ell+1)C_{ell}=0.12/0.10/0.20/0.6$ at $ell=2.7$, recovered by $ell \sim 8$). *Computes:* discrete-source flat-Bessel sum; flat-limit χ^2_0 control passes *Bound:* ordinary SW only - i deeper than Boltzmann depth (routed to that receipt) *Run:* `python3 receipts/P15_CR_cosmology/P15_verify_closedS3_nonsync.py`

P15R29 P15_verify_lowell_exact_measure [OK]
sec:largescale ((1) HZ weight $w_L = (L+1)/(L(L+2))$ DERIVED as closed- S^3 degeneracy β^2 x per-mode $1/(\beta(\beta^2-1))$ ($g^*P = w_L$ exactly; $w_L \cdot L \sim 0.998$ continuum); (2) $D_2/D_3=1.162$ stable across measure family - i floor starves $ell=2,3$ together (octopole slightly more)). *Computes:* first-principles derivation + flat-limit + measure-robustness + wrong-measure contrast *Run:* `python3 receipts/P15_CR_cosmology/P15_verify_lowell_exact_measure.py`

P15R30 P15_verify_doppler_lowell [OK]
sec:largescale (Doppler term (super-horizon velocity through j_{ell}) does NOT differentiate $ell=2$ from $ell=3$: CR/LCDM ratio $l^2 \sim 0.27$, $l^3 \sim 0.21-0.22$ across 4 treatments (none/coh+/coh-/quad), $D_2/D_3 \sim 1.29$ octopole slightly more suppressed; continuum validator reproduces LCDM rise). *Computes:* SW+ISW+Doppler transfer, 4 combination modes; continuum check; not tuned *Bound:* bare depth (milder exact depth = Boltzmann receipt) *Run:* `python3 receipts/P15_CR_cosmology/P15_verify_doppler_lowell.py`

P15R31 P15_verify_lowell_boltzmann [OK]
sec:largescale/sec:scope (exact low-ell depth via genuine Boltzmann transfer: discrete closed- S^3 source through CAMB’s exact $\Delta_l(k)$ (SW+ISW+Doppler); CR/LCDM = 0.473 ($l=2$), 0.410 ($l=3$), recover by l^7 , octopole/quadrupole 0.867 on the CONTROL background ($H_0 = 67.4$, $r_0 = 5064$) — **superseded as a depth quote ($r_{7049+70}$)**: the corpus’s 0.487/0.435/0.359/0.666 are arm A of ‘P15.the_low_multipole_depth_gap_closes_and_two_defects_were_cancelling’ on the adjudicated background, and this file names that in its header and gates it; what it carries for the corpus is its gate and its r_0 -drift table. GATE: continuum reproduces CAMB C_l to 4 figures). *Computes:* CAMB transfer x discrete source, Riemann-sum vs integral; gate-validated; r_0 -stable; ISW-retained diagnosis *Bound:* needs camb (high acc) *Run:* `python3 receipts/P15_CR_cosmology/P15_verify_lowell_boltzmann.py`

P15R32 P15_confront_lowell_data [OK]
sec:largescale (low-ell data confrontation (corrected depths): CR 0.47 sits ABOVE the sharp

observed quadrupole (~ 0.2), CR 0.41 mildly below the near- Λ CDM octopole (~ 0.6 -1.0) - *i* matches neither, a WASH; old 0.22/0.20 'striking match' superseded). *Computes*: CR (Boltzmann depths) vs literature observed multipoles *Bound*: body corrected to r962 depths; likelihood in next receipt *Run*: `python3 receipts/P15_CR_cosmology/P15_confront_lowell_data.py`

P15R33 `P15_verify_lowell_likelihood.v2` [OK]

sec:largescale/sec:scope (low-ell cosmic-variance likelihood: exact scaled- χ^2_{2l+1} , CR/ Λ CDM ratio $\Delta(-2\ln L)_l = (2l+1)[r_l(1/d_l-1) + \ln d_l]$; $l=2$ rewards CR -2.63, $l=3/4$ penalise +1.31/+2.10, central total +1.8, octopole range +0.3..+3.8 - *i* wash inside cosmic variance). *Computes*: exact likelihood with corrected Boltzmann depths; matches paper *Run*: `python3 receipts/P15_CR_cosmology/P15_verify_lowell_likelihood.v2.py`

P15R34 `P15_the_low_ell_minimum_is_at_ell_four` [OK]

sec:largescale/sec:scope (**SCOPE: THIS FILE CROSS-VALIDATES NOTHING.** Its arm A is the likelihood receipt's stored dict and **its arm B is the PAPER'S OWN FIGURE CAPTION, read by regular expression** — so the comparison is against the citing paper's typography, and the quartet 0.42/0.35/0.29/0.52 is banked nowhere. **What it does verify is that arm A's minimum sits at $l = 4$ and that the standing receipts always carried it, which is what it is now cited for.** The actual second arm is 'P15_the_second_arm_actually_run': it agrees on shape and NOT on depth, so the quartet 0.42/0.35/0.29/0.52 is not banked. What the file establishes is THE LOW-MULTIPOLE DEFICIT'S SHAPE, AND WHERE THE SECTOR'S WEIGHT ACTUALLY FALLS. ** IT IS NOT A MONOTONE RECOVERY FROM THE QUADRUPOLE BUT A DIP WHOSE MINIMUM IS AT $ell=4$ — and the quadrupole and octopole, the two multipoles the paper quoted, are its two SHALLOWEST points. ** ** THE SHAPE IS CROSS-VALIDATED BY TWO INDEPENDENT BOLTZMANN TREATMENTS of the same discrete source: a standard code's exact $\Delta_l(k)$ at the discrete k_L gives 0.47/0.41/0.36/0.68 at $ell=2,3,4,5$ and the programme's own photon hierarchy gives 0.42/0.35/0.29/0.52 — SAME minimum, SAME recovery, depth ratio 1.13-1.30, which is the size of the residual *sec:instrument* declares. The shape is cross-validated; the depth carries their spread. ** ** AND THE $ell=4$ MINIMUM WAS NEVER NEW: 'P15_verify_lowell_boltzmann.py' has tabulated 0.356 at $ell=4$ since r1395 and the likelihood receipt has consumed it ever since — the corpus's failure was one of QUOTATION, not of computation. ** ** THE OCTOPOLE VERDICT: on the exact cosmic-variance likelihood the quadrupole REWARDS the construction (-2.63), the octopole penalises it at +1.31, and the LARGEST single-multipole penalty in the sector is the +2.10 at $ell=4$ — the prediction's own minimum, and the one multipole of the four the large-angle literature does not treat as anomalous. Sector total unchanged at +1.8, a wash inside cosmic variance. **). *Computes*: both arms' depth tables read off their own sources (the likelihood receipt's dict; the paper's caption) and their argmin asserted equal to $ell=4$; the $ell=4$ depth asserted present and deepest in the standing r1395 receipt; the per-multipole likelihood re-derived from the depths and its argmax asserted at $ell=4$ with the total asserted at +1.8; the exact/WKB transmission spread asserted below 5%; and all eight corpus sites asserted to carry the corrected statement *Bound*: ** DEPTH IS QUOTED TO A TWO-CODE SPREAD AND NOT BETTER. ** And nothing here relieves the observed sky's selective suppression of $ell=2$ ALONE by a factor of order three, which this construction does not produce; that stays inside cosmic variance and belongs to the likelihood-level comparison *Run*: `python3 receipts/P15_CR_cosmology/P15_the_low_ell_minimum_is_at_ell_four.py`

P15R35 `P15_two_ranges_ratio` [OK]

sec:background (two ranges) (the local Hubble-Eddington radius $r_* = (M \alpha^2)^{1/3}$ and the expansion's amplitude $A = (2M \alpha^2)^{1/3}$ are ONE length in the fixed ratio $2^{1/3}$, for every M; A is the matter- Λ equality radius). *Computes*: r_* from $K_G = 1/\alpha^2 - M/r^3 = 0$; A from $\rho_m/\rho_\Lambda = \cosh^2(3\tau/2\alpha)$ at equality; ratio $A/r_* = 2^{1/3}$ symbolically, independent of M and α *Bound*: the r1608 identity; the four-ways reading (turnaround, amplitude, equality, structure boundary) is the paper's *Run*: `python3 receipts/P15_CR_cosmology/P15_two_ranges_ratio.py`

P15R36 `P15_the_second_arm_actually_run` [OK]

sec:largescale (**THE SECOND BOLTZMANN ARM, ACTUALLY RUN — THE SHAPE CROSS-VALIDATES AND THE DEPTH QUARTET DOES NOT.** P15 claimed the low-multipole deficit had been run a second time on the programme's own photon hierarchy, returning 0.42/0.35/0.29/0.52. **The receipt cited for it does not run the hierarchy: it reads arm A from a stored dict and reads arm B OUT OF THE PAPER'S OWN FIGURE CAPTION, by regular expression** — so the

cross-validation compared a table against the citing paper's typography and the quartet was banked nowhere. This file drives 'HIER_photon_hierarchy' itself: evolves it on a k-grid containing the discrete ladder $k_L = \sqrt{L(L+2)} \times 2.75/D_M$ plus a dense continuum grid, projects its own source terms to $\Delta_L(k)$ for $l = 2..44$, and forms the discrete w_L sum against the continuum $dl_n k$ integral, each normalised to its own $l = 25-40$ plateau. ****SHAPE:** minimum at $l = 4$ and recovery by $l \sim 7$, independently of the CAMB arm and of the caption. ****DEPTH:** 0.494/0.243/0.184/0.608 against CAMB's 0.473/0.410/0.356/0.676 — close at $l = 2$, a factor 1.7-1.9 apart at $l = 3-4$. So the quartet is returned by neither arm and the 'uniformly 10-25% deeper' claim is false; both withdrawn from P15 at c54.153.). *Computes:* the minimum over $l = 2..5$ asserted at $l = 4$; recovery asserted in $6 \leq l \leq 9$; the depth disagreement asserted above 1.4x; all ratios asserted finite *Bound:* ****scope:** this settles that the SHAPE claim has a computation behind it and that the DEPTH claim did not. It does NOT settle which depth table is right — the arms differ in late-ISW handling and in D_M (13864 here against the projection's 13927) — and it makes no attempt to reconcile them. **** Run:** python3 receipts/P15_CR_cosmology/P15_the_second_arm_actually_run.py

P15R37 P15_hubble_expansion_confrontation.v2 [OK]
sec:tensions (** THE STACKING-RULER COMPUTATION, AND THE CORPUS'S RULER IS THE LEAF'S (r6921).** *Its arithmetic stands and is live as the calibration 'P15_the_desi_dissolution_survives_the_le'* reproduces in its PART 1; what is superseded is the READING that the H_0 -independence it finds is the corpus's, since r_s is accumulated on the leaf rate, which carries w_r/h^2 , so H_0 does not cancel and the same data pin it. 'P15' no longer rests a claim on this row.* Original: SDSS DR12 BAO flagship: CR BAO ratios D_M/r_d , D_H/r_d H_0 -INDEPENDENT (identical at $H_0=67,73$); χ^2 CR=1.71 (any H_0 incl 73), LCDM(67.4)=4.37, LCDM(73)=49.45 = the tension; cosmic chronometers consistent with 73). *Computes:* geometric-rate H_0 -cancellation + χ^2 vs DR12; matches paper 1.7/49 *Run:* python3 receipts/P15_CR_cosmology/P15_hubble_expansion_confrontation.v2.py

P15R38 P15_desi_dr2_confrontation [OK]
sec:tensions (** THE STACKING-RULER COMPUTATION, SUPERSEDED AS A READING AND LIVE AS ARITHMETIC (r6921)** — **the same note as the DR12 row: the DESI fit here is on the radiation-free ruler, which is not where the corpus puts r_s , and 'P15' no longer cites it.* **!! MARKED c54.160: the docstring reads $\chi^2/\text{dof} = 13.70$ for LCDM at $H_0 = 73$ while the paper quotes about 15 — the same $\chi^2 = 178.16$ divided by 13 measurements rather than by the 12 degrees of freedom one fitted parameter leaves.** The paper's figure is the correct one and the receipt's annotation is not; the χ^2 itself is pinned). *Computes:* full-covariance χ^2 vs DESI DR2; matches paper 1.0/14; was uncited by name *Run:* python3 receipts/P15_CR_cosmology/P15_desi_dr2_confrontation.py*

P15R39 P15_expansion_law [OK]
sec:properframe/sec:flatlcdm (derivation core (symbolic): eq:amplitude $(6GM/\Lambda c^2)^{1/3} = 2^{1/3}/\sqrt{r}$ at Nariai; eq:scalefac $r = A \sinh^{2/3}(B \tau)$ solves the $E=1$ geodesic $(dr/d\tau)^2 = 2GM/r + (\Lambda/3)r^2$ ($2/3$ forced by wrong-exponent control); eq:rate $H^2 = (\Lambda c^2/3)\coth^2$; eq:omega-ratio $\Omega_m/\Omega_L = \text{csch}^2$). *Computes:* sympy: amplitude, geodesic solve, $\coth^2$ rate, csch^2 ratio; wrong-exponent control *Run:* python3 receipts/P15_CR_cosmology/P15_expansion_law.py

P15R40 P15_verify_throat_tower [OK]
sec:throat (throat mode tower + no-hair isotropization: $dS_2 \times S^2$, $m^2/H^2 = l(l+1)$, $\nu^2 = 1/4 - l(l+1)$; $l=0 \rightarrow \nu=1/2$ (scale-invariant base, survives), every $l \rightarrow \nu^2 \geq 0$ (heavy principal, decays) $\rightarrow$ throat isotropizes; grounded in Wald 1983 no-hair; guard: throat $l \neq$ CMB multipole). *Computes:* tower algebra + survives/decays split; theorem-grounded; guard held *Run:* python3 receipts/P15_CR_cosmology/P15_verify_throat_tower.py

P15R41 AS_amplitude_leftward [OK]
rem:transmission-leg (AS — THE AMPLITUDE, READ LEFTWARD. Family 3's question, and what C4 can and cannot say about it. CONFIRMATION 2, and the corpus is already correctly scoped here: P7: the inherited datum 'stands as a ONE-PARAMETER ACCOMMODATION rather than a parameter-free prediction.). *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt's own wording, condensed; not independently re-derived here *Run:* python3 receipts/P15_CR_cosmology/AS_amplitude_leftward.py

P15R43 BUILD_camb_store [OK]
sec:instrument (BUILD_camb_store — the CAMB side of the transfer comparison, with its settings RECORDED. WHY THIS EXISTS (r2345). 'ENVELOPE_residual.py' and its relatives load

‘/tmp/camb.tr.npz’ and measure our transfer against CAMB’s. Nothing in the corpus records HOW that store was built – not the receipt, not the changelog, not the instrument.). *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt’s own wording, condensed; not independently re-derived here *Run:* python3 receipts/P15_CR_cosmology/BUILD_camb.s

P15R44 C10_highl_ratio [OK]

sec:envelope-consequence (**!! CORRECTED c54.155: THIS ROW CARRIED THE RETIRED z_onset = 6850 NUMBERS** (r_s matched +0.76%, r_D +10.09%, theta_D/theta_* +9.26%). The shipped receipt hardcodes 6797 and produces +0.67%, +10.15%, +9.41%, l_* = 302.2. **And the receipt hardcodes th_ratio = 1.0926 with the comment ‘DERIVED in C9’ while C9 produces 1.0941.** P15 corrected to the live values). *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt’s own wording, condensed; not independently re-derived here *Run:* python3 receipts/P15_CR_cosmology/C10_highl_ratio.py

P15R45 C11TEST_radiation_zeroed [OK]

sec:envelope-consequence (CRRUN — THE SAME INTEGRATOR ON CR. The control passed at r1975, so this may now be run. WHAT CHANGES, and each from the corpus not from me: * BACKGROUND: $H^2 = H_0^2(\Omega_m a^{-3} + \Omega_L)$ at $H_0=73$, $\Omega_m=0.3066$ – radiation is content, not a source. * LOWER LIMIT: the SEAM, not eta-0 (C9: there is no observable expansion below it).). *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt’s own wording, condensed; not independently re-derived here *Run:* python3 receipts/P15_CR_cosmology/C11TEST_radiation_zeroed.py

P15R46 C11_early_isw [OK]

sec:envelope-consequence (C11 — THE EARLY ISW. The last named piece. CONFIRMATION 2/4 – the corpus settles the input, in its own voice: ‘radiation, like matter, is inherited content read off that clock, NOT A TERM THAT SOURCES THE RATE, and there is no radiation-dominated era.'). *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt’s own wording, condensed; not independently re-derived here *Run:* python3 receipts/P15_CR_cosmology/C11_early_isw.py

P15R47 C1_closure_of_the_driving [OK]

sec:envelope (C1-CLOSURE — DOES THE ACOUSTIC OSCILLATOR CLOSE IN ELEMENTARY TERMS ON CR’s COLLAPSE LEG? CONFIRMATION 4 first — WHICH background. The corpus is specific and I must not substitute: L2 (where the driving lives) = ‘the leaf’s local rate, ORDINARY FRIEDMANN, radiation GRAVITATING NORMALLY, on the progenitor’s collapse excursion’ – and P16: on the cooling leg $|H| = \sqrt{8 \pi G \rho}/3$, ‘identical to standard BBN at every...). *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt’s own wording, condensed; not independently re-derived here *Run:* python3 receipts/P15_CR_cosmology/C1_closure_of_the_driving.py

P15R48 C2_horizon_limits [OK]

sec:envelope (C2 — THE LIMITS. The comoving Hubble radius across the excursion, from the corpus’s own geometry. CONFIRMATION 4 — the object, and I take it from the corpus rather than from cosmology-by-habit: the $E=1$ (marginally bound) congruence IS this cosmology. On it $(dr/d\tau)^2 = E^2 - f = 1 - f$, with $f = 1 - 2M/r - r^2/\alpha^2$. The signed areal radius r is the scale-factor analogue.'). *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt’s own wording, condensed; not independently re-derived here *Run:* python3 receipts/P15_CR_cosmology/C2_horizon_limits.py

P15R49 C3_conformal_map [OK]

sec:envelope (**!! CORRECTED c54.155: ‘better than a percent at the entry radii of the modes in question’ IS 1.87% AT THE PAPER’S OWN 10 k_s THRESHOLD** (3.72% at 5 k_s, 24.4% at the seam); sub-percent begins near 30 k_s. P15 corrected). *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt’s own wording, condensed; not independently re-derived here *Run:* python3 receipts/P15_CR_cosmology/C3_conformal_map.py

P15R50 C4_driving_envelope [OK]

sec:envelope (**!! CORRECTED c54.155: ‘entry at $x = 1/\sqrt{3}$ for every k ’ IS A LIMIT, NOT AN IDENTITY** (the receipt’s own table gives $x_{\text{entry}} = 0.764$ at $k = k_s$, +32%), **and the ‘residual below a percent’ is an average over a 5-point grid that lands near zeros of $\cos(x_{\text{seam}})$: scanning the receipt’s own function over k/k_s in [10,120] reaches 7.3% at $k/k_s = 12$.** Both

qualified in P15). *Computes*: runs clean; registered from its own docstring and a live run *Bound*: description is the receipt's own wording, condensed; not independently re-derived here *Run*: python3 receipts/P15_CR_cosmology/C4_driving_envelope.py

P15R51 C5b_baryon_term [OK]

sec:envelope (C5 — THE BARYON TERM. The first of the two terms C4 named as missing. CONFIRMATION 4 – and the corpus fixes the division rather than me: P16 masthead: 'eta fixes the abundances and the CMB peak HEIGHTS, rho_r/rho_m the peak SPACING.' P15: this cosmology 'carries the matter density as the bend of the spatial cut WITHOUT YET REMOVING THE COMPONENT' – so rho_m is TOTAL matter and the baryon fraction is set separately,...). *Computes*: runs clean; registered from its own docstring and a live run *Bound*: description is the receipt's own wording, condensed; not independently re-derived here *Run*: python3 receipts/P15_CR_cosmology/C5b_baryon_term.py

P15R52 C6_neutrino_term [OK]

sec:envelope (C6 — THE ANISOTROPIC-STRESS TERM. The second of C4's two named terms. FINDING ZERO, before any physics: the corpus's TEXT says 'neutrino' ZERO times, and 'anisotropic stress' zero, and 'free-streaming' zero – while its BBN CODE carries them explicitly (bbn_network.py: 'neutrinos share the plasma T until ~ e+- annihilation, then decouple to $(4/11)^{1/3}$ ').). *Computes*: runs clean; registered from its own docstring and a live run *Bound*: description is the receipt's own wording, condensed; not independently re-derived here *Run*: python3 receipts/P15_CR_cosmology/C6_neutrino_term.py

P15R53 C7_equality_and_deficit [OK]

sec:envelope (C7 — THE STEP THE TRAP WAS GUARDING. full_transfer_verdict.py ASSUMED the high-ell peaks equal LambdaCDM's and applied the extra damping, getting a large deficit – and P15 disowns it because 'that assumption IS the unbuilt part.' C4 built it. So the same calculation can now be done with a DERIVED envelope. FIRST, though, one number that decides everything and that I have not yet checked.). *Computes*: runs clean; registered from its own docstring and a live run *Bound*: description is the receipt's own wording, condensed; not independently re-derived here *Run*: python3 receipts/P15_CR_cosmology/C7_equality_and_deficit.py

P15R54 C8_diffusion_length [OK]

sec:envelope-consequence (C8 — DERIVE r_D HERE, FROM FIRST PRINCIPLES, ON THE SAME FOOTING AS THE DRIVING. Nothing imported from the damping_tail/ files. Nothing that needs CAMB. CONFIRMATION 4: the object. Silk damping is a diffusion length built from the Thomson opacity and the expansion. The standard definition (Kaiser 1983; Hu-Sugiyama), in the Rb -> 0 limit: $1/k_D^2 = \int d\eta \cdot (1/(6 \tau \cdot \dot{\tau}))$).). *Computes*: runs clean; registered from its own docstring and a live run *Bound*: description is the receipt's own wording, condensed; not independently re-derived here *Run*: python3 receipts/P15_CR_cosmology/C8_diffusion_length.py

P15R55 C9_sound_horizon_and_ratio [OK]

sec:envelope-consequence (C9 — r_s AND r_D WITH THE CORRECT LOWER LIMIT: THE SEAM. A first pass integrated from a=0 and returned r_s = 256 Mpc against the corpus's 144 – absurd, and the error is structural, not numerical: *** ON THIS COSMOLOGY THERE IS NO OBSERVABLE EXPANSION BEFORE THE SEAM. *** P15: 'recombination is observable cosmology FROM THE SEAM OUTWARD'. The L1 foliation BEGINS at the seam;). *Computes*: runs clean; registered from its own docstring and a live run *Bound*: description is the receipt's own wording, condensed; not independently re-derived here *Run*: python3 receipts/P15_CR_cosmology/C9_sound_horizon_and_ratio.py

P15R56 H0_acoustic_angle_and_seam [OK]

sec:refit-bound (H0 — THE ACOUSTIC SCALE AT THE DIRECTLY MEASURED H0. The calculation I have been running backwards. CORPUS CLAIM (P7, P15): 'There is no second Hubble rate to reconcile: THE DIRECTLY MEASURED H0 IS THE GEOMETRY READ AT THE PRESENT EPOCH, while the lower value inferred from the microwave background rests on a radiation-governed sound horizon the construction does not share...'). *Computes*: runs clean; registered from its own docstring and a live run *Bound*: description is the receipt's own wording, condensed; not independently re-derived here *Run*: python3 receipts/P15_CR_cosmology/H0_acoustic_angle_and_seam.py

P15R57 ISW_line_of_sight [OK]

sec:refit-bound (ISW — THE EARLY INTEGRATED SACHS-WOLFE, ISOLATED, AND ITS

SHIFT ON THE FIRST PEAK. Same shape as everything else in A.0: the source is a line-of-sight integral over the set rate. $\Delta_l(k) = \int d\eta [S_{SW} + S_{ISW}] j_l(k(\eta_0 - \eta))$, $S_{ISW} = (\Phi' + \Psi') = 2\Psi'$ LambdaCDM has a nonzero early ISW because Ψ is still evolving at recombination (radiation matters). CR does not: C11 showed Ψ is constant on L1.). *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt's own wording, condensed; not independently re-derived here *Run:* `python3 receipts/P15_CR_cosmology/ISW_line_of_sight.py`

P15R58 `M2_reabsorption_minimization` [OK]

sec:refit-bound (M2 — THE MINIMIZATION. Can a parameter refit absorb the damping shape? The honest core of the likelihood question, done on the closed forms derived in C8/C9 – no CAMB. SETUP, stated before running: FREE : Ω_m , ω_b , and the inherited datum ρ_r/ρ_m (which fixes z_{onset}). CONSTRAINT: $1^* = \pi D_M/r_s$ pinned to the observed 301 – the peak positions are measured.). *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt's own wording, condensed; not independently re-derived here *Run:* `python3 receipts/P15_CR_cosmology/M2_reabsorption_minimization.py`

P15R59 `PEEB_peekles_on_the_set_rate` [OK]

sec:refit-bound (PEEB — THE PEEBLES IONISATION HISTORY ON THE SET RATE. ZREC used Saha only: right shift, wrong absolute (1283 vs CAMB's 1090), because Saha has no departure from equilibrium. Peebles adds it – and the departure is itself H-dependent, which is exactly why it must be integrated on the construction's own rate rather than inherited. Standard effective three-level hydrogen atom (Peebles 1968; Seager et al. fits).). *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt's own wording, condensed; not independently re-derived here *Run:* `python3 receipts/P15_CR_cosmology/PEEB_peekles_on_the_set_rate.py`

P15R60 `ROBUST_p1p2_scan` [OK]

sec:refit-bound (**!! FIXED c54.160: THE REGISTERED COPY WAS UNRUNNABLE FROM ITS OWN DIRECTORY** – it imported 'RD_diffusion_direct', which lives only in 'storyboard_receipts/', so it exited 1 on ImportError before reaching any computation and the sweep had to run it from the ORIGIN instead. *A receipt that cannot run where it is registered is not a receipt.* Path resolution added; it now exits 0 in place). *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt's own wording, condensed; not independently re-derived here *Run:* `python3 receipts/P15_CR_cosmology/ROBUST_p1p2_scan.py`

P15R61 `P15_the_first_peak_figure_is_not_stable` [OK]

the acoustic sector (**THE 150 IS NOT A PREDICTION: 'ROBUST_p1p2_scan's FIRST-PEAK POSITION AND PEAK-HEIGHT RATIO ARE NOT STABLE UNDER ITS OWN DOCUMENTED INITIAL CONDITIONS.** Built settling front #5, the corpus's two internal routes to the first acoustic peak (transfer 220, this instrument 150). **The front is posed as a disagreement between two established routes; one of the two is not established.** PART 1 the numerics are cleared first – stability number 0.47 against the file's own limit of 2.8, 120+ RK4 steps per oscillation, NS_CR x4 reproduces every figure. PART 2 Ψ 's VALUE comes from the smooth matched envelope and Ψ 's DERIVATIVE from the oscillatory closed form – two different functions, and the initial velocity is built entirely from the second. PART 3 across four readings of the SAME stated IC, ℓ_{l1} spans 150-315 and P1/P2 spans 0.93-2.02; **the reading the docstring actually describes ('velocities zero') returns 2.017 against the sky's 2.212, where the paper reported 1.45 as the disagreement.** PART 4 the comb the paper cites against it was never propagated either – 'verify_coherence_comb' writes down $\cos(k r_s)$ with r_s and D_C as literals. PART 5 **the residual: the source comb spacing is 0.72-0.79 of π/r_s under EVERY variant. The initial data move the first peak by 165 multipoles and do not move this.**). *Computes:* stability asserted under the file's own 2.8 limit and steps-per-oscillation over 50; the two derivative functions asserted to differ by more than 1.2x across the band and to agree as $x \rightarrow 0$; the control asserted to reproduce 1.447 and 150/360/555/780; the documented-IC run asserted at 2.017 AND asserted closer to the sky than the implemented one; ℓ_{l1} asserted to move by 150+ multipoles and P1/P2 by more than 2x; the comb receipt asserted to contain $\cos(k r_s)$ and NO integrator; the comb deficit asserted present, bounded, and STABLE across variants (max-min ; 0.15) – which is what makes it not initial data. *Bound:* **scope: this does NOT vindicate 220 and supplies no first-peak position. It removes one route from arbiter status and registers the comb deficit, which is not resolved here. The four variant figures are produced by 'computations/beyond_the_wall/L171_what_sets_the_first_peak.py', which execs the registered receipt's own

source with only the initial-data block substituted; its ICMODE=asis control reproduces the receipt exactly, assertions passing.** *Run:* python3 receipts/P15_CR_cosmology/P15_the_first_peak_figure_is_

P15R62 P15_the_crossing_exists_and_is_empty [OK]
the acoustic sector (**THE RE-ENTRY BETWEEN THE BRANCH POINT AND THE ONSET IS REAL, AND IT IS EMPTY: THE L1 POTENTIAL EQUATION CONTAINS NO k AT ALL.**
 Built working front #5, testing a candidate THIS FORK proposed at c54.165 – front #1 puts every mode super-horizon and frozen at the branch point, ‘prop:subhorizon’ puts the acoustic modes inside at the onset, so they re-enter in between, and a crossing is where flat LCDM acquires its k -INDEPENDENT driving shift. **The answer is no, and the reason is stronger than the question.** PART 1 the re-entry is real and its boundary is computed: the mode crossing AT the onset is $k = 0.0111/\text{Mpc}$, $\ell = 144$, so the peak modes crossed before the plasma began and $\ell \downarrow 144$ crosses after. PART 2 but it is a MATTER-era crossing – pressureless to better than a part in $1e4$, because L1 has no radiation SOURCE. PART 3 **and the $w = 0$ potential equation has no k in it**:
 Φ constant to twelve digits, identical across four decades in k , the integrator taking the SAME number of steps for every mode. PART 4 the contrast: in LCDM 5 of 6 cross under radiation, where $w = 1/3$ restores the k^2 term and Φ decays on the sound-crossing time by construction.).
Computes: every mode at/above the peak region asserted to cross before the onset AND $\ell = 28$ asserted to cross AFTER it (the first draft claimed ‘every observed mode’ and this assertion fired); the boundary multipole asserted inside 100-250; the background asserted pressureless to $1e-3$ at every crossing; Φ ’s spread across four decades in k asserted below $1e-9$ AND the solver step count asserted identical across k ; the LCDM contrast asserted to put 4+ modes under radiation with z_{eq} above 3000. *Bound:* **scope: this CLOSES a candidate mechanism and supplies none. It computes no peak position and uses no figure from the acoustic fold. It leaves ‘PO-7’ open and harder: the absence of a universal driving shift on this rate is not an omitted crossing but a scale-free interval.**
Run: python3 receipts/P15_CR_cosmology/P15_the_crossing_exists_and_is_empty.py

P15R63 P15_two_arm_control_and_guard [OK]
the acoustic sector (**A LIVE LambdaCDM CONTROL AND AN UNDRIVEN GUARD, ON ONE MACHINERY – AND THE CR ARM’S FIRST PEAK SITS 23% LOW AGAINST A 1.5% POSITION FLOOR.** Built for fronts #5 and #18. **This fork had never run a control**:
 ‘ROBUST_p1p2_scan’ quotes one from r1975 in a comment, and c54.164 then showed its figures move over ℓ_{11} in {150,165,315} with nothing to measure that against. PART 1 **the guard passes on BOTH arms** – every coupling to the potential removed at every site (4 Φ ’ in photon/neutrino/CDM continuity AND $k^2 \Psi$ in photon-baryon/neutrino Euler, both branches) and the source comb lands on the integers, LCDM 1.0147/2.0005 and CR 1.0121/1.9968, **so every departure from $n \pi/r_s$ in a driven run is the driving and nothing else**. PART 2 the control lands at 224/536/808/1116 against the sky’s 220.6/538.1/809.8/1147.8 – **positions to 1.5% at the first peak and 0.4%/0.2% at the second and third; HEIGHTS only to 13-26%, so no height claim from this instrument is meaningful below $\sim 25\%$ **. PART 3 the CR arm run on its PHYSICAL discrete ladder and on a dense continuum sampling gives **identical** peaks 172/396/624/904, so discreteness is not what sets the position – an objection closed by measurement. PART 4 $\ell_{11}/\ell_{1A} = 0.5703$ against the control’s 0.7433 and the sky’s 0.7312: **a 23% deficit against a 1.5% floor, a factor of 15 in margin**, with $P1/P2 = 0.866$ against the control’s 1.933.). *Computes:* the undriven comb asserted within 0.03 of the integers on both arms; the control’s position floor asserted under 3% AND its second and third peaks asserted within 1% of the sky; the discrete and continuum peak lists asserted identical; the deficit asserted at 5+ floors; CR’s ℓ_{11}/ℓ_{1A} asserted in 0.55-0.60 and the control’s in 0.72-0.76; the two arms’ 1_A asserted to agree to 1% (they do – D_M differs by 6.2% and r_s by 6.3% and they cancel). Every background quantity is RECOMPUTED rather than pinned. *Bound:* **scope: this does NOT settle ‘PO-7’ and the CR figure is not offered as a prediction – it uses the initial datum the corpus’s own text describes (flat in k , common phase, VELOCITIES ZERO) and c54.164 established the figure moves with that choice. What changed is that it now moves against something. NO FIGURE FROM THE ABANDONED ACOUSTIC FORK IS USED; that fork’s own reproduction gate fails in this tree, and this instrument disagrees with its 201.3 by 15%.** *Run:* python3 receipts/P15_CR_cosmology/P15_two_arm_control_and_guard.py

P15R64 P15_the_driving_shift_by_subtraction [OK]
the acoustic sector (**THE DRIVING SHIFT MEASURED MODEL-FREE BY SUBTRACTION: LCDM’S ACOUSTIC PHASE IS FLAT IN k TO 2.1%, CR’S VARIES BY 3.9x – AND

THE SCALING IS $k^{-0.62}$, NOT THE k^{-2} THE ABANDONED FORK'S MECHANISM REQUIRES.** Built for front #5 on the c54.168 instrument. Each k integrated TWICE on the same equations, driven and undriven, differing in one multiplicative switch and nothing else. $Q(k) = k \int c_s d\eta/\pi$ at the first acoustic turnover of Θ_0 . **PART 1 the undriven column is the CALIBRATION and is MEASURED: 0.9968-1.0003 on both arms, where a free oscillator must give exactly 1.** PART 2/3 LCDM's Q_{driven} runs 0.791 - $\lesssim$ 0.774 over $k = 0.045$ -0.16 (2.1% spread) because every mode crosses under radiation, where the potential decays on the sound-crossing time by construction; CR's runs 0.457 - $\lesssim$ 0.117, a factor of 3.9, because there is no radiation era to cross and c54.167 showed the pre-onset interval is scale-free. PART 4 **a power-law fit gives $k^{-0.62}$, collapsing the data to a factor of 1.2 where k^{-2} spans a factor of 16.** The fold reports $Q k^2$ constant and its seam-transient mechanism ($3H/k^2$) requires it. **The phenomenon reproduces here independently; the exponent does not.** Recorded as an inter-instrument disagreement, not resolved.). *Computes:* the undriven calibration asserted within 0.01 of 1 on BOTH arms (this is the file's own gate); LCDM's spread asserted under 6%; CR's variation asserted over 2x; the fitted exponent asserted inside (-1.2,-0.3); ** $Q k^2$ asserted to span MORE than a factor of 4 – i.e. the fold's constant- $Q k^2$ asserted FALSE here**); and the fitted exponent asserted to collapse the data better than k^{-2} , so the fit is not vacuous. *Bound:* **scope: two corrections were forced by this file's own calibration and are recorded because each would have been a false result – (i) reading Q on Θ_{hat} rather than Θ_0 calibrated at 0.0003, since DR switches the couplings into the fluid but not Psi's own evolution; (ii) the driven LCDM column then calibrated at 0.001 on a decaying-mode transient two grid points from the start, excluded by requiring $k \eta \lesssim 1$, which is the DEFINITION of an acoustic turnover and removes nothing on the CR arm. No figure from the abandoned fork is used.** *Run:* python3 receipts/P15_CR.cosmology/P15.the_driving_shift_by_subtraction.py

P15R65 P15_which_coupling_carries_the_k_dependence [OK]
the acoustic sector (**THE k -DEPENDENCE LIVES IN THE POTENTIAL'S GRADIENT, NOT IN ITS DECAY – WHICH IS THE REVERSE OF WHERE A RELAXATION TIMESCALE WOULD PUT IT.** Front #5, on the c54.168 instrument against its 1.000 calibration. The potential enters the plasma TWICE: as ' 4Φ ' in continuity (its rate of change feeding the density – **the decay channel**) and as ' $k^2 \Psi$ ' in Euler (its gradient driving the velocity). Switched independently on the same integration. PART 1 **flat LCDM's two couplings are each FLAT in k and they OPPOSE** – continuity alone puts the turnover at $Q = 1.23$ -1.28, LATER than a free half-period, the gradient at 0.73-0.87, earlier, composing to 0.77-0.86. **So the universality of the standard driving shift is a CANCELLATION between two flat terms, not one term's signature.** PART 2/3 on the geometric rate there is no cancellation left – both advance (0.11-0.18 and 0.06-0.57) and they add – **and the k -dependence sits in the GRADIENT: continuity varies 1.6x at $k^{-0.17}$, gradient 8.9x at $k^{-1.04}$.** PART 4 and **neither term alone is the answer**: the driven exponent -0.62 lies BETWEEN the two, so the scaling is their interference.). *Computes:* LCDM's continuity asserted ABOVE 1 and its Euler BELOW 1 (they must oppose) and all three driven exponents asserted flat to 0.15; CR's continuity asserted nearly flat ($|\exp| \lesssim 0.35$) and its Euler steep ($|\exp| \lesssim 0.8$) and the Euler term asserted to be the steeper of the two – **reversing that assertion would reverse the finding**); both CR couplings asserted below 1 (they add); the driven exponent asserted strictly BETWEEN the two and distinct from each by 0.2; and the undriven calibration asserted within 0.01 of 1 on both arms, which is the file's own gate. *Bound:* **scope: this localises the k -dependence to a coupling and shows the standard shift's universality is a cancellation this rate does not have. It does NOT name the process that makes the gradient coupling run as k^{-1} , and computes no peak position. It closes the abandoned fork's stated mechanism as an explanation of THIS measurement – a relaxation on $3H/k^2$ acts through the decay channel, and the decay channel is measured flat.** *Run:* python3 receipts/P15_CR.cosmology/P15.which_coupling_carries_the_k_dependence.py

P15R66 P15_the_gradient_coupling_in_closed_form [OK]
the acoustic sector (**THE GRADIENT COUPLING IN CLOSED FORM: THE TURNOVER IS AT A FIXED MULTIPLE OF $3H/k^2$, AND SINCE Q ALREADY CARRIES ONE FACTOR OF k THAT GIVES $Q \sim 1/k$, NOT $1/k^2$.** Front #5, closing the question c54.170 left. **The derivation is four lines.** (1) Φ 's own equation carries a damping term $-k^2 \Phi/3H$, so Φ relaxes on $\tau = 3H/k^2$. (2) With continuity off the oscillator is $\Theta_0'' + c_s^{-2} k^2 \Theta_0 = -(k^2/3) \Psi$, and **the k^2 in the forcing's amplitude is cancelled by the k^{-2} in its duration

– the delivered impulse is k-INDEPENDENT**. (3) So the first turnover is at the moment the impulse has been delivered, at a fixed multiple of tau: $\kappa = 1.79$, constant across a factor of eight in k. (4) $Q = k \int c_s \, da / \pi$ already carries one k, so $Q = 3 \kappa c_s H / (\pi k)$. **PREDICTED $Q k = 0.010403/\text{Mpc}$ AGAINST A MEASURED $0.010372 - 0.30\%$ – with nothing fitted but κ ; and the closed form reproduces Q itself to 1.6% across the sub-horizon band. $\Rightarrow$ **The abandoned fork’s TIMESCALE is right and its EXPONENT is out by exactly one factor of k – a bookkeeping error in its own mechanism rather than a disagreement about physics.** And the continuity channel is flat for the complementary reason: ‘4 Φ ’ feeds the density with the potential’s TOTAL change, $\int \Phi \, da = -\Phi_0$, the same however fast the relaxation runs. **So the observed $k^{-0.62}$ is not a power law of anything – it is the crossover between a flat channel and a $1/k$ one.**). *Computes:* κ asserted constant to 10% across the sub-horizon band; **the flattest grouping asserted to be $Q k^1$ and not $Q k^0$ or $Q k^2$ – if that assertion reverses, the derivation is wrong**); the predicted coefficient asserted within 5% of the measured one; the closed form asserted to reproduce Q to 5% across the band; the continuity channel asserted flattest UNGROUPED and asserted flat to within a factor of 2. *Bound:* **scope: this NAMES the process, so front #5’s question is answered. It does NOT make the first peak agree with the sky – the 23% deficit against a 1.5% control floor stands unchanged. What changed is that its cause is derived rather than described. No figure from the abandoned fork is used; its timescale is confirmed independently here and its exponent corrected.** *Run:* python3 receipts/P15_CR.cosmology/P15.the_gradient_coupling_in_closed_form.py

P15R67 P15_where_the_likelihoood_sits [OK]
the acoustic sector (**WHERE THE LIKELIHOOD ACTUALLY SITS: IT CANNOT ARBITRATE, AND THE INSTRUMENT’S OWN CONTROL IS WHY.** Discharges ‘L-147’, fenced since it opened on three conditions – falsifier fixed before any data is touched, a control reproducing a known number first, and not until the two internal routes agree. **All three met** (the routes collapsed at c54.164-168), so the fence came down. **F1** the pipeline is wired: the banked CAMB flat-LCDM best fit returns $\chi^2 = 206.4$ over 215 plik_lite TT bins, $\chi^2/\text{dof} = 0.96$. **F2** the instrument’s own floor, measured through the SAME likelihood on the SAME bins: this fork’s LCDM arm costs +18786 over CAMB. **F3** the only readable quantity, both arms of one instrument: CR - LCDM = +84160. **F4** the pre-registered rule returned ‘suggestive, not a measurement discrepancy’. **F6 – AND THE PRE-REGISTERED RULE WAS DEFECTIVE, WHICH RUNNING IT IS WHAT SHOWED.** It is a RATIO test and never asks whether the floor is small in ABSOLUTE terms. It is not: the control arm sits at $\chi^2/\text{dof} = 103$ against CAMB’s 0.96, because Planck’s binned errors are a few tenths of a per cent and this instrument’s heights carry 13-26%. **Both arms are far outside the regime where plik_lite discriminates, so the honest verdict is the WEAKER one: the likelihood cannot arbitrate.** **!!! That correction happens to FAVOUR the construction and is flagged for it** – it would apply identically had the CR arm come out better, and it rests on a height floor measured at c54.168 before any data were opened. **What survives as fact: on one instrument, same bins, same fitted amplitude, the CR arm costs 5.4x the LCDM arm’s χ^2 . An ordering, not a p-value.**). *Computes:* the banked LCDM fit asserted at χ^2/dof in (0.85,1.15) BEFORE anything else is read; every covered bin asserted non-empty (the keep mask); the instrument floor asserted POSITIVE (this instrument cannot beat a five-parameter CAMB fit, and if it appeared to, the binning would be wrong); the CR arm asserted to cost more than the control on the same instrument; and **F6’s premise asserted – if the control arm ever drops below $\chi^2/\text{dof} = 3$ the PART must be rewritten because the likelihood then CAN arbitrate.** *Bound:* **scope: plik_lite TT only – no polarisation, no ell j 30, no lensing, no external priors, a third-party implementation rather than clik (PROVENANCE.md), and 185 of 215 bins because the instrument reaches ell = 2000. The restriction to covered bins is done on the COVARIANCE and re-inverted, which MARGINALISES over the missing multipoles; dropping rows of the Fisher matrix would CONDITION on them. The banked r1934 CR figure (397.1 vs 206.4) applied the derived DAMPING suppression to CAMB’s LCDM spectrum – it tested damping on LCDM’s PEAK POSITIONS and could not have seen the position result, so it answers a different question and is SUPERSEDED here. ‘PO-7’ stays protected: this reports a number and does not convert it into a verdict.** *Run:* python3 receipts/P15_CR.cosmology/P15.where_the_likelihoood_sits.py

P15R68 P15_the_line_of_sight_transfer [OK]
the acoustic sector (**THE TRANSFER REBUILT ON A LINE-OF-SIGHT INTEGRAL: THE

CONTROL'S FIRST-PEAK POSITION ERROR FALLS FROM 1.66% TO 0.16%, AND THE CR DEFICIT DOES NOT MOVE AT ALL. ** Front #2. Until c54.173 the source was evaluated at a SINGLE eta_rec – an instantaneous last scattering. **The visibility $g = \tau' e^{-\tau}$ peaks at $\eta = 280.75$ with FWHM 37.8 Mpc, a tenth of a wavelength at the first peak. ** Rebuilt as $\Delta_l = \text{INT } S_j \Delta \eta$ with $S = g(\Theta_0 + \Psi) + e^{-\tau}(\Phi' + \Psi')$ + $(1/k^2) d/\Delta \eta [g \theta_{\text{b}}]$. PART 1 the control goes 1.66% $\rightarrow$ 0.16% in ell_1/ell_A: **sub-per-cent POSITIONS, which is what the likelihood needed of them. ** PART 2 **and the CR arm is unchanged to four figures, 0.5703 on both transfers, while the control moved 1.79%. The deficit stands at 21.9% against a 0.16% floor – 134 floors. ** The most suspect part of the instrument was replaced wholesale and the number did not follow it down. PART 3 **the heights are NOT fixed and the target is NOT met**: P1/P2 -13%, P1/P3 -34%, a residual growing with multipole and pointing at the damping tail (no polarisation term; a tight-coupling closure that fails where the visibility is). Stated as a partial result. PART 4 one correction was a DERIVATION: the Doppler term carries $1/k^2$ not $1/k$, since $v_b = \theta_b/k$. **With $1/k$ the second peak sat at 516 and P1/P2 at 3.15; with $1/k^2$, 532 and 1.93 – and ell_1 was 220 either way, so an instrument validated on the first peak alone would have carried the error. **). *Computes:* the control's position error asserted sub-per-cent AND asserted improved by 5x or more; the CR arm asserted to move less than 1% under the rebuild; the deficit asserted at 20+ floors; **the heights asserted NOT sub-per-cent – if they ever are, the PART is stale and front #2 should be struck**; and the corrected Doppler power asserted to move the SECOND peak toward the sky, which is what makes it a fix rather than a tuning. *Bound:* **scope: this delivers sub-per-cent POSITIONS and leaves the HEIGHTS at 13-34%, so the likelihood still cannot be run (c54.172). The remaining error is a high-multipole problem and neither of its two named causes is a CR question – both are checked against the LambdaCDM arm first. Late ISW is truncated at $\eta = 4000$, which affects only ell below ~ 30 and is outside both the grid and plik_lite's TT range. ** *Run:* python3 receipts/P15_CR_cosmology/P15_the_line_of_sight_transfer.py

P15R69 P15_the_derived_diffusion_damping [OK]
the acoustic sector (**THE HEIGHTS FROM 13-34% TO 2-3%: THE DIFFUSION DAMPING PUT BACK, DERIVED ON EACH ARM'S OWN OPACITY AND RATE. ** Front #2. **Diagnosed from the SIGN**: at c54.173 both height ratios were LOW, meaning peaks 2 and 3 too HIGH, worse at higher multipole – under-damping. **The hierarchy's tight-coupling closure switches off at $\tau' = 0.6/\text{Mpc}$ and the visibility peaks at $\tau' = 0.06/\text{Mpc}$, ten times lower, so the photon quadrupole and the baryon slip were absent through the WHOLE of last scattering and the line-of-sight path carried no Silk damping at all. ** The pre-LOS path hid this behind a hardcoded r_D . PART 1 the standard tight-coupling integral $1/k_D^2 = \text{INT} [R^2/(1+R) + 8/9]/[6(1+R)\tau'] \Delta \eta$, evaluated on this arm's own background: ** $r_D = 6.58$ Mpc against the 6-7 a Boltzmann code gives. Nothing fitted. ** PART 2 **and a DOUBLE COUNT had to be removed**: with the hierarchy's own damping left in over $\tau' \gtrsim 0.6$ AND the integral covering the same range, the control came out OVER-damped (+6.7%, +17%). **The sign flips either side of the correction, which identifies a double count rather than a wrong coefficient. ** PART 3 heights ** -12.9%/-33.5% $\rightarrow$ -2.8%/-2.1% **, on a control whose positions were already sub-per-cent. PART 4 **and the likelihood's floor falls 103 $\rightarrow$ 23 in χ^2/dof , a factor of 4.6, WITHOUT the verdict turning over** – 'L-147's answer stands, and the floor moving while the verdict does not is what measures how far the instrument still has to go.). *Computes:* r_D asserted inside 5.5-8 Mpc; τ' at the visibility peak asserted BELOW the gate (PART 1's premise); **the sign asserted to flip either side of the correction – if it does not, it is a coefficient error and not a double count**; the single-mechanism heights asserted within 5% and asserted better than BOTH the no-damping and the double-counted runs; the floor asserted to fall by 3x or more; **and the control asserted to remain ABOVE $\chi^2/\text{dof} = 2$ – if it ever drops below, the likelihood CAN arbitrate and 'L-147's verdict must be revisited. ** *Bound:* **scope: this does not reach sub-per-cent heights and does not make the likelihood answerable. The residual is still worst at high multipole: no polarisation term in the source, and a photon sector with no free-streaming hierarchy after decoupling. Neither is a CR question. ** *Run:* python3 receipts/P15_CR_cosmology/P15_the_derived_diffusion_damping.py

P15R70 P15_the_height_target_was_below_the_resolution_of_its_own_statistic [OK]
the acoustic sector (**THE HEIGHT TARGET WAS QUOTED AGAINST A SKY NUMBER WITH A 3.4% ERROR BAR THAT WAS NEVER WRITTEN DOWN, AND χ^2 – THE STATISTIC THAT CAN SEE – PREFERS A COEFFICIENT IT IS NOT ALLOWED TO CHOOSE. ** Front #2. Since c54.168 every height claim here (-13%, -34%, 2-3%, -0.05%)

compared P1/P2 and P1/P3 to two bare numbers, 2.217 and 2.277. ****PART 1**** the numerics are cleared first: 1.4x the modes, 1.3x the k-range and 1.8x the eta-sampling move the ratios by 0.09% and 0.37%, and the 2%/7% swings that prompted the check came from LMAXL=1300 truncating the k integral under the THIRD peak. ****PART 2**** read off the plik_lite bandpowers with the published covariance – the full 2x2 block, not a diagonal estimate – ****the sky’s own ratios are 2.256 +- 0.077 and 2.280 +- 0.074: 3.4% and 3.2%.**** So the 13% and 34% of c54.173 were four and ten sigma and stand; ****the 2-3% of c54.175 are about one sigma and do not.**** *Caught by bookkeeping and not by suspicion: X_data is binned C_l and not D_l, so peak-finding on it returned 464/761/1085 instead of 221/527/815.* ****PART 3**** a scan of one multiplier on 1/k_D^2 has P1/P2 selecting 1.094 +- 0.184 and P1/P3 selecting 0.897 +- 0.055 – ****a 1.03 sigma split, so my own ‘no single scale fits both, the residual is the envelope’s SHAPE’ is WITHDRAWN at its own error bar rather than published.**** ****PART 4**** chi^2 over 185 bins does separate them: the minimum sits at 0.865 against 8/9’s 0.859, and 16/15 costs 1123 units, seven inflated sigma. ****The coefficient is changed back to 8/9 and NOT because it fits better**** – neither value has ever been derived here (C8_diffusion.length names the ambiguity in its own text), and a remembered number is not a derivation any more than a fitted one is. ****PART 5**** L-147’s pinned chi^2 came from a script in /tmp; ‘chi2_of_spectrum.py’ puts that machinery in the corpus and returns 4170.2 and 50675.2 exactly.). *Computes:* converged spread asserted under 1% and the truncated run asserted separated from it; the sky’s recomputed ratios asserted within 1 sigma of the bare numbers they replace; the DAMPX multiplier asserted to reproduce the explicit POLC=8/9 run to 0.2%; ****the withdrawal asserted: if the split were 2 sigma or more the file FAILS for retracting a claim that in fact holds****; the chi^2 minimum asserted at the 8/9 multiplier within 5%; both pinned values asserted recomputed to 0.5%; and an assert that fires if the control ever reaches chi^2/dof ~ 1, since this file would then need rewriting rather than patching *Bound:* ****scope:** this corrects a MEASUREMENT PROTOCOL, not the construction, and it is a correction to my own work. It supplies no derivation of the shear coefficient – that is named as owed and is front #2’s first item: the free-streaming photon hierarchy with the polarisation multipoles. And the 3.2-3.4% is the single-bandpower-bin resolution; a full-curve fit determines the peaks far better, which is exactly why chi^2 replaces the ratios rather than joining them.** *Run:* python3 receipts/P15_CR_cosmology/P15_the_height.target.was.below.the.resolution.of.its.own.statistic.py

P15R71 P15_the_shear_coefficient_derived_not_remembered [OK]
the acoustic sector (****THE DIFFUSION-DAMPING SHEAR COEFFICIENT, DERIVED FROM THE POLARISED PHOTON HIERARCHY INSTEAD OF REMEMBERED OR FITTED – AND ADOPTING IT COSTS THE CONTROL 1123 UNITS OF chi^2.**** Front #2, closing the item c54.176 named as owed. ‘C8_diffusion.length’ has named ‘the 8/9 coefficient against the 16/15 polarization-corrected one’ in its own text since it was written, and neither had ever been derived here. ****METHOD**** two integrations of the same oscillator on the same background: the perfect tight-coupled fluid, undamped by construction, against photons carried to $l = 24$ with Thomson scattering, the polarisation multipoles evolved alongside and the baryons on their own velocity. ****Their ratio is the damping and nothing else – the $(1+R)^{1/4}$ WKB prefactor, the drift of c_s and the R-dependence of the oscillation are common to both and divide out identically.**** Gravity is off in both, which is the definition of the object rather than an approximation. ****PARTS 1-4**** with $G = 0$ the $l=2$ term is $-(9/10)\tau'F_2$, the textbook unpolarised closure, and $C = 0.8852$ against 8/9; with polarisation $C = 1.0618$ against 16/15; ****and the polarisation correction – the quantity actually in dispute – is a factor 1.1996 against 6/5, three parts in ten thousand.**** C is read *LOCALLY* between consecutive extrema and extrapolated in $(k/\tau')^2$, so the k^2 scaling is measured rather than imposed. ****PART 5**** 16/15 is adopted and the control’s floor goes 22.5 -j 28.6. ****The fit’s preference for 8/9, measured and refused at c54.176, is refused again: a coefficient chosen because it fits is a fitted parameter whatever it is called.**** ****PART 6**** and nothing downstream moves – sec:envelope-consequence’s 10.8% goes +10.83% -j +10.87%, because the coefficient nearly cancels in a ratio of two rates.). *Computes:* both intercepts asserted within 2% of the leading-order values and pinned to ~1% in the gate; ****the polarisation correction asserted within 0.5% of 6/5 and pinned to a tenth of a per cent – it is the number the file exists to produce****; the scatter about the line in $(k/\tau')^2$ asserted below 0.01, so a method that destroyed the extrapolation fails rather than shifting the intercept quietly; the sign of the finite- (k/τ') correction asserted, and the extrapolation asserted *SHORT* (under 2% of the coefficient swept over the fitted range); ****the chi^2 cost asserted POSITIVE – if the derived coefficient stopped costing chi^2 the file’s whole point would need**

restating**; and the C8 figure asserted to move less than a tenth of a point, so adopting the coefficient cannot silently shift a published number *Bound*: **scope: this derives the coefficient in the WKB damping integral and NOT the damping envelope's shape. It supplies the damping half of the polarisation physics only; the SOURCE half – $g\pi/4$ and $(3/4k^2)(g\pi)$ with $\pi = \Theta_2 + \Theta_{P_0} + \Theta_{P_2}$ – needs the hierarchy carried in the spectrum instrument and is what front #2 still owes. And one assertion of mine fired on its own data: I demanded both extrapolation slopes be of order unity and they are -0.150 and -0.942; the gate now checks that the extrapolation is SHORT, which is the thing that actually matters.** *Run: python3 receipts/P15_CR.cosmology/P15.the_shear_coefficient_derived_not_remembered.py*

P15R72 *P15_the_photon_hierarchy_in_the_transfer* [OK]
the acoustic sector (**THE PHOTON BOLTZMANN HIERARCHY WITH POLARISATION CARRIED INSIDE THE TRANSFER: THE CONTROL'S χ^2/dof FALLS 28.6 -; 7.1 AND THE FIRST FOUR PEAKS LAND AT 220/540/812/1124 AGAINST THE SKY'S 220.6/538.1/809.8/1147.8.** Front #2. Photons as multipoles to $l = 24$ with the polarisation hierarchy alongside, the baryons on their OWN velocity and their OWN density, and the source carrying $g\pi/4$ and $(3/4k^2)(g\pi)$. **THE HANDOVER MAKES A DOUBLE COUNT IMPOSSIBLE RATHER THAN MERELY ABSENT**: the fluid runs to $\tau' = 3/\text{Mpc}$ and the envelope is FROZEN there, so envelope and multipoles have disjoint supports – and only 4.2% of $1/k_D^2$ has accumulated at the handover, so 96% of the damping is dynamic. **PART 1** the second peak is 0.35% out and the third 0.27%, where the fluid had them 2.6% and 0.7% low. **PART 2** χ^2/dof 28.6 -; 7.1, and 20.0 -; 4.2 over the range where the wavenumber integral is not starved. **PART 3** and c54.177's prediction is checked against the number it predicted: **running the same hierarchy with ONLY the two polarisation source terms dropped – exactly the half an envelope has – gives 2022 against 1320, so they are worth $\Delta\chi^2 = 702$, 63% of the 1123 that adopting the derived 16/15 cost.** **PART 4** and half the baryon split is WORSE than none: own density while still sharing the photons' velocity moved χ^2/dof 133 -; 161 at development settings; both halves give 15.1 -; 7.1. *Twice now a physical effect taken in half has been worse than not taken – it is not a small error but a different and inconsistent model.* **PART 5** doubling the hierarchy depth moves χ^2 by 0.00% and doubling the handover opacity by 1.5%. **PART 6** and the CR arm is at $\text{ell}_1/\text{ell}_A = 0.5703$ for the SIXTH instrument state, while the control improved fourfold.). *Computes*: every peak asserted no FURTHER from the sky than the fluid transfer's; the χ^2 improvement asserted to be at least a factor of two and pinned at 7.14 / 4.17; both height ratios asserted within 2 sigma of the sky's own covariance-derived values; **the polarisation source terms asserted to recover between 40% and 120% of c54.177's 1123 – outside that range c54.177's statement could not be said to have predicted this and the file FAILS**; the full baryon split asserted to beat the shared-density run; the LG and handover sensitivities asserted below 0.1% and 5%; the CR arm asserted unmoved to the fourth decimal; and an assert that fires if the control ever reaches $\chi^2/\text{dof} \sim 1$, since L-147 would then have to be REOPENED rather than this file's closing line printed *Bound*: **scope: this is the LambdaCDM control and the CR arm on one instrument, and it converts nothing into a verdict – 'PO-7' is protected and 'L-147's answer is unchanged, because a control at seven times a fit still cannot certify what it is compared with. What remains is accuracy and no longer a named missing SECTOR: reionisation, neutrino mass, lensing, and the wavenumber range. And the aliasing gate was found MISSING from the line-of-sight path, which has been the default since c54.173; it cost a development run a first peak at 196 instead of 220 with nothing said, and is now on both paths.** *Run: python3 receipts/P15_CR.cosmology/P15.the_photon_hierarchy_in_the_transfer.py*

P15R73 *P15_what_is_left_is_lensing_and_not_reionisation* [OK]
sec:refit-bound (**BOTH OF FRONT #2's NAMED NEXT STEPS MEASURED BEFORE EITHER WAS BUILT, AND ONE IS WORTH EXACTLY NOTHING.** **PART 1** above $\text{ell} \sim 40$ reionisation's whole TT effect is the constant screening $\exp(-2\tau)$, and the amplitude here is fitted in CLOSED FORM – $A = (m F d)/(m F m)$ is homogeneous of degree -1 in m , so $m \rightarrow s m$ returns A/s and the residual is IDENTICAL. $d(\chi^2) = 0$ exactly, shown at $\tau = 0.054, 0.10$ and 0.30 , zero to machine precision at all three.** *The degeneracy is a property of the STATISTIC, not of the size of τ .* **PARTS 2/3** a Gaussian smoothing in ell , width scanned, minimises at $\chi^2 = 921$ against the control's 1320 – and **a width that GROWS with ell beats a constant one by 1.8x in $d(\chi^2)$, 400 against 225, each at its OWN optimum so the comparison is of SHAPE**. Lensing smooths more at high ell because a deflection of fixed angle subtends a

larger fraction of an acoustic wavelength, and that is the signature the data select. **PART 4** the width is FITTED, so the 400 bounds what a DERIVED calculation has to play for and is not a measurement of the lensing amplitude – and ~921 of the 1320 survives it, so lensing is the next build and is NOT the last one. **Computes:** the reionisation degeneracy asserted EXACT – if it ever moves χ^2 the amplitude is no longer fitted in closed form and PART 1's algebra no longer describes the pipeline; both smoothing optima pinned; the growing width asserted to beat the constant one by at least 1.5x, which is the SHAPE claim and the reason the word is 'lensing' rather than 'some smoothing'; what survives asserted above 60% of the baseline, so a rewrite is forced rather than a patch if a fitted smoothing ever accounts for most of the residual; and an assert that fires if a smoothing alone would take the control to $\chi^2/\text{dof} \geq 2$, since L-147 would then have to be revisited **Bound:** scope: this measures what two candidate builds can be worth on THIS statistic. It is not a result about the sky, not a measurement of the lensing amplitude, and the control does not improve – the smoothing width is fitted. Reionisation is STRUCK from the front's list rather than deferred, and the condition that would undo the strike is written down: a comparison reaching $\ell \geq 30$, a second spectrum, or a fixed amplitude. **Run:** python3 receipts/P15_CR_cosmology/P15_what_is_left_is_lensing_and_not_reionisation.py

P15R74 P15_derived_lensing_on_the_lcdm_arm [OK]

sec:refit-bound (**THE DERIVED LENSING c54.181 TEED UP, RUN WITH NO FREE WIDTH – AND IT COMES IN UNDER THE FITTED BOUND, WHICH IS WHAT A DERIVATION MUST DO.** Λ CDM's own non-perturbative lensed/unlensed ratio applied to the c54.178 LCDM arm takes the control 1320 – 989, $d(\chi^2) = 331$ – UNDER the 400 the c54.181 fitted smoothing bounded, and concentrated in the damping tail (ℓ 1100-1500) where lensing fills the troughs. The acoustic peaks move 0.0%. The corpus's own first-order Hu (2000) kernel, run on the SAME C^{phiphi} so only the ORDER differs, OVERSHOOTS to 508 because it BREAKS DOWN in the tail – a spurious +13% at $\ell=1900$ against the full operator's +6.5% – so the derived number is the full operator's 331, not the first order's 508. Validated on CAMB's own LCDM: 615 unlensed – 186 lensed ($\chi^2/\text{dof} \sim 1$). ~989 of 1320 survives, so lensing is real and NOT the last build.). **Computes:** lensed CAMB LCDM asserted at χ^2/dof in (0.75,1.25) so the operator and pipeline are validated before anything is read off the arm; the derived lensing on the arm asserted in (280,385) AND strictly under the c54.181 fitted bound of 400, which is the defining property of a zero-width derivation against a fitted upper bound; the first-order kernel asserted to OVERSHOOT the full operator by more than 80 in $d(\chi^2)$ via the tail artefact, a live check that LENS_correction is first order and that the tail is where it fails; and the peak shift asserted below 0.3%. **Bound:** scope: the lensing operator is Λ CDM's, imposed not fitted, so this is not a measurement of the lensing amplitude and the CR arm does not fit – it measures how much of c54.181's fitted-smoothing headroom a genuine zero-parameter lensing recovers (most of it), with the shortfall against the fit being the fit's free width. The residual ~989 is the instrument's transfer inaccuracy, not lensing's: CAMB's UNLENSED LCDM already sits at 615 on these same bins. 'PO-7' stays protected. **Run:** python3 receipts/P15_CR_cosmology/P15_derived_lensing_on_the_lcdm_arm.py

P15R75 UNC_error_budget [OK]

sec:refit-bound (UNC — QUANTIFYING WHAT WE DO NOT KNOW. The prediction with an error budget. Corrections folded in first: * the recombination WIDTH scales with the rate (A.22) – so the thickness contributes nothing to the RATIO and the signature is carried by r_D essentially alone; * the l_D anchor affects only the ABSOLUTE r_D and cancels in the ratio – it carries NO uncertainty into the prediction;). **Computes:** runs clean; registered from its own docstring and a live run **Bound:** description is the receipt's own wording, condensed; not independently re-derived here **Run:** python3 receipts/P15_CR_cosmology/UNC_error_budget.py

P15R76 P15_the_residual_is_contrast_and_the_lensing_potential_is_derived [OK]

sec:refit-bound (**WHAT THE CONTROL'S REMAINING χ^2 IS MADE OF, AND THE LENSING POTENTIAL BUILT TO ATTACK IT.** **PART A** templates projected through the same inverse covariance the χ^2 uses: positions remove 1.4 of 1320 – 0.1%, so the peaks are where the sky puts them and that is not where the residual lives; a smooth envelope 15%; the peak-trough oscillation at FIXED position 38%, with the model's contrast 13.1% TOO HIGH – which is what lensing reduces; and 53% in NEITHER, so a perfect lensing calculation leaves about half. Fitted templates, so each share is an upper bound on what the effect can claim. **PART B** the line-of-sight solve stops at $z = 12.8$ but the lensing kernel peaks at $z \sim 3.3$, so Φ is carried on by the background's own growth factor D prop. $H \int da/(aH)^3$ – exact in linear

theory, no transfer function imported, k-dependence from this instrument's own Phi. ****And the normalisation is the amplitude the TEMPERATURE comparison already fits, so lensing enters with NO new parameter.**** Limber checked against an EXACT projection (5% over $l = 5-200$); the deflection maximum is BROAD, within 10% over $l = 12-42$; ****rms deflection 2.69 arcmin with nothing tuned to it.****). *Computes:* positions asserted below 2% of the residual, so the diagnosis reorders loudly if they ever rise; the contrast excess pinned to $13.1\% \pm 2$ points, since that is what the convolution must remove; what survives BOTH template sets asserted at $53\% \pm 5$, ****so a build that forgets how much remains fails here****; Limber's departure asserted below 10%, since the convolution will use it; the deflection maximum asserted BROAD; and the absolute rms deflection pinned at 2.692 arcmin, which is the zero-parameter check on the normalisation *Bound:* ****scope:** PART A's shares are FITTED-template upper bounds, not measurements of physical effects, and the two sets overlap by ~ 7 points. And PART B's external agreement is weaker than it looks: the ~ 2.7 arcmin and the $\sim 1e-7$ deflection power it matches are RECALLED, not derived here and not checked against a source this corpus holds – this programme was bitten twice in three revisions by exactly that (the 16/15 coefficient at c54.176, and a Limber suspicion in this very file which was also recollection and also wrong). What PART B establishes is INTERNAL consistency; the external agreement is corroboration at the strength of a memory. **** Run: python3 receipts/P15_CR.cosmology/P15.the_residual_is_contrast_and_the_lensing_potential_is_derived.py**

P15R77 P15_the_phase_is_the_driving_and_the_undriven_arms_agree [OK]
sec:refit-bound (****WHY 0.62 pi: THE DRIVING — AND THE ATTRIBUTION IS COMPLETE. WITH EVERY COUPLING TO THE POTENTIAL REMOVED THE TWO ARMS' ACOUSTIC PHASES AGREE TO 0.013 OF l_A .** **** Front #2, lead 'L-507'. c54.191 closed with "**an acoustic phase shift is a computable consequence of the driving, so 'why 0.62 pi' has an address. This file does not have it."****** ****The instrument has carried the switch since c54.170** — 'NODRIVE=1' removes every coupling to the potential at every site (the $4\cdot\Phi$ ' in the photon, neutrino and CDM continuity equations and the $k^2\cdot\Psi$ in the Euler equations) while leaving Φ 's own evolution alone, that being the background and not a coupling. ****Both arms run through it at production depth here, which no revision had done.** ****PART 1 UNDRIVEN THE TWO ARMS ARE THE SAME OSCILLATOR:**** intercepts **** -0.135 and -0.149 of l_A — agreeing to 0.013**** — and both slopes l_A to a part in a thousand. ****Two constructions with different rates, sound horizons, starting redshifts and initial data give the SAME acoustic series once nothing drives it.** ****PART 2 AND THE DRIVING IS WHAT SEPARATES THEM:**** switched on it supplies **** -0.127 to the control and -0.729 here, a factor of 5.7****; the driven discrepancy is 0.615 and the undriven 0.013, so ****the driving accounts for 98% of it****. ****PART 3 THE SAME SWITCH ACCOUNTS FOR THE SPACING:**** undriven both slopes are 1.000 and 1.001 of l_A ; driven, the control's is 1.003 and this construction's 0.976 — ****so the 2.4% the spacing was short is the driving as well, and not a second effect****. $\Rightarrow$ *****THE WHOLE ACOUSTIC DISAGREEMENT IS ONE COUPLING BEHAVING DIFFERENTLY — and a coupling is a thing a theory says something about, where a ratio is not.** *****PART-HEADLINE CORRECTED c54.195 ('L-508'):** the 0.62 pi is the value at $\phi = 0$. Across four seam phases at production depth the asymptotic phase spans 0.891 and the CONTROL'S VALUE LIES INSIDE that span, so it is not a prediction. The driving ATTRIBUTION stands; its promotion to "the whole disagreement" does not. *******). *Computes:* ****the UNDRIVEN agreement asserted under 0.10 of l_A — if the arms still differed with nothing driving them the driving would not be the whole story and PART 2's headline would be wrong****; the ratio of what the driving supplies asserted above 3x and pinned at 5.7 ± 1.5 , without which PART 2 has no content; ****the undriven SLOPES asserted at l_A to 1%, which is what makes PART 3's "not a second effect" true****; the driven discrepancy re-derived at 0.615 ± 0.05 , tying this file to 'L-505' and 'L-506'; the driving's share asserted above 85%; and at least seven peaks per arm *Bound:* ****scope:** an ATTRIBUTION is not an explanation and it is not a verdict. What this establishes is that the acoustic disagreement lives in ONE COUPLING rather than in four items, a ratio, or an initial condition. IT DOES NOT SAY WHY the driving is 5.7x stronger here — the obvious candidate is that this construction's modes begin already sub-horizon at the seam carrying an assigned amplitude and ZERO velocity, in a potential that is not the equilibrium configuration for that state, where the control's begin super-horizon in adiabatic equilibrium; ****that is a HYPOTHESIS and this file does not test it****. The instrument carries the split that would: 'DRC' is the potential's rate of change feeding the density and 'DRE' its gradient driving the velocity, switchable separately — the next thing this front owes. 'F5' unsoftened; 'PO-7' protected; the conversion runs by 'F5's stated procedure. **** Run: python3****

P15R78 P15.the.phase.moves.with.the.datum.and.only.the.spacing.does.not [OK]
sec:refit-bound (**THE OBSERVER LINE'S ITEM 38 ANSWERED, AND THE ANSWER WITHDRAWS c54.190–191's HEADLINE. ACROSS FOUR SEAM PHASES AT PRODUCTION DEPTH THE ASYMPTOTIC ACOUSTIC PHASE SPANS 0.891 IN ϕ/π — AND THE CONTROL'S 0.263 LIES INSIDE THAT SPAN.** Front #2, lead 'L-508'. *Item 38 (r2485): of the 23 datum-scan spectra ZERO reach peak 8, so the quantity carrying the disagreement could not be tested against the one freedom known to move things. It named the experiment — two or three seam phases at production depth. c54.191 supplied one; this supplies two more.* **PART 1** at $\phi = 0, \pi/4, \pi/2$ and π the fitted ϕ/π is **0.878, 0.958, 0.066, 0.671** — *c54.191 read 34% closure from the two endpoints; **the interior is where the motion is***. **PART 2 SO 0.62 π IS THE VALUE AT ONE READING AND NOT A PREDICTION.** *The attribution to the driving (c54.193) stands — the driving is what separates the arms AT A GIVEN READING — but a quantity the datum can move across the control's value is not a prediction of the construction.* **PART 3 THE HEIGHTS MOVE TOO:** P1/P2 runs **0.483 $\rightarrow$ 1.618** against the sky's 2.217 and the control's 2.197, and **never reaches it**. **PART 4 WHAT IS ROBUST IS THE SPACING:** 0.9629–0.9814 of λ_A over the same four — **1.9%** — and tracking r_s at 98% of the acoustic rate under the fitted parameter. **PART 5 AND MATCHING THE PHASE DOES NOT FIX THE SPECTRUM**, which is what settles PART 2: the reading closest in phase ($\phi = \pi/2$, a phase gap of 0.197) has $\chi^2/\text{dof} = 224$ against the control's 3.71 on the same 185 bins — sixty times worse while agreeing on the phase**. $\Rightarrow$ ***So the phase was never carrying the disagreement.***). *Computes:* **the control's phase asserted INSIDE the span the seam phase reaches — without which there is no withdrawal and c54.190–191 stand as written**; the span asserted above 0.3 and pinned at 0.891, which IS item 38's question; **the low-ell transient asserted present in ALL FOUR at more than 3x the control's — this is what establishes the peak INDEXING, and if a reading showed none the span could be an artefact of labelling**; the spacing's stability asserted under 6%, the one thing this file does NOT withdraw; the heights asserted never to reach the sky's; and **the phase-matched reading asserted above 10x the control — PART 5 is what makes the withdrawal a finding rather than a shrug**
Bound: **scope: this is the THIRD withdrawal of this line's own headline in the span, and it is forced by the data rather than chosen. What it leaves is worse than c54.191 reported and truer: the acoustic SPACING is right and robust; the acoustic PHASE and the peak HEIGHTS both move substantially with a datum the corpus does not fix and neither reaches the sky at any reading tried; and no reading brings the spectrum within sixty times the control. **Where the disagreement lives is therefore not a single named quantity and this file does not supply one.**
'F5' unsoftened and it cuts both ways — a discrepancy resting on a free choice is not a framework verdict either. 'PO-7' protected; the conversion runs by 'F5's stated procedure.** *Run:* python3 receipts/P15_CR_cosmology/P15.the.phase.moves.with.the.datum.and.only.the.spacing.does.not.py

P15R79 P15.the.locus.is.wrong.in.six.places.and.the.lint.cannot.see.the.worst [OK]
sec:perturbations, sec:coherence, sec:envelope (**ROUTED ITEM 21 WORKED: SIX SITES SAID "BRANCH POINT" WHERE THEIR OWN RECEIPTS SAY "SEAM"/"ONSET", AND THE PHYSICS INVERTS BETWEEN THE TWO — SO A PROPOSITION TITLED "SUB-HORIZON" WAS TRUE AT ONE AND FALSE AT THE OTHER. AND THE LINT BUILT FOR THIS DEFECT COULD NOT SEE THE WORST OF THEM.** Front #2, lead 'L-509'; VEIN 'L-202'. **PART 1 THE INVERSION, RE-DERIVED FROM THE METRIC FUNCTION** rather than taken from the routing slip: normalised $1/aH$ is **1.000 at the seam and 0.051 toward $r=0$ **, and with the inherited datum the horizon maximum sits at $r^* = 1.5338 r_{\text{seam}}$, just OUTSIDE the seam** — so the seam is on the rising branch and the acoustic modes are already inside there, which is a *derivation* of prop:subhorizon and not a numerical coincidence of z_{onset} . **PART 2 SIX SITES REPAIRED, PINNED BY TEXT AND NOT BY LINE NUMBER** — including the subsection heading, *which contradicted its own proposition three lines below*, and the *sec:envelope* sentence *that claims to BE the derivation, with the locus backwards*. **One of the six was not on the routed item's list**; the lint found it. **The one true-as-written branch-point sentence — the neutrinos' decoupling, a TEMPERATURE ordering, flagged as a false positive by the finder in advance — survived the sweep.** **PART 4 AND THE GATE WAS VERIFIED AGAINST A CLEAN TREE, WHICH MEASURES NOTHING:** seeding prop:subhorizon 's body back to "at the branch point" left 'check.loci' printing *clean* and exiting 0. *A proposition states

its claim in the body and cites its receipt in the argument paragraph below, so the corpus's most load-bearing claim shape was the one shape a per-sentence scan is blind to — and it was the item's own first site.* $\Rightarrow$ ***Theorem-body binding added; 11 $\rightarrow$ 12 bindings, +0 false alarms, motivating defect MISSED before and CAUGHT after.***). *Computes:* **the inversion itself asserted from the metric function — without it the substitution is cosmetic and every edit is unmotivated**;
 r^*/r_{seam} re-derived to 1.5338 from the quartic rather than quoted; the six repaired strings asserted PRESENT and the six defective strings ABSENT, by text so a reintroduction fails this file;
the protected false positive asserted still present — a sweep that also took the one true sentence would be a different error with the same shape;
and **the recall hole asserted in BOTH directions — MISSED before the binder extension, CAUGHT after — so if the pre-extension scan ever starts catching it, this file says the hole was not real**;
plus the declared exception asserted to LAPSE when its sentence is rewritten *Bound:* **scope: this is exposition and instrument, not physics — no number in the cosmology moves. Its warrant is 'THE_METHOD' §III: a framework a reader cannot follow cannot be excavated, and this one had a heading contradicting its own proposition. The completeness qualification added at sec:coherence is transcribed from 'C2_horizon_limits' STEP 6, which the paper's sentence contradicted; it is not a new physics claim. 'check_loci' remains a triage lint and not a CI gate — the contributor's call, not reversed here.** *Run:* python3 receipts/P15_CR.cosmology/P15.the.locus.is.wrong.in.six.places.and.the.lint.cannot.see.the.worst.py

P15R80 P15_the_filter_is_a_sound_speed_filter [OK]

sec:what-crosses (**THE BRANCH-POINT SELECTION RULE'S EXPONENT HAS TWO FACTORS AND THE CORPUS VARIES ONLY ONE.** The damping is $e^{-k c_s |\Delta \epsilon|}$: 'sec:what-crosses' holds c_s at the plasma's value and varies k , reading a SCALE criterion (frozen against oscillating). **Hold k and vary c_s and the same inequality is a SPECIES criterion — and a pressureless component has $c_s = 0$ IDENTICALLY, so its exponent vanishes at EVERY wavenumber.*** THAT MAKES THE MATTER SECTOR'S INHERITANCE EXACT RATHER THAN ADIABATIC: ** at $c_s = 0$ the segment's mode equation is $\psi'' = 0$, whose constant solution the kernel leaves untouched with no approximation, whereas the frozen-mode argument rests on horizon exit and degrades at small scales. The two agree wherever both apply; only the pressureless one is available everywhere. COMPUTED on the corpus's own segment: (1) $|\Delta \epsilon| = 3.3197$ (the recorded 3.32); (2) exact transfer-matrix transmission in BOTH k and c_s , reproducing $-k c_s |\Delta \epsilon|$ to the digit for every constant c_s ; (3) $\ln T = 0$ EXACTLY at $c_s = 0$ for $k = 1, 10, 85.3, 1e3, 1e5$ — uniform in k **;
(4) at the first peak the exponent runs $\sim 1.6e2 c_s/c$, so the filter is opaque above $c_s \sim 3.5e-3$. ** CONSEQUENCE: a per-cent sound speed already gives $e^{-1.6}$ and ten per cent e^{-16} , so THE CROSSING CAN INHERIT PERTURBATIONS FROM A COLD SPECIES AND FROM NO OTHER — a sharp condition on what the progenitor may hand over. ** (SCOPE: the arithmetic is what this receipt establishes; no species selection rule follows from it. The kernel acts on OSCILLATORY content and nothing arrives oscillating ('P16_every_mode_is_frozen_at_the_crossing'), so the exponent computed here has nothing to act on and the crossing is lossless for EVERY species.***). *Computes:* the segment's conformal length asserted at 3.32; the plasma exponent asserted in (-160,-140); $\ln T$ asserted zero to $1e-9$ at $c_s = 0$ across five decades in k *Bound:* ** THIS IS THE FIELD HALF ONLY. ** What happens to perturbations of a given species; the detailed WORLDLINE dynamics of a concrete model at the branch point is a separate computation and is not done. ** And an honest bound**: on this segment the plasma exponent comes out -147 against the -152 the corpus records, a 3% difference from the sound-speed profile's discretisation — nothing here turns on it, the load-bearing result being the exact vanishing at $c_s = 0$, which is profile-independent *Run:* python3 receipts/P15_CR.cosmology/P15.the.filter.is.a.sound.speed.filter.py

P15R81 P15_the_collapse_leg_is_scale_invariant [OK]

sec:transmission (**THE COLLAPSE LEG IS A SCALE-INVARIANT BACKGROUND, AND P15 LISTS 'CR HAS NO INFLATIONARY SCALE-INVARIANT ATTRACTOR' AS AN ESTABLISHED SIGNATURE. THE ADJECTIVE WAS CARRYING THE SENTENCE.** For a background $a \sim (-\epsilon)^{\beta}$ with $z \sim a$, the Mukhanov-Sasaki potential is $\beta(\beta-1)/\epsilon^2$, so scale invariance requires $\beta(\beta-1) = 2$ — a quadratic with TWO roots: $\beta = -1$, de Sitter inflation (expanding), and $\beta = +2$, a MATTER-DOMINATED CONTRACTION.*** And the corpus's own collapse leg is $\beta = 2$ exactly:** its banked near-branch-point law $r^3 = (9/2) M \tau^2$ with $a = |r|$ gives $d \ln a / d \ln \tau = 2/3$ and $d \ln \epsilon / d \ln \tau = 1/3$, hence $a \sim \epsilon^2$ — forced by $f_{-i} - 2M/r$, the mass term dominating and the Lambda term vanishing, **which is the

same pressurelessness ‘A·4’ used at c54.112 to show such a component crosses exactly.** The mode equation integrated from vacuum data on both backgrounds returns $d \ln P/d \ln k = 0$ to a part in 10^4 . **So $n_s = 1$ is produced by the construction rather than inherited from the progenitor, and only the DEPARTURE from unity is owed.**). *Computes:* the two roots asserted $[-1, 2]$; both logarithmic slopes of the leg asserted exactly $2/3$ and $1/3$; both integrated spectra asserted flat to $1e-3$ *Bound:* **bound, and it is the whole caution: this is the STANDARD contraction result (Wands 1999; Finelli-Brandenberger 2002) applied to a background the corpus DERIVES. It inherits that literature’s known difficulty – whether the matching across the bounce selects the scale-invariant mode – and here the bounce is a branch point with an analytic continuation rather than a smooth bounce. THAT QUESTION IS NOT SETTLED HERE and is registered as ‘L-169’** *Run:* python3 receipts/P15_CR.cosmology/P15_the_collapse_leg_is_scale_invariant.py

P15R82 P15_the_continuation_is_diagonal [OK]

sec:predictions (**THE CONTINUATION THROUGH THE BRANCH POINT ACTS DIAGONALLY ON THE TWO PERTURBATION MODES, SO THE SCALE-INVARIANT SPECTRUM DOES NOT REACH THE OBSERVER.** The falsifier on the companion result, named at c54.122 and run at c54.123. **The scale-invariant spectrum sits in the mode that DOMINATES the contraction ($\zeta \sim \eta^{-3}$); the mode that SURVIVES on the expanding side is the constant one, whose spectrum from vacuum data is $n_s - 1 = 6$.** Whether the first reaches the second is a connection problem, settled here two independent ways. ***(i) PARITY:* the exponents 2 and -1 differ by an integer so a logarithm could mix them – but $\sinh^{2/3}$ is EVEN in τ , which places its correction at η^6 and steps the Frobenius recursion in SIXES past a resonance sitting at THREE. No logarithm.** ***(ii) NUMERICS:* continuing both solutions around the branch point, the diagonal entry goes to 1.000131 and the leakage falls as a clean $\delta^{2/3}$ power law – and the power law is itself evidence against a log, which would leave a residual no power of δ removes.** So c54.122’s scale invariance is confined to the contracting side. **What survives is narrower and sharper than what it replaced: the construction HAS a scale-invariant background, and the obstruction is a PARITY PROPERTY OF ITS OWN SOLUTION rather than a missing mechanism.**). *Computes:* indicial exponents asserted; both vacuum coefficients’ k -scalings asserted exactly $-3/2$ and $+3/2$; the absence of odd powers in the correction asserted; the resonance asserted unreachable; the diagonal entry asserted to $1e-3$ and the leakage ratio asserted equal to $10^{-(2/3)}$ at every decade *Bound:* **bound: this settles the connection for the SCALAR mode equation on this background. It does NOT settle what a background correction ODD in τ would do – which is what mixing would require and is the named open route. Three defects were caught in the making: a check that only proved invertibility, a branch error from squaring before taking the cube root, and a test run at δ where $k \eta \sim 1.4$, outside its own frozen-mode hypothesis** *Run:* python3 receipts/P15_CR.cosmology/P15_the_continuation_is_diagonal.py

P15R83 P15_the_evenness_is_the_time_symmetry [OK]

sec:predictions (**THE DIAGONALITY IS THE CONSTRUCTION’S TIME-REVERSAL SYMMETRY, AND THE SAME INVARIANCE THAT FIXES THE PEAK HEIGHTS IS WHAT STOPS THE SCALE-INVARIANT SPECTRUM CROSSING.** The falsifier left by the previous receipt – mixing needs a background correction ODD in τ , with the Z_3 monodromy the named candidate – fires NEGATIVE. **Write the law as $r = A u^{2/3} g(u)$ with $g = [\sinh(u)/u]^{2/3}$: ALL the branch structure sits in $u^{2/3}$, and g is EVEN, analytic and non-vanishing at $u=0$ ** – exactly, not to a truncation, since $\log(\sinh u/u)$ is analytic in u^2 near 0 and the exponential of a series in u^2 is a series in u^2 . **The three sheets differ by a CONSTANT cube root of unity, and a constant multiplier cannot change a parity, so no sheet has an odd part; the conjugate branch is even too and has no branch point at all.** **AND THE EVENNESS IS $r(-\tau) = r(\tau)$: the cosmogenesis is TIME-SYMMETRIC about the branch point, and a time-symmetric background cannot mix a growing mode with a decaying one because mixing would distinguish a direction of time the background does not.** P15 sec:amplitude already leans on this same invariance one observable over – the peak HEIGHTS follow from a driving amplitude exactly invariant under time reversal. **One symmetry, two consequences, and the corpus had banked only the welcome one.**). *Computes:* $\sinh(u)/u$ asserted even with unit value at 0; g asserted free of odd powers through u^{12} ; all three sheets asserted free of odd powers; $\cosh^{2/3}$ asserted even; $\sinh^2$ asserted invariant under $u \rightarrow -u$ *Bound:* **bound: the leg is exactly even because it is the marginally-bound $E=1$ geodesic of an exactly VACUUM SdS exterior. A progenitor with real matter content – pressure, dissipation, anything carrying an arrow – would not be. This receipt

does not exclude that; it LOCATES it, and puts the question back where ‘L-150’ already sits**
Run: python3 receipts/P15_CR_cosmology/P15_the_evenness_is_the_time_symmetry.py

P15R84 P15_the_geometry_transmits_no_parameters [OK]

sec:transmission (**THE INHERITED DATA ARE NOT INHERITED FROM THE COLLAPSE GEOMETRY, BECAUSE THAT GEOMETRY TRANSMITS ZERO PARAMETERS. A COUNT, AND THE CORPUS PROVED THE KEY STEP ITSELF WITHOUT CASHING IT.** The SdS progenitor family is parametrised by M alone – alpha is the one invariant and E=1 is a choice of geodesic – so the geometry is ONE-dimensional. **And c54.113 showed the Kretschmann along the bead is MASS-FREE in the faller’s own proper time ($dK/dM = 0$, re-asserted here; $K \sim (64/27)/\tau^4$). A quantity identical for every member carries no information about which member it was, so the approach transmits ZERO parameters, not one.** Against that the corpus draws at least FOUR independent numbers: A_s, n_s, eta, z_onset (= rho_r/rho_m, one datum by c54.105), and the light-element composition. **Four numbers cannot come from zero parameters, so ‘inherited from the progenitor collapse’ cannot mean inherited from the collapse GEOMETRY – it means inherited from the progenitor’s MATTER CONTENT, which M does not carry, the exterior being exactly vacuum and the interior dust without composition.** This RECLASSIFIES the row: not a derivation problem but a modelling one. **What the geometry does fix it fixes universally: $|\Delta \eta| = 3.32 \alpha = 1.8e4 \text{ Mpc}$, from Lambda alone – a CUT-OFF, not a CONTENT.**). *Computes:* dK/dM asserted zero and the 64/27 limit asserted; the count of drawn data asserted at least four; the conformal length asserted 3.32α and asserted to land between $1.5e4$ and $2.0e4 \text{ Mpc}$ *Bound:* **bound: a counting argument about what the construction’s own description of the progenitor can carry. It does NOT show that no model supplies eta – it shows no model of the VACUUM EXTERIOR can, and that the row needs an interior**
Run: python3 receipts/P15_CR_cosmology/P15_the_geometry_transmits_no_parameters.py

P15R85 P15_hbar_survives_in_As_and_cancels_in_ns [OK]

sec:transmission (**hbar IS A MULTIPLICATIVE CONSTANT IN THE POWER SPECTRUM, SO IT SURVIVES IN THE AMPLITUDE AND CANCELS IN THE TILT — WHICH IS WHY n_s IS DERIVABLE HERE AND A_s IS NOT.** The vacuum normalisation $v = \sqrt{hbar/2 c_s k}$ $e^{\{-i c_s k \eta\}}$ is the only place a quantum constant enters, and $\zeta = v/z$ with z classical, so $P(k) = hbar A_0 k^{(n_s - 1)}$: **A_s = P(k,0) carries hbar, and $d \ln P/d \ln k$ does not — asserted both ways.** An amplitude is the spectrum at one wavenumber; a tilt is its ratio to itself at two. **So the no-magnitude result (c54.128: neither real form supplies a second scale, and hbar, c, G are unit gauges over the single one) forbids deriving A_s and says nothing about n_s.** A_s is therefore permanently inherited while n_s is not, and the two were never the same kind of quantity — though the corpus has named them together in every statement of the frontier, which is how one got worked for thirteen revisions while the other went unexamined. **AND THE INVERSION LOOKED LIKE THE PAYOFF: a quantity not derivable from the invariants is a function of the moduli, so $A_s = F(2M/\alpha)$ and the observed A_s would MEASURE the parent’s mass. SUPERSEDED at c54.137 (‘P15_the_progenitor_vacuum_is_negligible.too’): F is computed, it is a function of TWO moduli rather than one, and it carries no fixed normalisation — the incoming amplitude is a classical datum, so the relation cannot be inverted. The hbar asymmetry itself stands unchanged.** Second handle on the same object: the spectral bound constrains total expansion past equality, this constrains the mass, and the recollapse condition caps that mass below Nariai.). *Computes:* the hbar-dependence of A_s asserted non-zero and of the tilt asserted zero *Bound:* **bound: F itself is NOT computed. The pieces exist — the mode functions, the monodromy, the mode map — and what is missing is the normalisation carried through all three rather than tracked as a scaling. The settled part stands alone: A_s is not derivable, for a reason, and the reason names which other quantities share its fate — every magnitude, and no ratio**
Run: python3 receipts/P15_CR_cosmology/P15_hbar_survives_in_As_and_cancels_in_ns.py

P15R86 I11_I1_one_condition_two_jobs_and_the_two_routes_are_independent [OK]

sec:properframe (I11+I1 — ONE CONDITION, TWO JOBS; AND P09’s TWO ROUTES ARE INDEPENDENT. Integrable-systems field bake, probes I11 and I1. $E = 1$ is $k = 0$ by $-k = E^2 - 1$; the $\sinh^{(2/3)}$ law satisfies the marginal equation identically and leaves a residual of exactly $+k$ away from it, so the closed form is the marginal member’s alone. The same condition puts $V_{\text{eff}} = 1$ at $M = -r^3/(2 \alpha^2)$, the comoving turnaround at NEGATIVE areal radius – so one condition fixes the rest frame by the field and makes the cosmology integrable. And P09’s routes are independent: route (a) grants an additively separable ansatz before deriving from it, route (b) runs on the

speciality invariant and contains no separability variable, which is why only (b) answers the prior question.). *Computes:* runs clean; twelve verdicts *Bound:* COMPUTES: alpha = 1 as the scale-invariant gauge, matching the thesis; no physical parameter pinned. Note: M and r are declared UNRESTRICTED, since positive=True silently removes the negative-radius root the probe is about *Run:* python3 receipts/P15_CR_cosmology/I11.I1_one_condition_two_jobs_and_the_two_routes_are.i

Q1_a_stated_tolerance_is_a_request_and_the_corpus_answers_it

[OK]

sec:diffusion-scale (Q1 — A STATED TOLERANCE IS A REQUEST, NOT A RESULT: RUN THE CORPUS'S ODEs AGAIN AND SEE. Numerical-analysis field bake, probe Q1, and this field's real target is the receipts rather than the prose. Census: 24 receipt files integrate an ODE and ALL 24 set an explicit rtol and atol, not one relying on a solver default; 4 contain any convergence or refinement language. So the corpus states its tolerances and, in twenty of twenty-four files, does not verify them. This receipt does the verification: scipy's solve_ivp is patched to run every call at 100x tighter tolerance, four receipts are re-run unmodified in subprocesses, and EVERY ONE still passes its own assertions. Control: a deliberately under-resolved stiff integration through the same harness DOES move, so the patch applies and the comparator sees. Verdict 5 names the margin on the corpus's one prose-side validation: r.s = 144.0 vs CAMB 144.4 is a 0.28% disagreement against the 8.2% signature it feeds, adequate by a factor of thirty.). *Computes:* runs clean; five verdicts and a control that detects a moved number *Bound:* derived here; a first comparator reported a 92% change that turned out to be a RESIDUAL column, which is supposed to move — the naive test was measuring its own patch, and the honest test is whether the assertions survive *Run:* python3 receipts/Lnumerics/Q1_a_stated_tolerance_is_a_request_and_the_corpus_answers_it.py

Q50_the_tolerance_comparisons_gate_the_verdict_and_a_third_of_them_are_not_tolerances [OK]

sec:diffusion-scale (Q5 asked whether the corpus's 688 (now 1116) 'abs(...) ; tol' comparisons carry meaningful tolerances and left it open for want of a mutation harness; the harness is built, and both halves of the answer are here — the comparisons DO gate the verdicts, and a third of them are not accuracy assertions at all). *Computes:* rewrites every site three ways and runs each from the receipt's own directory — margin (semantics-preserving, records E/T), mutate-up (abs(E+3T), catches the assert shape), mutate-down (abs(E)*0, catches the guard shape). Over 269 files and 1116 static sites: the margin transform reproduces the baseline verdict on 269 of 269; of 245 baseline-passing receipts 243 are gated by a tolerance comparison; and of 918 executed sites 210 sit at exactly zero and 54 at or over their tolerance. The receipt asserts the harness's five controls and four invariants live on a ten-file subset holding every verdict class *Bound:* SUPPORTS P15 — and closes Q5 as a CONFIRMATION, as Q1 closed. NOT CLAIMED: that any particular tolerance is the right one; this measures whether a comparison gates the verdict and how much room it has, not whether its author chose well. The two ungated files are a display filter and a documented skip that names its gated substitute *Run:* python3 receipts/Lnumerics/Q50_the_tolerance_comparisons_gate_the_verdict_and_a_third_of_them_are_not_tolerances.py

P15R87 P15_the_progenitor_vacuum_is_negligible_too

[OK]

sec:amplitude (**THE PROGENITOR'S OWN VACUUM, CARRIED THROUGH THE FULL PASSAGE AND AMPLIFIED BY THE BRANCH-POINT MIXING, IS ALSO NEGLIGIBLE — SHORT BY 1e104. So 'prop:amplitude' had ruled out the one vacuum the inheritance story was NOT claiming.** The collapse-side background is a single function, $a = M(\rho x + x^2/2)$ with $x = |\eta - \eta_c|$, whose Mukhanov-Sasaki potential $2/(x(x+2\rho))$ is **M-FREE**, so the mass enters only through the final division $\zeta = v/a$. The passage has three stages and each contributes one factor of $1/\rho$: (i) the mode freezes on the beta = 2 leg as $v \sim D_k/x$ with $D_k = \sqrt{hbar/2} k^{(-3/2)}$; (ii) **the connection through equality is elementary — $v = a \int dx/a^2$ solves the $k = 0$ problem exactly and carries D_k/x to the constant $(3/2\rho)D_k$; (iii) the crunch monodromy leaks it into the survivor with coefficient $2\pi/\rho$; and $a'(\eta_c) = -M\rho$ supplies the third. **THE TRANSFER LAW IS THEREFORE $P = 18 k^3 D_k^2/(M^2 \rho^6)$, with the k^3 cancelling identically on vacuum data — exactly scale-invariant.** On the vacuum that is $A.s = (9/4)(l_P/M)^2 \rho^{(-6)} = 2e-113$ at the recollapse cap and the determined ρ , against an observed $2.1e-9$. **The mixing buys eight orders over the bare vacuum and is still short by a hundred and four.** Two corollaries: A.s does NOT measure the progenitor's mass, D_k being free; and the classical datum has a size — the parent's growing-mode amplitude exceeded its own vacuum's by $\sim 1e47$. **The same closed form also returns c54.131's monodromy analytically, the $(x/\rho)\ln x$ term continuing to $-2\pi i/\rho$, where it had been obtained by numerical continuation.**). *Computes:* the M-free

potential asserted symbolically; the connection coefficient asserted in closed form and against integration from vacuum data to 0.10% over a decade in ρ and a factor 15 in k ; the transfer law asserted k -independent; the shortfall asserted between $1e101$ and $1e106$ *Bound:* ****bound:** $z = a$ with $c_s = 1$ is assumed on the $\beta = 2 \log - c54.122$'s own hypothesis and the standard matter-contraction idealisation, genuine dust having $c_s = 0$ and no vacuum oscillation to normalise. The $1e104$ is far too large for any $O(1)$ convention or plausible c_s treatment to touch****** *Run:* `python3 receipts/P15_CR.cosmology/P15.the_progenitor_vacuum_is_negligible_too.py`

P15R88 `P15_no_primordial_B_modes_unconditionally` [OK]

sec:amplitude (****THE TENSOR SECTOR IS WHERE THE COLLAPSE-TRANSFER MACHINE RUNS WITH NO IDEALISATION AT ALL, AND IT RETURNS $P_T \sim 5e-111$ — ONE HUNDRED ORDERS BELOW THE OBSERVATIONAL CEILING.**** The scalar transfer needs $z \sim a$, which for a fluid holds only where w and c_s are constant — and across the progenitor's own equality $(1+w)$ runs $1 \rightarrow 4/3$ while c_s runs $0 \rightarrow 1/\sqrt{3}$, so neither is. ****For tensors that is not a restriction: $z_T = a M_{Pl}/2$ EXACTLY, for any content, any equation of state, any sound speed, so $z_T''/z_T = a''/a$ identically and the entire passage — background, connection $(3/2 \rho)$, monodromy $(2 \pi/\rho)$, division by $a'(\eta_c) = -M \rho$ — applies verbatim with nothing assumed.**** It returns **** $P_T = 144 \pi (1P/M)^2 \rho^{(-6)}$, scale-invariant (k cancels identically)****, i.e. $4.8e-111$ at the recollapse cap and the determined composition, against a ceiling of $6.7e-11$ from $r \rightarrow 0.032$: ****below it by $1.4e100$, so $r = 2e-102$ **** So the absence of primordial B-modes is a prediction at any conceivable sensitivity, and ****it no longer rests on the substrate's own tensor floor — that argument had the same scope defect its scalar twin did, ruling out the substrate's vacuum and saying nothing about the progenitor's.**** And the ratio is fixed too: every k -dependent factor is shared by the two sectors, so **** $r_{out} = 6 r_{in}$ ($c54.146$: scalars mix twice as strongly as tensors), k -independently — the crossing can neither manufacture nor destroy a tensor signal, only rescale the ratio.**** The observed bound therefore measures the PARENT: its own tensor-to-scalar ratio was below $1.3e-3$). *Computes:* P_T asserted k -independent and asserted equal to $144 \pi (1P/M)^2 \rho^{(-6)}$ symbolically; the shortfall against the ceiling asserted above $1e95$; the crossing ratio asserted equal to 24 *Bound:* ****bound:** the factor 24 carries the scalar side's idealisation (it is $24(1+w)c_s$ on the contracting leg, the standard matter-bounce value) and no more. The absolute P_T carries nothing****** *Run:* `python3 receipts/P15_CR.cosmology/P15_no_primordial_B_modes_unconditionally.py`

A2.the_three_owed_derivations_are_one_boundary [OK]

sec:scope (the three owed derivations are ONE closed boundary: A_s , n_s and the inherited datum are all dimensionless magnitudes). *Computes:* asserts P15s own list, prop:amplitudes 10^{113} gap, the progenitor tilt, and the capstones derived progenitor composition (13 checks) *Bound:* NOT-A-PAPER-CLAIM — L-211 run on L-150 *Run:* `python3 receipts/L211_closure_adjacency/A2.the_three_owed.d`

P15R89 `P15_the_control_entered_the_regime_and_the_arm_did_not_move` [OK]

sec:refit-bound (****THE WAVENUMBER TRUNCATION WAS 78% OF THE CONTROL'S REMAINING χ^2 , AND REMOVING IT TAKES THE CONTROL TO $\chi^2/\text{dof} = 1.18$ OVER THE FULL RANGE AGAINST A TRUE Λ CDM FIT'S 1.01 — SO FRONT #2'S TARGET IS MET. ACROSS FOUR INSTRUMENT STATES THE CR ARM DID NOT MOVE, AND 'L-147's PRE-REGISTERED F4 FIRES.**** Front #2, lead 'L-500'. ****PART 1 WHERE THE RESIDUAL LIVES.**** Of the 989 surviving $c54.183$'s derived lensing, ****725 — 73% — is in the 30 bins above $\ell = 1500$, a sixth of the bins****; below $\ell = 700$ the control is at $\chi^2/\text{dof} = 0.85$ against CAMB's lensed Λ CDM at 0.82 on the same bins. ****PART 2 AND IT IS THE TRUNCATION, SHOWN BY REMOVING IT RATHER THAN BY ARGUING FOR IT.**** The grid is $k = \ell/D_M$ with $\ell \rightarrow L_{MAXL}$, so the top output multipole has NO k -headroom while C_ℓ draws on every k with $k \rightarrow \ell$. ****Re-run at $L_{MAXL} = 3000$ with the k -spacing held fixed and scored on the SAME 185 bins: 989 $\rightarrow$ 218, χ^2/dof 5.34 $\rightarrow$ 1.18, and the last band's ratio to the reference 0.42 $\rightarrow$ 0.99.**** So $c54.184$'s '53% in neither template set' was the truncation; the front's last named item is struck as NUMERICAL and no sector remains. ****PART 3 THE CR LADDER'S ALIAS-GATE WAIVER, CHECKED IN χ^2 FOR THE FIRST TIME.**** The gate demands 4 samples per Bessel period, the CR ladder has 2.3, and it waives itself with ***this is not aliasing — but it is only not aliasing if the answer does not depend on it. Run KCONT=1 to check.*** ****Run:** agreement better than 0.7% everywhere, χ^2 to 2.1 in 51817. ****That check existed for the PEAK POSITION and had never been run against the statistic the verdict reads.*** ****PART 4 FOUR INSTRUMENT STATES, full range, both arms on the same lensing operator: the control 21.2 $\rightarrow$ 27.7 $\rightarrow$ 5.34 $\rightarrow$ 1.18 and the CR arm 290.7 $\rightarrow$ 304.2 $\rightarrow$ 298.9 $\rightarrow$ 302.1.**** ****An**

error the INSTRUMENT carries moves both arms; this moved one – eighteenfold against 5%.*
****PART 5 F2 AND F3 AS ‘L-147’ DEFINES THEM, WITH BOTH ARMS AT THE SAME WAVENUMBER RANGE**** so the construction is not charged for the instrument’s truncation. Full range ****F2 = 31 and F3 = 51848****; below ell = 700 ****F2 = 3.8 and F3 = 23687****; below ell = 500 **F2 = -0.2**, the arm scoring no worse than the reference. ****F4’s second clause fires by three orders of magnitude where it asks for one.****). *Computes:* the k-adequate control at full range asserted at 1.18 ± 0.12 , ****without which there is no discriminating regime and nothing in the file may be read****; the share the truncation carried asserted above 60%, which is PART 2’s whole mechanism; F3/F2 asserted above 100 at full range AND below ell = 700, which IS the reopening; ****the ladder/continuum agreement asserted under 2%, without which the CR arm’s χ^2 is not admissible at all****; the continuum arm asserted at $l_1/l_A = 0.5703$; the four-state contrast asserted as a 5x control improvement against a 15% arm movement, which is what makes this a statement about physics rather than about one build; and the tail share asserted above 60%, since PART 1 is what sent PART 2 looking *Bound:* ****scope: this is a MEASUREMENT DISCREPANCY and NOT a framework verdict – ‘L-147’s own F5 says so and ‘PO-7’ is protected precisely here, so this file reports a number and does not convert it; the conversion runs by ‘F5’s stated procedure. The deficit itself is not new: the corpus has carried $l_1/l_A = 0.5703$ against the sky’s 0.7312 since c54.168 and P15 states it at 21.9%. What is new is a control good enough to read it through a likelihood instead of a ratio. AND WHAT IS NOT RULED OUT: a defect the instrument’s states SHARE – 0.5703 has not moved across EIGHT of them, which is evidence either of a robust prediction or of a shared upstream constant, and this file cannot separate those and does not claim to. Nor does $\chi^2/\text{dof} = 1.18$ make the control a FIT: it is 17% above a true LambdaCDM’s on the same bins, and what that residual is remains unnamed.**** *Run:* python3 receipts/P15_CR_cosmology/P15.the_control_entered_the_regime_and_the_arm_did_not_move.py

B1.the_control_separates_prediction_from_shared_constant

[OK]

sec:refit-bound (the control separates robust prediction from shared upstream constant: same code, different D_M and r_s, same l_A, peaks 21.8% apart, and the control lands on the sky to 0.17%). *Computes:* reads both arms from the c54.186 spectra and asserts the scaling test, the control agreement and the ladder/continuum equality (12 checks) *Bound:* NOT-A-PAPER-CLAIM — the adversarial check c54.186 requested *Run:* python3 receipts/L147_two_arm/B1.the_control_separates_prediction

B2.the_prose_duplicate_did_not_reach_main

[OK]

sec:refit-bound (the reported prose duplicate did not reach main: zero at three granularities across every commit, because the two edits were different paraphrases and git asked). *Computes:* scans every commit that touched the file at paragraph, sentence and line-window level and asserts the two diffs differ (14 checks) *Bound:* NOT-A-PAPER-CLAIM — checks a routed report before acting on it *Run:* python3 receipts/L147_two_arm/B2.the_prose_duplicate_did_not_reach_main.py

P15R90 P15.the_first_peak_is_the_seam_datum_and_the_spacing_is_not

[OK]

sec:coherence (****ell₁/ell_A = 0.5703 IS A STATEMENT ABOUT THE SEAM DATUM AND NOT ABOUT THE RATE, AND c54.186’s OWN CAVEAT IS WHAT SENT THIS LOOKING.**** Front #2, lead ‘L-501’. The CR arm begins at the seam ($z = 6761$, $\eta_{\text{S}} = 180.4$ Mpc) and a first-peak mode crossed the horizon at $\eta \sim 75$, so ****the modes that set ell₁ are ALREADY SUB-HORIZON at the start and their phase there is ASSIGNED rather than derived****. The corpus’s datum is ****ONE datum per mode and a COMMON phase**** – which fixes that the phase is common and not WHICH phase; the instrument picks a density extremum. ****PART 1 SCANNING THAT ONE FREEDOM MOVES ell₁/ell_A FROM 0.5703 TO 1.2599 – A FACTOR OF 2.21****, and at $\phi = 3\pi/8$ the peak at 172 is not there at all and the series starts at 380. ****PART 2 WHAT IS ROBUST IS THE SPACING, AND IT IS ROBUSTLY WRONG:**** the mean peak spacing holds at 0.734-0.818 of ell_A across the whole scan – a spread of 1.11 against the position’s 2.21 – and is ****never 1.0****. ***So the disagreement that does not depend on a choice is a ~21% SPACING deficit, not a 22% POSITION one.*** ****PART 3 AND ‘L-147’s F4 FIRES UNDER EVERY PHASE, WHICH IS WHY c54.186 SURVIVES THIS:**** on identical bins the CR arm runs χ^2/dof 202-449 against a control at 0.75, so ****even its BEST phase costs 269x the control****. ****PART 4 THIS REPRODUCES c54.164 ON THE CURRENT INSTRUMENT, WHICH HAD NOT BEEN DONE**** – that revision found ell₁ in {150, 165, 315} on the OLD ‘ROBUST_p1p2_scan’ code, and the finding was never carried across to ‘ACOUSTIC_two_arm’, which everything since is built on.). *Computes:* ****CRPHI = 0** asserted to reproduce the coded 0.5703, without which the knob is not a control on itself and every comparison is against the

wrong baseline^{**}; the position's spread asserted above 1.5x and its maximum pinned at 1.2599, which is the withdrawal; the spacing's spread asserted under 1.35x AND its maximum under 0.95 of ell_A, ^{**}since if the spacing ever moved this file would have no positive content^{**}; and the CR arm's BEST phase asserted above 50x the control and above χ^2/dof 150 — ^{**}if that ever falls, c54.186 must be RESTATED rather than defended^{**} *Bound:* ^{**}!! SUPERSEDED BY P15.the.spacing.is.right.and.the.acoustic.phase.is.wrong (r4401).^{**} *Headline claim withdrawn by a later revision of 'sec:refit-bound'; the only citation available would put back into the paper what the paper removed — attempted r4397, reverted r4399. ^{**}Kept, not deleted: the scans stand and this is the record of how the arc reached its present state.^{***} ^{**}scope: this WEAKENS a number the paper carries and STRENGTHENS a verdict the previous revision landed, and neither is a framework judgement. P15's '21.9% deficit, not an artefact of how last scattering was modelled' is TRUE and is not the sentence a reader takes from it: the deficit is not last scattering's, it IS a function of the seam phase, which is upstream of last scattering and is a choice inside the corpus's own stated datum. 'F5' is not softened — removing a confound makes a measurement cleaner, not a conclusion; 'PO-7' protected; the conversion runs by 'F5's stated procedure. AND WHAT IS STILL OPEN, narrower than before: the phase is ONE degree of freedom in the datum; Theta-hat's flatness in k is another and is NOT scanned here. A scan that moved the SPACING would be the one that mattered, and this file does not run it.^{**} *Run:* python3 receipts/P15_CR_cosmology/P15.the.first.peak.is.the.seam.datum.and.the.spacing.is.not.py

B3.a.dichotomy.stated.is.not.a.dichotomy.proved [OK]

sec:refit-bound (B1 stands but L-235s disposition did not follow: ruling out one horn establishes the other only if the dichotomy is exhaustive, and the truth was a third thing). *Computes:* reads the forks nine phase spectra and asserts the 2.21x position spread against the 1.11x spacing spread (12 checks) *Bound:* NOT-A-PAPER-CLAIM — corrects this lines own r2462 disposition *Run:* python3 receipts/L147_two_arm/B3.a.dichotomy.stated.is.not.a.dichotomy.proved.py

P15R91 P15.both.datum.freedom.opened.and.the.spacing.still.holds [OK]

sec:coherence (^{**}THE SECOND AND LAST FREEDOM IN THE SEAM DATUM IS OPENED, AND THIS FILE WIDENS ITS OWN PREDECESSOR RATHER THAN CONFIRMING IT.^{**} Front #2, lead 'L-502'. c54.187 scanned the common PHASE and named the other freedom: what "flat in k" is flat AT. The datum's amplitude is the corpus's C4 shape $T(x) = 3(\sin x - x \cos x)/x^3$; ^{**}the instrument evaluates it at a SINGLE argument $x_e = 1/\sqrt{3}$, which is that shape read at each mode's OWN horizon crossing^{**} ($x = k \cdot c_s \cdot \eta$ with $k \cdot \eta = 1$ gives exactly $1/\sqrt{3}$) — a self-similar reading. *The alternative evaluates the SAME shape at each mode's own phase AT THE SEAM, $x = k \cdot c_s \cdot \eta_{\text{S}}$. * Both are readings of "one datum per mode"; neither is a new assumption. ^{**}PART 1 THE POSITION IS NO MORE STABLE:^{**} across eighteen readings ell_1/ell_A spans ^{**}0.5570–1.2599, 2.26x^{**} against the phase scan's 2.21x. ^{**}PART 2 THE SPACING IS MEASURED ONLY WHERE THERE IS A SERIES TO MEASURE, WHICH DISQUALIFIES EIGHT OF THE EIGHTEEN:^{**} those return a spectrum whose higher peaks have COLLAPSED — three features, the last at zero — and *a spacing read off that is not a spacing*. Requirement stated before the numbers: four peaks, the fourth at least 5% of the first. ^{**}PART 3 OVER THE TEN THAT QUALIFY THE SPACING SPANS 0.6764–0.8179 OF ell_A — 1.21x, mean 0.772, never above 0.82.^{***} c54.187 reported 1.11x from the phase alone; opening the second freedom widens it to 1.21x, so this file weakens its own predecessor and the ~23% spacing deficit stands at LOWER strength.^{***} ^{**}PART 4 AND F4 FIRES AT EVERY ONE OF THE EIGHTEEN:^{**} χ^2/dof runs 157–460 against a control at 0.75 on identical bins, so ^{**}the arm's best reading costs 208x the control^{**}. *And the best-fitting reading is one of the eight DISQUALIFIED ones — it fits better by having less structure to disagree with. Reported because it is the best number in the table and a reader would find it; it is not a direction.*). *Computes:* the position's spread asserted above 1.5x with its maximum pinned at 1.2599, the standing withdrawal from c54.187; ^{**}the spacing's spread asserted under 1.6x AND its maximum under 0.90 of ell_A — the point past which c54.187's conclusion would have to be WITHDRAWN rather than widened^{**}; the usable-series count pinned at 10, since PART 3's range is computed only over those and a silent change in how many qualify would move it without moving the code; and ^{**}the arm's BEST reading asserted above 50x the control and above χ^2/dof 120 — if that falls, c54.186 is restated^{**} *Bound:* ^{**}!! SUPERSEDED BY P15.the.spacing.is.right.and.the.acoustic.phase.is.wrong (r4401).^{**} *Headline claim withdrawn by a later revision of 'sec:refit-bound'; the only citation available would put back into the paper what the paper removed — attempted r4397, reverted r4399. ^{**}Kept,

not deleted: the scans stand and this is the record of how the arc reached its present state.***
 scope: both freedoms the corpus's own phrase leaves open are now scanned and the datum is closed. What has NOT been varied is the background: 'Z.START' is solved so that $\pi \cdot D_M / r_s = 301.6$ exactly, which is a TARGET and not an output — a separate item from the datum, registered rather than resolved. 'F5' unsoftened, 'PO-7' protected, conversion Daryl's. Run: python3 receipts/P15_CR.cosmology/P15.both_datum_freedoms_opened_and_the_spacing_still_holds.py

P15R92 P15_the_floor_is_a_distance_between_models_not_a_number_from_the_data [OK]
sec:refit-bound (**THE CONTROL'S REMAINING 17% IS NAMED, AND NAMING IT REQUIRED CHANGING THE MEASUREMENT.** Front #2, lead 'L-503'. c54.186 left it unnamed; **'F2' as 'L-147' defines it is a difference of two numbers each computed AGAINST THE SKY, so it mixes how far the two models are apart with where each sits relative to one noise realisation.** **PART 1** amplitude-matched, the instrument tracks a reference LambdaCDM to **better than 1.6% everywhere**, the departure running -1.1% at $\ell \sim 200$ through zero near 600 to $+0.7\%$ at 1400 — *a slow undulation, not a mis-phased oscillation*. **PART 2 F2 IS NOT A CLEAN MEASURE, SHOWN BY MOVING THE REFERENCE:** three defensible LambdaCDMs give $+31.2, +21.5, +27.2$ — *a spread comparable to the value*. **PART 3 SO THE FLOOR IS MEASURED WITHOUT THE DATA** — $\chi^2_{sep} = (A_a m_a - A_c m_c)^T F (A_a m_a - A_c m_c)$, a distance between two MODELS: 21.3 over 185 bins, $0.11 \chi^2$ per bin, about a third of a standard deviation per bin**. **PART 4 AND THE ORDERING REVERSES, WHICH IS THE TRAP:** the massless-neutrino reference gives the **smallest F2 (21.5) and the largest separation (62.7)** — *a reference chosen to flatter the instrument through the data is the one it is furthest from as a model*. **AND c54.178's LIST IS NOW COMPLETE:** reionisation struck c54.181, lensing built c54.183, the wavenumber range closed c54.186, and **the neutrino mass — the one item never addressed — is worth about 10 of the 31 **, the reference carrying one massive species at 0.06 eV where this instrument carries none.). *Computes:* the instrument-vs-reference departure asserted under 3%, which bounds everything else; the model separation asserted under $0.5 \chi^2$ per bin, the number that replaces the unnamed 17%; **THE ORDERING REVERSAL asserted directly — if F2 and χ^2_{sep} ever stop disagreeing, PART 4 is not a trap and the paragraph is unearned**; and **F4's margin asserted above 100x at the WORST reference, since a verdict that depends on the choice is not one** *Bound:* **scope: $0.11 \chi^2$ per bin is NOT zero and this file does not say the instrument is exact. It says the residual is at the level where the REFERENCE's own parameter choices matter as much as the instrument's error, and that below that level this statistic cannot arbitrate between two LambdaCDM implementations at all. $F3 = 51848$ against a floor of 21–63 across every defensible reference, so 'F4's margin is three orders of magnitude whichever is taken — which makes 'L-147's reading SAFER and converts nothing. 'F5' unsoftened, 'PO-7' protected.** Run: python3 receipts/P15_CR.cosmology/P15.the_floor_is_a_distance_between_models_not_a_number_from_the_data.py

J1.the_disagreement_no_longer_has_two_sides [OK]
sec:flatlcdm (L-171s internal disagreement no longer has two sides: across 18 datum readings the perturbation route gives no definite first peak, and its 150 is c54.164s number from a retired instrument). *Computes:* reads every c54.187-188 spectrum, asserts 150 and 220 both absent and the 2.26x range, and ties it to the class c54.187 routed as item 35 (12 checks) *Bound:* NOT-A-PAPER-CLAIM — supersedes a register rows content; its next step is untouched Run: python3 receipts/L171_two_routes/J1.the_disagreement_no_longer_has_two_sides.py

P15R93 P15_the_spacing_deficit_survives_the_one_fitted_parameter [OK]
sec:tensions (**THE LAST FREE THING UPSTREAM IS THE CORPUS'S OWN ONE FITTED NUMBER, AND MOVING IT BY 31% MOVES THE SPACING DEFICIT BY 7%.** Front #2, lead 'L-504'. c54.188 closed both seam-datum freedoms and named this: **'Z.START' is solved so that $L_A = \pi \cdot D_M / r_s$ hits a TARGET rather than coming out as an output.** That is declared, not hidden — P15 sec:tensions says "the measured acoustic scale is reproduced at the directly measured H_0 by a single z_{onset} " and calls it **"the one fitted number"**. What had not happened is that the number was a literal buried in a 'brentq' call, so nothing downstream could vary it and nothing had.* **PART 1 MOVING THE PIN MOVES EVERYTHING IT SHOULD:** pinning L_A at 260/280/301.6/320/340 drives z_{onset} from 11009 to 5066 and r_s from 157.1 to 120.2 Mpc**. **PART 2 AND THE SPACING DEFICIT DOES NOT FOLLOW IT:** the mean peak spacing stays at $0.7647\text{--}0.8205$ of L_A — a spread of 1.07 against the pin's 1.31, mean 0.798**. *So the $\sim 20\%$ spacing deficit is a property of the construction and

not of the value its one fitted parameter was fitted to.* **PART 3** l_1/l_A runs 0.5176–0.6308 (1.22x) and **never approaches the sky's 0.7312** — and its drift is almost entirely l_A 's, the peak itself moving only 164 $\rightarrow$ 176 while l_A moves 260 $\rightarrow$ 340. **PART 4 THE STRUCTURAL STATEMENT UNDER IT:** in ordinary acoustics l_1 goes as D_M/r_s , so a 24% fall in r_s should raise l_1 by 31%; **here it raises it by 7%** $\Rightarrow$ ***This construction's peaks track its own sound horizon at 24% of the rate acoustics requires, and that — rather than any one ratio — is what the comparison with the sky is registering.*** **CORRECTED c54.190 ('L-505'): the spacing figure in this row is the mean of the FIRST THREE GAPS, which is all four peaks at $L_{MAXL} = 1000$ can give. At production depth the asymptotic spacing is 0.975 of l_A — 2.5% short, not 21% — and what is wrong is the ACOUSTIC PHASE, by 0.62 pi. The robustness this row measures stands; the name it gives the quantity does not.***). *Computes:* **the spacing's spread under the pin asserted below 1.20x — the point past which the deficit would BE the fitted parameter's and every conclusion resting on it withdrawn**; its maximum asserted below 0.90 of l_A , since a pin taking it near 1.0 would remove the deficit itself; the first-peak position asserted never to reach the sky's ratio at any pin, which is PART 3; **the peaks' sensitivity to r_s asserted in (0, 0.6) of the acoustic rate — if it ever reached that rate the disagreement would be about a NUMBER and not about a mechanism**; and all five pins asserted to give a four-peak series *Bound:* ***SUPERSEDED BY P15.the.spacing.is.right.and.the.acoustic.phase.is.wrong (r4401).** *Headline claim withdrawn by a later revision of 'sec:refit-bound'; the only citation available would put back into the paper what the paper removed — attempted r4397, reverted r4399. **Kept, not deleted: the scans stand and this is the record of how the arc reached its present state.*** **scope: the acoustic question on this front is now closed as far as the construction's FREEDOMS go — c54.187 scanned the seam phase, c54.188 the amplitude reading, this the fitted parameter, and across all of them the SPACING sits near 0.78–0.80 of l_A and never reaches 0.9 while the POSITION spans 2.26x and states nothing. What is left is not a freedom that can be scanned: whether the peaks SHOULD be tied to the sound horizon is a question about the physics. 'F5' unsoftened, 'PO-7' protected, conversion Daryl's. AND ONE INCONSISTENCY RECORDED RATHER THAN FIXED: the instrument pins $l_A = 301.6$ where 'P15_zonset_determinations' pins the MEASURED 301.76 — 0.05%, and it is why this instrument returns $z_{onset} = 6761$ where that receipt returns 6797. Named so the two are not read as a disagreement.** *Run:* python3 receipts/P15_CR_cosmology/P15.the.spacing.deficit.survives.the.one.fitted.parameter.py

P15R94 P15.the.spacing.is.right.and.the.acoustic.phase.is.wrong

[OK]

sec:refit-bound (**THE "21% SPACING DEFICIT" OF c54.187-189 IS THE FIRST THREE GAPS AND NOT THE SPACING. AT PRODUCTION DEPTH THE ASYMPTOTIC SPACING IS RIGHT TO 2.4% AND WHAT IS WRONG IS THE ACOUSTIC PHASE.** Front #2, lead 'L-505'. ***THIS FILE CORRECTS THREE OF ITS OWN LINE'S REVISIONS.*** *Those scans ran at $L_{MAXL} = 1000$ so that eighteen readings and five pins were affordable; at that depth the CR arm has four peaks, so "the mean peak spacing" was a mean of THREE GAPS — and the first three gaps are the only ones where the arms disagree.* **PART 1/2 AT PRODUCTION DEPTH BOTH ARMS CARRY EIGHT PEAKS:** Λ CDM's last four gaps average **1.002 of l_A ** and the CR arm's **0.975 — 2.5% short, not 21%**; gap by gap the CR arm runs **0.725, 0.853, 0.875** of the control's and is **level by the fourth (0.973)**). **PART 3 SO THE TWO SERIES ARE PARALLEL LINES WITH DIFFERENT INTERCEPTS, AND THAT IS A PHASE:** fitted on peaks 4–8, slopes **1.003 and 0.976 of l_A ** (agreeing to 2.6%) and intercepts **−0.263 and −0.878 of l_A **). *A driven series peaks at $k \cdot r_s = n \cdot \pi - \phi$, so the intercept IS $-(\phi/\pi) \cdot l_A$: $\Rightarrow$ ***the two differ by 0.62 pi in the ACOUSTIC PHASE SHIFT, at a spacing they agree on.*** **PART 4 AND A LOW-ell TRANSIENT THE CONTROL DOES NOT HAVE:** measured each against its OWN asymptotic line, the control's first three peaks sit within **16** of it and the CR arm's sit **142, +80, +18** $\rightarrow$, converging — *and that transient is what compressed the early gaps*. ***PART-HEADLINE CORRECTED c54.195 ('L-508'): the 0.62 pi is the value at $\phi = 0$. Across four seam phases at production depth the asymptotic phase spans 0.891 and the CONTROL'S VALUE LIES INSIDE that span, so it is not a prediction. The driving ATTRIBUTION stands; its promotion to "the whole disagreement" does not.***). *Computes:* **the CR asymptotic spacing asserted above 0.90 of l_A and pinned at 0.975 — if it were NOT near l_A there would be nothing to correct and c54.187-189 would stand as written**; the first-three-gap and asymptotic values asserted to STRADDLE 0.85, which IS the diagnosis (one number reported for the other); **the slopes asserted parallel to 6%, without which the offset is not a pure phase and PART 3 is wrong**; the phase offset

pinned at 0.615 ± 0.08 , which is what replaces the retracted number; the transient asserted at more than 3x the control's, since PART 4 is otherwise empty; and the weakest peak's contrast asserted above 1.05, since a series read off non-features is noise *Bound*: *****!! SUPERSEDED BY P15_two_arm_control_and_guard (r4401).** ****** *Headline claim withdrawn by a later revision of 'sec:refit-bound'; the only citation available would put back into the paper what the paper removed — attempted r4397, reverted r4399. ******Kept, not deleted: the scans stand and this is the record of how the arc reached its present state.******* ****scope**: WHAT THIS RETRACTS is this line's own — c54.187's " $\sim 21\%$ ", c54.188's " $\sim 23\%$ ", c54.189's " $\sim 20\%$ " and the paper's "acoustic series some 23% too close" are all the first-three-gap value. WHAT IT DOES NOT RETRACT is the robustness: the first-three-gap spacing IS stable at 0.77–0.82 across eighteen datum readings and five pins and F4 fires at every one; what changes is that the stable quantity was the wrong one to call the disagreement. AND THE CORRECTION MAKES c54.187 CENTRAL rather than a caveat — the disagreement is a PHASE, and the phase is exactly what the seam datum assigns and what "one datum per mode and a COMMON phase" does not fix. 'F5' unsoftened; 'PO-7' protected; the conversion runs by 'F5's stated procedure — and this makes the discrepancy SHARPER, not smaller: a spacing that is right and a phase that is wrong names where to look.****** *Run*: python3 receipts/P15_CR.cosmology/P15.the_spacing_is_right_and_the_acoustic_phase_is_wrong.py

B4.the_intercept_is_a_phase_and_the_control_proves_it [OK]

sec:coherence (the intercept IS the acoustic phase by change of variables, and the control validates the reading by reproducing the textbook 0.25–0.27; the 21% spacing figure was a depth artefact). *Computes*: derives the intercept identity, fits both arms on peaks 4–8, reproduces the gap-by-gap series and the low-l transient (14 checks) *Bound*: NOT-A-PAPER-CLAIM — the adversarial check c54.190 requested *Run*: python3 receipts/L147_two_arm/B4.the_intercept_is_a_phase_and_the_control_proves_it.py

B5.the_scan_cannot_test_the_asymptotic_phase [OK]

sec:coherence (the corrected claims load-bearing quantity cannot be tested by the datum scan: all 23 scan spectra stop at three or four peaks and zero reach the peaks-4-to-8 fit). *Computes*: asserts the depth and peak count of every scan spectrum, that the production pair alone supports the fit, and where the transient sits (11 checks) *Bound*: NOT-A-PAPER-CLAIM — names a small affordable experiment *Run*: python3 receipts/L147_two_arm/B5.the_scan_cannot_test_the_asymptotic_phase.py

P15R95 P15_the_acoustics_work_and_the_phase_is_the_whole_disagreement [OK]

sec:refit-bound (****THE ASYMPTOTIC SPACING TRACKS THE SOUND HORIZON AT 98% OF THE ACOUSTIC RATE, SO THIS CONSTRUCTION'S ACOUSTICS WORK — AND THE WHOLE DISAGREEMENT IS THE ACOUSTIC PHASE.** ****** Front #2, lead 'L-506'. c54.190 separated spacing from phase and owed both a production-depth test; ****the scans that varied them were all at the depth c54.190 showed to be insufficient****. ****PART 1 THE SPACING TRACKS r_s AT THE FULL RATE:** ****** moving the pin from $l_A = 301.6$ to 340 drops r_s by 11%, ordinary acoustics requires the spacing to rise 13%, and ****it rises 13% — 98%****. ****So the peaks in this construction ARE set by its own sound horizon.** ****PART 2 WHICH RETRACTS c54.189's HEADLINE:** ****** that revision reported ****the peaks track their own sound horizon at 24% of the rate acoustics requires**** — ****measured on the FIRST peak, which c54.190 showed sits 142 multipoles off the asymptotic line, inside a transient****. ****Over this file's pin range the first peak moves at 37% against the series' 98%; the figure is not reproduced and is not meant to be — what is reproduced is the FINDING.** ****PART 3 THE PHASE IS ROBUST TO THE FITTED PARAMETER:** ****** the intercept moves $-0.878 \rightarrow -0.899$ of l_A across the same 31% swing — ****3% of a discrepancy of 0.62****. ****PART 4 AND THE SEAM DATUM'S PHASE FREEDOM IS A REAL LEVER THAT SPANS A THIRD OF IT:** ****** at the opposite phase the intercept moves to -0.671 , closing the gap from 0.615 to 0.408 — ****34%, and no further****. $\Rightarrow$ ****Which is the confirmation c54.190's diagnosis wanted: the datum's phase controls the acoustic phase, as a phase diagnosis predicts, and cannot close the gap.** *****PART-HEADLINE CORRECTED c54.195 ('L-508')**: the 0.62 pi is the value at $\phi = 0$. Across four seam phases at production depth the asymptotic phase spans 0.891 and the CONTROL'S VALUE LIES INSIDE that span, so it is not a prediction. The driving ATTRIBUTION stands; its promotion to "the whole disagreement" does not.*******). *Computes*: ****the asymptotic sensitivity to r_s asserted in (0.85, 1.15) — if it were NOT near 1 the acoustics would not work and the phase reading would not be the whole story****; the FIRST peak's sensitivity asserted below 0.6, since PART 2 retracts a number and must show the quantity really is less sensitive; the pin's effect on the phase asserted below 15% of the discrepancy, without which the phase is the fitted parameter's; ****the seam phase's**

closure asserted in (0.15, 0.70) — if it ever closed the WHOLE gap the discrepancy would be the datum's alone and this front's verdict would have to be restated**; the phase discrepancy pinned at 0.615 +- 0.05; and at least seven peaks per arm, since every number here is an asymptotic fit *Bound*: **!! SUPERSEDED BY P15_two_arm_control_and_guard (r4401).** *Headline claim withdrawn by a later revision of 'sec:refit-bound'; the only citation available would put back into the paper what the paper removed — attempted r4397, reverted r4399. **Kept, not deleted: the scans stand and this is the record of how the arc reached its present state.*** **scope: the front's acoustic statement in final form — this construction reproduces the acoustic SPACING (the quantity its one fitted parameter is fitted to, and which it then tracks at 98% of the acoustic rate when that parameter is moved) and disagrees with the sky in the acoustic PHASE by 0.62 pi, robust to the fitted parameter and only a third reachable by the one freedom the seam datum leaves open. That is ONE number and ONE mechanism where the front began with four items and a ratio. 'F5' unsoftened, 'PO-7' protected, conversion Daryl's — and the discrepancy is now specific enough to be attacked: an acoustic phase shift is a computable consequence of the driving, so "why 0.62 pi" has an address. This file does not have it.** *Run*: python3 receipts/P15_CR_cosmology/P15_the_acoustics_work_and_the_phase_is_the_whole_disagreement.py

B6.the_acoustics_reproduce_and_the_dichotomy_is_false [OK]

sec:coherence (the acoustics reproduce at 98.2% of the required rate, and r2485s stated dichotomy was not exhaustive: the phase moves and stops at 34%). *Computes*: recomputes the r_s response and the four-row phase table from the forks spectra, and asserts both horns false (13 checks) *Bound*: NOT-A-PAPER-CLAIM — verifies c54.191 and corrects this lines own r2485 *Run*: python3 receipts/L147_two_arm/B6_the_acoustics_reproduce_and_the_dichotomy_is_false.py

B7.the_seam_phase_moves_the_asymptotic_intercept [OK]

sec:coherence (item 38 answered at production depth: the seam phase MOVES the asymptotic intercept by ~0.31 lA (half the 0.615 disagreement) while the spacing holds, so the 0.62pi is datum-contingent not structural). *Computes*: validates the phi=0 control against c54.186, fits three production seam phases on matched acoustic orders 4-7, asserts the intercept span and the stable spacing (5 checks) *Bound*: NOT-A-PAPER-CLAIM — a measurement; informs vein L-202, answers lead L-171; conversion to a PO-7 verdict is unseated *Run*: python3 receipts/L147_two_arm/B7_the_seam_phase_moves_the_asymptotic_intercept.py

K1.a_capability_assumed_from_one_failure [OK]

sec:coherence (the whole acoustic disagreement is the driving: undriven the arms agree to 0.013 in phi/pi and the CR slope is exactly 1.0000 lA, and both lines accepted a capability claim for eight revisions). *Computes*: fits all four production spectra, asserts the undriven agreement and the 5.72x driving ratio, and counts this lines own tarball absorptions (12 checks) *Bound*: NOT-A-PAPER-CLAIM — verifies c54.193-194 *Run*: python3 receipts/L239_capability_assumed/K1_a_capability_assumed_from_one_failure.py

B8.the_zero_velocity_band_is_a_third_of_the_gap [OK]

sec:coherence (the seam datums band across the two ZERO-VELOCITY phases is 0.207 against a 0.615 disagreement — a third, not most — and over that pair the control is NOT inside). *Computes*: solves sin(phi)=0 on [0,2pi), reads both admissible phases off four production spectra from two nodes, and withdraws this lines own L-202 link (13 checks) *Bound*: NOT-A-PAPER-CLAIM — narrows c54.195s withdrawal *Run*: python3 receipts/L147_two_arm/B8_the_zero_velocity_band_is_a_third_of_the_gap.py

P15R96 P15_the_admissible_band_is_a_third_and_the_two_entries_differ_against_the_potential [OK]

sec:coherence, sec:refit-bound (**ITEM 43 (r2509) ACCEPTED: OVER THE PHASES THE CORPUS ADMITS, THE ACOUSTIC PHASE MOVES 0.207 — A THIRD OF THE 0.615 GAP — AND THE CONTROL'S 0.263 IS OUTSIDE IT. THE DISAGREEMENT IS REAL AND BOUNDED.** Front #2, lead 'L-513'; VEIN 'L-202'. **PART 1** the pair is **forced**, not chosen: 'sec:what-crosses' says what crosses is **frozen**, a frozen mode has $\dot{\delta}\gamma=0$, continuity gives $\theta\gamma=\frac{t\text{frac34Dkc.s}\sin\phi}{\sin\phi=0}$ — the paper's own transmission argument read at the seam, in print before the scan existed. **PART 2 AND THE REASON c54.199 GAVE 56 IS WRONG:** 'y0[,6] = Ph0' is fixed at \$-1\$ independent of ϕ while 'dg0' carries $\cos\phi$, so the two entries are **not** a sign flip of the state — **what reverses is the relative sign of the density against the potential**, a compression against a rarefaction in the same well. **PART 3** 54's and cc54's production spectra agree to four decimals at both admissible phases. **PART 4** band 0.2069 vs gap 0.6152 — $2.97\times$, control **outside** [0.6711, 0.8780]. **PART 5** χ^2/dof **281 and 379** against 3.71 — $76\times$

and $102\times$ — so c54.195's PART 5 conclusion is stronger on the pair than on the span it was illustrated in. **PART 6** and P15 'sec:refit-bound' already carried "spans a third of it" and the 0.408, **two paragraphs above the paragraph that withdrew it**). *Computes:* the four-step admissibility chain asserted in the instrument's AND the paper's source — **if 'sec:what-crosses' did not say modes freeze, the pair would be a choice and r2509 weaker than this file claims**; 'dg0' asserted to flip while 'Ph0' does not, which is what makes item 17's reason wrong; **54 and cc54 asserted to agree to four decimals — a band measured on one node's spectra is a band measured once**; the ratio ~ 3 and, separately, the control asserted OUTSIDE the band, without which c54.195 stands as written; both admissible readings asserted above $50\times$ the control, without which the withdrawal takes the conclusion with it; and the paper's own earlier 0.408 asserted to reproduce *Bound:* **SUPERSEDED BY P15.two_arm_control_and_guard (r4401)**. **Headline claim withdrawn by a later revision of 'sec:refit-bound'; the only citation available would put back into the paper what the paper removed — attempted r4397, reverted r4399.** **Kept, not deleted: the scans stand and this is the record of how the arc reached its present state.** **scope: this corrects this line TWICE and in opposite directions — it makes the disagreement firmer than c54.195 left it, and it retracts the explanation c54.199 routed to 56.** 'F5' unsoftened; 'PO-7' protected; the conversion runs by 'F5's stated procedure. No new run: five banked production spectra, two nodes. *Run:* python3 receipts/P15_CR.cosmology/P15.the_admissible_band_is_a_third_and_the_two_entries_differ_against_the

B9.the_admissible_pair_is_forced_not_merely_distinguished [OK]
sec:what-crosses (the admissible pair ϕ in $\{0,\pi\}$ is FORCED by P15s own transmission argument — every mode freezes before the crossing, and a frozen mode has zero velocity). *Computes:* quotes the freezing argument at source, solves $\sin(\phi)=0$, and asserts the control lies OUTSIDE the band with both nodes agreeing to four decimals (12 checks) *Bound:* NOT-A-PAPER-CLAIM — verifies c54.200 and upgrades r2509 *Run:* python3 receipts/L147.two_arm/B9.the_admissible_pair_is_forced_not_merely_distinguished

B10.the_thermal_mechanism_needs_an_exponential_approach [OK]
sec:transmission (L-519 answered from the MECHANISM side: thermality needs an exponential near-horizon approach, the degenerate members is a power law, and P15 already derived that split for its transmission dichotomy). *Computes:* integrates the tortoise coordinate for a simple and a double root, re-verifies the Nariai double root, and asserts P15s exponential/power-law split at source (11 checks) *Bound:* NOT-A-PAPER-CLAIM — a third footing for L-519; no temperature value claimed *Run:* python3 receipts/L147.two_arm/B10.the_thermal_mechanism_needs_an_exponential_approach

PO-7 [OK]
sec:coherence (kill receipt for PO-7 under route (2): object named, four checks answered — and the CHAIN check does not clear, because the disagreement rests on four reproduced things and one ARGUED one). *Computes:* a kill receipt, not a script — the four checks written out with the inversion routes named *Bound:* NOT-A-PAPER-CLAIM — narrows PO-7; no authorisation requested *Run:* python3 receipts/kills/PO-7.md

S1.every_mode_of_interest_freezes_and_the_inversion_is_closed [OK]
sec:what-crosses (PO-7 chain-(4) link (d) reproduced on a second path: every mode of interest ell 28-2475 freezes before the crossing ($r=c_s k/|aH| \rightarrow 0$), so $\sin(\phi)=0$ forces ϕ in $\{0,\pi\}$, the band stays 0.2069 with the control OUTSIDE, and the kill receipt's inversion (a mode crossing unfrozen) is closed by the divergence of $|aH|$). *Computes:* reproduces the progenitor interior independently (matching P16's freeze-out to the digit, $x_{\text{freeze}}=0.002015$ at ell=2475), computes the velocity ratio $\rightarrow 0$ at the crossing for every mode, and anchors sec:what-crosses + the kill receipt's chain check (10 checks) *Bound:* NOT-A-PAPER-CLAIM — reproduces PO-7's one non-reproduced link; informs L-171/L-202; F5 unsoftened, no conversion claimed *Run:* python3 receipts/L805.freezing_reproduced/S1.every_mode_of_interest_freezes_and_the_inversion_is_closed.py

S1.a_massive_mode_freezes_too_and_the_mass_term_vanishes_at_the_branch_point [OK]
sec:what-crosses (A2 (PO-seam / PO-7 inversion 3): a massive mode freezes too, for ANY mass — the branch point $a\rightarrow 0$ annihilates the mass term $m^2 a^2$ while $|aH|$ diverges, so $\omega/|aH| \rightarrow c_s k x \rightarrow 0$ independent of m ; a massive trajectory carries no phase from non-freezing, closing PO-7 route 3 from the massive side). *Computes:* derives the mass term $+m^2 a^2$ from the covariant action (sympy), shows $\omega/|aH|$ at the crossing is m -independent to the digit up to $m=1e5$ across ell 28-2475, freeze-out epoch unmoved (5 checks) *Bound:* NOT-A-PAPER-CLAIM — A2; informs L-202/L-171; CRPHI stays assigned; F5 unsoftened *Run:* python3 receipts/L806.massive_freezing/S1.a_massive_mode_freezes_too_and_the_mass_term_vanishes_at_the_branch_point

- S1.the_peak_estimator_recovers_a_set_phase_independent_of_the_envelope** [OK]
sec:coherence (A10 (PO-7 inversion 2): the peak-4-8 estimator recovers a SET asymptotic phase to ± 0.005 in ϕ/π and is envelope-independent (spread ± 0.006) across six damping/width/tilt variations spanning the CR-vs-control transfer differences — so the 0.408 is not an estimator artefact; inversion route 2 closes and the disagreement hardens). *Computes:* injects synthetic acoustic combs with known ϕ in under six envelopes, runs the exact B7/B8 estimator, checks faithfulness and envelope-invariance (4 checks) *Bound:* NOT-A-PAPER-CLAIM — A10; informs L-171; F5 unsoftened, no conversion claimed *Run:* `python3 receipts/L807_driven_estimator/S1.the_peak_estimator_recovers_a_set_phase_independent_of_the_envelope`
- S1.the_seam_phase_is_derived_compression_correlated_on_the_observable_leg** [OK]
sec:what-crosses (PO-7/PO-seam: the seam phase CRPHI is DERIVED, not free = CRPHI=0 (a compression correlated with the well), on the observable leg — the pre-onset is pressureless (r2701) so no oscillation swings the inherited adiabatic overdensity's sign; bracket-checked against the LCDM control's own adiabatic IC; the $\{0,\pi\}$ band collapses to 0.878, disagreement pinned at 0.615, CRPHI= π (0.408, a rarefaction) anti-adiabatic and inadmissible). *Computes:* reads the code's CRPHI convention (overdensity in a well = CRPHI=0), shows a pressureless mode's sign is fixed while a pressured one swings, confirms the adiabatic bracket, and anchors the pressureless-onset statement in CR_cosmology.tex (4 checks) *Bound:* NOT-A-PAPER-CLAIM — closes PO-7 route (3)'s residue; informs L-171/L-202; F5 unsoftened, one assumption (Phi-continuity) flagged *Run:* `python3 receipts/L815_seam_phase_derived/S1.the_seam_phase_is_derived_compression_correlated_on_the_observable_leg`
- S1.the_banked_spectra_are_nk600_not_nk260_and_pass_the_guard** [OK]
sec:where-the-likelihood-sits (corrects C52's sampling premise: the banked two-arm spectra the likelihood scores are NOT under-sampled — they are NK=600 (the README command), which PASSES the guard at 5.7 pts/Bessel-period. cc54 (15GB) reproduced c54.178.lcdm BIT-FOR-BIT (max $|dD| = 8e-16$). C52 read the npz's 238-point shape as NK=260, but $238 = \text{len}(\text{arange}(100,2000,8))$ is set by LSTEP=8/LMAXL=2000, not NK; 56's 3.7GB container OOM'd at NK=600 so tested the guard-failing NK=260. The 7.14/280.09 stand; C51's dropped-bin point is separate and stands). *Computes:* confirms the 238-point shape is $\text{arange}(100,2000,8)$ independent of NK, computes guard pts/period= $2\pi(3NK-1)/(LMAXL-12)$ giving 2.46@NK=260 (fails) and 5.69@NK=600 (passes), and asserts the banked npz is bit-identical to cc54's NK=600 reproduction (4 checks) *Bound:* NOT-A-PAPER-CLAIM — corrects C52's provenance premise; the guard itself is right (NK=260 does under-sample); does not touch C51's real dropped-bin blocker *Run:* `python3 receipts/L820_banked_spectra_sampling/S1.the_banked_spectra_are_nk600_not_nk260_and_pass_the_guard`
- S2.the_lmax2512_extension_recovers_c51s_dropped_bins_and_CR_stays_disfavoured** [OK]
sec:where-the-likelihood-sits (discharges C51 (the damping-tail half of 56's resampling route): the LMAXL=2512 extension (302 multipoles to $\ell=2508$) recovers the 30 dropped bins (ℓ 1759-2508), and including them does NOT rescue CR. Two effects isolated: the wider k-range lifts the control 7.14- ± 3.81 /dof on the SAME 185 bins (c54.186's truncation effect), added tail - ± 3.68 ; the CR arm does not gain (280.1- ± 281.1 overlap) and stays 260.1/dof. F3 widens 50497- ± 51547 — the dropped region makes CR MORE disfavoured, not less). *Computes:* scores the LMAXL=2512 lcdm/cr extensions on the overlap ($\ell=1996$) and full (201) bin sets vs the banked pair, isolating the k-range effect from the damping-tail addition, and computes F3 on both bin sets (4 checks) *Bound:* NOT-A-PAPER-CLAIM — the C51 half of L-820; CR verdict unchanged (both F3 $\sim 2400x$ threshold); control's 3.68/dof still large, truncation-vs-physics not further split *Run:* `python3 receipts/L820_banked_spectra_sampling/S2.the_lmax2512_extension_recovers_c51s_dropped_bins_and_CR_stays_disfavoured`
- S1.the_cr_residual_is_acoustic_structure_not_truncation_and_that_is_why_it_is_unresponsive_to_lmax** [OK]
sec:where-the-likelihood-sits (PO-10 OWED #496 (the row's real remainder): DIAGNOSES the CR arm's 280/dof that r2781/C53 found "unresponsive to L_max and diagnosed by nothing". A per-bin χ^2 decomposition (full plik_lite covariance) localises the residuals: the control's is 75% in the high- ℓ tail ($\ell \geq 1200$, the truncation), the CR arm's is 57% in the acoustic-peak bands ($\ell \leq 850$) and 18% tail — so CR is acoustic-structure, not truncation, which is WHY it is unresponsive to L_max. CR comb compressed (172/404/636 vs sky 220/540/810, 11/1A 0.57 vs 0.73 = PO-7's deficit); rescaling doesn't collapse χ^2 (best ~ 200) so position+heights). *Computes:* computes the per-bin χ^2 contribution $r_i(\text{Fr})_i$ with the full covariance and groups by ℓ -band for both arms, reads the CR peak positions, and scores under an ℓ -axis rescaling (4 checks) *Bound:* NOT-A-PAPER-CLAIM — OWED #496 CR half; F5 reserves the verdict

(PO-7 protected); control third convergence point (L3200) measured separately *Run: python3 receipts/L822_cr_residual_diagnosed/S1_the_cr_residual_is_acoustic_structure_not_truncation_and_the*

S1.the_stored_cr_rs_is_the_from_onset_acoustic_horizon_and_matches_the_arms_own_integral [OK]

sec:acoustic (PO-10 (the code read 56's r2790 routed): the stored CR r.s=135.46 is NOT a book-keeping error. The line is R_S=rs_from(Z_START) with Z_START the FITTED onset; rs_from uses the SAME sound speed/grid/onset the acoustic oscillation uses, so 135.46 IS the arm's acoustic horizon and the peaks asymptote to L.A=301.6. r2790's "peaks demand 158" is the low-ell transient (first-4-gap mean -i, r.s=158, high-n gaps -i, ~139 bracketing the stored); its "direction requires 245" is the from-a~0 horizon, NOT the acoustic one (pre-onset pressureless, L-815, no oscillations before onset). Smaller than LCDM because CR starts oscillating later — the framework's fitted-onset design). *Computes:* reproduces R_S=rs_from(Z_START) via the brentq fit, computes rs_from from a~0 vs the fitted onset for both arms, and reads the CR peak gaps by ell-range (first-4 vs high-n) (4 checks) *Bound:* NOT-A-PAPER-CLAIM — the r2790 code read; not a bug, the fitted-onset design's output; whether that design is forced is F5/PO-10's *Run: python3 receipts/L823_cr_rs_is_the_onset_horizon/S1_the_stored_cr_rs_is_the_from_onset_acoustic_horizon_and*

S1.the_third_point_shows_the_control_converges_by_L3000_and_the_unlensed_floor_is_the_lensing [OK]

sec:acoustic (PO-10 (OWED #496, control half — the THIRD convergence point r2781 asked for): the control CONVERGES by L3000, it does NOT slide down an $L^{-3.4}$ law to "1.1 by L6000". On the same 185 bins the unlensed control goes 7.18→3.83→3.73→3.73 across LMAXL 2000/2512/3000/3200; the $L^{-3.4}$ law fit to the first two points predicts 2.23 at L3200, the measurement is 3.73 — the two-point rate was a one-time truncation recovery, not a convergence rate. The ~3.73 unlensed floor IS the lensing: c54.183's lensed/unlensed ratio takes the SAME converged spectrum 3.73→1.18, and the lensed control converges 5.38→1.33→1.19→1.18 to 1.18 by L3000 vs CAMB lensed's 1.014 (a ~0.16/dof instrument floor). Truncation (LMAXL) and lensing are ORTHOGONAL axes; F3 cancels the shared 1.18 floor). *Computes:* scores the four banked control spectra (c54.178 L2000, L820 L2512, c54.186 L3000, L824 L3200) on the fixed 185-bin set unlensed and under CAMB's lensed/unlensed ratio; checks the $L^{-3.4}$ extrapolation vs the measured third point, the L3000/L3200 convergence, and the top-bin truncation (4 checks) *Bound:* NOT-A-PAPER-CLAIM — control-arm convergence; does not overturn 56's convergence claim (the LENSED control does converge, to 1.18 by L3000); companion to L-822 (CR half); F5 untouched *Run: python3 receipts/L824_control_converges/S1_the_third_point_shows_the_control_converges_by_L30*

S1.the_converged_controls_remainder_is_a_broadband_instrument_floor_not_a_localized_defect [OK]

sec:acoustic (PO-10 (OWED #454, the remainder localized): after L-824's convergence the CONTROL arm's 1.18/dof vs CAMB lensed's 1.014 on the same 185 bins (the "~100" was pre-convergence, pre-lensing) is a BROADBAND instrument floor, not a localized defect. A per-bin $r_i(\text{Fr})_i$ decomposition shows every ell-band 100-2000 contributes a positive excess (+4.5/+6.0/+7.4/+1.6/+5.7/+4 total ~30 in χ^2), none dominating, slightly leading in the first two acoustic peaks (300-850 carries 13.4 of 30). So the ~1 target is instrument-accuracy-limited (a uniformly better transfer, not a patchable band), and $F3=\chi^2(\text{CR})-\chi^2(\text{LCDM})$ cancels this shared floor). *Computes:* per-bin decomposition of the converged lensed control (L824 arm) and CAMB lensed LCDM through plik_lite TT's full covariance on the fixed 185 bins, by ell-band (3 checks) *Bound:* NOT-A-PAPER-CLAIM — control-arm diagnostic; #454's target instrument-limited, still open; F5 untouched; continues L-824 *Run: python3 receipts/L826_control_floor_broadband/S1.the_converged_controls_remainder_is_a.br*

T1.the_transfer_is_half_built [OK]

sec:envelope (PO-12 is HALF BUILT: the debt is two steps and step (1) — the specification of how fluctuations gravitate on the geometrically fixed background — is computed in sec:envelope, two sections before the debt is named). *Computes:* asserts the two-step sentence, the envelope-is-derived sentence, the structural-argument clause and the tilt-irreducible-residual clause verbatim (9 checks) *Bound:* NOT-A-PAPER-CLAIM — narrows a register row; step (2) is genuinely not run *Run: python3 receipts/L202_the_seam/T1.the_transfer_is_half_built.py*

P15R97 C12.the_odd_even_half_has_its_parameter [OK]

sec:envelope (PO-10s odd/even half already has its mechanism and parameter: C5b_baryon_term puts the asymmetry on the expansion leg at Rb=0.60, which is the rows own description of the

item). *Computes*: asserts the rows wording, C5bs location and growth-factor and conclusion, and the papers own sentence (9 checks) *Bound*: NOT-A-PAPER-CLAIM — narrows a register row; the height pattern is not produced *Run*: `python3 receipts/P15_CR_cosmology/C12_the_odd_even_half_has_its_par`

P15R98 C14_po12_gates_po10 [OK]

sec:envelope (PO-12 GATES both of PO-10s runs: the textbook odd/even ratios at $R_b=0.60$ are LCDM peak-height formulae that assume a transfer, and both of PO-10s halves are statements about C.l). *Computes*: asserts PO-10s remaining half and P15s genuine-build sentence verbatim, computes the textbook ratios, and confirms neither row records the dependency (7 checks) *Bound*: NOT-A-PAPER-CLAIM — records an ordering between two rows *Run*: `python3 receipts/P15_CR_cosmology/C14_po12_gates_po10.py`

P15R99 C15_the_cancellation_does_not_reach_the_ratio [OK]

sec:envelope-consequence (the corpuess cancellation does not reach the odd/even ratio: it holds between two RATES (same quantity, microphysics identical) while odd/even compares two MULTIPOLES on one rate, where the envelope leaves 13-36%). *Computes*: asserts the cancellation sentence and both rate-ratio results verbatim, and computes adjacent-peak envelope ratios on three envelopes (9 checks) *Bound*: NOT-A-PAPER-CLAIM — supplies the reason behind r2646s gate *Run*: `python3 receipts/P15_CR_cosmology/C15_the_cancellation_does_not_reach_the_ratio.py`

P15R100 C16_the_transfer_is_six_eighths_built [OK]

sec:envelope (PO-12s step 2 is six-eighths built: the driving verified in closed form, source removal exact, projection calibrated at $l^*=302.2$ vs 301, and a C.l RATIO with no free parameter already in the paper (0.823 recomputed vs 0.82)). *Computes*: verifies the driving satisfies its ODE, is even, and normalises; asserts the genuine-build, projection and no-free-parameter clauses verbatim; recomputes the high-ell ratio (8 checks) *Bound*: NOT-A-PAPER-CLAIM — narrows a debt to the absolute spectrum *Run*: `python3 receipts/P15_CR_cosmology/C16_the_transfer_is_six_eighths_built.py`

P15R101 C17_the_instrument_already_carries_both [OK]

sec:instrument (CORRECTS r2658: both pieces it marked NOT LOCATED are built and validated — the Peebles recombination history IS the visibility function and the line-of-sight source with its j.l kernel IS the projection). *Computes*: asserts sec:instruments description, its validation figures and its flat-projection wording verbatim, against the debt's geometric-background clause (9 checks) *Bound*: NOT-A-PAPER-CLAIM — corrects a prior lines audit; the debt is now what the instrument RUNS ON *Run*: `python3 receipts/P15_CR_cosmology/C17_the_instrument_already_carries_both`

P15R102 C18_bespoke_means_two_legs [OK]

sec:envelope (what BESPOKE means for PO-12: the transfer must carry TWO backgrounds joined at the branch point — radiation-dominated collapse leg, geometry-set expansion leg — and the paper forbids mixing the rates). *Computes*: computes the friction coefficient for both contents, asserts the collapse-leg scoping, the L1/L2 division and the forced consistency rule verbatim (7 checks) *Bound*: NOT-A-PAPER-CLAIM — sharpens a debt; the branch-point join is untouched *Run*: `python3 receipts/P15_CR_cosmology/C18_bespoke_means_two_legs.py`

P15R103 C19_the_branch_point_join [OK]

sec:transmission (THE BRANCH-POINT JOIN COMPUTED: transmission is conservation of R, so the join is a change of variable worth exactly 9/10 — applied ONCE where LCDM spreads it over equality, which is why CR has no early ISW). *Computes*: asserts the not-yet-in-hand and transmits clauses, the matter-dominated-to-nine-orders and four-per-cent clauses verbatim, and derives 9/10 from $R/\Phi=(5+3w)/(3+3w)$ (7 checks) *Bound*: NOT-A-PAPER-CLAIM — super-horizon join only; sub-horizon modes and the dynamical crossing stay open *Run*: `python3 receipts/P15_CR_cosmology/C19_the_branch_point_join.py`

P15R104 C20_the_caveat_named_an_empty_set [OK]

sec:what-crosses (r2661s super-horizon caveat named an EMPTY SET: at the branch point $(rH)^2$ diverges, the comoving horizon goes to zero, and every mode is outside — so the 9/10 join is unrestricted). *Computes*: asserts the every-mode-outside and seam clauses verbatim, computes the divergence of $(rH)^2$ and the vanishing comoving horizon, and confirms the radiation term dominates (7 checks) *Bound*: NOT-A-PAPER-CLAIM — removes a caveat from a prior receipt; the crossing dynamics stay deferred *Run*: `python3 receipts/P15_CR_cosmology/C20_the_caveat_named_an_empty_set.py`

P15R105 C21_the_superhorizon_transfer_closes [OK]

sec:envelope (THE SUPER-HORIZON TRANSFER CLOSES: Φ_i - Φ_i exactly at the branch

point for every k (departure $O(k^2 \epsilon^2)$), so with r2661s join $\Phi_{\text{exp}}(k) = (9/10) \Phi_i(k)$ scale-invariantly — the branch point does not filter). *Computes*: computes the branch-point limit and the series coefficients, re-derives the join, and asserts the transmits clause verbatim; flags the 1/10 near-miss as different-origin (7 checks) *Bound*: NOT-A-PAPER-CLAIM — scalar super-horizon only; the single end-to-end run stays unrun *Run*: `python3 receipts/P15_CR_cosmology/C21_the_superhorizon.t`

P15R106 C22_the_end_to_end_number

[OK]

sec:earlyisw (THE END-TO-END NUMBER: 7.5% low-ell power deficit from the absent early ISW, 18% at 1.D rising to 54% at 2 1.D from damping — and the acoustic peaks BETWEEN them are where the chain stops, correcting r2661s no-further-evolution). *Computes*: asserts the scope qualification, the super-horizon-equation clause, the order-two decay and the not-a-radiation-effect clause verbatim, and computes both ratios (8 checks) *Bound*: NOT-A-PAPER-CLAIM — corrects a prior receipts scope; not a prediction against data *Run*: `python3 receipts/P15_CR_cosmology/C22_the_end.to.`

P15R107 C59_the_control_reproduces_camb_and_the_height_defect_was_k_truncation

[OK]

sec:coherence (**PO-24 STEP ONE: THE CONTROL RUN, AND IT COMES OUT THE OTHER WAY. THE HEIGHT MACHINERY IS NOT BROKEN.** ‘PO-24’ records the bespoke transfer as getting the positions right and the HEIGHTS wrong by 22.7% and 97.5% on the arm whose answer is known, and the r3869 handoff named the live lead: two projection paths that are not the same physics, with **which one produced the 2.721 not established**. ** (1) IT WAS `los_spectrum`, AND THAT IS THE SMALLER HALF. ** ‘_project’ also carries the polarisation source $g \Pi/4 + (3/4k^2) d^2[g \Pi]$, so the comparison to CAMB was not like for like. ** (2) THE LARGER HALF NOBODY HAD LOOKED FOR: THE k -INTEGRAL IS TRUNCATED WHERE IT IS NOT CONVERGED. ** The instrument built its k -grid from LMAXL — the grid of multipoles to PRINT — so choosing what to report chose where to stop integrating $C_l = \text{INT } P(k) \Delta_l(k)^2 dk$. Reported ell grid held FIXED and k_{max} alone moved: **2.721 -j 2.446 -j 2.399 -j 2.393**. ** (3) BOTH ARE NEEDED AND NEITHER ALONE SUFFICES. ** `los_spectrum` at converged k_{max} gives 2.393; `_project` at truncated k_{max} gives 2.516; both together give **2.197**. ** (4) THE RESULT: THE CONTROL REPRODUCES CAMB. ** Peaks **220 / 540 / 812** against the sky 220.6 / 538.1 / 809.8, ** $P_1/P_2 = 2.197$ against CAMB 2.200 – 0.14%** and inside the sky’s 1 sigma; $P_1/P_3 = 2.192$ against 2.277. Converged in k_{max} and stable to $2e-3$ over a 1.5-fold change in mode count. ** (5) THE FORK IS SETTLED: REPAIR. ** The two-arm architecture carries the transfer; a fresh build would have discarded a working instrument on the strength of an artefact. ** (6) AND THE RECORDED LN SCAN IS INERT: ** LN=12 and LN=25 give identical ratios to $1e-3$ with the state vector genuinely wider, against a recorded 4.496 -j 8.009.). *Computes*: the recorded 2.721/4.496 asserted REPRODUCED (so the row is not wrong about what it ran); k -truncation asserted to move both ratios on ONE path; the polarisation source asserted to move them again at converged k_{max} ; NEITHER-ALONE asserted; the headline asserted within 1% of CAMB; every peak asserted within 9 of the sky’s; convergence asserted to $2e-3$ across NK 280 vs 420; `Jac_of` asserted $= 1$ to $1e-12$ on the control so r3512’s HIER composition defect cannot reach this result; LN inertness asserted with the state width checked. **CONTROL THAT FIRES: at the TRUNCATED k_{max} the same NK widening is EQUALLY STABLE and equally WRONG** — so stability in the knob you varied is not convergence, which is the defect this receipt removes *Bound*: ** CONTROL ARM ONLY. No CR number is produced or corrected. ** The CR arm is truncated by the same mechanism and is NOT re-measured; r3512’s HIER composition defect is a no-op on the control ($\text{Jac} = 1$) and stays LIVE for CR, which the next step must settle first. NOT CLAIMED: that the bespoke transfer is finished, that PO-24 is closed, or anything about CR’s peak heights. What is established is that its control works *Run*: `python3 receipts/P15_CR_cosmology/C59_the_control_reproduces_camb_and_the_height_defect_was_k_truncation.py`

P15R108 C60_the_hier_composition_defect_names_two_flags_its_own_tree_never_had

[OK]

sec:coherence (**THE DEFECT FOUR DOCUMENTS DEFER TO IS NOT IN THE INSTRUMENT, AND WAS NOT IN THE ONE IT WAS WRITTEN AGAINST.** ‘C59’ closed PO-24’s control step and deferred the CR arm to r3512’s ‘HIER’ composition defect — “the first thing the next step must settle” — and THE REGISTER, INDEX and both appendices carry that deferral. ** (1) THE REMEDY NAMES TWO FLAGS ITS OWN TREE NEVER HAD. ** r3512’s fix is “give the hierarchy’s gravitational source the stacking clock and its diffusion the leaf”, i.e. teach ‘HIER=1’ about ‘SRCSTACK’ and ‘DIFFLEAF’; both occur **zero** times in `ACOUSTIC_two_arm.py` at 95559d53, the commit r3512 IS, whose 42 `os.environ` flags are listed. They were real on **6beeca84** (SRCSTACK x13, DIFFLEAF x3), which is **not an ancestor** of

95559d53 – two nodes, two lines, one instrument. ** (2) THE ASYMMETRY IT COUNTED IS ‘sound_phase’. ** ”The main path references two” counts evolve’s RHS plus ‘sound_phase’, which is CALLED ONCE in the file, from inside ‘qscan()’, the QSCAN=1 diagnostic that computes no spectrum. Like for like: each ODE right-hand side carries the clock **once**, and **neither projection carries it at all** – true at HEAD and at 95559d53 alike. ** (3) THE TWO RIGHT-HAND SIDES ARE THE SAME BYTES. ** Lines 576 and 959 are character-identical, as are the rate selections at 536 and 916, and every clock-or-source operation in ‘evolve’ is in ‘evolve_hier’. ** (4) AND IT MOVES: ** on ARM=cr toggling LEAFPERT changes evolve_hier’s returned state by 2.0 relative, so the hierarchy is not ignoring the clock. **=, C59’s deferral is discharged; what gates the CR arm is convergence in k, not a composition fix.**). *Computes:* SRCSTACK and DIFFLEAF asserted absent at BOTH 95559d53 and HEAD, with the 42-flag inventory printed; 6beeca84 asserted to carry them and asserted NOT an ancestor of 95559d53; 95559d53 asserted an ancestor of HEAD; the Jac_of call sites located by enclosing function at both commits with the RHS count asserted 1 and 1 and the projections asserted 0 and 0; sound_phase’s single call site asserted inside qscan’s line span; lines 576/959 and 536/916 asserted character-identical; the operation set of evolve asserted a subset of evolve_hier’s; Jac_of asserted != 1 on ARM=cr and the LEAFPERT toggle asserted to move evolve_hier’s state. **CONTROL THAT FIRES: the receipt EXITS 1 rather than passing if 95559d53 is not in the clone** – a shallow checkout makes every PART 1 assertion vacuous, which is the hollow-assertion failure the fork names *Bound*: ** ESTABLISHES AN ABSENCE, NOT A CORRECTNESS. ** That the named defect is not there; NOT that the HIER path is right. No CR number, no peak position and no height ratio is produced. r3512’s gate order 1, 2 and 4 – validate Pi on the control, the PISRC subtraction, the CR run – are untouched and remain PO-13 Run 1’s business. NOT CLAIMED: that r3512 was careless; two lines of work on one file is a corpus-mechanics failure *Run:* python3 receipts/P15_CR_cosmology/C60_the_hier_composition_defect_names_two_flags_its_own_tree_never_had.py

P15R109 C62_the_diffusion_signature_is_a_wash_and_the_isw_is_not_what_it_turned_on [OK]
sec:coherence (**PO-24: THE DIFFUSION-SCALE SIGNATURE IS RELOCATED INTO THE INFERRED TILT — NEITHER A TT-SHAPE TENSION NOR A WASH.** PO-24, narrowed at r4337, asks what the enlarged r_D does to the OBSERVED high-ell power, ”which turns on a parameter refit and on the early ISW term”. ** (1) THE JUDGEMENT: the early ISW is carryable, and the leaf assignment MULTIPLIES it rather than creating it. ** _rt, which sets the radiation fractions in the perturbation source, is the stack ”both arms” by the instrument’s own comment, so radiation is in the source under either assignment; measured, the post-recombination ISW is 0.348 of the SW amplitude on the leaf against 0.229 on the stacking rate. ** (2) BUT NOISW REACHED NO REPORTING PATH ** – read at one site in main()’s analytic block, zero references in los_spectrum, _project and hier_run – so the switch for the term this row turns on measured nothing. Repaired r4492; asserted at source here. ** (3) THE EARLY ISW IS NOT WHAT A HIGH-ELL QUESTION TURNS ON: ** 3.49 sigma/bin over l = 100-1296 and **0.77 sigma/bin over 700-1296**, propagated against plik_lite rather than quoted as a fraction. ** (4) THE SIGNATURE THROUGH A REFIT. ** Scaling r_D by the measured ratio multiplies the damping by a GAUSSIAN in ell; a tilt is a POWER LAW. Imposed on the measured sky and refitted on amplitude and tilt: **0.26 chi^2/bin over P15’s 185-bin ceiling, and MORE completely absorbed the higher one looks** (0.06/bin over 700-1760, 96% over 1000-2508) – because over a restricted range a Gaussian looks like a power law. ** (5) BUT THE ABSORPTION IS NOT FREE: dn_s = -0.0304 against sigma = 0.00323 derived from the SAME covariance that scores the fit – a 9.4 sigma cost. ** On the instrument’s own DSCAN pair the same fit gives 0.92/bin and 22.7 sigma. **The signature does not vanish under a refit; it MOVES, out of TT shape and into an inferred parameter.**). *Computes:* the r4492 repair asserted at source in both paths; r_D measured from the instrument at 7.1033 and 7.6398 Mpc, +7.55% raw, with DAMPX asserted to BE that ratio squared; the ISW’s imprint asserted larger on the leaf and asserted under 1 sigma/bin at high ell; the 185-bin ceiling asserted; the shape residual asserted under 0.6 sigma/bin on the data route and under 1.1 on both; the tilt cost asserted above 5 sigma on both routes. **CONTROL THAT FIRES: an injected tilt of +0.02 and +0.05 is recovered to within 5% with 99.9% absorbed** – a fitter that reports absorption is shown not to be manufacturing it *Bound*: ** THE MAGNITUDE IS NOT ROBUST TO A FACTOR OF THREE AND THE RECEIPT SAYS SO. ** The data-shape route multiplies the final spectrum by the Gaussian; the instrument applies the damping inside the source where it also enters the Doppler term through a derivative, on an unlensed ceiling-limited spectrum. The two differ 3.6x in residual and 2.8x in tilt; the larger is the more faithful

route, so the wash is stated at the WEAKER bound and closing the factor of three is named as work not done here. NOT CLAIMED: that the CR arm as a whole is consistent (r4136 has its heights at -20.7% and -29.2%); that dn_s of this size IS a tension, which is a statement about a joint fit this receipt does not perform. **A FORTIORI, BOTH WAYS: on the SHAPE residual, freeing only the named degeneracy is the least absorption a real refit could achieve, so the wash is a bound; on the TILT it is NOT a bound, since more parameters would SHARE the displacement** Run: python3 receipts/P15_CR.cosmology/C62.the.diffusion.signature.is.a.wash.and.the.isw.is.not.what.itturned.on

P15R110 C61_the_undriven_premise_is_false_on_the_rate_the_framework_assigns_the_perturbations [OK]

sec:coherence (**PO-13's DIAGNOSIS RESTS ON A CROSSING CENSUS, AND THE CENSUS COMES OUT THE OTHER WAY ON THE RATE THE FRAMEWORK ASSIGNS THE PERTURBATIONS.** P07 *sec:frontiers* states "the standard shift that carries it is universal only where every mode crosses the horizon while there is a plasma to be driven, and **on this rate the acoustic modes re-enter above the onset, so none of them does**", and PO13.WORKING_STATE gives the same premise as the structural reason the arm cannot reach the sky. **r3409 made LEAFPERT the default: the perturbations run on the LEAF congruence, and Hleaf carries the radiation term where the CR stacking rate does not.** Horizon crossing for the driving is a perturbation-sector event, so the census that decides the diagnosis has to be run on the leaf rate. ** (1) THE LEAF BACKGROUND HAS AN EQUALITY AND THE ONSET PRECEDES IT: ** $z_{eq} = 0m/Or - 1 = 3936$ (eta 236.4) against the onset at $z = 6761$ (eta 180.4). ** (2) THE FIRST PEAK IS SUPER-HORIZON WHEN THE PLASMA STARTS: ** on the leaf, $k_{l1}/aH(\text{onset}) = 0.858$; 1** for $l_{l1} = 204$, and it enters at $z = 5590$ **, above equality – a radiation-dominated crossing, **while there is a plasma**. ** (3) THE BAND IS NOT A SINGLE MODE: ** every l ; 237.7 enters after the onset and 155.6 ; l ; 237.7** enters in radiation. ** (4) AND THE OTHER RATE GIVES THE OPPOSITE ANSWER: ** on the stacking rate $k_{l1}/aH(\text{onset}) = 1.415$; 1** (already inside) and the background carries no radiation term at all, so it has no equality and the sentence is not merely true there but necessary. **=; The diagnosis was stated on the rate that carries the ruler and tested against a spectrum computed on the rate that carries the content.** And r3733's leaf reading for $l=220$ reproduces at 0.926 against its 0.92 – the premise's refutation was already in the record as a caveat.). *Computes:* both sentences asserted present verbatim in CR_framework.tex and PO13.WORKING_STATE.md, with the same P07 paragraph asserted to name the leaf congruence; LEAFPERT asserted on and RAD.IN.RATE asserted off; the leaf rate asserted to exceed the geometric rate at $a=1e-4$ (read, not assumed); the onset asserted to precede leaf equality; the after-onset and in-radiation bands computed from the instrument's own aH/c splines and the latter asserted to CONTAIN $l=204$; l_{l1} asserted super-horizon on the leaf and sub-horizon on the stack; the stacking rate asserted equal to $0m/a^3+OL$ to $1e-12$ at $a=1e-6$ where a radiation term would have been 254x the rest; r3733's 0.92 asserted reproduced. **CONTROL THAT FIRES: the same census on the STACKING rate returns the diagnosis's own answer** – so the census is not a construction that refutes everything put to it *Bound:* ** REFUTES A PREMISE, DOES NOT MEASURE A MECHANISM. ** No claim that the acoustic residual is explained, reduced or removed, and no measurement of how large the driving these modes receive is – NODRIVE=1 is what measures that and is not run here. The position deficit is untouched: the converged arm reports $l_{l1}/LA = 0.6764$ against the sky's 0.7312 whichever way the premise falls. NOT A VERDICT ON P07's SENTENCE: "this rate" is ambiguous in that paragraph between the stacking rate the section is about and the leaf rate the same paragraph names, and the sentence is TRUE on the first; what is established is that the reading supporting the diagnosis is the one the rate rule does not select. NOT CLAIMED: anything about z_{onset} as a fitted parameter, the alternation, or the Hubble-tension join P07 makes next Run: python3 receipts/P15_CR.cosmology/C61.the_undriven_premise_is_false_on_the_rate_the_framework_assigns_the_p

P15R111 C63_no_single_source_term_carries_the_undriven_split_and_the_first_probe_read_an_unwired_knob [PASS]

sec:coherence (**NO SINGLE LINE-OF-SIGHT SOURCE TERM CARRIES PO-13's 23% UNDRIVEN SPLIT.** Undriven, the CR arm's first peak sits at 1.1273 of its own angular acoustic scale and the control's at 0.9158 – a 23% split with $Q=1$ on both arms, so the oscillator is excluded and the split is in the projection. The DIFFUSION DAMPING is excluded too: DAMPX=0 removes it entirely and the split WIDENS to 26.0%. Removing the monopole, the Doppler dipole and the integrated term ONE AT A TIME leaves the split at 23.1%, 23.8% and 29.4% – it never

collapses, and removing the integrated term WIDENS it. So the answer to "Psi, integrated, or Doppler" is NONE OF THE THREE. ALSO PINS THE ROW'S PREMISE: "the same acoustic scale on both arms" is TRUE of the ANGULAR scale `l_A` (301.6 vs 301.4, 1 part in 1507) and FALSE of the PHYSICAL sound horizon `r_s` (135.46 vs 144.53 Mpc, 6.3% apart). The `l_A` match is a conspiracy – `D_M` differs by 6.2% too, within 0.07% of `r_s`'s own difference – not a shared scale.). *Computes:* eight runs of `ACOUSTIC_two_arm.py` under `NODRIVE=1`, both arms `x` (baseline, `NOISW=1`, `DPSRC=0`, `SWSRC=0`), at `LMAXL=520` where all eight first peaks reproduce the `LMAXL=1300` values exactly; each switch is CALIBRATED before any null is read off it *Bound:* A NEGATIVE result: it says where the split is NOT and is not a mechanism. Only SINGLE removals were run, so a cancellation between two terms is not excluded. The damping half of the projection kernel is now excluded and the VISIBILITY half is not: the arms last-scatter at $\eta = 449.6$ and 280.8 , a 60% difference in epoch against 7% in width, and that is the named unrun candidate. ZSTART is NOT a free knob – `r_s` integrates from the start, so moving it moves the acoustic scale itself (a trial took `l_A` from 301.6 to 172.8). Does not touch the driving (DRC/DRE are identically zero under `NODRIVE=1`). The `KCONT=1` sampling control leaves all four CR peaks unchanged, which bounds the sampling shift below one `LSTEP=8` grid step (2.65%) against a 23% effect – a bound, not an identity. *Run:* `python3 receipts/P15_CR_cosmology/C63_no_single_source_term_carries_the_undriven_split_and_the_first_probe`

P15R112 `C23_the_gap_estimated` [OK]
sec:earlyisw (ESTIMATE for the peak-region gap: the decay rate $k^2/(3H)$ is built from the thing that differs, so CRs potential decays $\sim 15\%$ faster and the peak power ratio is ~ 0.813 — BROAD deviation, not tail-confined). *Computes:* asserts the rate, the 13% and the factor-of-two clauses verbatim, computes the compounding, and flags the $0.813/0.823$ near-coincidence as different-origin (7 checks) *Bound:* NOT-A-PAPER-CLAIM — an ESTIMATE with its model stated, labelled as one; a hierarchy run would replace it *Run:* `python3 receipts/P15_CR_cosmology/C23_the_gap_estimated.py`

P15R113 `C24_the_substitution_itemised` [OK]
sec:instrument (PO-12s substitution ITEMISED: conformal time, `r_s`, the comoving horizon and the diffusion integral carry `H` while the Thomson rate and `x_e` do not — and the ratio does NOT cancel because `r_D` carries a square root that `r_s` does not). *Computes:* asserts the 13% clause and reconstructs it from `rho_r/rho_m=0.3`, asserts the microphysics-outside and `theta_*`-pinned clauses, and computes both scaling exponents (8 checks) *Bound:* NOT-A-PAPER-CLAIM — sets the bar for the two-leg run; P15s 9.4% is not re-derived *Run:* `python3 receipts/P15_CR_cosmology/C24_the_substitution`

P15R114 `C25_the_gap_closed_by_integration` [OK]
sec:diffusion-scale (the 2.6-point gap closed by INTEGRATION: `theta_D/theta_*` runs $+7.1\%$ at $z=1200$ to $+14.4\%$ at $z=10000$, with P15s $+9.4\%$ at $z\sim 2500$ — and the dependence is MONOTONIC, which is the papers own two-constraint argument). *Computes:* asserts the branch-point lower-limit clause and the single-datum clause verbatim, integrates the rate difference over five onset redshifts, and checks monotonicity (6 checks) *Bound:* NOT-A-PAPER-CLAIM — reproduces the papers shape on a simplified `rho_r/rho_m` model; the onset is the remaining unknown *Run:* `python3 receipts/P15_CR_cosmology/C25_the_gap_closed_by_integration.py`

P15R115 `C26_the_onset_is_not_free` [OK]
sec:tensions (PO-12s last free parameter is NOT free: the onset is fitted to the acoustic angle at $z\sim 6797$ and meets the scale at every `H_0` — and the residual $+13.1\%$ vs $+9.4\%$ is the WEIGHT $g(R)/x_e$, not the onset). *Computes:* asserts the onset value, the fitted-to-the-acoustic-angle clause and the not-a-knob clause verbatim, checks the model at the onset, and integrates under four weightings (7 checks) *Bound:* NOT-A-PAPER-CLAIM — power-law weights are stand-ins for $g(R)/x_e$, shown for direction and size *Run:* `python3 receipts/P15_CR_cosmology/C26_the_onset_is_not_free.py`

P15R116 `C27_the_number_bracketed` [OK]
sec:envelope-consequence (P15s $+9.4\%$ BRACKETED from outside its own machinery: Saha $+7.0\%$; Peebles ; unweighted $+13.1\%$, with the ordering FORCED by which history recombines faster — and cancel identically covers the CONSTANTS, not the weight). *Computes:* asserts the cancel-identically, constants-outside and Peebles-history clauses verbatim, shows the weight does not drop out, runs $g(R)$ with a Saha `x_e`, and checks 9.4 lies strictly inside (8 checks) *Bound:* NOT-A-PAPER-CLAIM — brackets rather than reproduces; the Peebles direction is argued, not computed *Run:* `python3 receipts/P15_CR_cosmology/C27_the_number_bracketed.py`

P15R117 C28_length_against_angle [OK]

sec:envelope-consequence (THERE WAS NEVER A DISCREPANCY: 9.4% is an ANGLE ratio (C10s $r=1.0926$, already netting the 0.7% sound-horizon shift) and 10.8% a LENGTH ratio (C8 — $r_{2686}-r_{2689}$ compared one to the other). *Computes:* asserts both statements and the 0.7% clause verbatim, reads C10s own r , and shows the two do not compose as this line assumed (7 checks) *Bound:* NOT-A-PAPER-CLAIM — corrects four of this lines revisions; C8 and C10 are run, not re-derived *Run:* `python3 receipts/P15_CR_cosmology/C28_length_against_angle.py`

P15R118 C29_nothing_to_calculate_across_the_join [OK]

sec:what-crosses (PO-12s remaining half has NO CONTENT: the pre-onset stretch is pressureless and at $w=0$ the potential equation loses k entirely, so there is no scale-dependent evolution for a single calculation across the join to compute). *Computes:* asserts the no- k , pressureless, boundary-mode and residue clauses verbatim, and verifies symbolically that k is present in the general equation and absent at $w=0$ (7 checks) *Bound:* NOT-A-PAPER-CLAIM — F5 reserves the strike; the residue routes to PO-7 *Run:* `python3 receipts/P15_CR_cosmology/C29_nothing_to_calculate_across_the_join.py`

P12R15 A7_the_frontier_has_two_kinds [OK]

sec:envelope-consequence (THE FRONTIER SORTS INTO TWO KINDS on P15s own $H(a)$ rule: FIVE rows ask whether the theory is DEFINED (PO-2/4/5/6/11) and TWO ask what it PREDICTS (PO-7/10) — and they fail differently, so size does not order them). *Computes:* asserts the $H(a)$ clause, checks the classification covers exactly the open rows, and pins each rows object against its kind (7 checks) *Bound:* NOT-A-PAPER-CLAIM — the classification is derived here; no paper states it *Run:* `python3 receipts/P12_algebroid/A7_the_frontier_has_two_kinds.py`

P15R121 C32_half_one_is_model_selection [OK]

sec:frontiers (PO-10s half (1) IS an information-criterion comparison: the corpus names "the likelihood-level model selection" while AIC/BIC/Akaike/Occam/Bayes-factor appear ZERO times — and the penalty is computable now, $dAIC=10.0$ and $dBIC=26.9$ in CRs favour). *Computes:* asserts the model-selection phrase and the 215-bin count verbatim, word-boundary-checks five model-selection terms at zero across papers and receipts (excluding itself), and computes both penalties (9 checks) *Bound:* NOT-A-PAPER-CLAIM — $k=6$ is the standard flat- Λ CDM count and must be stated with any result; the χ^2 is unrun *Run:* `python3 receipts/P15_CR_cosmology/C32_half_one_is_model_selection.py`

P15R122 C33_the_threshold_corrected [OK]

sec:tensions (THE THRESHOLD CORRECTED: r_{2709} s $k=1$ was wrong — P15 anchors A_s at the first peak, so CR is $k=2$ — and against Liddle/Jeffreys ($dBIC$ 2 positive, 6 strong) the threshold is $dBIC = 21.5$, still 3.5x the strong line). *Computes:* asserts the anchored-amplitude and one-parameter-accommodation clauses verbatim, tables all four parameter-count pairs against the Jeffreys scale, and computes the AICc correction (7 checks) *Bound:* NOT-A-PAPER-CLAIM — no χ^2 is scored; the count must be restated with any result *Run:* `python3 receipts/P15_CR_cosmology/C33_the_threshold_corrected.py`

P15R123 C34_the_deliverable_is_a_pair [OK]

sec:tensions (PO-10s DELIVERABLE IS A PAIR: the acoustic sector is open as PO-7, its phase freedom moves the gap $0.615 - 0.408$ and cannot close it — but the freedom is DISCRETE, so k is unchanged and both branches are reported at the same threshold). *Computes:* asserts PO-7s object, the phase-lever and cannot-close clauses verbatim with both values, and shows the discrete choice leaves $dBIC$ at 21.5 rather than 16.1 (5 checks) *Bound:* NOT-A-PAPER-CLAIM — neither branch is scored; that is the whole of what remains *Run:* `python3 receipts/P15_CR_cosmology/C34_the_deliverable_is_a_pair.py`

P15R124 C35_the_reference_is_F3 [OK]

sec:tensions (THE REFERENCE FORK SETTLES ITSELF AND AGAINST THIS LINES FRAMING: BIC uses only DIFFERENCES, so F3 (same-instrument) is the score and the CAMB-206.4 comparison charges CR an instrument floor CAMB never pays). *Computes:* asserts L-147s floor definition and pipeline-wiring clauses verbatim, shows $dBIC$ contains only a χ^2 difference, and confirms the threshold is invariant under the pair choice (7 checks) *Bound:* NOT-A-PAPER-CLAIM — corrects r_{2709} - r_{2711} s statement of what the threshold scores against; the threshold itself is unchanged *Run:* `python3 receipts/P15_CR_cosmology/C35_the_reference_is_F3.py`

P15R125 C36_the_negative_is_the_envelope [OK]

sec:envelope-consequence (SUPERSEDED r_{2725} (the check shared the runs own n_s -held assumption, so agreeing to the same order confirmed only that both held it fixed) — L-814s NEGATIVE

IS NOT AN ARTEFACT: P15s own published envelope, scored against cosmic variance on 215 bins with no pipeline or fit, gives $\chi^2 \sim 1.6e5$ against cc54s measured $5.05e4$ — the same order). *Computes*: evaluates the papers own $\exp[-(1/LD)^2(r^2-1)]$ across the band, scores it against cosmic-variance errors, reads cc54s floor finding from their receipt, and pins L-147s scope clause (6 checks) *Bound*: NOT-A-PAPER-CLAIM — no framework verdict; PO-7 protected and F5 reserves it *Run*: `python3 receipts/P15_CR_cosmology/C36_the_negative_is_the_envelope.py`

P15R126 C37_the_comparison_is_not_matched [OK]
sec:envelope-consequence (L-814s COMPARISON IS NOT MATCHED and its number is WITHDRAWN as a result: the CR arm was held at $k=2$ with n_s fixed at LCDMs fitted value, and freeing the tilt alone removes 15.6x). *Computes*: computes the envelope χ^2 with the tilt held and free, shows the threshold barely moves for the extra parameter, and reads cc54s own relative statement from their receipt (5 checks) *Bound*: NOT-A-PAPER-CLAIM — the $k=2$ spec was this lines at r2710; a matched comparison is not claimed to pass *Run*: `python3 receipts/P15_CR_cosmology/C37_the_comparison_is_not_matched.py`

P15R127 C38_the_comparison_scores_derivations [OK]
sec:tensions (PO-10s NON-FOREIGN COMPARISON IS A SCORE ON DERIVATIONS: a derivation has no k , so scoring θ_* , r , z_{eq} and the 9/10 transfer against measurement imports no parameter vector — and this receipt reports NO score, because the draft that did invented every sigma). *Computes*: pins P15s derived-vs-measured pairs and its own naming of Ω_m and A_s as fitted, and asserts its own refusal to score (6 checks) *Bound*: NOT-A-PAPER-CLAIM — no verdict on CR; the row owes published uncertainties and a derived-quantity list *Run*: `python3 receipts/P15_CR_cosmology/C38_the_comparison_scores_derivations.py`

P15R128 C39_the_derived_list_read [OK]
sec:tensions (PO-10s DERIVED-QUANTITY LIST READ from P15s own marker language: four pairs each with the papers own accuracy clause (θ_* 302.2/301, r_s 146.4/145.4, $1+z_{eq}$ 3399, eta 1.99 to one per cent) and three exclusions in the papers own words). *Computes*: pins all four derived pairs and all three fitted-exclusions verbatim, and the high- l ratios no-free-parameter clause (7 checks) *Bound*: NOT-A-PAPER-CLAIM — nothing is scored; the published uncertainties remain owed and are not this lines to invent *Run*: `python3 receipts/P15_CR_cosmology/C39_the_derived_list_read.py`

P15R129 C40_the_pair_was_quoted_against_a_rounding [OK]
sec:tensions (PO-10s FIRST PAIR MUST TAKE THE RECEIPTS VALUE, NOT THE PROSE: P15 writes "the measured ~ 301 " (tilde present, honestly approximate) while P15_zonset_determinations carries and asserts $L_A = 301.76$ — and the gap is 0.44, not 1.20). *Computes*: quotes both the prose and the receipts assertion, computes both gaps, and carries its own first drafts correction (6 checks) *Bound*: NOT-A-PAPER-CLAIM — no paper edit owed, the tilde is there; nothing is scored and the uncertainty is still not this lines *Run*: `python3 receipts/P15_CR_cosmology/C40_the_pair_was_quoted_against_a_rounding.py`

P15R130 C41b_a_tilde_on_a_settled_value_is_a_stale_hedge [OK]
sec:tensions, *sec:coherence* (A TILDE ON A SETTLED VALUE IS A STALE HEDGE: ~ 301 became 301.76 (asserted by its receipt) and $\sim 8\%$ became 8.2% in NINE places (computed on CAMBs exact ionization history), three of them while calling it "a real, computed effect"). *Computes*: confirms both figures are asserted by receipts, that no tilde survives on either, and that legitimately approximate tildes are untouched (7 checks) *Bound*: NOT-A-PAPER-CLAIM — nothing scored; not every tilde is stale, only those on figures a receipt asserts *Run*: `python3 receipts/P15_CR_cosmology/C41b_a_tilde_on_a_settled_value_is_a_stale_hedge.py`

P15R131 C41_a_tilde_is_stale_when_nothing_competes [OK]
sec:tensions (A TILDE IS STALE WHEN ONE RECEIPT ASSERTS AND NONE COMPETES: ~ 301 failed that test and P15 now reads 301.76; $\sim 8\%$ passed it — C8 derives +10.83% analytically and NAMES the disagreement with $damping_ratio_cleans +8.2\%$ — so nine edits were reverted). *Computes*: confirms the 301.76 edit landed and the nine tildes remain, pins C8s computed +10.83% and its own naming of the conflict (6 checks) *Bound*: PAPER-CLAIM (301.76 only) — the 8% figure is left tilde-marked and its discrepancy is filed as owed *Run*: `python3 receipts/P15_CR_cosmology/C41_a_tilde_is_stale_when_nothing_competes.py`

P15R132 C42_the_cancellation_needs_xe_identical [OK]
sec:coherence (THE DAMPING DISCREPANCY DIAGNOSED: C8s cancellation needs x_e identical in both cosmologies, and a different $H(a)$ changes the recombination HISTORY not merely

its epoch — Lambda, the upper limit, the radiation density and arithmetic all eliminated). *Computes*: reproduces C8 to six figures, varies $\Lambda / z_{\text{rec}} / \rho_{\text{r}}$ and shows none accounts for the gap, and pins C8s own PROVIDED clause (7 checks) *Bound*: NOT-A-PAPER-CLAIM — neither number is adjudicated; the x_e response is a calculation neither receipt has done *Run*: `python3 receipts/P15_CR_cosmology/C42.the_cancellation_needs_xe_identical.py`

P15R133 C43_the_gap_is_numerical_not_xe [OK]
sec:coherence (r2750 WITHDRAWN — THE DAMPING GAP IS NUMERICAL, NOT x_e: a pure H probe moves z_* by only 0.195% ($\sim 0.05\text{pp}$ on the ratio) against a 1.86pp gap, while the CAMB receipt prints a 7.1% miss against CAMBs own θ_{etad} on its OWN LCDM arm). *Computes*: runs CAMB at five N_{eff} values as an H-only probe, scales the response by r2750s own measured sensitivity, and pins the receipts self-reported GATE miss (6 checks) *Bound*: NOT-A-PAPER-CLAIM — C8 is not confirmed, and the tilde stays: two receipts still disagree, one now with a KNOWN defect *Run*: `python3 receipts/P15_CR_cosmology/C43.the_gap_is_numerical_not_xe.py`

P15R134 C44_the_gap_is_truncation [OK]
sec:coherence (THE DAMPING GAP IS TRUNCATION: the r_D ratio climbs 8.33% -i 9.94% with the upper limit and converges only by $z \sim 5e4$, while the CAMB receipts grid stops at $z=12000$ — and a normalisation factor CANCELS in a ratio, which withdraws r2751). *Computes*: computes the ratio at six upper limits, shows convergence, and demonstrates that a shared constant divides out (6 checks) *Bound*: NOT-A-PAPER-CLAIM — the receipts grid is reasonable for its own purpose; what is claimed is that its RATIO inherits a truncation bias *Run*: `python3 receipts/P15_CR_cosmology/C44.the_gap_is_truncation.py`

P15R135 C45_xe_does_not_cancel_from_a_ratio_of_integrals [OK]
sec:coherence (THE DAMPING DISCREPANCY RESOLVED: x_e does NOT cancel from a ratio of INTEGRALS even when identical — toggling it on the same range moves the ratio +9.94% to +8.37%, the whole gap — so C8s cancellation step is a real error). *Computes*: toggles x_e on a fixed range and measure with CAMBs own history, shows a shared CONSTANT does cancel exactly while x_e does not, and pins C8s every-constant-outside claim (6 checks) *Bound*: NOT-A-PAPER-CLAIM — which figure is P15s signature is not settled; C8s reduction and baryon correction stand *Run*: `python3 receipts/P15_CR_cosmology/C45_xe_does_not_cancel_from_a_ratio_of_integrals.py`

P15R136 C46_the_nine_are_right_and_the_one_is_wrong [OK]
sec:tensions (THE 9.4% TRACED: P15 -i C10 (+9.26%) -i C9, which divides r_D 1.1015 by r_s 1.0067 — the ANGLE ratio, correctly, but from an r_D that omits the x_e weighting. Corrected it lands at +7.6% to +8.2%, so the nine $\sim 8\%$ were RIGHT and the one 9.4% was the error). *Computes*: pins the citation chain P15-iC10-iC9 and reruns C9s own division on three r_D ratios (6 checks) *Bound*: PAPER-CLAIM — ten instances set to 8.2%, and the tilde removed per r2749s test now that nothing competes *Run*: `python3 receipts/P15_CR_cosmology/C46.the_nine_are_right_and_the_one_i`

P15R137 C47_the_neutrinos_were_missing [OK]
sec:coherence (THE +5.66% RECONCILED AND IT WAS THIS LINES ERROR: r2752 used photons alone where the receipt uses $O_{\text{gamma}} + O_{\text{nu}}$ (a 69% underestimate of what sources H) — and the CR arm has no radiation at all, so the omission hit ONE ARM ONLY. With neutrinos in, the ratio is 1.0896 against the receipts 1.0897). *Computes*: runs the full Hu-Sugiyama for both rates under two radiation densities with CAMBs own x_e, and confirms the absolute r_D difference cancels from the ratio (6 checks) *Bound*: NOT-A-PAPER-CLAIM — only the RATIO is claimed to four figures; the absolute r_D still differ by $\sim 3\%$ from grid and quadrature *Run*: `python3 receipts/P15_CR_cosmology/C47.the_neutrinos_were_missing.py`

P15R138 C48_the_pairs_are_three [OK]
sec:tensions (PO-10s PAIRS ARE THREE, NOT FOUR: r_s and $1+z_{\text{eq}}$ hold against asserting receipts (C9 145.38, DESI 3402), but the onset ratio is an IDENTITY ON INHERITED INPUTS — "the quoted value to one per cent, from standard thermodynamics" — same class as N_{eff} and A_{s}). *Computes*: finds the asserting receipt for each measured value, pins the thermodynamics clause, and records the 1.9968 near-miss where another receipt asserts a different quantity with the same digits (6 checks) *Bound*: NOT-A-PAPER-CLAIM — the onset ratio is not wrong, only not a TEST; nothing is scored *Run*: `python3 receipts/P15_CR_cosmology/C48.the_pairs_are_three.py`

P15R139 C49_the_row_has_a_likelihood_not_a_lookup [OK]
sec:tensions (PO-10 DOES NOT NEED ERROR BARS — IT HAS A LIKELIHOOD: `plik_lite`

over 215 TT bins with a covariance and a banked LCDM fit the pipeline calls wired. What blocks it is recorded in the same file — the CONTROL arm lands at $\chi^2/\text{dof} \sim 100$). *Computes*: pins the instrument, its calibration standard, its self-recorded F4 defect, and F5s protection of the verdict (6 checks) *Bound*: NOT-A-PAPER-CLAIM — the control defect is not diagnosed here, and no verdict on CR is drawn *Run*: `python3 receipts/P15_CR_cosmology/C49_the_row_has_a_likelihood_not_a_lookup.py`

P15R140 C50_the_control_is_at_seven_not_a_hundred [OK]

sec:tensions (THE CONTROL ARM IS AT 7.14, NOT ~ 100 : the receipts F4 prose carried the c54.172 floor while its F6 PRINT reports $1320.5/185 = 7.14$, and F6 says the floor fell $103 -j 22.5 -j 28.6 -j 7.1$, a factor of 14). *Computes*: pins the corrected prose, the f-string print fields, the fall history, the 185-vs-215 bin difference and F6s unchanged verdict (6 checks) *Bound*: NOT-A-PAPER-CLAIM — 7.14 is not acceptable either; both arms remain outside the discriminating regime *Run*: `python3 receipts/P15_CR_cosmology/C50_the_control_is_at_seven_not_a_hundred.py`

P15R141 C51_the_dropped_bins_are_the_damping_tail [OK]

sec:tensions (THE THIRTY DROPPED BINS ARE ell 1759-2508 — THE DAMPING TAIL: the likelihood arms model ends near ell 1760 and nan-drops the rest, discarding exactly the region P15 names as its exposed edge, where the suppression runs 24% to 42%). *Computes*: reads the bin edges from the likelihoods own arrays, locates the cut at which 185 survive, and profiles the damping suppression across the dropped range (6 checks) *Bound*: NOT-A-PAPER-CLAIM — the ell limit is a cost not a mistake, and which way the omitted bins would land is the point of running them *Run*: `python3 receipts/P15_CR_cosmology/C51_the_dropped_bins_are_the_damping_tail.py`

P15R142 C52_the_banked_spectra_fail_the_sampling_guard [OK]

sec:tensions (THE BANKED SPECTRA FAIL THE INSTRUMENTS OWN SAMPLING GUARD: LMAXL=2000 NK=260 gives 2.5 points per Bessel period and prints UNDER-SAMPLED — and the guard says the source comb stays correct while the projection aliases, so no comb-level check could catch it). *Computes*: fixes the banked configuration from the npz shape, computes the sampling ratio and projection memory across four NK values, and pins the guards own wording (6 checks) *Bound*: NOT-A-PAPER-CLAIM — whether aliasing moves the χ^2 enough to matter is UNMEASURED, and measuring it needs a run that will not fit in 3.7 GB *Run*: `python3 receipts/P15_CR_cosmology/C52_the_banked_spectra_fail_the_sampling_guard.py`

P15R143 C53_the_k_range_fixes_one_arm_only [OK]

sec:tensions (THE k-RANGE FIXES ONE ARM ONLY: raising L_max 26% drops the control 7.14 -j 3.81 on the SAME 185 bins while CR moves 0.4% — a response ratio over twenty to one, so r2760s undiagnosed factor of seven is a k-truncation and CRs 281 is not). *Computes*: computes both arms responses and their ratio, checks F_3 widens in the direction one-arm improvement predicts, and labels the two-point trend as an extrapolation (6 checks) *Bound*: NOT-A-PAPER-CLAIM — radiation is the first candidate not a demonstrated mechanism; the convergence trend rests on TWO points *Run*: `python3 receipts/P15_CR_cosmology/C53_the_k_range_fixes_one_arm_only.py`

P15R144 C54_the_281_is_the_prediction_being_measured [OK]

sec:tensions (CRs 281 IS THE ORDER P15s OWN PREDICTION PRODUCES: scoring the damping residual over 185 bins gives χ^2/dof from 204 ($\sigma=1\%$) to 5099 ($\sigma=0.2\%$), so 281 sits INSIDE that range and BELOW the value at Plancks quoted errors — the arm is scoring the effect P15 predicts). *Computes*: pins P15s no-free-parameter high-ell formula, scores its residual at three error scales, pins F5, and names the SHAPE test that would settle it (5 checks) *Bound*: NOT-A-PAPER-CLAIM — an ORDER comparison against a flat sigma, not a derivation against the plik covariance; supplies a candidate, does not close the row *Run*: `python3 receipts/P15_CR_cosmology/C54_the_281_is_the_prediction_being_measured.py`

P15R145 C55_the_shape_test_says_peak_misalignment [OK]

sec:tensions (THE SHAPE TEST RUN: the CR arms residual is neither a damping-profile match nor flat — it OSCILLATES, 0.237 to 2.375, correlation -0.296, dominant period 317 against lA = 301. The 281 is PEAK MISALIGNMENT, and r2786 is withdrawn by its own named test). *Computes*: computes the banked arms ratio, its correlation with P15s profile, its dominant Fourier period against lA, and the lA-agrees / r.s.-differs contrast (5 checks) *Bound*: NOT-A-PAPER-CLAIM — the damping signature is not shown absent, only non-dominant; physical vs numerical phase slip is the open question *Run*: `python3 receipts/P15_CR_cosmology/C55_the_shape_test_says_peak_misa`

- P15R146** `C56_la_is_computed_and_its_residual_is_too_small` [OK]
sec:tensions (LA IS COMPUTED NOT CALIBRATED (pi D_M/r_s reproduces the stored value in both arms) and its survival is a real cancellation P15 claims in advance — but the +0.075% residual explains under 1% of r2787s measured swing, two orders too small). *Computes:* checks pi D_M/r_s against the stored LA in both arms, sizes the D_M and r_s moves, pins P15s met-from-the-other-end clause, and propagates the residual against the measured swing (5 checks) *Bound:* NOT-A-PAPER-CLAIM — the cancellation is observed not re-derived; amplitude is what remains after two eliminations, a candidate not a finding *Run:* `python3 receipts/P15_CR_cosmology/C56_la_is_computed_and`
- P15R147** `C57_the_cr_peaks_are_not_at_its_own_la` [OK]
sec:tensions (THE CR ARMS PEAKS ARE NOT WHERE ITS OWN LA SAYS: mean spacing 258 against a stored LA of 301.6 (ratio 0.855) while LCDM sits at 0.995 — so the stored quantities are consistent with each other and NOT with the computed C_ell). *Computes:* finds peaks in both banked arms, compares mean spacing against each arms stored LA, and sizes the mismatch against r2788s residual (5 checks) *Bound:* NOT-A-PAPER-CLAIM — which of D_M, r_s or the projection is wrong is not established; the CR spacing could be a real feature of a transfer on the geometric rate *Run:* `python3 receipts/P15_CR_cosmology/C57_the_cr_peaks_are_not_at_its_own_la.py`
- P15R148** `C58_the_stored_rs_moves_the_wrong_way` [OK]
sec:tensions (THE STORED CR r_s MOVES THE WRONG WAY: removing radiation must RAISE the sound horizon (146.5 -j 245.2 Mpc integrated), the peak spacing independently demands 158.35, and the stored value is 135.46 — BELOW LCDMs 144.53). *Computes:* solves the spacing for each candidate, integrates r_s with and without radiation, and shows pi D_M/r_s on both stored values reproduces the stored LA exactly (5 checks) *Bound:* NOT-A-PAPER-CLAIM — 158.35 and 245.16 are not proposed as the right value; what is established is the DIRECTION and that the stored value has the wrong sign of deviation *Run:* `python3 receipts/P15_CR_cosmology/C58_the_stored`
- R1.the_correction_stopped_at_the_sentence_and_the_number_it_defines_was_left_behind** [OK]
sec:envelope-consequence (r2755 CORRECTED THE SENTENCE AND NOT THE NUMBER THE SENTENCE DEFINES: ‘theta_D/theta_’ was corrected from \$9.4\{\}%\$ to \$8.2\{\}%\$ and ‘sec:envelope-consequence’s \$r\$, one paragraph later, IS that ratio and still read 1.093 — so the paper stated one ratio twice, differently, and the second is the one the prediction is made of. Corrected from three agreeing routes to \$r=1.0816\$: the ratio at \$\{\ell_D\$ moves 0.823 → 0.844, at \$1.5\{\ell_D\$ 0.645 → 0.682, \$\{\ell_D(\{\rm CR)\$ 1281 → 1294. **FIFTEEN receipts carried it — eight SILENTLY (exiting zero, six of them evaluating the envelope with the wrong value) and seven LOUDLY (failing every full run since r2755 — and they are the seven that PRODUCED the correction).** CONTROL: C10’s gate was built so the paper and the receipt “cannot drift apart silently in either direction”, and it worked — they were consistent with each other and both wrong.). *Computes:* COMPUTES: the identity \$r=\{\theta_D/\{\theta_*\$ read from C10’s own assertion message; the corrected value from three routes and the four quantities that follow; the fifteen receipts split by failure mode and counted at the commits where they exist; the C41 double-allocation resolved as one rule at two states; and the register files deliberately left alone (21 checks) *Bound:* **bound: 1.0816 is NOT re-derived here** — it is read from ‘P15_damping_ratio_clean’, ‘C46’ and the corrected sentence, and checked for agreement. **Not claimed that the envelope is right**, only that it now runs on the ratio the paper’s own preceding paragraph derives. **The correction FAVOURS the construction (16% suppression at \$\{\ell_D\$ rather than 18%) and is flagged for it**; it would apply identically the other way. ‘PO-7’ is ‘sec:refit-bound’/‘sec:coherence’ and is untouched. *Run:* `python3 receipts/L557_the_correction_stopped_at_the_sentence/R1.the_correction_stopped_at_the_sentence_and`
- P1.the_pin_test_run_the_spacing_follows_the_pin_so_the_ratio_does_not** [OK]
sec:tensions (THE PIN TEST, RUN — the runs the observer line’s container killed twice. **The peak spacing tracks the one fitted number PROPORTIONALLY** (‘LATARG’ 280/301.6/320 → mean spacing 229.3/245.3/261.3), so spacing/ ℓ_A = 0.8190/0.8134/0.8167 — **0.69% spread across a 14% pin range**, against the **13.4%** a constant-spacing arm would give: a factor of twenty, so the measurement DISCRIMINATES. ⇒ **The routed dichotomy is inverted: following the pin is exactly what makes the RATIO — which is what the deficit is — independent of the pin. THE DEFICIT SURVIVES THE FIT.** Also: ‘KCONT=1’ at NK=320 returns the same four peaks, discharging the instrument’s own standing sampling caveat; and ** ℓ_1 = 172 at all three pins**, so ℓ_1/ℓ_A is pin-dependent while the spacing ratio is not. LCDM

control on the same grid: 0.9909, reproducing the sky to 6 in ℓ). *Computes:* COMPUTES: five banked runs parsed from their own printed blocks; the spacing ratio and its spread; the CONSTANT-spacing alternative computed as the control and the discrimination factor between them; the KCONT identity and its sampling-guard margin; ℓ_1 's invariance and ℓ_1/ℓ_A 's spread; and the LCDM arm checked against the sky before being used (21 checks) *Bound:* NOT-A-PAPER-CLAIM — ***and the declaration is deliberate: this is a measurement on the instrument's own fitted parameter, delivered to a routed question, and whether it lands in 'sec:tensions' is the observer line's call under 'PO-7'.* **** A node that banked it into the paper on its own initiative would be taking a step toward the verdict the row protects. ***bound:* this reports a number and does not convert it into a verdict — 'PO-7' is protected. **** Not that r2789's 258 was wrong (different grid; the control was re-run here rather than compared across grids). Not that peaks are known better than the ℓ -grid: 'LSTEP=8', ± 4 per peak, ± 8 per spacing — the invariance claim is $20\times$ outside that and the individual spacings are not. Not that the deficit is explained, only that the fitted number does not produce it. *Run:* python3 receipts/L562_the_pin_test/P1_the_pin_test_run_the_spacing_follows_the_pin_so_the_ratio_does_not.py

P15R149 P15_the_driving_is_bought_by_decay_during_oscillation [OK]

sec:transmission (THE DRIVING SHIFT IS BOUGHT BY POTENTIAL DECAY OCCURRING WHILE A MODE OSCILLATES, so a mode whose oscillation begins after the potential has settled inherits the UNDRIVEN phase. **** Coupled photon/matter/potential solve on a matter-and-radiation background, with the potential closed by the ENERGY CONSTRAINT rather than evolved and the acoustic turnover taken at the first zero of the photon velocity that BEGINS A SEQUENCE SPACED BY π — the free oscillator's own spacing, which the undriven gate validates at 1.0000 on both arms. **** SCOPE: the ASYMPTOTIC statement only, $Q \rightarrow 1$ at large k , which is what P15 and P07 assert; NOT the low- k values, and NOT a magnitude (neutrino free-streaming omitted, $\sim 15\%$ low). A sign flip in the initial amplitude is a π phase shift and moves WHICH ZERO IS FIRST by one half-period, so four initial signs agree to 0.012 at $k=160$). *Computes:* COMPUTES: a coupled photon/matter/potential solve on a matter-and-radiation background, the potential closed by the ENERGY CONSTRAINT rather than evolved; the UNDRIVEN gate validated at \$1.0000\$ on both arms before use; the driven arm asserted to FALL toward \$1\$ from above and to reach the free-oscillator value to \$0.02\$ at large \$k\$; the control asserted well below \$1\$ and flat in \$k\$ to \$0.10\$; the two shapes asserted qualitatively distinct by a factor of two in range; and the robustness leg showing a factor of two in the radiation budget barely moves it. Re-run r3537, ALL PASS *Bound:* SCOPE, and the receipt states it: the ASYMPTOTIC statement only, \$Q\{\}\$ to \$1\$ at large \$k\$, which is what 'P15' and 'P07' assert; ***NOT* the low-\$k\$ values and NOT a magnitude**** — neutrino free-streaming is omitted, some \$15\{\}\$%\$ low *Run:* python3 receipts/P15_CR_cosmology/P15_the_driving_is_bought_by_decay_during_oscillation.py

P15R150 N8_the_transmission_dichotomy_is_a_capacity_dichotomy [OK]

sec:transmission (*prop:transmission*, *rem:transmission-leg*) (P15 proves a transmission dichotomy — a non-degenerate horizon ($p=1$) imprints a scale, a degenerate one ($p=2$) transmits — and *rem:transmission-leg* says "the leg multiplies the spectrum by a constant and the seam imprints nothing: neither carries a scale, and a spectrum can only be tilted by something that does". That is a CHANNEL claim, and "carries a scale" is what decides its capacity). *Computes:* fits the output tilt on four disjoint k -bands: $p=2$ returns the same tilt on every band (spread $1.7e-16$) while $p=1$ spreads by 7.93, which IS the scale; the control puts a cutoff into the $p=2$ kernel by hand and the spread jumps to 1.91, so the test can fail; and the $p=1$ spread shrinks monotonically $30.2 \rightarrow 7.9 \rightarrow 2.3$ as κ rises, tracking the kernel's scale *Bound:* SUPPORTS P15 — transparent means the answer does not depend on where you look, and imprinting means it does. NOT a Bogoliubov calculation; no Hawking temperature claimed *Run:* python3 receipts/P15_CR_cosmology/N8_the_transmission_dichotomy.py

P15R151 P15_the_history_is_spherically_symmetric_throughout_so_the_chern_simons_number_never_moves [OK]

*does the construction's own history pass through any member carrying a ***twist***, and does the gravitational Chern–Simons number change across it? 'r6762' made the violation a ***boundary*** quantity — the right shape for a net count produced across a history — and 'P15' names the open item it could answer, the ***baryogenesis-analogue*** derivation of order a billion photons per baryon (***No twist anywhere on the history, so the count is exactly conserved — and not because the number comes out small.*** ***Q1*** the path is fixed three ways: 'P16' states the spherically symmetric class as a ****premise**** and forbids dropping it while keeping the branch-point locus;*

$\psi \equiv 0$ on the general *dynamic* spherically symmetric class (four arbitrary functions of (t, r) , off-diagonal kept — ‘r6762’'s identity was *static* and does not reach collapse); and the twisted member's transverse block is a *torus* against this history's closed S^3 , which no deformation joins *Q2* no, at both levels — a travelling tensor wave gives *exactly zero* at any polarisation, and the only nonzero source is the parity-odd product $\psi \omega$ of the two channels, needing both polarisations AND an areal factor AND broken spherical symmetry; the history supplies one of three *Q3* *zero*, and endpoint-independent — all four components of K^μ vanish identically on the class, so the number is zero at *every* slice, the $r=0$ crossing included, where a merely divergence-free quantity could have jumped *Q4* net count $3 \times 0 = 0$ *Q5* the first branch, blocker named). *Computes*: C1 Nariai in its *own* $dS_2 \times S^2$ form (radii $\alpha/\sqrt{3}$), not as a value of $f(r)$ — zero, and still zero with a $d\tau, d\varphi$ term, so the zero is not the product structure C2 the polarised cut ($\omega \equiv 0$, ‘P11’ eq:metric) zero for arbitrary A, ψ, R ; unpolarised nonzero; and *silencing* either channel kills it, each by rebuilding the metric rather than substituting a symbol for a function C3 Stokes *exact*: the volume integral of the density and the boundary flux of K^μ both give $8/15 - \log(390625/6561)$, with ‘r6762’'s constant -1 re-verified on a different member the machinery is read out of ‘r6762’'s own receipt rather than re-typed, so the two cannot drift *Bound*: *NOT* claimed that no mechanism could produce the item's number — only that this one does not, and why. *No* photon number is supplied or invented; the verdict does not need one, a zero numerator giving zero for any finite denominator. *No* direction is claimed for any asymmetry, there being none to direct — had the count been nonzero its sign would have been correlated with the twist's, per ‘C51’. Nothing reopens ‘r6762’'s current, source or inflow findings, the global group, the gauging's status, or weak isospin; no cosmological implication is drawn. Nothing is named *Run*: python3 receipts/P15_CR_cosmology/P15_the_history_is_spherically_symmetric_throughout_so_the_chern_simons.r

P15R152 P15_the_likelihoood_pair_is_another_instruments_and_the_crossing_run_needed_a_missing_knob [OK]

‘PO-10’ reopened at ‘r6780’ on a contradiction between ‘P15’'s body and ‘P15’'s own receipt: the body reports $\chi^2 = 397.13$ against 206.44 over 215 ‘plik-lite’ TT bins with five parameters free in each, and the receipt records that pair as *superseded*. Which comparison is legitimate, on what run, with the floor beside it (There are TWO instruments here, and the body's pair is the other one's — which is why the body and the receipt are both accurate. *Q1* ‘fit.py’+CAMB fits five parameters on 215 bins and its CR arm is CAMB's Λ CDM TT *times* an ℓ -only damping envelope; ‘ACOUSTIC_two_arm’+‘chi2_of_spectrum’ fits one amplitude on 185 covered bins and its CR arm is the construction's own spectrum. The second is the one to report, and the first is *not malformed* — it answers the damping question *Q2* the second gives 51817.0 against 1320.5 — *and* the crossing configuration was unreachable, the CR arm's background being written in as literals ($H_0 = 73.00$, $\Omega_m = 0.3066$); ‘CRH0’/‘CROM’/‘CROMBH2’ exposed, defaults byte-identical *Q3* $F_2 = +1114.0$, $F_3 = +50496.5$, forty-five times it — *and* the body's $\Delta \chi^2 = 190.7$ is *below* that floor, readable on the first instrument only because its control *is* the CAMB reference so its floor is identically zero *Q4* the deficit is in the second's spectrum and *structurally absent* from the first's *Q5* both of the order's two options at once: ‘cr.json’ banks a genuine five-parameter optimum at $H_0 = 78.13$, and ‘fit.py’ shows the shape refitted was CAMB's Λ CDM times the envelope). *Computes*: C1 ‘F1’ first, non-optional: the banked CAMB fit at $\chi^2 = 206.4$ over 215 bins, $\chi^2/\text{dof} = 0.960$ the envelope's inability to carry a comb *measured*, not argued — across envelopes strong enough to move ℓ_{11} by up to eight multipoles the spacings hold within 6% ($320/272/312$ to $312/272/304$) the sound horizon scanned over *four decades* of starting redshift, converging monotonically to $r_s = 256.13$ Mpc with a residual drift of 0.5 in ℓ_A — so “converges at its upper end” is a measurement here and not a quotation the exposed knobs' defaults verified byte-identical on ℓ_A , r_s , D_M and the peak list *Bound*: *NOT* claimed that the body's computed 298.0 is wrong, nor that the instrument's convention is the right one — only that they *differ*, the body putting r_s on the radiation-carrying leaf rate while ‘rs_from’ integrates the radiation-free one, and which is intended is the paper's question. *No* χ^2 is manufactured against a comb the paper does not claim, so the crossing-configuration figure the order asked for is reported as unreachable rather than supplied. Nothing reopens the handover resolution. *PO-7* protected throughout: a negative is a measurement

discrepancy and no verdict on the construction is drawn from any χ^2 here *Run:* python3 receipts/P15_CR.cosmology/P15.the_likelihood_pair_is_another_instruments_and_the_crossing_run_needs

P15R153 P15_the_chiral_state_the_route_needs_is_forced_absent_not_merely_unchosen [OK]
r6766 named what a successor to the closed route would need — a chiral *state* on the three-sphere layer, not a chiral member — and left it unclassified: does it reduce to the handedness choice ‘PO-30’*’s* law places outside, or is it something the geometry might still supply? (**Neither: it is forced absent. **It is not the handedness choice** — that selects one of two equivalent options, while this asks whether the state is imbalanced *at all*, which is prior to any selection. **The layer is the same one ‘P10’ works on**, established from ‘P10’*’s* own words: it lifts to “the closed- S^3 layer’s propagating sector”, where the transverse-traceless graviton modes form the tower. **And there the balance is forced**: regularity imposes the regular branch fibre by fibre, the surface gravity belongs to the background horizon and is common to every fibre, and the operator labelling the fibres is a sum of squares with a single coefficient — no helicity label and no sign, so the two towers are populated alike. **The parity-odd source is exactly that difference**, its expectation vanishing under equal population. $\Rightarrow$ ***‘P10’*’s* helicity cancellation and *r6766*’s source form are one statement from two sides; the route closes by a condition the geometry imposes, not by its silence on a choice***). *Computes:* the parity-odd expectation vanishing under equal population and not under unequal; the product dying when either channel is silenced *Bound:* **NOT that the tower is achiral** — ‘PO-44’ is explicit it remains chirally capable and must not be read as the achirality branch; what is forced is the *population*. Nothing wider about states. Nothing about the handedness choice. ***‘P15’*’s* item stays open** — what is settled is that this route to it is closed, and why *Run:* python3 receipts/P15_CR.cosmology/P15.the_chiral_state_the_route_needs_is_forced_absent_not_merely_unchosen

P15R154 P15_the_legs_closed_form_at_the_two_loci [OK]
sec:envelope (the leg’s closed form read at the two loci: at the CROSSING it is the ordinary frozen adiabatic state exactly ($\Theta_{\text{hat}} = \Psi_i/2$, $\Psi = \Psi_i$), and the coded handover’s 0.4835 Ψ_i is Ψ at horizon entry halved, which is neither locus). *Computes:* $\Psi = \Psi_i T(x)$ and $\Theta_{\text{hat}} = (\Psi_i/2) \cos x$ evaluated at the crossing, at entry and at the seam over $k/k_s = 1$ to 300; Θ_0 ’s own driven equation integrated directly as an independent check, with the residual measured to scale as 0.399×0 *Bound:* asserts the arithmetic of three candidate amplitudes and where each comes from; says nothing about which is right for the locus the instrument imposes it at, and nothing about the spectrum *Run:* python3 receipts/P15_CR.cosmology/P15.the_legs_closed_form_at_the_two_loci.py

P15R155 P15_the_handover_at_the_crossing_and_what_it_costs [OK]
sec:refit-bound (moving the handover from the onset to the crossing removes 71 per cent of the arm’s excess χ^2 over the control and takes P1/P2 from -20.7 to +1.5 per cent against the sky – and does not remove the rejection, 35.5 per bin against the control’s 2.10). *Computes:* reproduces *sec:refit-bound* three ways (the control’s peaks and P1/P2, the coded arm’s, both arms’ *plik_lite* χ^2 , and the sky’s own phase intercept); then the crossing arm’s comb, phase and heights, converged over two decades in ZSTART, to the ell-grid’s own resolution at LSTEP=1, and against the continuum ladder at KCONT=1 *Bound:* the rejection stands and is stated as one; the comb comes out 4.2 per cent narrow and the arm spends no fitted number; the reported LA is bookkeeping on a sound horizon the oscillator does not run on *Run:* python3 receipts/P15_CR.cosmology/P15.the_handover_at_the_crossing_and_what_it_costs.py

P15R156 P15_the_desi_dissolution_survives_the_leaf_ruler_but_only_by_moving_the_onset [OK]
sec:tensions (the DESI DR2 H0-dissolution survives the adjudicated leaf clock – 0.88 per dof, flat to two decimals from $H_0 = 70$ to 80 – but by compensation rather than cancellation, and the price is the onset: its ρ_r/ρ_m runs 51.0 down to 5.8 across that band, against the 1.7 the stacking ruler puts it at). *Computes:* reproduces the banked stacking-ruler fit (Ω_m 0.3066, z_{onset} 6764, χ^2 12.01 on 12 dof) and measures its H_0 spread as exactly zero; then the leaf ruler without the onset, which re-pins H_0 to 68.5 and breaks at 73 at 10.7 per dof; then the leaf ruler with the onset re-solved from θ_* at each H_0 ; and the acoustic angle alone as an independent determination agreeing with BAO to 0.05 in H_0 *Bound:* the conclusion survives and the argument does not – on the leaf clock H_0 is not FORCED by BAO rather than ABSENT from it; says nothing about which clock is right, and nothing about the spectrum *Run:* python3 receipts/P15_CR.cosmology/P15.the_desi_dissolution_survives_the_leaf_ruler_but_only_by_moving_the_o

P15R157 P15_the_damping-to-comb_ratio_picks_the_crossing_and_the_leaf_clock_out_of_four [OK]

sec:coherence (theta_D/theta_star separates the four handover-locus-by-clock combinations and picks exactly one – the crossing on the leaf clock, at 1.022 of the control’s ratio, against 1.135, 1.353 and 0.652 for the other three – and neither choice was made to fix this quantity). *Computes:* r_D/r_s on the corpus’s own Silk integrand with the opacity taken from RD_diffusion_direct, over all four combinations; the log-a quadrature converged to 0.006 per cent from n = 3001 to 12001; and the crossing rows re-run over a hundredfold range in the locus, moving 0.07 per cent *Bound:* the two choices are not separable – neither helps at the other’s wrong partner – so this is one configuration and not two improvements; and getting this ratio right is necessary and not sufficient, the crossing arm still being rejected at 35.5 per bin *Run:* python3 receipts/P15_CR_cosmology/P15_the_damping-to-comb_ratio_picks_the_crossing_and_the_leaf_clock_out_of_four

P15R158 P15_the_onset_bracket_family_is_latent_everywhere_and_was_live_in_one_place [OK]

sec:acoustic (the (1500, 60000) onset bracket is a family – 27 live acoustic-onset solvers and 46 retired, 18 of the live ones below the leaf ruler’s root of 61,580, which is 2.6 per cent past the ceiling – and exactly one member was ever reached, failing by a quarter of a multipole). *Computes:* both roots recomputed from the instrument’s own integrands (6761 stacking, 61,583 leaf); pi D_M/r_s at the old ceiling measured at 301.85 against the 301.6 target; the whole tree swept and every onset solver classified; and the six files a leaf-clock run actually enters checked to carry the widened ceiling *Bound:* the other 18 are LATENT and not broken – each integrates r_s on the stacking clock where the root is 6,764 – and are recorded rather than pre-emptively widened; says nothing about which ruler is right *Run:* python3 receipts/P15_CR_cosmology/P15_the_onset_bracket_family_is_latent_everywhere

P15R159 P15_the_third_peak_deficit_is_radiation_driving_and_both_routes_to_the_equality_agree [OK]

sec:envelope (P1/P3 tracks the leaf equality and not the route to it – 2.299 against 2.294 at z_eq 3447 and 2.474 against 2.460 at 3000, across a 12 to 24 per cent change in Omega_m and therefore in D_M and the whole projection – so the third-peak deficit is radiation driving, and the arm’s own equality is the residual). *Computes:* the crossing handover at z_eq 3936, 3447 and 3000 reached twice over, through Omega_r at fixed Omega_m and through Omega_m at fixed Omega_r; P1/P3 compared across the routes; the radiation route verified to move neither r_s nor D_M and the matter route verified to move both; and at 3447 the four peaks, the fitted comb and the acoustic phase against the sky’s *Bound:* a diagnosis and not a fit – 3447 is LCDM’s value and not a freedom this arm has, the arm is still rejected at 4.86 per bin against the control’s 2.10, and the scan is not monotone, so it measures where the equality should be and gives no direction to push it *Run:* python3 receipts/P15_CR_cosmology/P15_the_third_peak_deficit_is_radiation_driving_and_both_routes_to_the_equality

P15R160 P15_the_envelope_turnover_is_stated_on_a_third_equality_and_the_leaf_background_moves_it [OK]

sec:envelope (the driving envelope’s turnover is placed at equality and equality is then put at $(1+z_{\text{onset}})/2 = 3399$, “essentially flat LCDM’s” – but the leaf background the driving is integrated on has equality 3936, 14.2 per cent from the control and 15.8 per cent from the paper’s own figure, so the claim that the turnover wavenumber matches LCDM’s is carried by whichever of the two is meant). *Computes:* the paper’s 3399 reproduced from its own arithmetic; k_eq computed from each background directly as a_eq H(a_eq)/c rather than from the matter-domination closed form; the projection measured to cancel roughly half of it, k_eq +14.2 per cent against ell_eq +7.1 per cent; and the self-consistent point (68.60, 0.2973) shown to put the leaf equality at 3370, 2.2 per cent from the control, with nothing fitted to reach it *Bound:* does NOT claim the turnover sits at equality – that is the paper’s premise, taken as given – and does not claim the envelope argument fails, its conclusion resting on the closed form and not on this number; the 6797 is backed out of the paper’s 3399 and is 0.5 per cent off the 6761 the instrument solves, which is noted and not chased; routed to the chat seat, whose file CR_cosmology.tex is *Run:* python3 receipts/P15_CR_cosmology/P15_the_envelope_turnover_is_stated_on_a_third_equality_and_the_leaf_background

P15R161 P15_the_damping_signature_error_budget_and_the_convention_dominates_it [OK]

sec:coherence (the crossing arm’s damping signature has a cosmological parameter budget of 0.02 points and an endpoint budget of 3.10 – moving r_D’s upper limit from recombination to the computed visibility peak, 0.36 per cent away in redshift, takes it from +2.21 to -0.89 per cent, straddling zero – so it is not a few-per-cent observable with an error bar and must

be quoted with its endpoint named). *Computes:* the visibility peak located from the computed visibility rather than assumed; UNC_error_budget's own excursion list (H0, Om, omega_b, z_rec) propagated one at a time and summed in quadrature and linearly; the endpoint term measured beside them; the clock and locus terms kept apart as configuration rather than uncertainty; and the four-way ranking re-derived through a second code path and shown to survive both endpoints *Bound:* explains rather than resolves the +3.1 against +2.2 disagreement between the instrument's header and the standalone integration – neither was wrong and the gap is this sensitivity; does not claim the ranking is endpoint-dependent, which is checked and is not; UNC_error_budget carries no such term and that is not an omission in it, one endpoint having been quoted throughout on the configuration it was written for *Run:* python3 receipts/P15_CR.cosmology/P15.the_damping_signature_error_budget_and_the_convention_dominates.it.p

P15R162 P15_at_its_own_preferred_H0_the_crossing_arm_predicts_the_acoustic_comb_with_no_fitted_number [OK]

sec:refit-bound (at the (H0, Om) = (68.60, 0.2973) its own leaf ruler's DESI fit returns, the crossing arm with no pin puts the fitted acoustic comb at 298.0 against the sky's 298.4 – 0.15 per cent, as an output – with P1/P2 = 2.264 against 2.217, P1/P3 = 2.298 against 2.277, gap ratios 0.8861 and 1.1286 against 0.8812 and 1.0966, and the 700-1000 band falling from 85.9 to 4.2 per bin; chi2 is 4.19 per bin against the control's 2.10). *Computes:* the comb fitted by sec:intro's own procedure and checked sub-per-cent against the sky; the reported ruler and the fitted comb checked to agree to 1.6 per cent where at H0 = 73 they were 172.8 against 286.0; heights and both gap ratios gated against the sky; every band gated within a factor four of the control; and both instrument paths reported, the comb verified path-independent *Bound:* still rejected against LCDM at a factor 2.0, stated as the result and not as a caveat; H0 and Om ARE fitted, to BAO and the acoustic angle rather than to TT, so the cosmology is not parameter-free and only the spectrum is out-of-sample; the acoustic phase remains 2.3 per cent out and is now the only surviving position error; the height result is polarisation-path specific; and the configuration is the 133-bin unlensed one at LMAXL = 1300, not the 185-bin lensed comparison *Run:* python3 receipts/P15_CR.cosmology/P15.at_its_own_preferred_H0_the_crossing_arm_predicts_the_acoustic_comb_w

P15R163 P15_the_full_range_lensed_comparison_is_the_unfavourable_one_and_the_control_is_nearly_camb [OK]

sec:refit-bound (on the 185-bin full-range lensed configuration – the one the corpus's own chi2 values are quoted on – the crossing arm at (68.60, 0.2973) sits at 2.98 per bin against the control's 1.16, a ratio of 2.57, which is WORSE than the 1.98 the 133-bin unlensed comparison showed, because lensing is worth proportionally more to the control). *Computes:* the bin count asserted at 185 over ell 100-1996 rather than taken on the configuration's name; the arm and control checked to cover the same bins; the lensing operator checked against P15_derived_lensing_on_the_lcdm_arm PART C's +6.5 per cent at ell 1900, returning 1.0666, so it is the full operator and not the first-order kernel; both arms checked to fall under lensing; and the ratio gated against being the more favourable one *Bound:* states both comparisons so neither can be picked for being the kinder; and withdraws, rather than relies on, the caveat raised at cc66.9 that the control might carry ~700 of transfer inaccuracy – this control is within 13 per cent of CAMB unlensed and 15 per cent lensed, where the c54.178 control was 2.1 times CAMB's, so the ratio is a statement about the arm and not about the instrument *Run:* python3 receipts/P15_CR.cosmology/P15.the_full_range_lensed_comparison_is_the_unfav

P15R164 P15_the_anomalous_driving_belonged_to_the_pin_and_not_to_the_construction [OK]

sec:refit-bound (the driving subtraction on the adjudicated arm is 0.96 times the control's, where the pinned arm the paragraph carries was 2.48 times – so the anomalous driving belonged to the pin and not to the construction – and the two instrument paths agree to four decimals, unlike the heights). *Computes:* the first peak located driven and undriven on both paths and on a control run here rather than quoted; the driven and undriven runs checked to report the same lA; the ratio gated against parity and against the paper's 2.4 for the pinned arm; the two paths checked to agree; and the two-multipole difference from the quoted control priced as one grid step at LSTEP=2 *Bound:* states the convention explicitly – ell_1 over the REPORTED lA and not over the fitted comb, which differ by 0.7329 against 0.7450 on this arm – and does not claim a smaller driving shift is evidence the arm is right, only that it removes a discrepancy; the 2.3 per cent phase residual is untouched *Run:* python3 receipts/P15_CR.cosmology/P15.the_anomalous_driving_belonged_to_the_pin_and_no

P15R165 P15_the_crossing_spectrum_reproduces_on_a_second_instrument_and_the_172_is_the_radiation_free. [OK]

The crossing configuration's spectrum on a SECOND implementation: node 66's code seat integrated it on the polarisation path over 133 bins, and 'PO-10's row routed the full-spectrum run away from this seat at 'r6772+66.36' — so what is left to ask is whether an independent integration on a different path, a different wavenumber grid and a different bin range returns the same spectrum (**It does, and the agreement is the result rather than any χ^2 .) Hierarchy path, 185 covered bins, ℓ 100–1996, one fitted amplitude, at $(68.62, 0.2973)$ with the arm's own handover datum: peaks $220/540/820/1132$ against node 66's $222/538/818/1134$, heights $2.273/2.319$ against $2.264/2.298$, the 700 – 1000 band 4.02 per bin against 4.23 — ***within one grid step on every peak, within one per cent on the heights, neither seat knowing the other had run it*** **and node 66's fourth-peak excess reproduces at 1132 against 1123.9 , which makes it the spectrum's and not either implementation's** against the configuration this replaces, on the same instrument and bins: $\chi^2 = 1205.4$ where the pinned arm gives 51817.0 and the control 1320.5 , with positions -0.3% to $+0.4\%$ to $+1.3\%$ where the deficit stood at 7.5% — the first two peaks inside one grid step and ***the third at 1.28 steps and not inside it***). *Computes:* C1 the banked pair reproduced on this scorer first (1320.5 and 51817.0) before any new number was read **W1 the substituted-datum control, which reversed a reading of mine**: the first run carried 'CRIC=branchpoint', the control's super-horizon datum, and repeating it with the arm's own datum left the positions and χ^2 alone (1191.0 to 1205.4) while ***moving the heights $2.152/2.168$ to $2.273/2.319$ *** — so "the heights did not come in" was the substitution's artefact and is withdrawn the amplitude is not doing the work either: the crossing arm wants the **control's** amplitude to 0.04% where the pinned arm wanted one 8% away three spectra banked with their exact commands in 'spectra/README.md' *Bound:* **NOT a preference over Λ CDM**: -115.1 against F_{25} 's floor of $+1114.1$, a tenth of it, and this control carries its own truncation error ('c54.186') — ***the papers quote node 66's lensed 2.57 times and this receipt quotes nothing against it***, 'PO-7' protected exactly there **NOT the discreteness control**, which is named and in flight rather than omitted: at the run's own 'NK=600' a continuum grid gives 2.8 points per Bessel period and ***the instrument refuses to run***, clearing the guard taking 'NK=900' and 2700 modes against the ladder's 1452 — until it lands what stands against aliasing is node 66's independent grid, which is weaker for that question and is stated as weaker **NOT a discrepancy with the body's comb**: the paper's answer is the **leaf**, so $\ell_A = 172.3$ is the radiation-free ruler and a different object — that reading of mine is withdrawn here and the heights are the **path's**, the line-of-sight path overshooting at $2.543/3.264$ *Run:* python3 receipts/P15_CR.cosmology/P15_the_crossing_spectrum_reproduces_on_a_second_instrument_and_the_172.i

P15R166 P15_the_refit_leaves_the_background_where_the_distances_put_it_and_does_not_close_the_phase [OK]

sec:refit-bound (the parameter refit: given four free parameters the crossing arm moves H_0 by 0.011 per cent and Ω_m by 0.20 per cent, so the background the baryon-acoustic data fix is the background the spectrum wants – and freedom does NOT close the two residuals, the acoustic phase going 2.3 to 4.5 per cent out and the fourth peak 0.9 to 0.7, so both are properties of the construction rather than background choices). *Computes:* a measured response rather than a search – 18 runs giving gradient and diagonal curvature per arm, the amplitude closed-form; the minimum VERIFIED by real runs at the best-fit parameters, predicted 118.2 and 170.6 against measured 118.3 and 171.1; every parameter flatness-tested against a one-step excursion, all four constrained on both arms; and the bin count checked at 132 *Bound:* the range is 132 bins, ℓ 100–1287, not the 185 first asked for, so ω_b and n_s are the loosest numbers; τ is not a free direction at all, being exactly degenerate with the amplitude where no reionisation is modelled; and the arm is still disfavoured at 1.45 times the control, stated as the result rather than a caveat *Run:* python3 receipts/P15_CR.cosmology/P15_the_refit_leaves_the_background_where_the_distances_put_it_and_does_n

P15R167 P15_the_signature_collapses_at_the_adjudicated_ratio_and_the_endpoint_sets_its_sign [OK]

sec:diffusion-scale (at the adjudicated ratio the diffusion-scale signature costs 12.6 and 1.7 in χ^2 over 185 bins – under a tenth per bin on either endpoint – and a tilt of -0.0093 or $+0.0034$ absorbs seven tenths of that, against 159.9 and -0.0341 at the 1.082 every quantitative leg of the row was computed at; and the two r_D endpoints disagree in SIGN, not only in size). *Computes:* the ratio re-measured at the adjudicated background on both endpoints, 0.10 and 0.07 points from the 1.022 and 0.991 the row carries; the joint amplitude-and-tilt fit on the arm's

own 185-bin spectrum with the window asserted at ℓ 100-1996 and the tilt's uncertainty propagated through the fit's own parameter covariance; the tilt's running with the window measured at 5.80 against the 5.54 the $(l_{\max}/l_{\min})^2$ result predicts; the r^2 -1 scaling on which the whole re-pricing rests checked to 2 per cent in the tilt and 8 per cent in the χ^2 ; the base and the lensing each shown to move nothing; the fitter controlled on injected tilts; and the endpoint settlement measured – the instrument needing no surgery to terminate both integrals at one epoch, and the corpus's +2.2 per cent being the COMMON reading at recombination rather than the mixed one the ruling describes, which measures 1.02830 *Bound:* the endpoint was settled by the chat seat at r6797 AFTER this run – both lengths to the visibility peak – so the ruled reading is 0.99179, -0.82 per cent at the adjudicated background rather than the -0.9 per cent the ruling quotes, which is that reading at the $H_0 = 73.00$ background; the recombination row is kept as what the corpus carried and not as an open alternative; the structural results are carried from C62 and not re-derived; and nothing here says the arm fits, the refit leaving it at 1.30 per bin against the control's 0.90 and the full-range lensed comparison at 2.57 times *Run:* python3 receipts/P15_CR.cosmology/P15.the.signature.collapses.at.the.adjudicated.ratio.and.the.endpoint.set

P15R168 P15_the_low_multipole_floor_moves_with_no_background_and_the_factor_two_is_the_late_isw [OK]

sec:largescale (on the adjudicated background the low-multipole floor does not move – r_0 shifts 0.26 per cent and the lowest mode lands at $l_2 = 7.81$ against 7.74 – and the two Boltzmann arms still disagree, by a factor 2.02 at $l = 4$ and 1.73 at $l = 3$, WIDER than the control's 1.84; and the disagreement is located in the LATE ISW, which the photon-hierarchy arm does not have and cannot be made to have). *Computes:* r_0 computed from the paper's own parameter-free formula and asserted to reproduce its 5064 Mpc before being used; both arms given ONE r_0 , the banked run's 2.75/D_M ladder re-run separately so the 4.8 per cent that correction costs is measured rather than waved at; each arm validated on the control background against what is banked before either is moved; the geometry ruled out by measurement, 1 per cent in r_0 buying 3.5 per cent at $l = 4$ against a 102 per cent gap; the late-ISW diagnosis tested by pushing the line-of-sight cut from $z = 53.5$ to $z = 15$ and finding $l = 3$ and $l = 4$ move towards the CAMB arm; and the hierarchy shown non-finite past z about 10 under the defaults and under two refinements of the step count and the freeze threshold, so it is not a step-size failure *Bound:* which arm is right is NOT settled – carrying the late ISW is a reason to prefer the CAMB arm AT THESE MULTIPOLES and not a general verdict, the hierarchy existing because the fluid-plus-envelope treatment fails at high l ; and node 66's part (b), the floor scored against the sky, is NOT attempted because its stated condition – that the two paths can be brought together – is not met, the fix being a named instrument build (the post-recombination source carried with the photon hierarchy decoupled) rather than a knob *Run:* python3 receipts/P15_CR.cosmology/P15.the_low_multipole_floor_moves_with_no_background_and.the_fact

P15R169 P15_the_full_range_refit_holds_the_background_and_the_phase_residual_was_quantised [OK]

sec:refit-bound (the 185-bin full-range refit: with the damping tail inside the fit the crossing arm's background stays pinned – H_0 moves 0.028 per cent and Ω_m 0.031 per cent, so Ω_m is held six times tighter than on 132 bins and H_0 twice as loosely, both inside a thirtieth of a per cent – and cc66.18's phase residual of 4.5 per cent is WITHDRAWN as quantisation, the control having returned the same number). *Computes:* the minimum located on a measured response (18 runs, gradient and diagonal curvature per arm, amplitude closed-form) and then VERIFIED by real LMAXL=2000 runs at the best-fit parameters, predicted 185.1 and 292.5 against measured 186.5 and 292.4; every parameter flatness-tested, all four constrained on both arms; the bin count asserted at 185; and the peak locator's own resolution measured against a banked LSTEP=1 spectrum BEFORE use – the raw locator errs by 3.1 in ℓ at the grid the refit runs on and the parabolic refinement by 0.13 *Bound:* the arm is still disfavoured at 1.57 times the control at the verified minimum, stated as the result rather than a caveat; τ is not a direction of the fit at all, being exactly degenerate with the amplitude where no reionisation is modelled; and the refined phase residual, 3.4 per cent against the control's 1.6, changes the numbers cc66.18 landed while leaving its verdict – freedom does not close the phase – standing *Run:* python3 receipts/P15_CR.cosmology/P15.the_full_range_refit_holds_the_background_and.the_phase_residual.was

P15R170 P15_the_low_multipole_depth_gap_closes_and_two_defects_were_cancelling [OK]

sec:largescale (the low-multipole depth gap CLOSES: the two Boltzmann treatments agree to 3 per cent across $\ell = 2$ -8 where the corpus carries a factor 2.02 at $\ell = 4$, and the factor of two was

TWO defects in the photon-hierarchy arm that were partly cancelling – a line-of-sight cut at $z = 53.5$ that omitted the late ISW, biasing the ratio down, and a continuum integral truncated at $0.5 k_2$, biasing it up; the confrontation with cosmic variance carried then returns a wash, $\Delta(-2 \ln L) = +1.58$). *Computes:* the withdrawal measured rather than argued – the undecoupled hierarchy runs to $a = 1$ finite once the opacity grid’s resolution is held fixed as the cut moves, so the blocker was never the $LG = 12$ truncation; the continuum’s low- k reach converged to 1 per cent at $0.1 k_2$ and shown to move $\ell = 2$ by tens of per cent at 0.5 ; the two defects shown to OPPOSE, the continuum fix alone widening the gap past a factor 3; both arms on both backgrounds with the decoupled build and the module’s own per-mode freeze agreeing to 4 per cent; convergence in the late step count and the opacity grid to 0.1 per cent; and the likelihood the exact scaled χ^2 with $2l+1$ degrees of freedom, so the sky’s own scatter is carried rather than bolted on *Bound:* it does NOT say the low-multipole sector discriminates – it does not, and that is now a measurement rather than an open question; two claims of this line are withdrawn with it, the $LG = 12$ mechanism and the arm-B quartet $0.4974/0.2326/0.1933/0.6186$; and nothing here touches the acoustic range, where the hierarchy exists because the fluid-plus-envelope treatment fails *Run:* python3 receipts/P15_CR.cosmology/P15.the_low_multipole_depth_gap_closes_and_two_defects_were_cancelling.py

P15R171 P15_there_is_no_phase_residual_and_the_fourth_peak_is_not_the_damping_envelope [OK]
sec:refit-bound (there is no acoustic phase residual: measured against a sky whose peaks are located by the SAME procedure, with the locator’s own spread as the uncertainty, this arm’s ϕ/π sits 1.0 sigma from the sky on the three-peak fit and 0.0 on the four-peak fit, and 1.6 and 0.6 sigma from the control – and the fourth peak is NOT the damping envelope, forcing the arm’s damping to the control’s moving it 0.13 in ℓ against an offset of 1.95). *Computes:* one locator applied identically to the sky and both arms – bin to plik_lite’s bins, convert to D.1, spline, parabola over a window – with the window swept over seven values so the locator’s own spread is the uncertainty the comparison carries; the locator first shown to reproduce sec:intro’s own sky quartet, with the second peak identified as the hardest and its spread the largest; the three procedure mismatches in the earlier reading priced one at a time; the damping test validated by its inverse, imposing the arm’s envelope on the control and getting an equal and opposite shift; and the residual decomposed against the arm’s own comb width, which accounts for about half of peaks three and four *Bound:* the per-cent offset does NOT shrink under the matched procedure – 3.4 becomes 4.2 – so what dissolves the residual is the sky’s own uncertainty and not the central value, and the receipt says so rather than the other way round; the three leftovers after the comb-width term are 1.4, 0.6 and 1.0 in ℓ , the same sign and order but not a clean constant, and a finer statement is not available at these locating spreads; order (3), the neutrino sector, is NOT run because the order made it conditional on a uniform phase offset surviving and none does; and nothing here says the arm fits, the verified refit leaving it at 1.58 per bin against 1.01 *Run:* python3 receipts/P15_CR.cosmology/P15_there_is_no_phase_residual_and_the_fourth_peak_is_not_the_damping_envelope.py

P15R172 P15_three_quarters_of_the_arms_residual_is_the_controls_and_what_is_left_is_position_not_amplitude [OK]
‘PO-47’s successor and the acoustic figure; ‘sec:refit-bound’ (**THREE QUARTERS OF THE ARM’S RESIDUAL IS THE CONTROL’S, AND WHAT IS LEFT IS POSITION RATHER THAN AMPLITUDE — BUT IT IS UNDER TWO PER CENT OF THE MISFIT.** Whitenes against the full bandpower covariance the two residual vectors sit at cosine $+0.855$, and 73.1% of the arm’s χ^2 lies along the control’s own direction***, projecting out to leave 76.2% of 283.0 — stable at $72.5\% - 73.7\%$ across three bin cuts. **WITHDRAWN AT ‘r6881+cc66.34’ — the inference, not the number.** *This row read the 73.1% as attribution. Both arms are fitted to the same data, so $r_{\text{CR}} = r_{\text{ctl}} + (m_{\text{CR}} - m_{\text{ctl}})$ exactly and the statistic ranks MODEL SIMILARITY: a control deliberately tilted by $\delta n_s = +0.02$, at $\chi^2 = 214.6$, scores 82.2% — higher than the arm. **The corrected reading points the other way: the control already fits at $0.994/\text{bin}$, so the arm’s $+105.1$ excess is the construction’s.** Everything else in this row stands. $\Rightarrow$ *Of the rest, one further parameter at a time.* **peak-position rescale $\epsilon = -7.5 \times 10^{-4}$, $\Delta \chi^2 = +4.68$ **, damping-shape $+1.36$; **tilt $+0.09$ ** — and on the control the position direction buys $+0.00$ while the damping buys $+0.30$. ***So position is the construction’s and the tilt is exhausted*** (the refit spent it: $\delta n_s = +0.01$ **costs** $+11.2$). **But ϵ is 0.8 multipoles at the fourth peak — consistent with the $+2.0$ at ‘r6875+cc66.32’ — and 4.7% of 283 is 1.7% : amplitude, tilt, damping and position together do NOT account

for the shape rejection, and this receipt does not say what does. *And the quick render's band means were about three times these: the swing's shape reproduces (band 4 high, band 5 low, on both arms) and its amplitude does not — fitting the amplitude on diagonal errors rather than the covariance puts the arm 0.83% high and roughly doubles band 4, about half the difference*). *Computes:* the banked refit spectra reproducing the refit's own χ^2 (\$186.51\$ and \$292.42\$ over \$185\$ bins) before anything is read off them; band means in sixths three ways (covariance amplitude with diagonal σ , whitened, and diagonal amplitude) with the rms growing 0.78 to 1.39; the whitened cosine, shared fraction and residue at three bin cuts; the three single-parameter scans on both arms; and every headline number the figure plots recomputed independently and gated against 'cc66_fig_acoustic_numbers.npz' to seven figures, so figure and receipt cannot drift — 13 gates *Bound:* no mechanism is offered for the bulk of the misfit — four directions are excluded as the whole of it and none is put in their place; "the transfer's" is the order's phrase for not construction-specific and is not a claim about the implementation; the refit minima are 'r6825+cc66.25's and are used as banked; the low-multipole floor's score is 'r6831's and untouched; whitening mixes bins, so a whitened band mean is a mean over a rotated basis and is reported beside the diagonal one rather than instead of it *Run:* python3 receipts/P15_CR_cosmology/P15_three_quarters_of_the_arms_residual_is_the_controls_and_what_is_left...

P15R173 P15_the_shared_fraction_does_not_mean_what_i_said_and_the_peak_trough_pattern_is_the_arms_alone [OK]

node 66's work order 'r6881', 'sec:refit-bound', continuing 'r6879+cc66.33': four properties of the acoustic residual measured by the chat seat *on diagonal errors*, with the burden stated at the outset — *all wanting the full covariance behind them* — and the four offered *to be overturned*, closing on *what sets the 1.3% and on if the ratio is not 1.3% on the full covariance, say so plainly* (*THE SHARED FRACTION NEVER MEANT WHAT I SAID IT MEANT, AND THE THREE-QUARTERS SENTENCE IS WITHDRAWN.* Both arms are fitted to the SAME data, so $r_{\text{CR}} = r_{\text{ctl}} + (m_{\text{CR}} - m_{\text{ctl}})$ exactly (verified to 8.9×10^{-16}) — the two residuals share the d term by construction, so a "fraction along the control's direction" measures how alike the two MODELS are and cannot attribute a misfit. The control the statistic needed and never got: a flat- Λ CDM control deliberately tilted by $\delta n_s = +0.02$ — a model nobody believes, at $\chi^2 = 214.6$ — scores 82.2% shared, HIGHER than the arm's 73.1% , and the score falls away with the tilt (82% to 43% to 16%), which is the signature of a similarity measure. $\Rightarrow$ And the corrected reading points the OTHER WAY: the control already fits at 0.994% /bin, so there is no shared defect for the arm to be an amplification OF; the arm exceeds it by $+105.1$ and $m_{\text{CR}} - m_{\text{ctl}}$ alone carries 77.3% of that — *the excess is the construction's*. And of the order's four diagnostics, *three do not survive on the control*: (1) the peak/trough pattern is the ARM'S ALONE — control $+0.03/-0.06\%$ (diag) and $+0.03/-0.07\%$ (whitened) against the order's $+0.57/-0.67\%$, arm $+0.36/-0.51\%$ and $+0.42/-0.52\%$ — *so the composite, that BOTH arms show it says the bulk belongs to the transfer*, *fails at its premise*; (3) both do grow with ℓ and the first third matches (0.67%), but the control's last third is 0.88% and not 1.46% ; (4) the $\ell \gtrsim 1000$ trough is the arm's — control $+0.06\%$ where the order has -1.56% . $\Rightarrow$ *WHAT DOES REPRODUCE IS THE RMS RATIO*, 1.357% against the quoted 1.34% (1.261% whitened) — and the order's closing question has a plain answer: nothing amplifies anything. $r_{\text{ctl}} \text{ rvert} = 13.34\%$, $m_{\text{CR}} - m_{\text{ctl}} \text{ rvert} = 8.79\%$, $r_{\text{CR}} \text{ rvert} = 16.82\%$ — *the factor of 1.3% IS the model difference's own size*, 77.3% in χ^2 . *What does NOT reproduce alongside it is the correlation:* 0.837% , not 0.96% , so "the same series scaled" is too strong even before the objection to what that would mean). *Computes:* the algebraic identity proved on the actual fitted vectors before any statistic is read off them; both arms rescored from the banked refit spectra; *FOUR CONTROLS* built to break the statistic and they do — flat Λ CDM tilted by $\delta n_s = +0.02, +0.05, +0.10, -0.05\%$, the first scoring above the arm and the rest falling away monotonically; each of the four diagnostics computed *twice*, once on a diagonal amplitude and once whitened against 'COV_TT', with the order's own quoted value printed beside every one; the peak/trough split taken from the sign of the CONTROL's binned $\mathcal{D}_{\ell}$ curvature for *both* arms so the two are sorted by the same partition — 14 gates *Bound:* *WITHDRAWING "IT IS THE TRANSFER'S" IS NOT SHOWING THE TRANSFER IS INNOCENT* — no statistic here separates a transfer defect from

a cosmology difference and none is offered; what is established is that the shared fraction was never that statistic ****no mechanism is added**** — ‘cc66.33’ excluded four directions and this excludes none further the rest of ‘cc66.33’ stands: the band means, the three single-parameter scans and the figure are untouched, and it is the attribution sentence alone that is struck the diagnostics are computed on this tree’s \$179\$ scored bins over $\ell \leq 1900$, which is the figure’s own cut and not the order’s; a different cut moves the third decimal and no verdict using each arm’s own curvature for the split is not run, and is named rather than done *Run: python3 receipts/P15_CR_cosmology/P15_the_shared_fraction_does_not_mean_what_i_said_and_the_peak_trough_pat*

P15R174 *P15_the_model_difference_is_an_acoustic_contrast_difference_and_it_is_not_one_skys_luck*
[OK]

node 66’s work order ‘r6885’, ‘sec:refit-bound’, continuing ‘r6881+cc66.34’: ****take the sky’s noise realisation out**** — every number in the sector so far compares each arm *to the sky*, and the control fits at \$0.994\$/bin, so the control’s residual essentially IS the noise. Four asks: the coefficient hiding inside the 73% , the exact three-term decomposition, Δ ’s shape ****because it is smooth and readable where a residual is not****, and a short list of four mechanisms — ****match, do not fit ... a negative is worth more than a match reached by adjusting one of them**** (****THE MODEL DIFFERENCE IS AN ACOUSTIC *CONTRAST* DIFFERENCE, AND THE REJECTION IS NOT ONE SKY’S LUCK.**** $\chi^2_{\text{arm}} = \chi^2_{\text{ctl}} + 2\angle r_{\text{ctl}}, \Delta\angle + \text{IVert}\Delta\text{rVert}^2$ exactly: $282.96 = 177.88 + 27.82 + 77.26$, so **** $\text{IVert}\Delta\text{rVert}^2$ carries 74% of the excess and the cross term 26% **** — the order’s conditional does not fire. ****Set the cross term to its expectation of zero and the arm still scores 256.3 , $\mathbf{1.43}$ per bin on a TYPICAL sky**** against the control’s \$0.994\$. ***And the 1.15 is 1.078 : the order’s coefficient multiplies the WHITENED cosine 0.855 by the DIAGONAL rms ratio 1.34 ; consistently it is 1.078 whitened or 1.137 diagonal.*** $\Rightarrow$ ****More than that, $b-1$ IS $\angle\Delta, r_{\text{ctl}}\angle/\text{IVert} r_{\text{ctl}}\text{rVert}^2$ — the “amplification along the noise direction” and the cross term are ONE NUMBER seen twice — and against its own sky-random null it is 1.078 ± 0.049 , $\mathbf{+1.58\sigma}$ ****, stable at $\pm 1.07\sigma$ to $\pm 1.58\sigma$ across four bin cuts: ***a 1.6σ departure from 1.00 is what noise looks like, so there is no amplification for the order’s two candidate explanations of it to act on.*** $\Rightarrow$ ****AND WHAT Δ IS:**** it is ****trough-dominated**** — $+0.011\sigma$ at the peaks against -0.760 at the troughs, so ***the two arms agree where the peaks are and differ between them*** — and split about a smooth envelope the ****oscillatory part carries 67 – 75 of the 77.3 ****, peak-high and trough-low ($+0.389/-0.420$), antisymmetric about the envelope and not about each peak. *****That is a CONTRAST, not a phase and not an envelope: the arm’s acoustic oscillation is 1.040 times the control’s about its own envelope.***** One direction built from the CONTROL alone — raise the oscillation at fixed envelope, no run and nothing fitted — carries **** 51% of $\text{IVert}\Delta\text{rVert}^2$ **** (46 – 51% across a factor two in its one window), and with position, tilt and damping the span reaches 66.8% against **** 5.7% for the whole of ‘cc66.33’’s four-parameter family**** — ***which is what “amplitude, tilt, damping and position together do not account for the shape rejection” was pointing at: the family was missing a direction and the direction has a name.*** $\Rightarrow$ ****THE SHORT LIST GIVES THE NEGATIVE THE ORDER SAID IT WOULD RATHER HAVE.**** The handover amplitude (0.4835 against 0.5) is ****excluded EXACTLY and without a run**** — the instrument sets $\hat{\Theta}_k$ independently, so the single fitted amplitude absorbs it and χ^2 moves by 9×10^{-13} . Switching each of the other three off on ****both**** arms leaves 93.7% (neutrino depth LN_{12-24}), 92.8% (early ISW) and 87.6% (the driving’s continuity half) of $\text{IVert}\Delta\text{rVert}^2$; the driving’s ****Euler**** half takes it to 68.3% but at cosine -0.16 , so *** Δ is REPLACED rather than reduced and the 32% is a norm and not a share***. *****Not one of them removes the contrast***** (1.038 – 1.044 against 1.040). $\Rightarrow$ ****AND A FIFTH, WHICH THE SHAPE NAMES BY ITSELF AND WHICH THE INSTRUMENT’S OWN DOCSTRING ALREADY DESCRIBES****: a mis-weighted Doppler term ****fills the troughs at high multipole ... while leaving the FIRST peak’s position almost alone****. ***Its knob is a **KNOB SHADOW** on the refit path — ‘_SWSRC’ and ‘_DPSRC’ are read only inside ‘los_spectrum’, ‘HIER=1’ does not take that path, and ‘DPSRC=0’ at the refit configuration returns a **BIT-IDENTICAL** spectrum on both arms.*** $\Rightarrow$ Tested where the knob reaches: ****removing the Doppler dipole nearly doubles each arm’s oscillation about its own envelope (to 1.85) and its shape sits at cosine 0.88 – 0.89 with the contrast di-**

rejection — the Doppler dipole IS the contrast knob $\Rightarrow$ and the MONOPOLE brackets it from the other side — ‘SWSRC=0’ $\Rightarrow$ inverts the oscillation, to -0.300 , at cosine -0.79 , so the contrast direction is the monopole-to-dipole BALANCE, which neither switch alone would have established $\Rightarrow$ AND ‘r6887’ $\Rightarrow$ SHARPENED ASK — Δ read against the three features ‘cc66.34’ proved are the arm’s own — comes back: ALL THREE ARE Δ ’S. The trough deficit (-0.760 against the control’s -0.200); the ℓ trough, where the control sits at -0.103 , the arm at -1.177 and Δ carries -1.074 , 91% of it, in 15 bins; and the growth with multipole, which Δ does monotonically (0.33 to 0.55 to 0.68) where the residuals do not — because a residual is Δ plus a noise floor of order one and the floor flattens it. ‘r6887’ also voids its own part (1); the coefficient is reported anyway because it had been run and what it shows is not the coefficient as evidence but that it IS the cross term). Computes: the three-term identity proved on the actual fitted vectors before anything is read off it, at four bin cuts; the coefficient shown to be the cross term ALGEBRAICALLY (to 3×10^{-16}) rather than numerically alongside it; the handover-amplitude exclusion done by rescaling the banked spectrum and refitting, so it is measured and not argued; the contrast direction built twice, from a polynomial envelope in $\ln \ell$ (three degrees) and from a running geometric mean over one acoustic period (four windows), with its one tunable reported over a factor two rather than chosen; the candidate test chosen to be the right one and the wrong one printed beside it — a knob’s per-arm shape can sit at cosine -0.63 with Δ and still carry none of it, because a knob that does the same thing to both arms CANCELS in the difference, so the column is $\text{IVert} \Delta \text{rVert}^2$ with the knob off; the knob shadow PROVED rather than inferred — a static check that ‘_DPSRC’ occurs once and inside ‘los_spectrum’, a bit-identical pair on the refit path, and a 62% move on the path where it is wired, which is the calibration r4558’s own note demands before any null is read off a switch; and Δ cross-checked between the two instrument paths at cosine $+0.76$ with the same contrast excess — 38 gates, four candidate pairs and three line-of-sight pairs banked at ‘spectra/r6885-’ with their commands Bound: NAMING THE SHAPE IS NOT NAMING THE MECHANISM — “the arm’s oscillation is 4% larger at fixed envelope” is a measurement, and the channel is identified rather than the cause measured: deleting the Doppler term is all-or-nothing, it leaves the arms’ contrast RATIO where it was and DOUBLES $\text{IVert} \Delta \text{rVert}^2$, so the arms differ in HOW MUCH that channel supplies and not in whether it is there 33% of $\text{IVert} \Delta \text{rVert}^2$ is unnamed by any direction here switching a driving or source term off is a LARGE excursion and not a derivative: both arms move far from their own minima, so the candidate column answers “does Δ survive this” and not “this term contributes so much of it” the LN result is a DIRECTION and not a convergence test — doubling the depth removes 6.3% and the sign says more depth removes more the line-of-sight path’s χ^2 is not comparable with the hierarchy path’s, as this tree’s own ‘spectra/README.md’ records, so only shapes and within-path ratios are read from PART 5 nothing here bears on whether the transfer or the cosmology is at fault — ‘r6881+cc66.34’ withdrew the statistic that was read that way and this adds no replacement the knob shadow is reported, NOT repaired: wiring a source term is a change to the instrument Run: python3 receipts/P15_CR.cosmology/P15_the_model_difference_is_an_acoustic_contrast_difference_and_it_is_not

P15R175 P15_the_source_decomposition_is_reachable_on_the_reporting_path_and_the_neutrinos_have_a_knob [OK]

node 66’s work order ‘r6889’, ‘sec:refit-bound’, continuing ‘r6885+cc66.35’: the knob shadow, before anything else. That receipt found ‘_SWSRC’/‘_DPSRC’ read only inside ‘los_spectrum’, so ‘HIER=1’ — the path every refit number in this sector is computed on — was blind to them. The order: “make the source decomposition reachable on the hierarchy path, or establish that it cannot be and say why,” then re-run the two bracketing tests there; and on the free-streaming phase shift, “either a knob is buildable — in which case say what it would cost — or the phase shift cannot be tested on this instrument at all” (THE SHADOW IS CLOSED, AND THE DEFAULT IS PROVED RATHER THAN ASSERTED. ‘_SWSRC’ and ‘_DPSRC’ now reach all three source constructions — ‘los_spectrum’, the hierarchy path and the low-multipole path — where they reached one; the monopole bracket is split so the switch multiplies $g(\Theta_0 + \Psi)$ and not the polarisation term that shares it. $\Rightarrow$ The unset configuration reproduces the banked spectra with $\max \text{IVert} \Delta \mathcal{D} \ell \text{rVert} = 0.0$ on BOTH arms — exactly zero, not nearly — so nothing this sector has reported moves. And that took a second attempt, which is on the record: written ‘_SWSRC * g_ * ($\Theta_0 + \Psi$)

+ $\dots$ the default sums in a different **order**, and floating-point addition is not associative — measured, 1.1×10^{-16} . Keeping the factor INSIDE the bracket makes it exact, because $x \times 1.0$ is. $\Rightarrow$ **AND THE PAIR THAT MAKES THE SHADOW A PROOF RATHER THAN A STORY**: the same switch, the same two commands, **exactly** 0.0 before the repair and $62.3\% / 61.3\%$ after — **a null and an unwired knob are indistinguishable until both halves are on the record, which is ‘r4558’s own rule and the reason this revision exists.** $\Rightarrow$ **THE TWO BRACKETING TESTS SURVIVE THE MOVE TO THE REPORTING PATH**: ‘DPSRC=0’ at cosine $\mathbf{+0.798}$ with the contrast direction (LOS: $+0.893$), taking the arm’s own oscillation to 1.828 (LOS: 1.855); ‘SWSRC=0’ at $\mathbf{-0.765}$ (LOS: -0.791), **inverting** it to -0.399 (LOS: -0.300) — **the same opposite-sign bracket, so ‘cc66.35’s reading that the contrast direction IS the monopole-to-dipole balance was not an artefact of the path it had to be measured on.** **The two deletions are not equally inert on the arms’ contrast ratio and that is reported rather than averaged: the dipole moves it by -0.0025 and the monopole by $+0.042$, and neither collapses it toward 1.000 .** $\Rightarrow$ **AND THE FREE-STREAMING PHASE SHIFT NOW HAS A KNOB** — the answer to “what would it cost” is **FOUR LINES**. **What makes a neutrino free-stream is its anisotropic stress $\sigma_{\nu} = F_2/2$, at exactly two dynamical sites (the Euler equation and Ψ ’s shear term), so ‘NUFS’ multiplies σ_{ν} and the F_2 source on both solver paths; the quadrupole’s initial condition is exactly zero, so at ‘NUFS=0’ it is never sourced, the whole $\ell \geq 2$ ladder stays zero and the sector is a perfect fluid at the SAME background density — ‘FNU’ and the density fractions untouched. $\Rightarrow$ **It moves $\mathcal{D}_{\ell}$ by $36.3\% / 37.3\%$ and pushes EVERY peak on BOTH arms to LARGER ℓ , $+9.00$ uniformly across the first four** — which is the sign the Bashinsky–Seljak pull has and the shape a **phase** shift has rather than a rescaling of the acoustic scale. **Its size is exactly one binned grid step (8.9999), so the sign and order of magnitude are established and the value is not).** *Computes:* the shadow stated as a property of the SOURCE TEXT and not of a memory — ‘DPSRC’ occurring once, inside ‘los_spectrum’, before the repair — beside the banked bit-identical pair that found it, re-gated here; the repair’s default gated at **exactly zero** on both arms and on identical multipole grids, before any other number in the receipt is read; **each newly wired switch calibrated where it was newly wired**, because ‘r4558’s own note is the rule this revision enforces and a new knob that had not been shown to move something would be the same defect landed twice; the ‘NUFS’ claim carried by three static checks rather than by assertion — four use sites, ‘y0 = np.zeros(...)’ with no assignment to the quadrupole anywhere in the file, and no ‘NUFS’ within the density-fraction block, which is what makes ‘NUFS=0’ a perfect fluid rather than a frozen state; and the peak shift gated on its **sign** and its **uniformity across the first four peaks** rather than on its size, with the size then shown to be one grid step — 22 gates, four pairs banked at ‘spectra/r6889_’ with the launcher at ‘computations/beyond.the.wall/r6889_directions/’ *Bound:* **NO MECHANISM FOR THE CONTRAST IMBALANCE** — ‘r6889’ said that boundary is right and is not moving it, and neither does this **and no VALUE for the phase shift as a result about this construction**: the knob is built and calibrated, its size is grid-limited, and pointing it at the question is the next order’s the drag half — the amplitude suppression free-streaming also causes, $36\% - 37\%$ in $\mathcal{D}_{\ell}$ — is the large effect and must not be quoted as the same number as the phase shift the low-multipole path is wired for consistency and is **not exercised** here; naming it rather than quietly leaving it is the point **no other knob is audited**: three shadows have now been found in this sector by three different routes, and nothing here says there is not a fourth *Run:* python3 receipts/P15_cosmology/P15_the_source.decomposition.is_reachable.on_the_reporting_path_and_the.m**

P15R176 P15_the_monopole_zero_point_is_not_the_channel_and_the_two_residuals_point_opposite_ways

[OK]

node 66’s work order ‘r6897’: **is the contrast excess and the alternation excess one number?** — **do not remove a term; measure a quantity both arms have**: **(a)** the value the monopole oscillation swings **about** at last scattering, in units of that arm’s own Ψ ; **(b)** what each arm’s own loading $R = 3\rho_b/4\rho_{\gamma}$ at its own visibility peak accounts for; **(c)** **from the residual alternation alone, solve for the effective ΔR that would produce it; from the residual contrast alone, solve for the effective ΔR that would produce it — do the two agree?**, the order adding that **no mechanism is being asked for and none should be claimed**, and asking for ‘ETA_LS_W’ in the header while I was in there (**THE MONOPOLE’S ZERO POINT IS NOT THE CHANNEL, AND THE SIGN IS WHAT SAYS**

SO.** On both arms the offset of $\Theta_0 + \Psi$ approaches the tight-coupling equilibrium $R\Psi$ **from below**, reaching \$0.78\$ of it on the control and \$0.76\$ on the arm at the visibility peak — *so (b)’s absolute question answers NO on both arms and by nearly the same amount, which is the approach to equilibrium and not a property of either arm: Ψ decays inside the horizon and R grows.* $\Rightarrow$ **And calibrated against a KNOWN ΔR ** — the control re-run with ω_b displaced $\pm 8\%$, the estimator tracking 77% of it, which is ‘r4558’*s* rule applied to a *measurement* rather than to a knob — ***the arm’s offset FALLS SHORT of what its own loading accounts for, by an effective ω_b of -2.9% , on top of the -2.0% its fitted ω_b already is.*** **Too much loading is what deepens troughs and raises alternation; this arm’s monopole behaves as though it had too little, and its troughs are deeper anyway.** *On the order’s own branching this is a THIRD outcome — neither “the construction supplies an R -like offset” nor “both arms sit on their own $(1+R)$ ” — and it refutes the loading reading **by sign** rather than leaving it undetermined.* $\Rightarrow$ **AND THE TWO RESIDUALS ARE NOT ONE NUMBER: THEY DIFFER BY A FACTOR OF SIXTEEN AND IN SIGN.** Against the control, the arm’s *contrast* is $+4.0\%$ and its *alternation* — the odd-even amplitude, with the envelope’s own curved decline *fitted* rather than assumed away — is about 2% **lower**. Converted through the control’s own measured responses ($\mathrm{d}(\text{contrast})/\mathrm{d}\omega_b = +7.97$ and $\mathrm{d}(\text{alternation})/\mathrm{d}\omega_b = +1.85$, both positive, so more loading gives more of both), **the contrast asks for an effective ω_b of $\mathbf{+22.9\%}$ and the alternation for $\mathbf{-1.4\%}$ **. $\Rightarrow$ **AND THE $+22.9\%$ IS A LOWER BOUND, BECAUSE THE CONTRAST RESPONSE SATURATES***:* over the whole $\pm 8\%$ range the contrast spans only 0.028 and its increments fall monotonically ($+0.0119, +0.0087, +0.0054, +0.0020$), so a straight line *overstates* what ω_b can deliver — ***a four per cent contrast excess is beyond what the baryon density reaches in this construction at any value, not merely at an implausible one.*** *And the monopole offset agrees with the alternation, at -2.9% against -1.4% : two independent measurements of the loading displacement agree and it is the contrast that stands apart.* $\Rightarrow$ **AND PART OF THAT IS A CORRECTION TO THE ORDER’S PREMISE, WHICH MIXED TWO REFERENCES***:* the alternation excess is read against the *sky* ($P_1/P_2 = 2.264$ against 2.217) and the contrast against the *control* (1.040). *Against the control, on the banked spectra, the arm’s P_1/P_2 is $\mathbf{2.141}$ against $\mathbf{2.191}$ — **lower**. *The two were never pointing the same way; the appearance that they were is the two references.* $\Rightarrow$ **ONE POSITIVE LOCALISATION, WITH ITS OWN SIGN PROBLEM STATED***:* the arm’s *dipole-to-monopole* amplitude ratio at the visibility peak is $+1.8\%$ and *grows* with wavenumber. *But the Doppler term FILLS troughs — ‘cc66.36’ measured ‘DPSRC=0’ taking the arm’s oscillation from 1.040 to 1.828 — so a larger dipole fraction makes troughs shallower, and this arm’s is larger while its troughs are deeper. It works AGAINST the contrast excess, which leaves a source larger than four per cent and partly cancelled — a statement about size, not a mechanism.* $\Rightarrow$ And the header now carries the visibility peak, its redshift, its FWHM and R there on *every* path: the two arms’ last-scattering widths side by side for the first time on the reporting path, 38.04 Mpc against 43.59). *Computes:* ‘ZPSAVE’ is new and wired into ‘hier_run’ — the *reporting* path — because ‘PHISAVE’ is one of the nine switches ‘r6893+cc66.37’ measured as OFF it, so using it would have measured the low-multipole construction and called it the reporting one; its default gated *bit-identical* on both arms before any number is read, and it saves the *undamped* monopole because the envelope multiplies the offset too; the offset estimator’s three predecessors recorded with the bias each carried (a midpoint of extrema alternating by a factor of three; a quarter-half-quarter combination leaving $\pm 15\%$ of curvature; a one-period window ill-conditioned by collinearity) and the verdict shown unchanged across five window widths; the calibration against a known ΔR carried as its own gate; the contrast statistic reproducing ‘cc66.35’*s* 1.0401 so the space is that receipt’s; the alternation’s sign shown independent of the trend degree; and both ω_b responses shown non-null and linear over the range, so neither residual is converted through a response that is not there — every long run sliced on ‘KBATCH’, which ‘r6895+cc66.38’ measured as exact to 10^{-16} \$ *Bound:* **NO MECHANISM FOR THE CONTRAST IMBALANCE** — the order says none is asked for and none is claimed *the dipole excess is NOT claimed to produce the contrast excess*, its sign being wrong for it the offset’s shortfall against $-R$ is *not* a defect of either arm: it is the same shortfall on both the ω_b response is measured on the *control* and the two arms differ in more than ω_b ,

so each implied displacement is *effective* and is called that the width story the order withdrew before sending is *not* reinstated — nothing here attacks its reasoning *Run: python3 receipts/P15_CR_cosmology/P15.the.monopole.zero.point.is.not.the.channel.and.the.two.residuals.poin*

P15R177 *P15.the.free.streaming.knob.is.common.to.both.arms.and.the.switch.sweep.finds.no.further.shadow* [OK]

*node 66's work order 'r6891', 'sec:refit-bound', continuing 'r6889+cc66.36', in two parts: **point** 'NUFS' at the question on a grid that can resolve it — "a locator on a finer ℓ grid, both arms, so the shift is measured rather than bracketed at one bin step — and the two arms' shifts compared, since a phase shift common to both is not a candidate for Δ and one that differs between them is", with "the drag half reported separately"; and **sweep** the switches, because the rate is the finding — "enumerate every environment switch this instrument reads, and for each one record which of the three source constructions and which of the two solver paths actually reads it — from the source text, not from memory — and, for every switch reachable on the reporting path, whether setting it away from its default moves the spectrum there", the order adding that **the output wanted is the table and not a repair campaign** (**THE SWEEP IS EXHAUSTIVE AND THE ANSWER IS AN ACCOUNTING, NOT A NEGATIVE.** Sixty environment switches enumerated from the source text through 'ast', each tagged with which of the three source constructions and which of the two solver right-hand sides reads it and whether that site is *written into* the construction or merely downstream of it; the reporting path declared from the dispatch's own three lines, with 'main's live prefix ending at the 'return 0' of the 'HIER' branch. **A binding** is not a **use**, and that distinction is the whole of the static half — a first pass keyed to binding sites called fifty-five of sixty live, because a module-level 'os.environ.get' executes on every path and proves nothing. $\Rightarrow$ **Fifty-one** have a live use site there; the nine that do not come back BIT-IDENTICAL on the reporting path — all eighteen runs at exactly \$0.0\$, twice over, and again at full ℓ reach where 'DAMPX' and 'RD' would have shown if they touched the damping tail. $\Rightarrow$ **AND FIFTY-FIVE SWITCHES MEASURED ON BOTH ARMS, ONE AT A TIME:** the set of runs that came back bit-identical is EXACTLY the set four readings predict — off-path, rate-identity on the control arm, the arm branch, and gated by another switch — no unexplained null, and nothing explained away that in fact moved. **The rate-identity family is the pleasing one:** 'GSRC', 'LEAFSCALES', 'PHASEONLY', 'PHASEPOW', 'STACKPERT' are bit-identically inert on the **control** and every one moves the arm, because on the control 'Hphys' and 'Hleaf' are the same expression, the Jacobian is \$1\$ and $x \times 1.0$ is exact — the same floating-point fact 'cc66.36's reassociation episode turned on. $\Rightarrow$ **TWO THINGS THE SWEEP DID TURN UP,** neither of the 'r6476' class and neither moving a reported number: **(i)** 'LRS-FROM' moves the instrument's reported r_s by a quarter ($145.38 \rightarrow 110.49$ Mpc, ℓ_A \$301.5 \rightarrow 396.8\$) and $\mathcal{D}_\ell$ by **exactly zero** — R_S and ℓ_A are **diagnostics**, reaching a 'print' and the 'SAVE' metadata and nothing else, and 'hier_run' accepts ℓ_A , D_M and r_s and **loads none of the three**; 'r6476' certified that switch on the ground that the header moved, and **the header is not the reported number** — the certification was of the wrong quantity, and no number moves; $\Rightarrow$ **and the consequence points the useful way** — because no transfer function reads ℓ_A , the printed $\ell_1/\ell_A=0.7312$ against the sky's $220.6/301.7$ is an agreement between **two independently computed quantities** and not a value fed in; **(ii)** 'LATARG', which the file calls the corpus's one fitted number, has **no root** at the arm's adjudicated background — the onset solve raises across the whole bracket 'r6760+cc66.1' had widened — which is why the refit command supplies 'ZSTART=3e7'. $\Rightarrow$ **AND THE FREE-STREAMING SHIFT IS MEASURED.** Two independent locators — a parabola vertex at each acoustic extremum and a sub-bin cross-correlation of the **envelope-normalised** oscillation — on both arms, and again at $L_{STEP}=2$, four times the multipole sampling, where they agree to better than half a multipole. **IT IS NOT UNIFORM, WHICH CORRECTS 'r6889':** band by band it RISES monotonically, \$+2.9/+5.6/+9.4/+10.9/+12.6\$ on the control and \$+3.1/+5.7/+9.3/+10.9/+12.5\$ on the arm — *the uniformity 'cc66.36' gated was the grid, and the gate was a tolerance of \$0.05\$ on integers that could only differ by a whole bin; and a pure rescaling does not fit it either, the straight line having an intercept of three multipoles.* $\Rightarrow$ **AND IT IS COMMON TO THE TWO ARMS** — largest band-by-band difference \$0.17\$ of a multipole, and in units of each arm's own ℓ_A the extremum-averaged shift agrees to 1.7×10^{-4} — so on the order's own criterion it is NOT a candidate for Δ . **And the drag half, kept apart and split in two** because it is two things: an ENVELOPE rescale of \$1.2573\$ and a peak-to-trough CONTRAST*

ratio of \$0.9875\$, the two arms agreeing to \$0.0004\$ and \$0.0006\$ — and Δ is a CONTRAST difference, so the knob's large effect is in the wrong quantity.** *In Δ 's own space the arms' 'NUFS' directions sit at cosine \$0.99918\$; their difference freely rescaled reaches \$8.7\%\$ of $I_{\text{Vert}} \Delta r_{\text{Vert}}^2$ at a *negative* coefficient, and no such freedom exists because both arms carry one neutrino sector*). *Computes:* the reporting path declared from the dispatch and gated line by line, with branch pruning only where an environment comparison settles the test so the live set OVER-counts and can only under-report a shadow; 'hier_run' gated as accepting three quantities and loading none of them; the nine off-path switches gated bit-identical at reduced AND full reach, and 'RD' at a second value so the null is not one value's accident; the accounting gated as a SET EQUALITY between observed nulls and predicted nulls, which is the only form the claim is worth anything in; the shift's non-uniformity gated on the spread exceeding the grid step and on monotonicity band by band, on two locators and two grids; the annotation of the instrument gated bit-identical on both arms because 'cc66.36' is why this seat no longer asserts that a change is nothing — 46 gates (34 at 'r6893+cc66.37'; the twelve added at 'r6895+cc66.38' are the finer grids' own and the slicing check's), the screen banked at 'spectra/r6893_switch_screen_{lcdm,cr}.npz', the fine grid at 'spectra/r6893_fine_grid.*' and the full-reach nulls at 'spectra/r6893_full_reach_nulls.lcdm.npz' *Bound:* **NO MECHANISM FOR THE CONTRAST IMBALANCE** — 'r6891' says that boundary has not moved and this does not move it *the growth of the shift with ℓ is not attributed*: separating the Bashinsky–Seljak constant from the k -dependent change in the potentials' decay that 'NUFS=0' also causes is not attempted *the sweep is of ENVIRONMENT switches*: a hard-coded literal that ought to be a switch is a different search, and 'cc66.17's 'NS' literal is the reminder the switch screen runs at $\text{LMAXL}=500$ and only the NULLS are re-run at full reach — a switch that moves is not re-measured there no pinned value of n_s , H_0 , Ω_m or ω_b *Run:* python3 receipts/P15_CR_cosmology/P15_the_free_streaming_knob_is_common_to_both_arms_and_the_switch

make_fig_acoustic_two_arm

[OK]

'r6879's figure; 'sec:refit-bound' (**THE ACOUSTIC FIGURE, BANKED AND RECEIPTED.** Two panels plus residuals: *(a)* linear in ℓ in $\mathcal{D}_\ell$, both arms at their verified \$185\$-bin refit minima through P15's own derived lensing operator, *the single amplitude fitted on the full bandpower covariance rather than diagonal errors*; *(b)* logarithmic from $\ell=2$, so the discrete closed- S^3 floor sits in the same frame as the peaks with its *minimum at $\ell=4$ rather than the quadrupole* marked — the one shape this construction predicts that the standard model does not. *Whitened residuals beneath each, both arms on one axis so the shared part is visible.* *The floor is carried by the sweep as a ratio to the flat transfer and is put back into $\mathcal{D}_\ell$ against the control's own low- ℓ spectrum — a reconstruction, named as one, there being no absolute low- ℓ bandpowers in this tree.* *And $\mathcal{D}_\ell$ rather than C_ℓ is not a presentation choice: plotted as the binned C_ℓ the likelihood ships, the peaks vanish under the falling plateau — the same trap the locator hit at 'cc66.28', here in the figure*).* *Computes:* writes 'corpus/fig_acoustic_two_arm.pdf' and banks every plotted number to 'spectra/cc66_fig_acoustic_numbers.npz', which the companion receipt recomputes and gates *Bound:* the \$1900\$ cut on the scored bins is the figure's own so the shifted-model tests share the bin set; the full \$185\$-bin χ^2 is quoted in the caption from the refit itself; no foreground or beam term beyond what 'plik_lite's covariance marginalises *Run:* python3 receipts/corpus/make_fig_acoustic_two_arm.py

P15R178 P15_the_skys_own_fourth_peak_cannot_tell_the_arms_apart_and_the_displacement_is_shared_with_th [OK]

'PO-47'; 'sec:intro's locator, continuing 'r6835+cc66.28' (**THE STOPPING RULE FIRES — AND THE SPREAD THAT FIRES IT IS NOT THE ONE 'cc66.28' QUOTED.** That receipt gave the sky's fourth peak as \$1121.9 \pm 0.87\$, and *that \$0.87\$ is a PROCEDURE spread* — how far the answer moves as the parabola window is swept on one realisation. $\Rightarrow$ Propagating 'plik_lite's *bandpower covariance* through the identical parabola gives the sky's own uncertainty: 1121.9 ± 2.03 (statistical) ± 0.87 (procedure) ± 2.21 combined at the reference window, ± 1.57 at the tighter one. *Against that, the construction's own displacement — arm minus control, \$+2.00\$ in ℓ — is \$0.90 \sigma\$ at \$W=55\$ and \$1.27 \sigma\$ at \$W=80\$:* it does not reach significance at either admissible window, so **THE SKY CANNOT TELL THE TWO MODELS APART AT THE FOURTH PEAK.** *What is established is "not resolved" rather than "zero", and the receipt says so rather*

than smoothing it.* $\Rightarrow$ ***The three candidates are NOT run, per the order's own stopping rule.*** **AND WHAT DOES NOT DISSOLVE IS SHARED AND IS NOT THIS CONSTRUCTION'S**:

both models sit high of the located sky — the control by $\$+2.65\$$ ($\$1.2\{\}\sigma\$$) and the arm by $\$+4.65\$$ ($\$2.1\{\}\sigma\$$), $\$57\{\}\%$ of it the control's** — named and not pursued. *And the order's $\$+10.1\$$ was never this number: it is the paper's stored quartet against the paper's stored sky, two procedures; through one locator the arm-minus-sky offset is $\$+4.65\$$.* **AN INSTRUMENT TRAP IS REPORTED AS A FINDING**:

'cc66.28's locator finds peaks by free extremum search, which is right on a smooth spectrum and **unusable on a noisy one** — under the covariance it returns $\$1051\{\}\pm 132\$$ for the fourth peak, seventy multipoles off. **Error propagation through it must anchor the window**).

Computes: the sky quartet and its procedure spreads reproduced against 'cc66.28'; $\$600\$$ covariance realisations through the anchored parabola at four windows with per-peak bias and spread; the window chosen on the **bias-variance trade** ($\$W=40\$$ rejected — the parabola inverts on $\$12\{\}\%$ of realisations and $\$\{\}\sigma_4\$$ explodes to $\$122\$$; $\$W=110\$$ rejected — bias reaches $\$-6.4\$$, larger than the displacement under test); seed-independence; and the three pairings in $\$\{\}\sigma\$$ — **11 gates with TWO controls that break as they must**:

a planted displacement of $\$4\$$ and $\$10\$$ in $\$\{\}\ell\$$ recovered to $\$+4.56\$$ and $\$+11.71\$$ (so a real displacement WOULD show), and the free-search failure itself *Bound:* **not a full sky-uncertainty budget** — 'COV.TT' is the shipped bandpower covariance with foregrounds and calibration marginalised, with no beam or theory-side term added; the central value is the locator's on 'plik_lite's binning and 'sec:intro's own $\$1123.9\$$ sits two multipoles away, inside. **None of 'PO-47's three candidates is run** — the third acoustic spacing, the baryon loading's effect on position and the transfer's resolution at the fourth peak are left, a convergence check being named as where the shared offset would go. Nothing re-opens the phase intercept, the damping envelope, the driving or the refit

Run: python3 receipts/P15_CR.cosmology/P15_the_skys_own_fourth_peak_cannot_tell_the_arms_apart_and_the_displacem

P15R179 P15_the_ladders_discreteness_does_not_set_the_spectrum_and_the_check_was_run_in_pieces [OK]

The control 'r6788' declared open and node 66 asked for by name ('FOR_60' item 5): 'KCONT=1', the CR arm's discrete $\$k\$$ -ladder replaced by a continuum grid on the crossing configuration. The alias gate waives its 4-points-per-Bessel-period requirement for this arm because the ladder is physical, and the waiver's own text says that is only not aliasing if the answer does not depend on it (**It does not, and the waiver is honest here.** Ladder ($\$1452\$$ modes, $\$2.3\$$ pts/period) $\$\chi^2 = 1205.3755\$$ against continuum ($\$2700\$$ modes, $\$4.3\$$) $\$\chi^2 = 1205.3745\$$ — ***peaks identical*** at $\$220/540/820/1132\$$, heights identical to three decimals, the single fitted amplitude $\$3\$$ parts in $10^{\{8\}}$ apart, spectra agreeing to $\$6.7\{\}\times 10^{\{-8\}}\$$ of the peak **and the reason it agrees far better than $\$2.3\$$ points per period predicts is measured rather than guessed**:

$\$\sqrt{L(L+2)}\{\}$ to $L+1\$$, so the "discrete ladder" is asymptotically *uniform* — within $\$1\{\}\%$ of its median spacing over $\$99.9\{\}\%$ of its gaps — making this a comparison of two near-uniform samplings differing in spacing, not of resolved against aliased **run in six slices, because neither seat's container survives it whole**:

the check costs $\$2700\$$ modes against the run's $\$1452\$$, mine was killed three times and 'cc66' restarts every $\$1\$$ – $\$15\$$ min).

Computes: C1 **the segmentation proved exact before anything was read through it** — a whole run against three slices summed, $\$\max\{\}\lvert\{\rm sum\}-\{\rm whole\}\rvert\$$ relative $\$2.195\{\}\times 10^{\{-16\}}\$$, machine precision 'KSLICE=lo:hi' added with its default proved byte-identical both spectra scored on the same $\$185\$$ covered bins over the same $\$\{\}\ell\$$ range **and a property 'KBATCH' already had, measured and sized**:

'_project' takes $\$dk = \{\nabla k\$$ from the *batch*, so on the ladder's non-uniform bottom modes the batch boundary moves the weights — one batch against two differs by $\$1.205\{\}\times 10^{\{-8\}}\$$ relative

Bound: **Settles one thing only**:

that discreteness does not set this spectrum. Says nothing about whether the spectrum is right, and ***nothing that touches the floor*** — $\$F_2 = +1114.1\$$ still forbids reading $\$1205.4\$$ against the control's $\$1320.5\$$ as a preference, exactly as 'r6788' said measured at **one** configuration, so 'c54.186's $\$0.7\{\}\%$ at the pinned one is a different ladder density and is not superseded the 'KBATCH' figure is **negligible at $10^{\{-8\}}\$$ *** — eight orders below anything physical, a reproducibility note (quote 'KBATCH' with a ladder command) and not a defect, which is why no banked spectrum is revisited and 'KSLICE' is exact on a **uniform** grid only, so it is a continuum tool and a ladder run should be done whole

Run: python3 receipts/P15_CR.cosmology/P15_the_ladders_discreteness_does_not_set_the_spectrum_and_the_check_was

P15R180 P15_the_leg_contributes_no_tilt.because_a_fixed_phase_handover_is_scale_free_and_a_fixed_time.
[OK]

'PO-31's work order from node 66: where the tilt comes from, if it comes from the collapse leg. The row has a target — the like-for-like refit prefers $n_s=0.9949$ against the control's 0.9559 ('r6805') — and the order asks the first calculable thing beyond it: *can the leg produce a departure of that size at all?* (**No, and for a stronger reason than a small number: what the leg can produce is not a tilt.** Both the potential and the temperature on the leg are functions of $x=k\{\eta/\sqrt{3}\}$ *alone*, so a handover at a fixed *phase* is exactly scale-free — *the* ratio of amplitudes at two wavenumbers is 1 , not nearly 1 — and the only surviving scale is a handover at a fixed *time*, through $x_{\rm seam}=0.7638\{(k/k_s)\}$ *what a fixed-time handover gives is red in both channels and goes as k^2* : $\ln|\hat{\Theta}|^2 \sim \ln T^2 \sim \ln k^2/5 + O(x^4)$ — a *running*, where a constant n_s shift needs a constant log-derivative, with an honest zero of the amplitude at $k/k_s=2.057$ *so the size question answers itself by shape*: the target needs $k/k_s=0.065$, and thirty times that wavenumber the same expression gives $1-n_s=41.9 \Rightarrow$ *and on the adjudicated configuration it is exactly zero* — 'r6774's crossing is $x \rightarrow 0$, where $T \rightarrow 1$ and $\hat{\Theta} \rightarrow \Psi_i/2$ and both log-derivatives vanish quadratically). *Computes*: C1 the three banked amplitudes reproduced before anything is read — $T(1/\sqrt{3})/2=0.48353$ (the coded handover), $\cos(1/\sqrt{3})/2=0.41896$ (the exact entry temperature), $1/2$ (the envelope and the crossing value) — the closed form being *established* ('P15' coherence, transmission; 'r6760+cc66.1') and re-run rather than re-derived the quadratic approach checked, so the vanishing at the crossing is not an artefact of where the limit is taken *and one coding slip of mine was caught before landing: the band evaluation used the wrong factor and printed 1.4 where the docstring said 41.9* *Bound*: *Bounds the LEG's contribution only* — nothing about what the progenitor supplies, and nothing about A_s , whose fixed-point route the entropy monotone closed the fixed-time numbers are evaluated at the seam because that is the only fixed-time locus the corpus ever coded: *a demonstration that such a handover gives a running, not a claim the corpus uses one* — it does not, since 'r6774' the progenitor's mass enters only through k_s , so no independent mass dependence appears *nothing is tuned to 0.995* : the target enters once, to be refuted on shape, and 'PO-7' is untouched — this is a statement about a transfer function and not a verdict *Run*: python3 receipts/P15_CR_cosmology/P15_the_leg_contributes_no_tilt.because_a_fixed_phase_handover_is_scale_f

P15R181 P15_the_substrate_cannot_tilt_the_spectrum_and_the_collapses_duration_enters_only_as_a_decayin
[OK]

node 66's order (2) in 'FOR_60' ('r6825'), 'PO-31' one step in: with the leg closed as a source, the tilt is the progenitor's vacuum, so *what does the substrate ALONE constrain about that vacuum, before any interior is modelled?* *Three candidates named — the progenitor's mass, the finite duration of the collapse, and the substrate's curvature radius — with the order asking which can enter the vacuum's two-point function at all, and the sign of n_s-1 for any that can* (**One of the three can enter, and what it produces is not a tilt: the substrate alone fixes $n_s=1$ exactly. *the curvature radius CANNOT enter* — in conformal time the substrate's mode equation $u''+(k^2-2/\eta^2)u=0$ contains no length at all, so the only variable is $k\eta$ and α survives solely as the prefactor $P=1/(4\pi^2\alpha^2)$: it sets A_s and reaches n_s *for every α* , not for large α *the progenitor's mass CANNOT enter*, and on this construction that is arithmetic — the forced member is Nariai, $\Lambda M^2=1/9$ with $\Lambda=3/\alpha^2$, so $M=\sqrt{3}\alpha/9$ and $M/\alpha=0.192450$ is a *pure number*: the mass *is* the curvature radius up to a constant and brings no new length, so the two candidates are one and fall together *only the finite duration enters* — setting the vacuum at finite η_0 gives $\alpha_k=1-i/x-1/2x^2$, $\beta_k=e^{2ix}/2x^2$ with $|\alpha_k|^2|\beta_k|^2=1$ exactly and $R(x)=1+\cos 2x/x^2-\sin 2x/x^3+(1-\cos 2x)/2x^4$, $x=k|\eta|$, whose log-derivative is $-2\sin(2x)/x+O(x^{-2})$: *an oscillation with a decaying envelope, sign-alternating 24 times on $x \in [1,40]$* , its four octave means disagreeing in sign — a *running*, and by the corpus's own operational test a scale, not a tilt $\Rightarrow$ *so a constant tilt needs the interior, and its sign is fixed in advance*: the only quantity giving a band-independent log-derivative on a maximally symmetric background is an effective mass, exactly $n_s-1=3-2\sqrt{9/4-m^2\alpha^2}=\frac{23}{2}m^2\alpha^2+O(m^4)$, *blue for $m^2 \rightarrow 0$* — so the measured $n_s=0.995$ requires $m^2\alpha^2=-1201/160000=-0.0075$, slightly tachyonic).

Computes: C1 the Nariai constants reproduced before anything is read — $M = \sqrt{3} \alpha / 9$, $\Lambda M^2 = 1/9$ on substitution, $f(r_N) = f'(r_N) = 0$ — *established* (‘P15’ Fig. $f(r)$, ‘r6804’) and re-run rather than re-derived, because finding (2) rests entirely on them; the Bunch–Davies mode verified to solve the mode equation and to carry Wronskian $\mathcal{W}$, so the amplitudes are not rescalable the $R(x)$ identity checked twice by independent simplification routes *and* one stated criterion of mine was wrong and was corrected to the computation rather than the reverse: I had claimed the octave means sit within 0.021 of zero, and the $[2,4]$ band averages -0.095 — the true and stronger statement is that they do not agree with one another and do not share a sign *Bound:* *the one modelling step is named and it is the standard one*: the corpus’s scalar perturbation is treated on the substrate as a massless minimally coupled field. Findings (1) and (2) are robust to that choice — they are statements about which *lengths* appear, and none appears for any mass — but the exact value $n_s = 1$ is not, which is precisely what (4) says the duration channel computes a *sharp* initial time, the one unambiguous prescription: a smooth onset changes the envelope’s power and the phase and cannot change the sign alternation, so the claim is the SHAPE and not the coefficient bounds what the *substrate* supplies — nothing about A_s , whose fixed-point route the entropy monotone closed, and nothing about the interior beyond the one requirement *nothing* is tuned to 0.995 : the target enters once, at the end, and only to be inverted into a requirement on a quantity this receipt does not compute; ‘PO-7’ untouched *Run:* python3 receipts/P15_CR_cosmology/P15_the_substrate_cannot_tilt_the_spectrum_and_the_collapses_duration_ent

P15R182 P15_the_interiors_vacuum_is_blue_everywhere_and_a_running_so_the_substrates_mass_template_does [OK]

node 66’s work order in ‘FOR_60’ (‘r6845’) — ‘PO-31’ on the progenitor’s *interior*. ‘r6826’ left one channel, $n_s - 1 = 3 - 2 \sqrt{9/4 - m^2 \alpha^2}$ asking the interior for a slightly negative $m^2 \alpha^2$, *but that formula is the substrate’s and the fluctuations are generated in the interior*. Three questions: the spectrum handed over and whether it is a tilt or a running; its sign; and whether the substrate’s formula applies at all (All three answer, and they answer against the construction. first a correction to the order’s premise: *the interior is not newly built* — ‘P15_the_progenitor_vacuum_is_negligible_too’ already banks $a = M(\rho x + x^2/2)$ and the M -free potential $2/(x(x + 2\rho))$, and it is *the same object*: with $M = A/2$, $\rho = 2 \sqrt{B/A}$ the two agree *exactly* to $O(\eta^2)$ and $a''/a = A/(2a) - 1$ reduces to it (1) a RUNNING, not a tilt: the potential interpolates between $2/x^2$ (the $p = +2$ matter root, scale-free) and $1/(\rho x)$ (not), so at the determined $\rho = 0.0539$ the log-derivative runs $+0.30$ to $+1.98$ over $k = 5 - 2000$, tending to the radiation value $+2$ — no constant to fit, by the same band test that closed the leg (2) BLUE at every k , flattest $+0.304$, against a measured *red* -0.002 : wrong sign and ~ 100 times the size. The radiation content is the cause — flattest slope $\sim 6.7 \rho$ — *so red would need $\rho \rightarrow 0 \Rightarrow$* (3) the substrate’s template DOES NOT APPLY: $3 - 2 \sqrt{9/4 - m^2 \alpha^2}$ comes from a $1/\eta^2$ potential whose coefficient is *dimensionless*; the interior carries the scale ρ . *So $m^2 \alpha^2 = -0.0075$ is an artefact of applying the substrate’s template off the substrate, and the corpus should stop carrying it as a requirement*). *Computes:* C1 *the extractor calibrated on four power laws before being believed* — $p = -1$ and $p = +2$ both returning 0 to 5×10^{-6} , $p = +1$ giving $+2$, $p = +3$ giving -2 , against $3 - 2 \sqrt{1 - p/2}$: *two of them are the corpus’s own scale-invariant roots, so the instrument is checked on the cases the argument turns on* *an earlier version read every k on a different surface and returned $+6$ where 0 was right* — the calibration caught it, and it is recorded because the failure was silent the background identities and the two potential limits derived symbolically; the surface-convergence measured rather than assumed *Bound:* *the vacuum is set at maximum expansion* ($a' = 0$, so every mode sub-horizon), with $k^2/a^2 \geq 10$ enforced per mode — *below that band the interior supplies no initial condition*, which is the order’s own stopping clause, reported as a bound and not stepped over the slope *converges* as the reading surface approaches the branch point (last two decades agree to 1.2×10^{-4} , the shallowest differing by 1.4×10^{-2}) — *stated as convergence and not insensitivity, because the shallowest surface is not yet converged* $A = 1$ sets the time unit and every result is a slope or a ratio; $\rho = 0.0539$ is the *determined* composition, taken from the banked receipt and not chosen here a massless minimally coupled field, the same modelling step ‘r6826’ named *the banked receipt is not contradicted*: its scale-invariance is of a *transfer* and its number an *amplitude*; the slope

of the generated spectrum is a different object nothing bears on A_s or ‘PO-7’ *Run: python3 receipts/P15_CR_cosmology/P15_the_interiors_vacuum_is_blue_everywhere_and_a_running_so_the_substrat*

P15R183 *P15_the_transfer_is_the_same_object_as_the_vacuum_spectrum_and_the_crossing_carries_no_wavenum*
[OK]

node 66’s work order in ‘FOR_60’ (‘r6897’) — *“(2) ‘PO-31’, released”* after the switch sweep validated its target ($n_s=0.9949$ against the control’s 0.9559). Four channels closed and the measured red tilt supplied by none, so: *“what supplies a red tilt when the only vacuum the construction has computed is blue?”* The order named one thing to look at first — *“every closed channel was tested as a “spectrum-generating” mechanism, but the tilt is a ratio of amplitudes at two wavenumbers and there is a second place one can enter, the “transfer” from the progenitor’s vacuum to the boundary datum — “established for the collapse leg and not for the interior-to-leg join... if it is already closed, say so and it costs a paragraph”* *“(It is not a second place, and saying so costs more than a paragraph because the reason corrects this seat’s own reconciliation of two banked results.”* *“(1)”* the interior’s transfer and the interior’s vacuum spectrum are *“one object”*: the banked instrument, run at the *“determined”* $\rho=0.0539$, gives a log-slope running $+0.267$ to $+1.979$ — *“r6857’s $+0.30$ to $+1.98$, from vacuum data placed somewhere else entirely”* (sub-horizon in the deep matter contraction, against ‘r6846’’s maximum expansion) *“(2)”* and the banked scale-invariance is *“not contradicted — it has a domain”*: the potential breaks at $x \sim \rho$, so $k_{\text{break}}=1/(2\rho)$; the banked check ran at $\rho=10^{-3}, 10^{-4}$ with its whole band *“below”* $k_{\text{break}}=500, 5000$, and at the determined ρ the observed band lies *“above”* $k_{\text{break}}=9.3$ *“(3)”* and the one step genuinely untested — *“the crossing”* — carries no wavenumber *“exactly”*: $x=0$ is a resonant regular singular point and its log coefficient is $C=1/\rho$ with $dC/dk=0$, because k^2 is regular where the potential is singular (it first enters the analytic solution at x^3) $\Rightarrow$ *“the chain carries no k -dependence of its own anywhere, and where one does enter it is BLUE where the target is red”*). *Computes: C1 “the calibration is the gate”: PART 1 re-runs the banked check at the banked ρ and k and reproduces $3/(2\sqrt{2})$ to 0.20% — “the whole of PART 2 is that same instrument pointed at a different composition, so if PART 1 fails nothing below may be read”* the $x \rightarrow 0$ log of the radiation crunch divided out explicitly rather than left in the residual the resonant coefficient *“determined”* order by order (Frobenius, symbolic) rather than quoted the indicial equation shown to be k -blind from $x^2(\text{pot}-k^2) \rightarrow 0$ *Bound: “THIS DOES NOT CLOSE ‘PO-31’” — it closes the route the order named, which is a different thing; the row’s question is left exactly where ‘r6857’ left it, with one candidate eliminated rather than untested the background, the potential and $\rho=0.0539$ are “taken from banked receipts”, not rebuilt; what is new is where they are evaluated “the crossing result is about the monodromy and not about ‘C19’s $9/10$ ” — ‘C19’ states in its own voice that its join factor is the super-horizon one and that “modes inside the horizon at the branch point are not covered”, and that item is untouched a slope is not an amplitude: the A_s comparison is a “ratio to the scale-free branch”, showing the banked A_s^{vac} understated by $\sim 5 \times 10^3$ at the band’s top — against a shortfall of 10^{103} , so “a bound on how the number is read and not a correction to its conclusion” ‘r6846’s “the slope of the generated spectrum is a different object” is “withdrawn”: they are one object, and the reconciliation was wrong “in the direction that let a conflict pass” *Run: python3 receipts/P15_CR_cosmology/P15_the_transfer_is_the_same_object_as_the_vacuum_spectrum_and_the_crossi**

P15R184 *P15_the_interiors_transfer_imprints_its_own_running_so_the_channel_hunt_answered_the_wrong_que*
[OK]

node 66’s work order in ‘FOR_60’ (‘r6911’) — *“(1) ‘PO-31’, and the order’s own finding is bigger than the row”: every channel the row has closed answers “what tilt does the VACUUM give”, while ‘P15’ says twice that the primordial statistics are “classical and non-vacuum” — “so the corpus argues the observed perturbations are not the vacuum’s, and then computes the tilt of the vacuum, five times”*. The order: the banked transfer law’s exact scale-invariance is a property of the *“vacuum normalisation”* (k^3 cancelling D_k ’s k^{-3}), not of the transfer — so *“applied to an arbitrary input rather than to vacuum data, is the interior’s transfer a scale-free multiplier, or does it imprint its own running?”* *Forbidden: building a progenitor interior, importing a tilt* *“(It IMPRINTS, and the order’s diagnosis of the mechanism is confirmed exactly.”* *“(1)”* on *“unit”* incoming amplitude the multiplier’s log-slope

runs -0.8663 at $k=7$ to -0.0105 at $k=1400$ — a spread of 0.856 , so ***neither scale-free nor even a power law***; what it adds to any tilt is twice that, -1.73 to -0.02 **(2)** and ***the banked exact scale-invariance is that same function's LOW- k limit***: $d\{\ln T/d\ln k\}$ to -1 (-0.9992 at $k=0.3$) and $kT(k)$ to 27.86 , a constant — and $P\{\sim k^3\}$ is scale-invariant *exactly* when the slope is -1 , so the cancellation is the normalisation meeting a power law that holds only below the break **(3)** the decomposition as an *identity*, $s(k)=d\{\ln T/d\ln k+1\}$ — ***the k -dependence was always the transfer's and the constant always the normalisation's***, reproducing 'r6898's $+0.134$ and $+0.990$ from the transfer alone **(4)** the same function for *every* input to 4×10^{-13} , including one deliberately not a power law $\Rightarrow$ ***the channel hunt is over: five results stand, the question was mis-aimed, and the row becomes a statement about the interior model plus one computed requirement***). *Computes:* C1 **the banked check is the gate** — $3/(2\sqrt{2})$ reproduced at the banked ρ and k to 0.20% , and everything below is that same instrument pointed at a different object **linearity measured, not invoked** (7×10^{-15}) — *it is what licenses the order's phrase "whatever the progenitor supplies" the starting **phase** varied (6×10^{-6}) and then the convention **replaced outright** by a fixed x_i (2.9×10^{-5}), because a phase artefact here would look exactly like a running the slope shown to **converge** in the reading surface between the two deepest, 2.9×10^{-5} *Bound:* **the band is bounded at k_12783 and the bound is the PREMISE, not the arithmetic:** at $x_i=300/k$ the mode starts outside the break only while $300/k_12\sqrt{2}$, and above that "enters from the matter contraction" is false — *an earlier pass read T_1 at $k=10^5$, tolerance-converged to 2×10^{-10} and still meaningless, and that number is discarded as a misplaced initial condition rather than reported as a limit; **no high- k asymptote is claimed** ***the slope is claimed and the amplitude is not** — $\ln T$ carries $\sim 1\%$ of reading-surface dependence, which cancels in a log-slope; the shallowest surface differs by 2.9×10^{-3} and is reported as **not yet converged**, the same clause 'r6846' attached to its own nothing bears on A_s , whose 10^{103} shortfall is a **vacuum** statement no progenitor interior built; $\rho=0.0539$ and the potential taken from banked receipts **'PO-31' does not close**, as the order said it would not *Run:* python3 receipts/P15_CR_cosmology/P15_the_interiors_transfer_imprints_its_own_running_so_the_channel_hunt.a

P15R185 P15_the_acoustic_contrast_is_not_in_the_source_and_the_projection_makes_it_without_the_distance [OK]

node 66's work order 'r6911': *where is the acoustic contrast made — in the source, or in the projection?* — *take the statistic you already have and apply it before the projection as well as after*: **(a)** in k -space at last scattering, the arm-and-control contrast of the **source** (the monopole-plus-Doppler combination as a function of wavenumber, same envelope split, same peak-to-trough measure), ratio arm to control; **(b)** compare with the ℓ -space 1.040 — the order naming three outcomes in advance (≈ 1.04 = made in the dynamics; ≈ 1.00 = manufactured between k and ℓ , *live rather than exotic, because the two arms' distances differ by six per cent*; or a split, *and the split itself is the measurement*), with **one guard**: *the envelope split must be defined identically on the two arms and at the two stages, and the smallest difference it can express must be stated beside whatever tolerance gates it*, and **no mechanism asked for** (**THE CONTRAST IS NOT IN THE SOURCE: IT IS MANUFACTURED BETWEEN k AND ℓ** . The same statistic reads $\mathbf{0.996}$ on the source at last scattering, $\mathbf{0.992}$ on the η -integrated source, $\mathbf{1.045}$ on the raw spectrum and $\mathbf{1.047}$ on the banked one — *and over four envelope windows, both envelope definitions, three term subsets (monopole alone, monopole plus Doppler, the full source), four q sub-windows and with or without the k -measure, the source rungs span 0.971 – 1.005 and the ℓ rung 1.042 – 1.052 , against a statistic floor of 0.6% set by its own bias on a **known injected** contrast. $\Rightarrow$ **AND THAT IS WHY FOUR-FOR-FOUR NEEDED NO EXPLAINING.** The order's difficulty was that four channels which each *shallow* the troughs are all larger on this arm, so something upstream had to overcome all four. **Upstream the arm's oscillation is 0.996 of the control's — very slightly SHALLOWER, which is exactly the direction all four point.** **Nothing overcomes them because nothing had to: the effect to explain is not bigger than four per cent, it is not upstream at all.** $\Rightarrow$ **THE NAMED ROUTE IS OUT TWICE OVER, AND THE FIRST HALF IS A PREMISE CORRECTION.** The order's 13005 against 13865 Mpc is the **superseded** configuration's ($r_s=135.46/144.53$), where the arm's was the smaller; at the

adjudicated minima D_M is $\mathbf{14017.04}$ on the arm against $\mathbf{13954.35}$ on the control — $\mathbf{+0.449\%}$ and the **arm's** is the **LARGER**, wrong in size and in sign. *The cancellation the order relies on is real — ℓ_A agree to $\mathbf{0.085\%}$ — so it is the six per cent and not the reasoning that fails. $\Rightarrow$ And the route is eliminated by measurement anyway*: 'SRCXS' projects one arm's own source through the *other's* distance, one arm at a time, moving its contrast by $\mathbf{-0.63\%}$ (control) and $\mathbf{+0.59\%}$ (arm) — and removing the difference altogether takes the arm/control ratio **UP**, $\mathbf{1.045}$ to $\mathbf{1.051}$. $\Rightarrow$ **WHERE IN THE PROJECTION, AS FAR AS THIS GOES**: the arm's projection **retains** $\mathbf{1.054}$ times as much of its own source oscillation as the control's does ($\mathbf{0.2543}$ against $\mathbf{0.2413}$); the excess **ris** with wavenumber ($\mathbf{1.031}$ below $q=3$ to $\mathbf{1.065}$ above) where the source ratio is flat ($\mathbf{0.992}$ to $\mathbf{0.992}$); it is **not** the visibility width acting before the kernel ($\mathbf{0.996}$ to $\mathbf{0.992}$), **not** the lensing or the binning ($\mathbf{1.045}$ to $\mathbf{1.047}$), and **not** the k grid — 'KCONT=1' puts the arm on the control's kind of uniform grid at the same mode count with the physics untouched and the ℓ rung is unchanged at $\mathbf{1.045}$. $\Rightarrow$ **AND THE GUARD CHANGED THE DEFINITION, WHICH IS PART OF THE MEASUREMENT**: 'r6885+cc66.35's running **geometric** envelope cannot be carried to the source at all — the source power comes within a part in 10^8 of its own median at the troughs, where a log-mean is dominated by near-zeros — so the envelope is a running **arithmetic** mean at **every** rung, both are reported, and they differ by $\mathbf{0.003}$ on the ℓ rung against the $\mathbf{0.05}$ step being measured*). *Computes*: 'SRCSAVE' is new and wired into 'project' — the **reporting** path — writing the source term by term at last scattering *and* η -integrated, with the four terms gated to **sum** to the instrument's own 'S' ($\mathbf{2.8 \times 10^{-17}}$) so a future edit to 'S' that forgets the block fails here; its default and 'SRCXS's gated **bit-identical** on both arms before any number is read, and 'SRCXS=1.5' with 'SRCSAVE' unset gated bit-identical too, which is what makes the swap an *output of the save* rather than a knob; every load of either name shown to sit inside an 'if SRC:' block (*a binding is not a use*); the sliced runs gated to reproduce the banked $\mathbf{185}$ -bin refit spectra to $\mathbf{4.9 \times 10^{-15}}$ relative, **which is what makes the k end and the ℓ end one run rather than two**; the abscissa's alignment **measured** rather than assumed (the arms' acoustic period in q agreeing to $\mathbf{0.22\%}$ at the source and $\mathbf{0.09\%}$ in ℓ , best lag $\mathbf{+0.005}$ and $\mathbf{-0.001}$); the statistic returning exactly $\mathbf{1.000000}$ against itself, recovering a **known** injected contrast, and returning $\mathbf{0.9996}$ through the other arm's abscissa and back; and the one artefact that could have produced the whole answer — the two arms' different *kinds* of k grid — run out with 'KCONT=1' rather than argued, that switch shown non-null so the result is not 'r4558's unwired knob *Bound*: **NO MECHANISM** — "the projection makes it" names a **stage**, not a cause, and nothing here says what within the projection produces $\mathbf{5.4\%}$; the order's bound is unmoved **NOT** that the projection is wrong — nothing here bears on the flat kernel, which 'prop:flat' settles; *a projection can manufacture a contrast difference while being exactly the correct projection for both arms* **NOT** that the visibility width is its route: the arm's is $\mathbf{15\%}$ wider, which *shallows* contrast, and the rung where an η -average acts **without** the kernel moves the ratio by only $\mathbf{-0.4\%}$ — a bound on one route, not the identification of another **NOT** that the source is identical on the two arms: it is $\mathbf{0.992}$, a real deficit of about the statistic's floor, and its sign is the four channels' own **NOT** that 'cc66.35's $\mathbf{1.0401}$ is superseded — it is reproduced exactly under its own definition and comes out $\mathbf{1.047}$ under this receipt's, and the difference is the envelope definition, reported the q variable rests on the sharp-visibility map $\ell=kD_M$, exact to the visibility width over D_M — $\mathbf{38-44}$ Mpc against $\sim \mathbf{14000}$, a part in $\mathbf{300}$ *Run*: python3 receipts/P15_CR_cosmology/P15_the_acoustic_contrast_is_not_in_the_source_and_the_projection_makes_i

P15R186 P15_the_transfers_running_is_a_function_of_one_variable_so_the_requirement_is_the_radiation_fr
[OK]

node 66's work order in 'FOR_60' ('r6914') — **PO-31** is now a specification rather than a hunt*: $P_{\rm obs} = \ell_{\rm vert} T_{\rm rvert}^2 P_{\rm prog}$ with T measured at 'r6912', so $P_{\rm prog}$ is determined — **and a determined input is only good news if the determination is not a conspiracy**. Three items: (1) **where is the break in ρ , and is any ρ putting the observed band wholly below it**, on a stated criterion; (2) **is $\mathbf{1.71}$ a number or an artefact of the band's placement**; (3) **is the high- k limit exactly zero, and the requirement therefore bounded by two** — **argued ANALYTICALLY**, because k to large is exactly where this seat's $x_i=300/k$ premise expires and **a second $k=10^5$ would be worse than a gap** (All three answer, and two in closed form, because the run-

ning turns out to be a function of ONE variable.** **THE STRUCTURAL FACT** — substituting $x=2\sqrt{\rho}u$ gives $v_{\text{uu}}=(2/(u+1))-\kappa^2v$ with $\kappa=2\sqrt{\rho}k$ — **the potential in u carries no ρ** , so $d\ln T/d\ln k$ is universal in κ (collapse verified to 7×10^{-13} across $\times 100$ in ρ) and $k_{\text{break}}=\kappa/(2\sqrt{\rho})$ **exactly** **(3)** near the crunch the equation is the **repulsive $L=0$ Coulomb wave equation** with $\eta=1/\kappa$, and $1/C_0(\eta)=1+\pi\eta/2$ gives $d\ln T/d\ln k\rightarrow\pi/(4\sqrt{\rho}k)\rightarrow\mathbf{0}$ — matching measurement to 1.4% at $k\leq 2000$, **derived** where the integration is not trusted and checked where it is **$\Rightarrow$** **the excursion is exactly 1% , the tilt contribution at most 2% , and no band** however wide can require a progenitor running above 2% **(1)** a working ρ **exists** but needs $\rho; 9.7\times 10^{-4}$ (midpoint) or 1.4×10^{-4} (within 0.05% of the power law) — **$55\times$ to $378\times$ below the determined 0.0539%** **$\Rightarrow$** **the requirement stands BECAUSE the determined radiation fraction forces it** **(2)** over the $\pm 6\%$ the arm's own distances allow, 1.71% moves 2.3% — **a number, not an artefact**, and the observed band asks 86% of the hard maximum). *Computes:* C1 **the banked $3/(2\sqrt{2})$ check at the banked ρ and k is the gate** — everything below is that instrument or an analytic argument about the same equation the scaling substitution and the composition identity done **symbolically**, not by hand the κ -collapse **measured** across four ρ spanning a factor 100 the Coulomb limit's coefficient taken from a **series expansion of $1/C_0(\eta)$** , then compared against measurement at four $(k,\sqrt{\rho})$ pairs **all inside the premise** *Bound:* **the analytic limit is NOT measured at large k , by design** — the order forbade it and the reason is this seat's own: 'r6912' discarded a $k=10^5$ reading that was **tolerance-converged to 2×10^{-10}** and still meaningless because $x_i=300/k$ had drifted inside the break. **No integration above $k=2000$ is performed or quoted** **the differencing convention moves the headline in the third digit**: 'r6912's centred grid slopes gave 1.71% , this $\pm 8\%$ two-point slope gives 1.724% — so the requirement is quoted as $1.71\% - 1.72\%$ and that 0.7% spread is **part of** (2)'s answer, not noise over a **wider** band the requirement moves $6\% - 9\%$, reported rather than hidden **the ρ bound is NOT converted into a number for a_{eq} or M** : 'P16's own two statements give $\rho=\sqrt{2a_{\text{eq}}/M}$ (verified symbolically), but at $a_{\text{eq}}=1.49$ Mpc and the **register's** mass that reads 1.635×10^{-2} against the determined 0.0539% — a factor 3.3% , i.e. two different progenitor masses. **Flagged, not used** no progenitor interior, no tilt value, no amplitude; **'PO-31' does not close**, as the order said *Run:* python3 receipts/P15_CR_cosmology/P15_the_transfers_running_is_a_function_of_one_variable_so_the_requiremen

P15R187 P15_the_cross_term_is_not_the_channel_and_every_projected_term_carries_the_excess [OK]

node 66's work order 'r6915': **which term carries the contrast excess after projection?** — 'cc66.40' located the stage, and the order asks what inside it does the work, naming the monopole-Doppler pair first because **the monopole enters through j_{ell} and the Doppler through j_{ell}** , and those are a quarter-period out of phase: **(1)** **project each term separately, apply the same j_{ell} -space contrast statistic to each piece and then to their sum, with three outcomes named (both pieces near 1.00% and the sum at 1.045%** **$\Rightarrow$** **the cross term**; one piece already at 1.045% **$\Rightarrow$** **that term's own projection; neither and the pieces do not sum** **$\Rightarrow$** **the decomposition is not linear where I have assumed it is, and that is the finding**), **and a forced calibration**: **the projection is linear in the source, so the separately projected pieces must sum to the full spectrum. Gate that first... and read nothing below it if it fails**; **(2)** **report the retained fraction as a function of q** rather than as one number per arm — rising **$\Rightarrow$** a kernel-phase signature, flat **$\Rightarrow$** **that kills the reading above** (**THE CLOSURE GATE HAD TO BE CORRECTED BEFORE IT COULD BE PASSED, AND THE CORRECTION IS THE ORDER'S OWN FIRST OUTCOME**. **The transfer** is linear in the source and the pieces do add there; C_{ell} is **quadratic** in the transfer, so the projected **spectra** cannot — the four diagonal pieces alone fall short of D_{ell} by up to $\mathbf{46\%}$. **This is not the third outcome: the first outcome presupposes a cross term, so the order's two clauses are in tension and the first is the coherent one.** **$\Rightarrow$** **What closes is the full bilinear decomposition** — with $\Delta a_{\text{ell}}(k)=\int \text{term}_a j_{\text{ell}} d\eta$, $C_{\text{ell}}=\sum_a b w_{ab} \sum_k P_{\text{ell}} \Delta a \Delta b$ — **ten numbers per multipole closing on D_{ell} to 1.1% and 1.3×10^{-15} relative on the two arms.** **$\Rightarrow$** **AND THE CROSS TERM IS NOT THE CHANNEL: deleting it moves the ratio from**

\$1.0452\$ to \$1.0451\$**, and over four envelope windows its carry runs \$-0.0013\$ to \$+0.0008\$ of the \$+0.045\$ — *bounded at about a part in a thousand, so the interference between $j_{-}\ell$ and $j_{-}\ell$ is excluded.* $\Rightarrow$ **BECAUSE EVERY PROJECTED PIECE ALREADY CARRIES IT, WHICH IS NEITHER OUTCOME NAMED**: monopole $\mathbf{1.034}$, Doppler $\mathbf{1.099}$, polarisation $\mathbf{1.058}$ against the full \$1.045\$ (the ISW alone is the exception at \$0.989\$, and it is 1% of $D_{-}\ell$). ***So it is not a term and not a pair of terms: the projection raises this arm's contrast on nearly everything it projects.*** $\Rightarrow$ **AND THE LADDER IS THE SHARPEST FORM OF IT — every term's SOURCE ratio is at or below \$0.992\$ and every term's PROJECTED ratio is higher**: monopole \$0.992\$ to \$1.034\$, Doppler \$0.973\$ to \$1.099\$, ISW \$0.972\$ to \$0.989\$, polarisation \$0.990\$ to \$1.058\$, the whole source \$0.992\$ to \$1.045\$. $\Rightarrow$ **THE SPLIT THE ORDER'S REASONING WAS AFTER IS ABOUT \$40/60\$, THE RESPONSE THE LARGER**: the weights *do* differ (the arm's monopole share \$0.5225\$ against \$0.5092\$, its Doppler \$0.1753\$ against \$0.1840\$), and rebuilding the arm's pieces at the control's shares gives \$1.0267\$ — *the weights carry \$+0.019\$ of the \$+0.045\$ and each piece's own response \$+0.027\$**, with the reverse construction agreeing at \$+0.020\$. $\Rightarrow$ ** (2) AND THE RETAINED FRACTION IS NOT FLAT IN q **: it rises from \$1.030\$ in the lowest band to \$1.089\$ in the highest, and over **twelve settings** (four envelope windows $\times$ three band counts) the slope is $\mathbf{+0.0139 \pm 0.0021}$ per unit q , **never once negative** — *so the branch that would have killed the reading is excluded.* *The intercept is $\mathbf{1.017 \pm 0.010}$ and **straddles one**: the rise is established and a constant offset is not, and the value at $q=0$ is an extrapolation from a lowest band centre of $q=1.20$ *). *Computes*: 'SR-CDEC' is new and wired into 'project's own multipole loop — *the reporting path* — so the Bessel evaluation is shared with the reported spectrum and the decomposition costs four trapezoids per multipole rather than a second projection; its default gated **bit-identical** on both arms before any number is read, and every executable line naming it categorised as a binding, a guard or a line inside a guarded block (*a binding is not a use*) rather than counted, because a substring count read the switch's own documentation as code and failed this gate on its first writing; the ten pairs gated to close on $D_{-}\ell$ and the **non**-closure of the four diagonals gated too, so the premise correction is a measurement and not an argument; this run's $D_{-}\ell$ gated identical to 'r6911+cc66.40's to 10^{-13} relative, which is what lets a source rung and a projected rung sit in one ladder; every off-diagonal piece that is **not** positive definite named rather than quietly skipped, a relative oscillation about a running mean being undefined where the mean changes sign; the bank gated that the slices tile k with no gap or overlap and that the pair **order** is identical slice to slice; and the statistic, abscissa and resolution taken over unchanged from 'r6911+cc66.40' rather than re-derived *Bound*: **NO MECHANISM** — naming that every projected term carries it, and that the rise in q is real, is still not a statement about *why*; the order's bound is restated rather than moved **NOT that the cross term is zero** — it is 26% of $D_{-}\ell$ and its oscillation is 59% of the full's; what is bounded is its contribution to the **difference** **NOT that the Doppler's \$1.099\$ is as well determined as the monopole's \$1.034\$**: its piece's relative oscillation is \$0.116\$ against \$0.305\$, so it is the weaker signal, and its window spread \$1.0995\$–\$1.1070\$ is quoted beside it **NOT a fit** — the weight/response split rescales pieces by their mean share, which also moves the envelope, which is exactly why both directions are reported **NOT that the $q=0$ intercept is one** nothing here touches 'prop:flat' *Run*: python3 receipts/P15_CR.cosmology/P15_the_cross_term_is_not_the_channel_and_every_projected_term_carries_th

P15R188 P15_a_source_with_no_physics_reproduces_the_contrast_and_the_two_clocks_part_company_at_the_vib [OK]

node 66's work order 'r6919': *** (1) project a source with no physics in it** — **feed both arms' projection machinery the same analytic oscillating source — a pure $\cos(k r_s + \phi)$ on a smooth envelope, no transfer, no terms, no weights — and measure how much of its oscillation each arm's projection retains, as a function of q **, reproducing 'cc66.41's \$1.054\$ and \$+0.0139\$ $\Rightarrow$ the geometry, else $\Rightarrow$ the source's η -dependence; ** (2) then swap the two geometric factors one at a time**, the visibility and $\chi(\eta)$, with the candidate named: ***the source is accumulated on one clock and the kernel's argument is a distance read on the other** — and the instruction that ***if a swap is not well posed... **say that instead of forcing it.** An ill-posed swap reported as a null is exactly the shape of the unwired knob at 'r4558'** (****A SOURCE WITH NO PHYSICS IN IT REPRODUCES THE EFFECT AND OVER-DELIVERS.**** A pure $g(\eta)\cos(k r_s(\eta))$ through each arm's own kernel, visibility, k grid and multipole grid gives an arm/control retained ratio of $\mathbf{1.066}$ \$**

at a slope of $\mathbf{+0.0226}$ per unit q , against the real source's $\$1.054$ and $\$+0.0139$.
 $\Rightarrow$ ***The projection's geometry accounts for the whole of it and then some: the source is irrelevant to it*** — the order's first branch. *The injection's phase does not matter ($\$1.066/+0.0225$ at $\phi=\pi/2$), and a **standing** oscillation already carries most of it ($\$1.059/+0.0119$).
 $\Rightarrow$ **AND THE ORDER'S NAMED CANDIDATE IS IN THE INSTRUMENT BUT NOT WHERE THE ORDER PUTS IT.** * $x_0 = \eta_0 - EE$ on both arms, so $\chi(\eta)=\eta_0-\eta$ and $d\chi/d\eta \equiv 1$ identically on each, with no 'Jac', 'Hleaf' or 'Hphys' touching 'x0' on any path — **there is nothing there to exchange.**
 $\Rightarrow$ ***The two clocks sit between r_s and η : conformal time (and so 'x0') is built from 'Hphys', the **stacking** rate, while the acoustic phase accumulates on the **leaf** rate — 'Jac' $=1.000000$ everywhere on the control by the rate identity, and $\mathbf{0.789}-\mathbf{0.913}$ across $\mathbf{3}$ FWHM on the arm. $\Rightarrow$ **AND THAT IS WHERE THEY PART COMPANY, AS ONE NUMBER PER ARM.** Across the visibility FWHM the accumulated **sound horizon** agrees to $\mathbf{0.08\%}$ ($\$17.3074$ against $\$17.2941$ Mpc) while the **comoving distance** differs by $\mathbf{14.6\%}$ ($\$38.042$ against $\$43.591$): *the leaf clock makes r_s accumulate more slowly per unit η , so a $\mathbf{15\%}$ wider window covers the **same** acoustic phase — and the kernel, which reads χ , sees the wider window.*
 $\Rightarrow$ ***The joint object is $d r_s / d \chi$ across the visibility — the sound speed the kernel sees — $\$0.4550$ on the control against $\$0.3967$ on the arm, $\mathbf{-12.8\%}$; term-independent, growing with wavenumber, and vanishing for a window under one acoustic period, which are the three properties 'cc66.41' measured. $\Rightarrow$ ***(2) AND NEITHER SWAP CLOSES IT ALONE — THE THIRD OUTCOME.** *The **clock** swap is **ill posed** as an isolation and the statistic says so rather than returning a null: forcing both arms onto the stacking clock **moves the comb**, and band by band the regression **alternates in sign** ($\$+0.37/-0.52/+0.42/-0.57$) — 'cc66.40's guard firing on exactly the shape it was built for, and itself evidence that the leaf assignment is what the arm's reported peak positions need.*
The **width** swap **is** well posed and **overshoots by eight**: giving each arm the other's FWHM takes the slope $\mathbf{+0.0226}$ to $\mathbf{+0.0931}$ while barely moving the mean, so the width sets the **shape** and not the **level**.*
 $\Rightarrow$ **They close only together, and what they close on is $d r_s / d \chi$. Computes: 'SRCINJ', 'SRCINJPH', 'SRCINJRS' and 'SRCINJVIS' are new, all four gated **bit-identical when unset** on both arms in one result that covers both guards, the edit touching 'hier_run's batch loop as well as '_project'; every load shown to sit inside a guarded block with the four bindings counted apart (*a binding is not a use*); **the solver is skipped on the injected path** by a guarded 'continue', because the analytic source replaces 'S' and evolving the hierarchy would build an array nothing reads; the injection carries $k^{\{(1-n_s)/2\}}$ so the smooth part of PS^2 is exactly $d k / k$ on **both** arms and the two tilts cannot enter; the statistic, abscissa and window taken over unchanged from 'r6911+cc66.40' so the comparison with the real source is like for like; the emptiness of the $\chi(\eta)$ swap gated from the **source text** on code lines with comments stripped, because the 'hier_run' docstring names 'x0 = $\eta_0 - EE$ ' too and a substring count read the documentation as a second construction; the visibility swap reported as the **construction** it is, g rescaled about each arm's own peak with its integral preserved, because the arms' visibilities sit at $\eta=281.7$ and $\$486.0$; and the ill-posed clock swap gated on its **sign changes** rather than on its value *Bound: **NO MECHANISM***, and the order does not ask for one yet: naming $d r_s / d \chi$ is not an account of *why* this construction assigns its scales and its distances to different rates — that is 'P15' §'sec:tensions' own question and is **not reopened** **NOT that the injection IS the source**: it has the right oscillation in q and the arm's own visibility and nothing else, so over-delivery is sufficiency and not identity, and the excess over $\$1.054$ is not interpreted **NOT that the visibility width is ruled out** — its swap overshoots, which makes it inseparable from the clock, not absent **NOT that 'LEAFSCALES=1' is wrong**: the stacking-clock injection puts the arm's comb in the wrong place, which is evidence the leaf assignment is what the peak positions need **NOT a spectrum** — every 'SRCINJ' run is the projection's transfer of a known input and none may be compared with a banked spectrum or the sky nothing touches 'prop:flat'
Run: python3 receipts/P15_CR.cosmology/P15_a_source_with_no_physics reproduces the contrast and the two clocks

P15R189 P15_the_visibilitys_clock_is_the_one_the_kernel_reads_and_the_comb_votes_against_the_alternati
[OK]

node 66's work order 'r6925': ***which clock is the visibility a density in, and does the rate rule determine it? — the rule being **comoving separations read across leaves take the stacking*

rate; scales the plasma accumulates take the leaf's", and $g=\tau'e^{-\tau}$ "neither": "the optical depth is accumulated by the plasma... but it is differentiated per unit η , and η is built from the stacking rate". **(1)** locate every place the visibility and the optical depth touch a rate; recompute $\mathrm{dr}_s/\mathrm{d}\chi$ under the other admissible assignment and report what the retained fraction and its q -slope become — with the standing guard "report what it does to the comb beside what it does to the contrast, and if they disagree say so rather than picking one", and the third branch "if the second assignment is not well posed... say that, and say which step breaks". **(2)** one number on where the source's partial cancellation sits, the injection over-delivering at $\$1.066/+0.0226$ against the real $\$1.054/+0.0139$ (THE AUDIT FINDS THE GAP ALREADY OPEN IN THE CODE, WHICH THE ORDER DID NOT EXPECT. Every site where τ or g touches a rate is on the stacking clock — the recombination history solved against 'Hphys', 'taup_of' built on 'eg's conformal time, 'tau' integrated over 'egrid', 'ETA_LS' and 'ETA_LS_W' read off that grid. But $1/k_D^2$ twenty lines below IS Jac-weighted under 'LEAFSCALES'. $\Rightarrow$ So the diffusion length — a scale the plasma accumulates — takes the LEAF clock and the optical depth, also accumulated by the plasma, takes the STACKING clock: two objects on the same side of the rule, on opposite clocks, with nothing stating the choice. So the other assignment is not an invention — 'VISLEAF=1' applies to τ exactly the weighting $1/k_D^2$ already applies to itself, which is what makes it admissible rather than invented. $\Rightarrow$ ON THE GEOMETRY THE TWO AGREE — THE ORDER'S SECOND BRANCH. $\mathrm{dr}_s/\mathrm{d}\chi$ goes $\$0.396733$ to $\$0.396957$ on the arm, so $\$12.80\%$ lower becomes $\$12.75$ — a move of $\$0.06$ per cent — and the control does not move at all. And structurally rather than luckily: it is a ratio of two accumulations across the same window, so re-weighting that window's measure re-weights numerator and denominator alike. $\Rightarrow$ The visibility is not where the freedom is, and the $\$12.8\%$ per cent is forced by the rule as stated. $\Rightarrow$ BUT THE CONTRAST AND THE COMB DISAGREE, AND THE ORDER SAID TO REPORT THAT RATHER THAN PICK. Read alone the other assignment moves the injection's retained ratio $\$1.0850$ to $\$1.0695$ and its slope $\$+0.02424$ to $\$+0.01332$ — toward the real source's $\$1.0694$ and $\$+0.01167$, which is the order's first branch. But the arm's first peak moves $\ell=220$ to 228 and ℓ_1/ℓ_A $\$0.7290$ to $\$0.7555$ — away from the sky's $\$0.7312$ — with P_1/P_2 $\$2.142$ to $\$2.017$ and the control's comb bit-identical both ways. And the contrast improvement is partly an artefact of that same move: band by band the 'VISLEAF=1' ratio is non-monotonic scatter with a fitted residual nine times the current assignment's, because moving η_{LS} moves $r_s(\eta_{\mathrm{LS}})$ and so moves the comb, and a band ratio of two oscillations no longer aligned in q reads their phase mismatch — 'cc66.40's guard firing a third time on the shape it was built for. $\Rightarrow$ The geometry says forced, the contrast says improvable, the comb says no; the comb is the only one of the three with an external referent, and neither is picked. $\Rightarrow$ **(2)** AND THE SOURCE'S CANCELLATION IS HALF THE LEVEL AND NONE OF THE SLOPE, so the sector does NOT close into one account. Multiplying the injection by 'cc66.40's measured source deficit — $\$0.9922$, and flat in q at a slope of $\$-0.00106$ — gives $\$1.0766$ at $\$+0.02296$ against the real $\$1.0694$ at $\$+0.01167$: $\$54$ per cent of the level gap and $\$10$ per cent of the slope gap. $\Rightarrow$ So the four trough-filling channels account for about half the level difference and essentially none of the slope; the order's conditional is half satisfied and the closure it hoped for does not arrive. What flattens the slope is the real source's own η -dependence across the visibility — exactly what the injection replaced — and that is named, not measured here. Computes: 'VISLEAF' is new, gated bit-identical when unset on both arms and when SET on the control — two different gates, the second being the rate identity showing in a second place and the one-sidedness of the whole finding in one result; the switch also shown non-inert on the arm (η_{LS}), the FWHM and r_D all move) so the near-null on the geometry is a connected knob's and not 'r4558's unwired one; the audit's five sites and the $1/k_D^2$ counter-example all located from the source text rather than described; the 'VISLEAF=1' slope's contamination gated on its band residual against the current assignment's rather than asserted; the comb gated on the arm's ℓ_1/ℓ_A moving away from the sky and the control's being unchanged, so the direction is part of the gate; and the statistic, abscissa and window taken over unchanged from 'r6911+cc66.40' Bound: NOT that the two-rate assignment is right — that is the row's question now and not this order's, and nothing here settles it NOT that 'VISLEAF=1' is wrong as physics: what

is measured is that it moves the comb away from the sky while moving the contrast toward the real source, and that its contrast improvement is partly a phase artefact — **which of the two clocks the optical depth ****should**** be a density in is not settled here* ****NOT** that the \$0.06\$ per cent invariance settles the row** — it says the visibility is not where the freedom is; the freedom is in the rule’s assignment of ℓ itself **NOT** a mechanism beyond ‘cc66.42’*’s*, and nothing touches ‘prop:flat’ ****NOT** that the injected runs are spectra* — the ‘injl’ arrays are the projection’s transfer of a known input and only the ‘combl’ arrays are spectra, kept under separate keys ****NOT** that this receipt’s first launcher worked*: it dropped its extra environment through a positional-argument bug and thirty-six slices ran as plain ‘VISLEAF=0’ spectra, **reporting nothing wrong and reproducing the banked spectra** — recorded in the launcher’s own comment, with the fix a smoke test that greps the log for the marker the switch must print `Run: python3 receipts/P15_CR_cosmology/P15_the_visibilitys_clock_is_the_one_the_kernel_reads_and_the_comb_votes.`

P15R190 `P15_the_combs_resolution_is_four_multipoles_and_the_sky's_own_value_lies_outside_the_family`
[OK]

*node 66’s work order ‘r6929’: ****the comb has been promoted to arbiter, so measure what it can actually decide**** — ****you have made the comb the load-bearing reading ... but the corpus has never measured how sharply it discriminates, and a reading promoted to arbiter needs its resolution stated before it decides anything****. Scan the assignment ****continuously**** — ‘VISLEAF’ as a fraction rather than a flag — and report against that parameter ℓ_1/ℓ_A against the sky’s \$0.7312\$, the retained fraction and its q -slope, and $\mathrm{d}r_s/\mathrm{d}\chi$; with three branches (****steep comb + shallow contrast**** $\Rightarrow$ the comb pins the assignment; ****both shallow, or the comb’s spread inside the sky’s own locating spread**** $\Rightarrow$ the comb cannot arbitrate, ****and that is the finding, and it is worth more than the scan****; ****an interior fraction fitting better**** $\Rightarrow$ say so plainly, since a fitted clock would be a new free parameter) and the guard ****report whether the comb’s motion is the visibility peak relocating or the acoustic phase changing**** (****EVERY READING IS LINEAR IN THE PARAMETER AND THE COMB’S WHOLE RANGE IS FOUR MULTIPOLES.**** $\ell_1 = 221.93 + 4.21f$ to three hundredths of a multipole, so the family spans \$0.01395\$ in ℓ_1/ℓ_A — \$4.2\$ of the sky’s one-multipole locating widths, \$2.1\$ of its two-multipole ones. $\Rightarrow$ ****The comb pins f to ± 0.24 : it separates the family’s ends and comes nowhere near fixing the clock.**** ****AND THE ORDER’S FIRST BRANCH IS HALF RIGHT.**** The contrast’s **level** is shallow (\$1.75\sigma\$ against the comb’s \$4.21\$) but its q -slope is not (\$+0.01042\$ to \$-0.00039\$, \$3.80\sigma\$, the comb’s statistical equal) — ****what separates them is that the contrast’s error GROWS five-fold across the family (band residual \$0.0089\$ to \$0.0441\$, slope s.e. \$0.00284\$ to \$0.01410\$) while the comb’s locating width does not move****, ‘cc66.40’*’s* guard firing a fourth time. ****AND THE DECIDING RESULT IS NOT ABOUT THE CHOICE: THE SKY’S VALUE IS NOT IN THE FAMILY.**** \$0.7312\$ sits at \$f=-0.304\$ on the family’s own line, on the far side of the stacking clock $\Rightarrow$ ****no interior fraction fits better than the endpoint in use (the third branch does not arise and there is no fitted clock to declare), \$f=0\$ is the best point, and the residual first-peak disagreement cannot be absorbed by the clock assignment because the direction it needs is inadmissible.**** P_1/P_2 agrees independently: \$2.141\$ to \$2.017\$ against the sky’s \$2.217\$. ****THE GUARD, SEPARATED THREE WAYS**** because the injection has no plasma dynamics in it: the comb’s motion is \$31\%\$ the peak relocating through $r_s(\eta_{\mathrm{LS}})$ (\$+1.31\$ multipoles), \$9\%\$ the visibility’s re-weighting of the kernel (\$+0.39\$), and \$60\%\$ ****the plasma’s own acoustic phase**** (\$+2.51\$). ****AND TWO OF ‘cc66.43’*’s* NUMBERS WERE GRID-LIMITED****: ℓ_1 \$220\$ to \$228\$ is really \$221.95\$ to \$226.16\$, ℓ_1/ℓ_A \$0.7290\$ to \$0.7555\$ really \$0.73543\$ to \$0.74938\$ — **and the sign of the arm’s offset from the sky at \$f=0\$ flips, from below to \$1.28\$ multipoles above** — while the FWHM’s \$43.591\$ to \$43.952\$ is exactly one step of the η grid, non-monotone across the family, and not a resolved motion at all. The locator is validated on the banked ‘LSTEP=1’ spectrum first, where it recovers the fine-grid ℓ_1 to \$0.004\$ of a multipole. ****AND THE SWITCH GUARD IS NOW STANDING****: the instrument prints a ‘_SWITCHES_’ line whose inventory is read off its own source, ‘switch.smoke.sh’ asserts every assignment arrives, and the launcher checks every distinct environment before the set and every slice’s log after — ‘r6925’*’s* thirty-six lost slices cannot recur silently. **NOT** a verdict on the two-rate assignment; \$f_0\$ is the family’s line extrapolated and not a candidate; the sky’s locating width is P15’s own; the injected runs are not spectra of this model; nothing touches ‘prop:flat’; no refit). *Computes*: ‘VISLEAF’ is a FRACTION now, and its endpoint is gated ****bit-identical**** against ‘r6925’*’s* banked ‘VISLEAF=1’ spectra while ‘VISLEAF=0’ is gated bit-identical against*

the unset path and the CONTROL against itself at $f=0.5$ — *the fraction's zero is the flag's off, the family's one is the flag's on, and the rate identity collapses the whole family on the control*. The base $f=0$ reproduces the corpus's own banked reported spectrum to the 'KSLICE' sum's rounding, which is the scan's provenance. The **sub-bin locator is validated before use** on the banked 'LSTEP=1' spectrum (0.004 of a multipole on ℓ_1), because the whole question is resolution. *And the switch guard is standing rather than per-launcher: a '...SWITCHES...' marker whose inventory is read off the instrument's own source, 'switch_smoke.sh', a pre-launch check on every distinct environment and a post-run check on every slice's log* *Bound: **NOT a verdict on the two-rate assignment*** — the row's question, and how well the comb constrains it is evidence toward that **NOT that f_0 is admissible**: the -0.304 is the family's own straight line extrapolated, reported because the order asked what the comb can decide, and the family is bounded by the two clocks **NOT a re-derivation of the sky's locating width**, which is 'P15_the_sky_phase_fit_and_its_uncertainty's and is taken as given **NOT that the injected runs are spectra of this model** — they are the projection's transfer of a known input, under separate keys *no mechanism beyond 'cc66.42's; nothing touches 'prop:flat'; no refit* *Run: python3 receipts/P15_CR_cosmology/P15_the_combs_resolution_is_four_multipoles_and_the_skys_own_value_lies_o*

P15R191 P15_the_locator_is_good_to_three_hundredths_and_the_fourth_peaks_residual_is_the_controls_too [OK]

node 66's work order 'r6941' (headed 'r6939'): **'PO-56' — the fourth peak, and the locator before the residual**. *'cc66.44' closed the clock route, so what is left undecomposed is the fourth peak — $222/538/818/1134$ against the sky's $220.4/537.7/817.3/1123.9$, peaks one to three within a grid step and peak four 10.1 out, and the comb fitted on the first three, which makes **peak four the only one of the four out of sample**. *But the first thing asked is the instrument: **establish the locator's own precision at each of the four peaks before reading any residual off them**, since it was validated at ℓ_1 and ℓ_4 sits where the damping has flattened the peak — with the stopping rule that **if the locator at ℓ_4 is worse than ten multipoles the residual is not measured and the order ends at step one**. Then (3) the three-way separation 'cc66.44' built, at every peak index, with the reading fixed in advance; and the guard: **is the four-peak pattern one systematic or two, and do not pick** — three candidate shapes named and none of them fitting, so the enumeration is probably incomplete* (**THE STOPPING RULE DOES NOT FIRE, AND IT MISSES BY A FACTOR OF FOUR HUNDRED.** *Run again at 'LSTEP=1 LMAXL=2000' — 1900 multipoles against the reported 238 , on both arms — the reported grid's locator recovers the fine-grid position to $0.0007/0.0126/0.0283/0.0176$ of a multipole on the control and $0.0035/0.0089/0.0167/0.0229$ on the arm.* ***two hundredths at ℓ_4 against a bar of ten***, *and the extremum search is insensitive to its own width (order 3 to 40 identical).* ***WHAT IS IMPRECISE IS THE PARABOLA'S WINDOW, AND IT IS A BIAS.** *Over 'PO-47's admissible $W=15 \dots 110$ the located peak moves $0.08/2.77/4.73/5.82$ on the arm and $0.11/2.98/4.97/6.49$ on the control — growing with peak index because a wider fit on an asymmetric, damping-suppressed hump pulls its apex down the envelope — so at ℓ_4 the window's bias is comparable to the residual, and it displaces the sky and both models alike, which is what matched-procedure differencing is for* (at $W=25$ it agrees with the three-point locator to 0.2). **AND THE ORDER'S PATTERN IS TWO ARTEFACTS, NEITHER OF THEM PHYSICS.** *First the quartet: $222/538/818/1134$ is 'sec:refit-bound's **line-of-sight** path, while every bank here is the **hierarchy** path, whose raw reading is $220/540/812/1132$ — and **at ℓ_3 the two bracketing 'LSTEP=8' bins differ by four parts in ten thousand, so which is called the peak is a coin flip**: the paper quotes 820 , this locator picks 812 , the sub-bin apex is 815.40 and the fine grid's own maximum is at 815 . Sub-bin the arm is $221.96/536.11/815.40/1130.53$, so the residual is $+1.56/-1.60/-1.90/+6.63$ — ***peaks two and three were never 'on', they are each about 1.7 LOW, and peak four is 6.6 out rather than 10.1 ***. **Second, and decisive: the CONTROL produces four fifths of it** — $-0.05/-1.41/-2.97/+5.32$ through the identical locator — so ***what is the construction's is $+1.61/-0.19/+1.07/+1.31$, a near-constant ONE multipole at all four peaks: a constant $\Delta \ell$, the FIRST of the order's three shapes, fitting half again better than the ruler's constant $\Delta \ell / \ell$ (rms 0.68 against 1.02) and nothing like a driving error growing with ℓ *** $\Rightarrow$ **So the pattern needs ONE systematic and not two**, and every one of the four displacements is inside the sky's own locating spread 'PO-47' measured (1121.9 ± 2.36 , arm-minus-control 0.83σ), so *the sky cannot tell it from zero and it is reported as a shape rather than a disagreement*. ** (3) AND THE SEPARATION

AT EVERY PEAK INDEX**: relocation \$31.2\{\}\text{to}94.1/83.4/89.3\{\}\%\$, the visibility's weighting \$9.2\{\}\text{to}26.4/22.7/23.5\{\}\%\$, the plasma \$59.6\{\}\text{to}-20.5/-6.0/-12.8\{\}\%\$ — ***\$\{\}\text{ell}_1\$ is the outlier and nothing else is: at \$\{\}\text{ell}_2\$ to \$\{\}\text{ell}_4\$ the motion is almost entirely geometric and the plasma's phase partially CANCELS it.*** *By the order's own reading the plasma's share does not grow, so the residual is not in the driving, and the relocation share does, which points at the ruler* — *but the third reading is the one that applies:* **the shares are not flat and the residual is not reached**, the family's motion being \$+0.6\$ to \$+0.7\{\}\%\$ with one sign at every peak while the residual alternates. *Motions resolved: fine against coarse they agree to \$0.02\$ of a multipole*). *Computes:* The fine reference is the reported configuration re-run at eight times the multipole sampling on both arms, 'HIER=1 LSTEP=1 LMAXL=2000' in 'KSLICE' pieces of 250 — 35 slices, one 'cr' slice costing 4m37s — with the standing switch guard of 'cc66.44' run on every distinct environment before the set and every slice's log checked after. *The 'VISLEAF' endpoints are re-run fine too, so (3)'s motions are measured rather than inherited, and they agree with the 'LSTEP=8' banks to \$0.02\$ of a multipole.* **No corpus edits, as the order directs** — the paper-side consequences (that 'sec:refit-bound's "the first three peaks land within a grid step" is the line-of-sight path's raw reading, and that on the hierarchy path sub-bin peaks two and three are each about \$1.7\$ low) are reported to 66 in 'FOR_66.md' rather than applied *Bound:* **NOT a mechanism** for the one-multipole constant offset — it is measured, named as a constant \$\{\}\Delta\{\}\text{ell}\$, and left **NOT a re-derivation of the sky's locating spread**, which is 'PO-47's and is cited **NOT that the window convention is an error** — it is a convention, and what is established is that it is shared and that the tight window agrees with the three-point locator **NOT that peak four is uninteresting**: it is the largest residual of the four, and what is shown is that four fifths of it is the control's *no verdict on the two-rate assignment; no refit; nothing touches 'prop:flat' or the clock family* *Run:* python3 receipts/P15_CR_cosmology/P15_the_locator_is_good_to_three_hundredths_and_the_fourth_peaks_residual

P15R192 P15_the_contrast_excess_is_symmetric_about_the_envelope_and_the_troughs_are_where_the_sky_measures [OK]

node 66's work order 'r6955': ***PO-56' — the troughs, which is where the \$\{\}\chi^2\$ actually lives**. *Four routes are eliminated — the contrast is not in the source at any grain, not the cross term, not absorbable by the clock assignment, not the comb residual — so what is left is the \$\{\}\chi^2\$: the spacing is right to a part in six hundred and the arm still scores \$1.43\$ per bin against the control's \$0.99\$.* **66's reading, stated as its own to be knocked down**: *the paper's discriminant of principle \$\{\}\theta_D/\{\}\theta_*\$ is a ratio of two lengths the plasma accumulates, so it rides ONE clock and a common difference cancels — while a trough DEPTH needs the diffusion scale in multipoles and so needs the projection distance, which rides the other. (2)^a Locate the excess before assuming it, decomposing the contrast into what the peak heights carry and what the trough depths carry* — **if it is in the peaks, stop and report**: (2)^b then the clock sensitivity of whichever carries it, against \$\{\}\mathrm{d}(\{\}\theta_D/\{\}\theta_*)/\{\}\mathrm{d}f\$; (2)^c and the sky's own spread on it, the way 'PO-47' did for the fourth peak. Guards: the window bias applies to troughs and worse; **path provenance in the receipt's header from now on*** (** (2)^a THE EXCESS IS SYMMETRIC ABOUT THE ENVELOPE, so it is neither trough- nor peak-dominated.** *Splitting the band variance of the envelope-normalised oscillation at its own zero — a decomposition, the parts adding to the whole to machine precision — the arm/control ratio is \$1.0668\$ on the positive side and \$1.0561\$ on the negative; at the literal extrema the arm exceeds the control by \$5.7\$ per cent at the maxima and \$5.3\$ at the minima.* $\Rightarrow$ ***It is an AMPLITUDE excess: \$\{\}\Delta\$'s trough dominance is a statement about the whitened residual and does not transfer to the contrast's own decomposition*** — which the order declined to assume, and the answer is that they disagree. *The stop condition does not fire either: the excess is not in the peaks, so the row is not pushed back onto the driving.* ** (2)^b THE DEPTHS ARE THREE TIMES THE MORE CLOCK-RESPONSIVE — \$-2.58\$ per cent across the 'VISLEAF' family against the heights' \$-0.77\$ — BUT \$\{\}\theta_D/\{\}\theta_*\$ MOVES \$-4.08\$, MORE THAN EITHER**, because \$r_D\$ is itself 'Jac'-weighted under 'LEAFSCALES' and the \$\{\}\tau\$ re-weighting moves it directly. $\Rightarrow$ ***The paper's discriminant of principle is the most sensitive of the three and not the insensitive one, so by the order's own rule the depths are not a new handle on the clock*** ** (2)^c AND YET THE TROUGHS ARE WHERE THE ASSIGNMENT BECOMES OBSERVABLE, FOR A REASON NEITHER SEAT NAMED: THE SKY MEASURES DEPTHS TWICE AS WELL AS HEIGHTS.** *Same data, same likelihood binning, same anchored locator, 'COV_TT' propagated by Monte Carlo: the sky's spread is \$0.00588\$ on the depth

and \$0.01135\$ on the height, seed-stable. The arm-minus-control excess is the same size in both — \$+0.0106\$ and \$+0.0103\$ — so it reads* $^{+1.81}_{-0.91}\sigma$ in the depths against \$+0.91\$ in the heights.* And the CONTROL lands on the sky’s depths at \$-0.05\sigma\$ while the arm sits \$+1.76\$ above.* the first statistic in this sector whose residual is NOT shared with the control*, against the fourth peak’s \$0.83\sigma\$ with both models high of the sky. $\Rightarrow$ So the order’s conclusion stands and its argument does not.* THE GUARDS*: the anchored depth has NO window bias — identical over \$W=20\ldots 70\$ on the sky and both arms, because it reads a *value* at a located extremum and not the *location* of one, where ‘cc66.45’*s* parabola apex drifted six multipoles at \$\ell_4\$ — while a FREE search under noise reproduces ‘PO-47’*s* trap at six times the spread, which is why the anchoring is necessary; and the envelope’s abscissa is worth about a third of a sigma and is reported rather than minimised*).
Computes: Path provenance in the header, as the order directs*: every model number is the *hierarchy* path (‘cc66_r185_verify_’, the ‘LSTEP=1’ fine references ‘r6941_fine_’, and the ‘VISLEAF’ family ‘r6929_scan_cr’ / ‘r6941_fine_cr_visleaf’), and ‘sec:refit-bound’*s* quartet is the *line-of-sight* path’s and is not read at all — searched for by grepping the receipt for each of the four values and for every line-of-sight bank name, none of which occurs in its code. *The sky side is ‘plik_lite’ TT through the likelihood’s own binning, with the models binned identically before any comparison, so matched-procedure differencing is by construction and not by assertion.* And this revision cost no solver time*: it is analysis on banks ‘cc66.44’ and ‘cc66.45’ already built, which is why the order’s three parts and three guards all fit in one revision *Bound:* NOT that \$1.8\sigma\$ is a detection* — it is \$1.8\$ of the sky’s own spread on one statistic, and the same differencing at the fourth peak gave \$0.83\$ NOT a mechanism* for the amplitude excess: this locates it and measures how well the sky sees it NOT a re-derivation of ‘PO-47’*s* peak-position spreads*, which are cited untouched NOT that the depths discriminate the CLOCK* — they do not, and that branch of the order’s reading is refuted here *no verdict on the two-rate assignment; no refit; nothing touches ‘prop:flat’ or the clock family; no corpus edits* *Run:* python3 receipts/P15_CR_cosmology/P15_the_contrast_excess_is_symmetric_about_the_envelope_and_the_troughs.a

P15R193 P15_the_windows_phase_spread_is_nearly_equal_because_the_visibility_widens_as_the_leaf_clock.s
[OK]

‘sec:refit-bound’ — the normalisation across the visibility is a real channel carrying about a *THIRD* of the contrast excess, and it is peak-weighted where the excess is symmetric — so it is the first partial mechanism in this sector and still not the whole one (node 66’s ‘r6959’ order, three items. (1)^a *Measure the source’s conformal-time dependence across the visibility window on both arms, and report it as a function rather than as a ratio****; (1)^b *imposing one arm’s normalisation on the other should move the contrast toward unity, and it should do so by an amount the measurement predicts in advance**** $\Rightarrow$ *predict the size first, then run it*”; (1)^c *state in advance what would REFUTE it**** and *say what the normalisation swap does to the comb and to the depths as well as to the contrast****. Guards: path provenance in the header (standing), *keep the two statistics apart** since two transfers had already failed to hold, and no detection language). *Computes:* (1)^a THE FUNCTION, AND A CANCELLATION IN IT.* The source’s own weight across the window, band by band in \$q\$, has its spread in the phase variable \$r_{\rm leaf}\$ at \$0.06523\$ of \$r_{\rm s}\$ on the control and \$0.06424\$ on the arm — *the arm narrower by one and a half per cent**, and only that much because *the arm’s visibility is 14.6\$ per cent WIDER in conformal time while its phase accumulates 13.7\$ per cent SLOWER per unit of it** (‘Jac’ \$0.789\$–\$0.913\$ against an identical \$1\$), the product coming to \$0.9890 \Rightarrow\$ *the two-rate structure reaches the window and then very nearly cancels inside it**** (1)^b THE ANALYTIC PREDICTION, PRE-REGISTERED*: $D_{\rm cr} / D_{\rm lcdm} = 1.00078$ to \$1.01654\$ against a measured \$1.0215\$ to \$1.0762\$ — *R5 (sign) survives, R2 (size) fires at 0.223\$ of the bar, R1 (shape) fires because the measured excess extrapolates to 1.0400\$ at \$q=0\$ where a characteristic function is identically 1**** AND R3’s BRACKET WAS WRONG IN DIRECTION, WHICH IS MINE*: ‘PREDICTION.md’ argued the contrast responds between \$f\$ and \$f^2\$; measured it responds \$2.3\$ to \$26\$ times MORE, at both coefficients and in every band, and the condition passed only because its tolerance was written on \$f\$ rather than on \$f-1\$ *THREE WIRINGS, THE FIRST TWO NOT THE OPERATION**: the all-terms taper cuts the ISW’s own \$\eta\$-integral to \$0.656\$ and \$0.238\$ of itself (moving \$\ell_1\$ by \$7.7\$ and \$27.3\$), and holding the window’s total weight fixed then lands on the ISW-preserving run to parts in ten thousand — *so that second diagnosis of mine was wrong too, and the over-response is the statistic’s own sensitivity**** THE

SIZE, FROM THE INSTRUMENT'S OWN TWO-COEFFICIENT RESPONSE RATHER THAN A MODEL OF IT**: the arm's own narrowing delivers **\$23\$ to \$45\$ per cent of the band excess above $q=1.9$ **, and the direct swap closes \$20\$ to \$39\$ per cent there — *the same answer by a different road* $\Rightarrow$ the narrowing for ALL of it is \$4.5\$ per cent against the arm's \$1.7\$, **a factor \$2.7\$** *(1)^c R4, AND THE REFUTATION FROM 66'S OWN PREVIOUS REVISION**: 'cc66.46' measured the excess symmetric about the envelope, and this channel is not — the arm-sized swap delivers **\$81\$ per cent of the peak-height excess and \$14\$ per cent of the trough-depth excess, a \$5.7\$-fold asymmetry** $\Rightarrow$ ***a peak-weighted channel cannot carry a symmetric excess alone, whatever its size, and that argument is independent of every size estimate*** the taper that would deliver the whole excess moves ℓ_1 by \$18.5\$ multipoles and the heights by \$45\$ per cent; the arm-sized one overshoots ℓ_1 past the arm's own value while ℓ_2 , ℓ_3 , ℓ_4 stay inside the sky's widths *Bound*: **NOT that the normalisation across the window is the mechanism** — it carries about a third, it is peak-weighted where the excess is symmetric, and R1's q -independent offset is outside it **NOT that it is nothing**: it is the first channel in this sector measured to carry any definite share, from a quantity nobody chose **NOT a claim about the term mix**, which is reported (the arm holds more of its window's power in the monopole in every band, \$0.1837\$ to \$0.2171\$ at $q=1.2$) and **not swapped** **NOT a detection**: the \$1.8\$ of 'cc66.46' is one statistic's spread and nothing here moves it NOT a verdict on the two-rate assignment; NOT a re-derivation of 'PO-47's peak spreads, which are quoted *The lowest band is the one the inversion cannot be trusted in and that is stated rather than averaged away: there the swap overshoots, taking the excess below unity* No refit, nothing touching 'prop:flat' or the clock family, and **no corpus edits** — the paper-side consequences are routed to 66 *Run: python3 receipts/P15_CR_cosmology/P15_the_windows_phase_spread_is_nearly_equal.because.the_visibility_wider*

P15R194 *P15_the_term_mix_has_the_shape_the_offset_needs_and_over_delivers_its_size* [OK] *'sec:refit-bound' — the term mix has the shape the q -independent offset needs and over-delivers its size by half again, so the two channels do not add and the "remainder" is a construct of the composition rule* (node 66's 'r6975' order, three items. (1) ****Decompose the excess into the peak-weighted part and the remainder, explicitly, and characterise the remainder rather than the whole****; (2) ****say what class of mechanism can produce a symmetric excess at all, before hunting one**** — **not a fitted direction and not a scan over knobs — a statement about what kind of thing it has to be, with the arithmetic that says so**; (3) ****the term mix you reported and did not swap ... swap it and report what it does to the contrast, the depths and the comb, with the prediction stated first****. Guards: path provenance (standing); **the pre-registration lesson from my own 'cc66.47' — **write the tolerance on the quantity that would move, not on the quantity it is derived from**; keep the two statistics apart; no detection language). *Computes: (1) THE REMAINDER.* Dividing the measured excess by what the window channel delivers at the arm's own size leaves \$1.0184\$ at $q=0$ — **\$46\$ per cent of the offset R1 fired on** — carrying \$123\$ per cent of the measured q^2 slope, and trough-weighted at \$0.49\$ where the channel that left it is peak-weighted at \$12.44\$ (2) AND THE STATISTIC HAS A BASELINE I HAD NOT COMPUTED. Applying each named class to the control's own spectrum and re-reading it with the same envelope and locator: amplitude \$1.96\$, envelope \$1.96\$, loading \$0.63\$, smearing \$-5.28 \Rightarrow\$ ***a SYMMETRIC operation reads \$1.95\$ here and not \$1\$****, stable across a fivefold range of operation sizes, because the running-mean envelope is recomputed and shifts the oscillation upward by a constant $\Rightarrow$ **so the anchored reading CONFIRMS 'cc66.46's variance split rather than contradicting it** — \$2.20\$ against \$1.96\$ is agreement to twelve per cent, and my own note that the two statistics disagreed is retracted in the pre-registration before the runs landed (3) THE TERM-MIX SWAP, ON A KNOB ALREADY WIRED. The coefficient giving the control the arm's monopole fraction is solved from the profiles and comes out \$0.860\$–\$0.897\$ in all seven bands — ***one constant to two per cent, so the difference is a single scalar on the Doppler and not a reshaping*** **T1 the sign passes** (the contrast rises in every band) **T2 the shape passes and is the finding: the response is q -INDEPENDENT**, the slope worth three per cent of the intercept (\$0.031\$ of it) with an intercept of \$1.0805\$ at $q=0$ — ***the first channel measured with the signature the offset needs, where a smearing's characteristic function is identically one*** **T3' the weighting FIRES**: \$2.23\$ and \$2.21\$ at the two coefficients, peak-weighted at the symmetric baseline, where the remainder it was to be is \$0.49 \Rightarrow\$ **the term mix is not the remainder** **and it OVER-DELIVERS**, raising the control's contrast by \$1.10\$ to \$2.77\$ times the whole excess, mean \$1.58\$ **T4 the comb fires and in the wrong direction**: ℓ_1 \$-1.04\$ and ℓ_2 \$-1.79\$, both outside the sky's

widths, where the arm sits at \$+1.61\$ **THE CONSEQUENCE, WHICH IS THE RESULT.** The window channel's third and the term mix's \$1.6\$ times together make \$1.72\$ times what is measured $\Rightarrow$ **they cannot both be present at their measured sizes and simply compose —** and (1)'s remainder is a **RATIO** of two responses, so it is a construct of that composition rule and not a residual channel****, which is why its \$0.49\$ and the swap's \$2.23\$ are not in conflict** **AND MY OWN (2) IDENTIFICATION IS REFUTED BY (3)**: I argued the Doppler fills the oscillation and removing it should read as the loading class near \$0.6\$; it reads \$2.23\$, and the profiles say why — its band-to-band power tracks the monopole's at correlation \$0.95\$, so it is an **OSCILLATING** term in quadrature and not a smooth additive one *Bound*: **NOT** that the term mix is the remainder **— T3' refutes that NOT that it is the mechanism**: it over-delivers by half again and moves the comb the wrong way **NOT that it is nothing**: it is the first channel measured to carry the $\$$ -independent signature the offset needs, from a difference nobody chose **NOT a replacement decomposition** — what is established is that the composition rule is at fault, and this receipt does not supply a better one **NOT a detection; NOT a verdict on the two-rate assignment; NOT a re-derivation of 'PO-47's spreads, which are quoted 'The lowest band is where the over-delivery is largest (\$2.77\$) and that is reported rather than trimmed' No refit, nothing touching 'prop:flat' or the clock family, and 'no corpus edits' Run: python3 receipts/P15_CR.cosmology/P15.the.term.mix.has.the.shape.the.offset.needs.and.over.delivers.its.size**

P15R195 P15.the.two.channels.compose.multiplicatively.and.the.pair.is.flat.where.the.excess.grows [OK]

*'sec:refit-bound' — the composition rule is MEASURED and it is multiplicative, which retracts 'cc66.48's inference and confirms its arithmetic: the two channels compose exactly as that revision assumed, and the pair is flat in $\$$ where the measured excess grows (node 66's 'r6983' order, one item. **PO-56 is no longer which channel carries the excess but how two channels compose** — 'cc66.48' divided one response into the excess, got a remainder, and argued the remainder was an artefact of a composition rule nobody had measured, so the order is to measure the rule. Guards: path provenance (standing); both coefficients as their own revisions solved them and **neither re-chosen**; every weighting reading against the measured symmetric baseline \$1.95\$ and not \$1\$; **no third channel**; no detection language). Computes: Both knobs on ONE control spectrum at the sizes their own revisions solved — 'SRCTAPER=1.100877765e-4 SRCTAPERS0=145.3465211 SRCTAPERNORM=1' from 'cc66.47' and 'DPSRC=0.8794' from 'cc66.48' — read against four conditions pre-registered before the run. **(1) T-SIZE PASSES and refutes QUADRATURE**: the joint lands within the pre-registered \$0.005\$ of the product in \$7\$ of \$7\$ bands and of the sum in \$7\$ of \$7\$, and of quadrature in \$0\$ of \$7\$, quadrature's worst miss \$0.018\$ being three and a half times the bar *the pre-registration declared in advance that product and sum differ here by at most \$0.0016\$ and are NOT separable; they are not separated, which is the declared outcome and not a failure* **and the pair is slightly SUB-multiplicative, consistently**: \$0.971\$ of the product and \$0.985\$ of the sum, below both in every band and above quadrature in every band **(2) T-WEIGHT PASSES and is the sharpest of the four**: predicted \$2.83\$ from the two channels' separate height and depth changes, bracket \$[2.2, 3.6]\$, and the joint reads **\$2.80\$** — one per cent from a number computed before the run, on an axis where quadrature predicts nothing at all **(3) T-COMB PASSES**: $\$ \setminus \{ \}$ predicted \$+1.79\$, bracket \$[+1.0, +2.6]\$, measured \$+1.41\$ — below the additive centre, the same mild sub-additivity the sizes show **(4) T-INTERCEPT PASSES**: the joint intercept against $\$q^{\{2\}}$ is **\$1.0993\$** against a multiplicative \$1.1035\$ with nothing fitted (\$0.0042\$ away), a sum's \$1.1019\$ (\$0.0026\$) and quadrature's \$1.0839\$ (\$0.0154\$, outside) **and the joint response is the flattest thing this sector has measured** — its $\$q$ -dependence is \$0.004\$ of its intercept against the term mix's \$0.031\$ and the measured excess's \$0.442\$, a factor of a hundred **THE CONSEQUENCE, IN THREE PARTS.** **Confirmed by direct measurement**: 'cc66.48' put the pair at \$1.72\$ times the excess by adding two separate shares; composing them in ONE spectrum reads \$1.70\$ **Retracted**: that revision inferred from the over-delivery that the channels do NOT compose as assumed, so a remainder got by DIVIDING one response into the excess was an artefact of a wrong rule — **the rule is now measured and it IS the assumed one**, so dividing is the right operation and the remainder is a well-defined object; the over-delivery was evidence about the SIZES, not about the RULE **And the obstruction that survives is a SHAPE no coefficient can remove**: the pair over-delivers \$3.87\$ times in the longest-wavelength band and \$1.38\$ in the shortest, because it is flat where the excess grows $\Rightarrow$ **scale it to the offset at $\$q=0$ and it is short at high $\$q$; scale it to high $\$q$ and it is an order too large at low $\$q$***

Bound: ****NOT** that the composition is exactly multiplicative****** — it is multiplicative to within the pre-registered bar with a consistent \$3\$ per cent deficit, and product and sum are NOT separated here, as declared in advance ****NOT** that quadrature is refuted as a rule in general******: it is refuted for THIS pair at THESE sizes ****NOT** that either channel is the mechanism****** — both over-deliver together and the shape argument says neither rescaling helps NOT a third channel, which the order forbids and none is added; NOT that the excess is explained; NOT a detection; NOT a verdict on the two-rate assignment; NOT a re-derivation of ‘PO-47’'s spreads, which are quoted *The joint spectrum is a sum of disjoint mode slices and the tiling is ASSERTED rather than trusted: the bank reconstructs each slice’s span from its filename and refuses unless the spans tile \$[0, 2547]\$ with no gap and no overlap — the run was re-sliced twice midway because this container is reclaimed faster than a large slice completes, which is exactly the circumstance a fixed-step check would have passed over* No refit, nothing touching ‘prop:flat’ or the clock family *Run:* python3 receipts/P15_CR.cosmology/P15.the.two.channels.compose.multiplicatively.and.the.pair.is.flat.where.

P15R196 P15.the.excess.decelerates.and.nothing.measured.in.this.arm.carries.its.wavenumber.dependence [OK]

‘sec:refit-bound’ — the excess *DECELERATES* with wavenumber, which excludes the parametrisation this sector quotes its own variation statistic in; and the first positive search the row has ever run comes back *EMPTY*, with nothing already measured in this arm carrying the dependence (node 66’s ‘r6993’ order, one item, ****redirecting this seat’s own stated next object****. cc66.49 left it as **what sets the sizes**; 66 moved it to ********‘what channel carries the excess’s own wavenumber dependence’********, on the argument that a shape refutation is not closed by any account of sizes — **and made it **the first POSITIVE search criterion this row has ever had***, every previous step having been an elimination*. (1) characterise the target’s shape before hunting; (2) enumerate what has that dependence and filter ****on paper****; (3) control the filter itself; (4) and nothing else. Guards: pre-register and make it cost something; the anchoring guard; ****a size and a shape are two objects****; the banking discipline). *Computes:* ****(3) RUN FIRST, AND THE INVERSION IS THE METHOD****: (3) asks about the INSTRUMENT, and its answer is what (1)’s pre-registration must write its tolerances on — the alternative is a guessed resolution ****a known \$q\$-dependence READS BACK****: six forms injected into the control’s own spectrum, including two turnovers with a SCALE in them, recover to a worst error of \$1.3\$ per cent ****but the estimator MANUFACTURES band-to-band structure**** — its per-band bias swings about one per cent and the six forms agree on it seven times more closely, so ********a constant contrast reads as a wobble******** and band ordering at the per-cent level is the instrument ****and the MEDIAN envelope is excluded with its mechanism, not dismissed, and would otherwise have been the headline****: it reads \$1.49\$ against the mean envelope’s \$0.44\$, and ********the tell is that it does not move with its own window******** — at high \$q\$ the running median collapses onto the curve itself, within \$3.6\$ per cent of it against the mean’s \$14\$, because the median of a locally monotone stretch is its central value whatever the window the rise survives the mean envelope at \$0.44/0.44/0.40 \Rightarrow\$ ********the RISE is real, the WOBBLE is not******** ****(1) THE RISE LINEAR IN \$q^2\$ IS EXCLUDED**** at \$\chi^2/\nu = 4.66\$, the only form excluded of six — ********and it is the parametrisation ‘cc66.47’, ‘cc66.48’ and ‘cc66.49’ all quote their variation statistic in******** the concave family all fit and ****none is preferred****, best-over-next \$\Delta\chi^2 = 0.43\$ against a bar of \$4\$ ****both pre-registered NON-separations held**** — power law against logarithm \$3.42\$, power law against turnover \$0.99\$ ****NO SCALE IS RESOLVED****, both scale-bearing forms putting \$q_0\$ with its uncertainty on the bottom edge — **and the rule as written caught this seat’s own code, which had asked only that the central value be inside* **the rise is a PREFERENCE and not an exclusion of flatness***: every rising form beats a constant by \$6.0\$ to \$10.4\$, yet the constant’s own \$\chi^2/\nu = 2.03\$ is under the exclusion bar ****(2) AND THE FILTER’S FIRST APPLICATION RETURNS EMPTY.**** The target’s departure grows by \$G = 3.55\$ with negative curvature; ********every candidate already measured in this arm fails the growth tooth******** — six source terms (\$0.54\$–\$1.00\$), the dipole-to-monopole ratio (\$1.08\$), and all three measured channels, window \$0.55\$, term mix \$1.53\$, the pair \$1.27\$ ****and the order’s own named candidate disagrees with the register****: recorded there as two per cent ABOVE the control and rising, it reads fourteen per cent BELOW and flat on the hierarchy path at each arm’s own visibility peak *Bound:* ****NOT** that the form is a turnover, a power law or a logarithm****** — none is preferred and that is stated as a non-separation ****NOT** that a scale exists or does not******: none is RESOLVED, which is weaker ****NOT** that the excess is inconsistent with flatness******: flatness is disfavoured, not excluded ****NOT** that the dipole-to-monopole ratio is eliminated****** — it fails the filter as measured

on the two-rate assignment *No ‘PREDICTION.md’ is written and the reason is stated rather than skipped: nothing is run, and the only test — the second tooth — is a criterion already fixed in ‘r6993’'s pre-registration, so it was committed before the measurement it is applied to* Nothing RUN; no refit; nothing touching ‘prop:flat’ or the clock family; no corpus edits *Run: python3 receipts/P15_CR_cosmology/P15.the.two.readings.are.different.quantities.and.the.projection.width.is*

P15R198 *P15.the.two.projection.widths.differ.by.the.jacobian.alone.and.the.channel.that.opens.is.a.qua*
[OK]

‘sec:refit-bound’ — *“the projection’s two widths differ by the JACOBIAN and by nothing else”, which makes the difference a prediction of the two-rate assignment rather than a property of this instrument; the contrast channel it opens is at most a quarter of the excess and fails the filter on curvature; and the filter itself is shown to be blind to sign* (node 66’s ‘r6999’ order, four items. (1) *“impose the conformal width at the size the arm HAS and not a fitted one”*, pre-registering every outcome *“including the one where it does nothing”*; (2) *“apply your own filter to it first”* — *“if it fails the filter on paper, that is the answer and the run is not needed”*; (3) *“is the width difference FORCED or CHOSEN”* — *“if it is forced by the construction, this is a CR prediction nobody has stated... that would be worth more than the contrast result”*; (4) the sub-period estimator SAID and not built. Guards: *“a statistic must carry its domain”*; *“say which quantity, always”*; exclude by mechanism; *“and pre-register the NULL”*). *Computes: “(3) THE WIDTH DIFFERENCE IS FORCED, AND BY ONE OBJECT.”* The two sound horizons are one integrand on two rates, so $d(r_{\{s,\}\rm leaf})/d(r_{\{s,\}\rm stack}) = \mathrm{Jac}$ — *“checked pointwise across the window to one part in a million on the arm and exactly on the control”*, where $\mathrm{Jac} \equiv 1$ by the rate identity *“On the RULER clock the two arms are the same instrument”*: the window’s conformal width against its width in $r_{\{s,\}\rm stack}$ agrees between them to 0.3% per cent on both core width definitions, *“the visibility being laid down in η by the same Thomson physics on both”* *“On the LEAF clock it is +14.5% per cent, and the whole of that is Jac — Jac share \$1.1484\$ against a leaf ratio \$1.1446\$, and the arm’s own leaf-to-ruler width ratio equals $\angle \mathrm{Jac} \angle$ to 0.4% per cent $\Rightarrow \mathrm{Jac} = H_{\rm phys}/H_{\rm leaf}$ has no free coefficient and is identically 1\$ on any one-rate cosmology, so the different ratio IS a prediction of the two-rate assignment”* (2) AND THE FILTER IS APPLIED IN THE INSTRUMENT’S OWN KERNEL”, the order’s operation done analytically: hold the source phase $\cos(k r_{\{s,\}\rm leaf})$ and stretch ONLY the Bessel argument by the measured $s=1.135$ *“and this corrects its own first pass by a factor of fifteen AND in sign”*: the plane-wave proxy $\int e^{-ik\eta} \int \mathrm{rvert} \int \mathrm{int} g e^{-ik\eta} \int \mathrm{rvert}$ assumes the Bessel argument advances at rate k , and $j_{\ell}(x)$ near its turning point $x \sim \ell$ — *“where the whole window sits, $kD_M \sim \ell$ being what the projection IS”* — oscillates at local rate $\sqrt{1-\ell^2/x^2}$, which vanishes there *“the sign is NOT determined on paper”*: mean-anchored $+0.0034$ to $+0.0196$, peak-anchored -0.0034 to $+0.0016$ and crossing zero, so G is UNDEFINED there — *“a stretch about the wrong point is a stretch plus a displacement, and a displacement moves the COMB”* *“verdict: curvature $+0.00016$ and $+0.00037$ against the target’s -0.00327 , so it ACCELERATES where the target decelerates, and at the top band it delivers $+1.96$ per cent against the $+7.62$ needed”* *“and the filter needed a THIRD tooth”*: the superseded numbers run -0.033 to -0.297 with $G=8.93$ and curvature -0.0014 , *“passing both pre-registered teeth while moving the contrast the wrong way in every band”* — G is blind to the common sign, so *“SIGN is now the first tooth”* (1) AND THE RUN CANNOT BE CONSTRUCTED”, which follows from (3): *“the arm’s conformal width at the same leaf width”* is *“the arm’s Jac ”*, and a control with $\mathrm{Jac} \neq 1$ is not a control *Bound: “NOT that the width does nothing”* — it is a real channel of measured size, bounded at a quarter of the excess at the top band *“NOT that it is the carrier”*: it fails the committed curvature tooth under both anchorings *“NOT a measurement of the contrast”*: the (1) run is not constructible on a one-rate control and is reported so rather than substituted for *“NOT that ‘cc66.51’'s 7.3% per cent was wrong”* — it is the RMS reading of the same object, and RMS weights the window’s long tails, which neither the projection nor the phase sweep responds to; the core measures agree with each other to better than a hundredth of a per cent at 14.5% *“NOT a claim about the comb or the peak positions”*, which the pre-registration marks as the warning sign rather than the result *NOT a detection; NOT a verdict on the two-rate assignment Nothing SOLVED; no refit; “no corpus edits”* — the order’s , and (4) is said and not built *Run: python3 receipts/P15_CR_cosmology/P15.the.two.projection.widths.differ.by.the.jacobian.alone.and.the.channe*

thing and the placement is the chat seat's Nothing SOLVED; ****no corpus edits**** Run: python3 receipts/P15_CR_cosmology/P15.the_held_period_estimator_reaches_below_the_floor_and_the_tooth_that_

P15R200 P15_the_lowest_band_is_closed_by_the_fields_and_the_excess_deceleration_is_carried_by_it_alone [OK]

*'sec:refit-bound' — **the lowest band is closed to any oscillation-amplitude estimator by the FIELDS, at an exact floor**; the excess's deceleration is robust in sign and is **carried by that same band alone** — and **is not robust to the envelope's definition**, which this seat reports against its own result; and the filter's third condition is permanently unavailable **exactly for the class of candidate the physics says can carry the excess*** (node 66's 'r7003' order, three items. (1) *****can the lowest band be reached by any estimator, or is it closed by the fields?*** — ***is that a property of the band's width, of its placement, or of the fields themselves... if the fields close it, then say so as a structural statement******; (2) *****is the TARGET's own curvature robust enough to carry the claim the paper makes?*** — ***I would rather learn that from you than from a reader******; (3) *****what can the filter still decide*** — ***is a two-condition filter with the third permanently unavailable simply not a filter?******; (4) *****nothing else*****. Guards: *****a stability check licenses the statistic it was run on and no other*****; sign first, growth after; *****a width — or a period, or a curvature — is not a quantity until its definition is named****; and *****pre-register the ways the measurement can fail to decide, not only its outcomes*****). Computes: ****(1) THE BAND IS CLOSED BY THE FIELDS AND THERE IS AN EXACT FLOOR.**** The criterion is named before use and is a necessary condition from identifiability rather than a chosen threshold: ***an oscillation amplitude at \$q_0\$ is identified only if the window holds a TURNING POINT on each side of \$q_0\$***, because over a span with no turning point the held-period pair is monotone and the baseline polynomial already spans it ****The monopole's turning points are \$0.996, \{, 1.915, \{, 2.912, \{ \dots\$ with NONE below the first** — the first excursion is one-sided — giving a floor \$q=1.455\$ against the dipole's \$0.962\$, so ****the monopole binds**** $\Rightarrow$ *****the filter's lowest band, \$q \in [0.85, 1.55]\$, lies \$86\$ per cent below that floor and every other band lies entirely above it***** ****And it is not the window, shown three ways****: the same eight widths at identical conditioning spread \$0.004\$ at \$q_0=1.90\$ and \$0.016\$ at \$1.20\$ with a sign change (***width***); sweeping the left edge, the departure is negative for every window opening past the monopole's first turning point and positive for every one staying above it, ***what lies below being the field's rise from its initial condition and not an acoustic oscillation* (*placement*)**; and ****every centre below the floor spreads by more than every centre above it****, which the floor was not fitted to (***prediction***) $\Rightarrow$ *****no estimator of an oscillation amplitude can reach inside the first excursion***** ****(2) AND THE TARGET'S CURVATURE, IN THREE PARTS.**** ******(a)**** robust within the statistic as defined******: negative in all six variants moving the envelope width, band edges and sampling, -0.00377 to $-0.00291$$, with band 1 stable at $+0.0201$ to $+0.0240$$ ******(b)**** and carried by band 1 alone******: with band 1 dropped the curvature runs -0.00121 to $+0.00031$$, ***sign not determined*** $\Rightarrow$ *****the deceleration is the lowest band being LOW, not the upper bands bending***** ******(c)**** and NOT robust to the envelope's DEFINITION****** — a running median, everything else unchanged, *****reverses it to $+0.00504$***$; that is a different statistic (its envelope absorbs about half the top band's oscillation on both arms) ****but it is not obviously the worse envelope****, so the honest reading is that the sign belongs to the statistic rather than to the excess ****(3) AND THE THIRD CONDITION IS NOT UNAVAILABLE IN GENERAL, WHICH IS WORSE THAN IF IT WERE****: it needs a band-1 value, and band 1 is closed to ***amplitude*** estimators but not to a candidate COMPUTED from the kernel — 'cc66.52's projection width had one and was excluded on curvature $\Rightarrow$ *****the filter's full strength is available exactly for the class that cannot carry the excess, and its third condition is permanently unavailable exactly for the class that can*****, since 'cc66.51' settled on physics that what fills a trough is an oscillation amplitude ****As an exclusion device it has lost nothing**** — each remaining condition is necessary and the exclusions already made were made on growth alone — ****and as a confirmation device it never worked, not with three either****: all three are conditions on SHAPE, and the candidate matches sign and growth direction while being 5.3 times smaller at the top band $\Rightarrow$ ***the row's remaining question is the coupling, which is quantitative and needs band 1 not at all*** **Bound: ****NOT** that band 1 is hard to measure**** — it is closed, and the distinction is the result ****NOT** that the deceleration claim must come out******: it is supported on its own statistic ****NOT** that it is independent of that statistic****** — the median envelope reverses it, and that exposure is reported rather than argued away ****NOT** that the candidate is confirmed or excluded******: it passes what can be applied, which is not a promotion, and a missing condition is not an acquittal ****NOT** a new channel****** — the coupling**$$$**

question is named as the question, not proposed; the order's (4) closes the list NOT a detection; NOT a verdict on the two-rate assignment Nothing SOLVED; **no corpus edits** *Run: python3 receipts/P15_CR_cosmology/P15_the_lowest_band_is_closed_by_the_fields_and_the_excess_deceleration.i*

P15R201 *P15_the_coupling_is_measured_and_negative_and_the_contribution_is_undetermined_because_its_in*
[OK]

'sec:refit-bound' — the coupling between the Doppler amplitude and the band contrast is MEASURED, is negative at every band on both envelopes over every interval, and is fixed by the construction; and the candidate's contribution is still undetermined, because the two readings of what the coupling multiplies disagree in SIGN — the third revision these two readings have decided an answer between them and the first in which they decide its sign (node 66's 'r7005' order, three items. (1) **the size, with the same discipline the shape work had** — **what fraction of the excess does it carry... and say whether the shortfall is constant across the range or grows — a constant shortfall is a coupling, a growing one is a second shape mismatch**; (2) **and what would set it** — **is the coupling... something the instrument fixes, or something the construction fixes? If the construction fixes it, the size is a prediction and not a fit**; (3) **and one thing about the statistic** — **does the candidate's contribution reverse with [the median envelope], or does it survive both**; (4) **nothing else**. Guards: **a claim and its implied independence are two claims**; **name the criterion before using it, and prefer a necessary condition to a threshold**; **a stability check licenses the statistic it was run on and no other**; **pre-register the failure modes ahead of the outcomes**. And: **do not revisit the envelope question to settle it**). *Computes: THE COUPLING IS MEASURED, NOT MODELLED.* *'DPSRC' scales the Doppler source term, so the three banked control spectra at 'DPSRC' $s=1, \{0.8794, 0.6\}$ give $d \ln C / d \ln s$ per band as a finite difference — three points, so the linearity is CHECKED and not assumed, and it steepens towards $s=1$ at all seven bands, so the local slope there is both the applicable one and the one measured over the shortest step Near $s=1$ on the arithmetic envelope it runs -0.45 to -0.80 with **no trend in q** $\Rightarrow$ **NEGATIVE AT EVERY BAND, ON BOTH ENVELOPES, OVER EVERY INTERVAL — forty-two measurements of the sign and not one positive** — **more Doppler fills more trough and LOWERS the contrast, which is 'cc66.51's own trough-filling physics read forwards** (2) **AND THE CONSTRUCTION FIXES IT, SHOWN BY WHAT DOES NOT CHANGE IT**: the control's own Doppler-to-monopole band-power share runs 4.30 down to 0.65 , **a factor of 6.6 across the bands, and the coupling's sign is the same at every one** $\Rightarrow$ **a quantity whose sign is invariant across a factor of six in the very ratio it depends on is not set by a knob** — **'DPSRC' is the probe**, not the setter, **so the size is a prediction and not a fit** **and the one thing not measured is stated: all three 'DPSRC' banks are the CONTROL, so the arm's coupling is assumed to be the control's; its share differs by about a fifth against the factor of six across which the sign does not move, so the assumption cannot reach the sign and is not asked to reach more** (1) **AND THE CONTRIBUTION IS NOT DETERMINED — NOT BECAUSE OF THE COUPLING BUT BECAUSE OF ITS INPUT.** The criterion was named before use: **the coupling multiplies a fractional change in the Doppler's oscillation amplitude relative to the monopole's** — and two measured quantities claim to be it and **disagree in sign**: the FIELD reading ('cc66.51's held-period estimator at last scattering) has the arm **higher** by $+0.5$ to $+1.4$ per cent $\Rightarrow$ contribution -0.004 to -0.010 , **-7 to -13 per cent of the excess, the WRONG SIGN**; the PROJECTED reading ('cc66.50's quantity, the square root of the banked 'w2dp/w2sw' share, **which is what 'DPSRC' actually scales**) has it **lower** by 10 to 13 per cent $\Rightarrow$ contribution $+0.066$ to $+0.108$, **$+188$ down to $+94$ per cent, the RIGHT SIGN** $\Rightarrow$ **the coupling turns a disagreement about a quantity into a disagreement about whether the candidate helps at all — a factor of seven in magnitude even at their closest** **And the order's second half: the fraction is NOT constant on either reading — it grows in magnitude on the field reading and FALLS on the projected one** $\Rightarrow$ **a SHAPE MISMATCH and not a coupling deficit, on either, and the fourth this sector has found**; the coupling being flat, the q -dependence belongs to the input (3) **AND THE ENVELOPE QUESTION HAS THE GOOD ANSWER**: the coupling's sign survives both envelopes at every band, so **the contribution does not reverse with the statistic and the coupling question does not inherit the envelope ambiguity** — though its magnitude does, the median envelope's coupling reaching $2.2 \times$ the arithmetic one's at the top band, **so a quoted FRACTION inherits the ambiguity while the SIGN does not, said before any fraction is quoted** *Bound: NOT that the candidate is excluded — one reading of its input has it carrying essentially all of the excess NOT that it is the carrier — the other**

has it working against the excess, and neither is chosen **NOT** a resolution of the two readings^{cc66.51}: chose between them once and this revision shows the choice decides the sign, so choosing again is exactly what is not done **NOT** an envelope choice^{cc66.51} — the order forbids it; both are carried and no conclusion rests on one **NOT** a claim about the arm’s coupling^{cc66.51} — it is the control’s, transferred, and only as far as the sign **NOT** a new channel^{cc66.51}: the bank that would settle the input is named, not proposed Nothing SOLVED; **no corpus edits** *Run: python3 receipts/P15_CR_cosmology/P15_the_coupling_is_measured_and_negative_and_the_contribution_is_undetermined*

P15R202 P15_the_bank_already_existed_and_the_doppler_carries_a_growing_minority_of_the_excess [OK]

‘sec:refit-bound’ — *the bank the row needed already existed*, so the ARM’s coupling is now measured rather than transferred; the Doppler carries *a growing MINORITY* of the excess and is sign-indefinite at the bottom^{cc66.55}; and *the four shape mismatches share a reason that is about the excess and not about the candidates* (node 66’s ‘r7007’ order, three items. (1) **bank** the oscillation amplitude of the projected contribution^{cc66.55} — **say** what the instrument has to emit for that... and if it cannot emit it without a change this seat should not make unilaterally, say that and stop^{cc66.55}; (2) **then** the contribution, with the fraction carrying both envelopes^{cc66.55}, pre-registering every outcome^{cc66.55} including the one where the right quantity lands between the two wrong ones and settles nothing^{cc66.55}; (3) **and** the fourth shape mismatch counted rather than passed over^{cc66.55} — **four** is a pattern rather than a run of bad luck... if they share a reason, that reason is the sector’s real finding^{cc66.55}; (4) nothing else. Guards: **the knob is the probe** and not the setter^{cc66.55}; **do not choose between two readings of a quantity, name the quantity**; a claim and its implied independence are two claims; **pre-register the failure modes**, including **settles nothing**^{cc66.55}. And: **do not choose an envelope**, still). *Computes*: **(1) THE INSTRUMENT ALREADY EMITS IT AND THE BANK IS ALREADY ON DISK**.^{cc66.55} ‘SRCDEC’, added at ‘r6915+cc66.41’, writes the full bilinear decomposition — $\sum_{\ell} C_{\ell} = \sum_{\ell} \sum_{\ell'} w_{ab} \sum_k P_{\ell} \Delta^a \Delta^b$, **ten** ℓ -resolved terms per multipole summing to C_{ℓ} exactly^{cc66.55} — and ‘r6915_pairs_lcdm,cr’ carry them for both arms, to 1.2×10^{-15} $\Rightarrow$ **no run, no instrument change, and the order’s escape hatch is not needed**. And the coarse grid is checked rather than assumed: **238** multipoles against **1900** reads the contrast **1.9** per cent low, and the deficit agrees between the arms to 3×10^{-4} , so it CANCELS in the ratio — the only thing read from it **AND THE BANK DISCHARGES A CAVEAT ‘cc66.55’ COULD ONLY STATE**: the s -scaling of every pair is exact (s^2 on ‘dp*dp’, s on the three ‘dp’ crosses), so $d_{\ell}/d_{\ell'} \ln s$ is exact per multipole and **the coupling follows analytically FOR THE ARM as well as the control** — -0.48 to -0.86 on each, **equal between the arms to 4** per cent^{cc66.55} and agreeing with ‘cc66.55’s three-point finite difference to **7** **AND THE FIRST CONSTRUCTION IS REPORTED AS FAILED RATHER THAN DROPPED**: $\sqrt{\frac{\text{osc}(\text{dp*dp})}{\text{osc}(\text{sw*sw})}}$ is small on the arithmetic envelope and reaches **+134** per cent under a median one, **because** the oscillation of a weak smooth term about a median envelope is not well conditioned^{cc66.55} $\Rightarrow$ that definition inherits the envelope ambiguity through its **own** conditioning, so it is not used **WHAT IS USED NEEDS NO EQUIVALENT- s STEP: A ONE-AT-A-TIME SWAP** — the arm’s four Doppler-containing pairs replaced by the control’s, envelope-scaled, on the arm’s own q grid, the share being $(C_{\ell}^{\text{arm}} - C_{\ell}^{\text{swapped}})/(C_{\ell}^{\text{arm}} - C_{\ell}^{\text{control}})$; **same shape of operation as ‘SRCINJRS’**’s clock swap, which the instrument already sanctions^{cc66.55} **(2) AND THE CONTRIBUTION IS A MINORITY SHARE THAT GROWS AND IS SIGN-INDEFINITE AT THE BOTTOM**: -12 to $+17$ per cent on the arithmetic envelope, -20 to $+48$ on the median one, negative at $q=1.90$ on both $\Rightarrow$ **the candidate is NOT the carrier** **It lands between the two wrong readings, which said -13 and $+188$ per cent** — the outcome the order required be tabled first — **and it does not settle nothing: it settles that the candidate is a real but minority contributor, which neither wrong reading said** **And ‘cc66.55’s split is confirmed rather than assumed: the coupling’s SIGN is the same on both envelopes while the FRACTION moves by 2.7×10^{-4}** **(3) AND THE FOUR MISMATCHES DO SHARE A REASON, AND IT IS ABOUT THE EXCESS**. The excess has **ONE** dominant feature: **band 1 is 0.33 of the mean of the rest and sits 4.9 scatters below it**, while above band 1 a constant already fits (0.0088 scatter on a mean of 0.0645) and a line only halves the residual $\Rightarrow$ **the excess’s q -structure is a STEP at the lowest band, not a trend** — and all four candidates were judged on a trend across bands 2–7, where the excess is very nearly featureless^{cc66.55}: a flat candidate matches the flat part and misses the step, a rising one matches

the mild rise and misses the step, and there the two are barely distinguishable $\Rightarrow$ **the sector has been spending its discriminating power where the excess has least structure, because the part that has the structure is the band ‘cc66.54’ showed it cannot measure a candidate in** *Bound: NOT that the excess is explained* — a minority share is not an explanation *NOT that the candidate is excluded*: it contributes measurably and its share grows *NOT a definite share at the bottom bands* — negative at $\$q=1.90\$$ on both envelopes, so it cannot be told from zero exactly where the excess’s structure is *NOT an envelope choice*: both carried, the order’s refusal held for the second revision *NOT a claim on the failed construction’s arithmetic number* — it is reported as failed, with its reason, and is not quoted as the answer *NOT a new channel*: nothing proposed; (4) holds Nothing SOLVED, nothing RUN; *no corpus edits* *Run: python3 receipts/P15_CR_cosmology/P15_the_bank_already_existed_and_the_doppler_carries_a_growing_minority.o*

P15R203 *P15_the_step_is_the_excesss_own_and_it_sits_at_the_second_acoustic_peak_and_none_of_the_four_pr*
[OK]

‘sec:refit-bound’, ‘sec:scope’ — the step is the excess’s and not the estimator’s, surviving three envelopes and one reading that needs none, with the edge hazard ruled out the right way round; it sits at the SECOND ACOUSTIC PEAK to $\$0.9\$$ per cent and is sharper than the window that found it; and all four candidates can be scored on it and none of them produces it (node 66’s ‘r7009’ order, three items, *sequenced*. (1) *is the step the excess’s or the estimator’s* — pre-register that before anything else — *“a step at the lowest band is exactly where an envelope artefact would sit... I would rather lose the step now than build two revisions on it”*; (2) *then locate it as a scale* — *“if the step’s location coincides with a scale the construction fixes, that is the carrier’s signature and it carries no free coefficient”*; (3) *and re-score the four candidates on the step rather than on the trend*; (4) nothing else. Guards: *a step at the edge band is where an edge artefact lives*; the knob is the probe and not the setter; do not choose between two readings, name the quantity; *report a failed construction as failed and date it*; pre-register the failure modes including the one that embarrasses the revision. And: *do not choose an envelope — add a third*). *Computes: THE SEQUENCING WAS HONOURED AND IS CHECKED*: the pre-registration says in terms that nothing in (1) had been computed when it was written, names the step’s definition before use (*band 1’s excess over the mean of bands 2–7*), and *tables FIRST* the outcome that withdraws ‘cc66.56’s (3) — which ‘r7009’ had already landed in two sections *(1) THE STEP SURVIVES EVERY READING*. Three envelopes differing in *kind* — running arithmetic mean, running median, local quadratic (Savitzky–Golay) — and one that needs *no window at all*, the peak-to-trough depth per acoustic cycle: step ratios $\$0.333\$$, $\$0.391\$$, $\$0.633\$$, $\$-0.025\$$, *never near one* *And the envelope-free reading is the sharpest: band 1’s excess on it is $\$-0.0017\$$, indistinguishable from zero, against a bands 2–7 mean of $\$+0.0654\$$* *AND THE EDGE HAZARD IS RULED OUT THE RIGHT WAY ROUND*, which is what makes it ruled out: band 1’s envelope comes within $\$0.018\$$ in $\$q\$$ of truncating, but moving its lower edge UP from $\$0.85\$$ to $\$1.15\$$ makes it read $\$+0.0215 \setminus \{\}$ to $\$+0.0361\$$ — *higher, where a truncation artefact would have to make it read lower* *Its SIZE is reading-dependent and is quoted as a range — band 1 between none and two thirds of the rest — not as a number; no envelope is chosen* *(2) AND IT SITS AT THE SECOND ACOUSTIC PEAK*. The half-rise point in sliding windows at three widths is $\$q = 1.789, \setminus \{\}, 1.788, \setminus \{\}, 1.805\$$ — $\$1.794 \setminus \{\}$ *pm $\$0.008\$$* — against the second peak at $\$1.7775\$$ (control) and $\$1.7760\$$ (arm): *a match to $\$0.9\$$ per cent, where the nearest other scale the construction fixes — the monopole’s second turning point at $\$1.915\$$ — is seven per cent away and $\$q=2\$$ is twelve* *And the plateaux are $\$0.026\$$ below and $\$0.053\$$ above on all three widths: a factor of $\$2.0\$$ reached within about a tenth of a comb period, sharper than the narrowest window that found it $\Rightarrow$ the excess is one size in the first acoustic cycle and twice that in every cycle above it* *(3) AND ALL FOUR CAN BE SCORED ON THE STEP, AND NONE PRODUCES IT*. The window weighting and the term mix were measured *flat in $\$q\$$* , and a flat candidate’s step ratio is exactly one, by construction and without a new number; the *projection width* (kernel-class, reachable at band 1) is fitted by a straight line in $\$q\$$ to $\$2.6\$$ per cent of its own range, *so linear, no step*; and the *Doppler* by the swap route that reaches band 1 runs $\$-0.0016\$$ to $\$+0.0014\$$ in sliding half-period windows with means $\$-0.0001\$$ below the step and $\$-0.0002\$$ above — *noise at the step’s resolution and no transition at all $\Rightarrow$ this is NOT the identifiability floor closing over the list — every one of the four WAS evaluable — it is the list EXHAUSTED against the right feature, for the first time* *Bound: NOT that the step is a mechanism* — *a step at a scale is a signature to be explained*, which the pre-registration said would not be claimed *NOT a*

on **both** the windowed and the window-free contrast: the control departs from its own bands 2–7 trend by \$+30\$ to \$+44\$ per cent at band 1 and the arm by \$+27\$ to \$+39\$, **the arm always the SHALLOWER**, by some eleven per cent of the step $\Rightarrow$ **SO OF A STEP WORTH TENS OF PER CENT IN EACH SPECTRUM, ABOUT NINE TENTHS IS COMMON TO THE TWO ARMS AND CANCELS IN THE RATIO; THE EXCESS'S STEP IS THE TENTH THAT DOES NOT** **That is the pre-registration's "both arms" row** — the step belongs to the acoustic physics the two share — and it explains, without a new number, why 'cc66.57' found the location at fixed \$q\$ on BOTH arms *Bound:* **NOT** that the excess is ZERO below the step — the order's stronger claim is *not established*, and *not excluded* either, because the one reading that suggested it has no resolving power there **NOT** that any candidate produces the step — the term mix carries a minority of it in the right direction and the window channel pushes the wrong way, which is a PARTIAL account and not a producer **NOT** that the flatness was measured circularly — the range was full; it is the STATISTIC that was wrong, and that is the half this seat owns **NOT** a mechanism, an envelope, a basis, or a new candidate — (4) holds; four bases are reported and none chosen, for the fourth revision running on the same discipline **AND THE CAUTION IS THIS SEAT'S, NOT THE ORDER'S**: a small residual of two large common features is exactly where a nearly-common systematic would sit, so the next reading of the step should be **differential by construction** rather than a difference of two large numbers Nothing SOLVED, nothing RUN; **no corpus edits** *Run:* python3 receipts/P15_CR_cosmology/P15_the_window_free_reading_cannot_resolve_the_first_cycle_the_flatness.w

P15R205 P15_the_step_survives_a_differential_estimator_and_no_single_bilinear_term_carries_the_shared [OK]

'sec:refit-bound', 'sec:scope' — **the step SURVIVES an estimator in which the two large common steps are never formed**, so the tenth that failed to cancel is not the residual of two large numbers; **no single bilinear term carries the shared step and it is a property of the SUM**, though the two highest-leverage terms both carry a Doppler factor; and **the "42 per cent" is 42 per cent of the EXCESS's step**, not of the shared one (node 66's 'r7015' order, three items, on this seat's own closing caution. (1) **build the differential estimator: ratio first, contrast second** — **everything so far forms each arm's contrast and then compares** — two large numbers each carrying a large step, with the object of interest in the difference", and the test named in advance: **does the step survive at the size the present route gives it, and at what significance**; (2) **name the shared nine tenths, because the bank already can** — **does the shared step live in one term, or in a few**, and **a better-posed residual is worth more than a bigger one**; (3) **say which step the 42 per cent is 42 per cent of** — **if the pair carries two fifths of the EXCESS's step that is a large result; if it carries two fifths of the SHARED step, most of what it accounts for cancels**; (4) nothing else. Guards: **a statistic that fits a trend cannot see a step** — score on the residual"; **envelope-free** is about bias, not resolution; **a small residual of two large common features is where a nearly-common systematic sits**; **and when a feature is mostly common, say which part a share is a share of**; **pre-register the outcome that costs you most, first** — **and commit it separately**). *Computes:* **THE SEQUENCING**: 'PREDICTION.md' is its own commit ahead of the working script, tables FIRST the outcome that **ends the row's present object**, and names **both** hazards the new estimator carries — its phase sensitivity and the conditioning of a division whose divisor passes through the first acoustic trough INSIDE the band under test — before either was looked at **(1) THE STEP SURVIVES THE DIFFERENTIAL ESTIMATOR**. **Writing each arm as** $D = E(1+o)$, the present route forms $\operatorname{std}(o_a)$ and $\operatorname{std}(o_c)$ and divides; the ordered route forms $R = \frac{D_a}{D_c}$ and takes the contrast of **that**, so it reads $\operatorname{std}(o_a - o_c)$ and **the common oscillation divides out before any width is taken** Band 1's departure from its own bands 2–7 trend is \$-0.374\$ to \$-0.387\$ per common ℓ and \$-0.382\$ to \$-0.383\$ per common q : **same sign on all four trend bases AND both abscissas**, at \$3.2\$–\$3.6\sigma\$, about 65% of the present route's fractional size $\Rightarrow$ **SO THE TENTH THAT FAILED TO CANCEL IS NOT THE RESIDUAL OF TWO LARGE NUMBERS — IT EXISTS IN AN ESTIMATOR IN WHICH THE TWO LARGE NUMBERS ARE NEVER FORMED** **And the conditioning hazard does not fire** — the control never falls below \$0.67\$ of its band median — while the **smoothed-divisor control** turns the departure POSITIVE, back toward the arms' own \$+0.3\$: **it is the differencing, not the division, that produces the negative step** **(2) NO SINGLE BILINEAR TERM CARRIES THE SHARED STEP**. **The 238-multipole 'SRCDEC' total first reproduces the 1900-multipole**

step to better than \$0.006\$ in departure on **both** arms, which is what licenses a per-term reading; then removing each term in turn, **the losses sum to \$182\{\}\%\$, far more than one** **the step is not additive and is a property of the SUM** — the pre-registered null **But the LEVERAGE is not flat, and that is what the null leaves standing: each term's share of the STEP against its share of the OSCILLATION puts the two highest-leverage terms BOTH on a Doppler factor — 'sw*dp' at \$5.59\{\}\times\$ and 'dp*dp' at \$3.80\{\}\times\$, against the best non-Doppler 'sw*isw' at \$1.23\{\}\times\$ — while the monopole 'sw*sw' carries \$88\{\}\%\$ of the oscillation at only \$0.72\{\}\times\$** **a step-weighted reading of the bilinear decomposition is led by the Doppler where an amplitude-weighted one is led by the monopole** **(3) THE 42 PER CENT IS 42 PER CENT OF THE EXCESS'S STEP**, read off 'cc66.58's own file and gated on it: it divided by the departure of 'MEAS - 1.0', and a channel response and the excess are both ratios to the SAME control **the large reading** **And the two normalisations are ONE departure, \$-0.0323\$ in excess units — \$-0.601\$ of the excess's own extrapolated size and \$-0.100\$ of the control's contrast departure —** **provable rather than asserted, because the arms' own log-departures differ by that same number to \$4.6\$ per cent** **Bound:** **NOT that the differential estimator measures an AMPLITUDE difference** — $\{\}\operatorname{std}\{\}\{\operatorname{o_a} - \operatorname{o_c}\}$ is sensitive to a **phase** difference too, named in the pre-registration before the measurement: a null on it would have been strong, a signal on it does not by itself say amplitude, and its absolute size carries no expectation **NOT that the Doppler PRODUCES the shared step** — **leverage is not authorship**, and the non-additivity is the reason it is not **NOT that every Doppler term leads**: 'dp*isw' has NEGATIVE leverage at $-0.91\{\}\times$, and 'isw*isw' at $-2.07\{\}\times$ sits lower still, so the ordering is not Doppler-versus-not **NOT a naming of the shared step** — (2) is a null on "one term" and a naming only on "which sector" **NOT an envelope, a basis, an abscissa, a candidate or a mechanism** — (4) holds, and **two abscissas are reported with neither chosen**, the same discipline extended to the degree of freedom this estimator introduces Nothing SOLVED, nothing RUN; **no corpus edits** **Run:** python3 receipts/P15_CR_cosmology/P15_the_step_survives_a_differential_estimator_and_no_single_bilinear_term

P15R206 P15_the_surviving_step_is_amplitude_and_not_phase_and_the_candidate_shares_do_not_survive_the_ [OK]

'sec:refit-bound', 'sec:scope' — **the surviving step is an AMPLITUDE feature and not a PHASE one**, so the first acoustic cycle is WEAKENED rather than displaced and the row is not re-framed; **the candidate shares do not survive the change of denominator**, the window channel reversing sign and the realised pair falling to zero; and **the step does not compose the way the contrast does** — the two knobs nearly cancel where they multiply (node 66's 'r7017' order, three items, on this seat's own pre-registered caveat. (1) **amplitude or phase — decompose the surviving step** — **the surviving step might not be a contrast feature at all; it might be a phase feature of the first acoustic cycle, and those are different objects with different physics behind them**, with the reframing outcome to be tabled first and **an inseparability is a finding here, not a gap**; (2) **re-score the candidates on the differential estimator** — **every share in the row is measured on the ratio-of-contrasts route, where nine tenths of the feature enters and cancels**; (3) **does the step compose the way the contrast does** — **if it composes differently, that is a new property of the step and it is worth more than the share**; (4) nothing else. Guards: **a differential estimator is a different quantity, not a cleaner version of the same one**; **a share needs its denominator named in the same breath**; leverage is not authorship and a matching size is not authorship either; a statistic that fits a trend cannot see a step; **and pre-register the outcome that reframes the row, first**). **Computes:** **THE SEQUENCING**: 'PREDICTION.md' is its own commit ahead of the working script, tables **phase** — the reframing outcome — first, carries an explicit **inseparable** row, puts a licence gate before the reading, and **names the amplitude/phase trade-off hazard before it was met** **(1) THE DECOMPOSITION IS AN IDENTITY, NOT A FIT.** With $\operatorname{o_c} = \operatorname{A_c}\{\}\cos\{\}\psi$ and $\operatorname{o_a} = \operatorname{A_a}\{\}\cos\{\}\psi + \{\}\Delta$, $\{\}\operatorname{std}\{\}\{\operatorname{o_a} - \operatorname{o_c}\} = \{\}\operatorname{frac}\{\operatorname{A_c}\}\{\sqrt{2}\}\sqrt{\operatorname{r}^2 - 2\operatorname{r}\{\}\cos\{\}\Delta + 1}$, amplitude-only $\{\}\operatorname{frac}\{\operatorname{A_c}\}\{\sqrt{2}\}\sqrt{\operatorname{r} - 1}\operatorname{rvert}$ and phase-only $\{\}\operatorname{frac}\{\operatorname{A_c}\}\{\sqrt{2}\}\sqrt{\sin\{\}\Delta/2}\operatorname{rvert}$ — **reproducing the difference's own measured comb amplitude to \$0.00\{\}\%\$ pointwise**, so the gate passes exactly **AND THE ANSWER IS AMPLITUDE**: the amplitude-only term keeps its sign at every window half-width and tracks the full statistic (\$-0.227\$ to \$-0.260\$ against \$-0.204\$ to \$-0.236\$), supplying \$0.958\$ of it at band 1 against phase's \$0.284\$ **SO THE STEP IS A WEAKENING OF THE FIRST ACOUSTIC CYCLE, NOT A DISPLACEMENT**

OF IT, AND THE ROW IS NOT REFRAMED*** *But the phase channel is **unresolved, not merely small**: its departure runs $\$+3.54\$, \$+0.66\$, \$-0.46\%$ across three half-widths and **changes sign** where the amplitude term's does not — the pre-registered trade-off firing. The relative phase is $\$0.0068\%$ rad, $\$0.39\%$ degrees, against a relative amplitude of $\$0.0554\%$ $\Rightarrow$ **amplitude on the sign, inseparable on the share**, and what would separate them is named: a phase read against the comb itself over a longer lever arm in $\$q\%$ **AND A CORRECTION TO 'cc66.59' THE DECOMPOSITION FORCED**: a band spans $\$0.70\%$ in $\$q\%$ against a comb period of $\$1.00\%$, so **a raw band 'std' samples an incomplete cycle and is phase-dependent by construction** — the step reads $\$-0.45\%$ on that route and $\$-0.22\%$ on the phase-insensitive one, **surviving on both, neither chosen** ***(2) AND THE SHARES DO NOT SURVIVE THE CHANGE OF DENOMINATOR.** On the differential estimator: the **window channel steps $\$+1.05\%$ to $\$+1.32\%$, OPPOSITE in sign to the arm's**>; the **term mix is no longer a step** where it carried $\$63\%$; and the **JOINT changes sign across the bases** and measures zero to within its own scatter where it carried $\$42\%$ $\Rightarrow$ ***A CHANNEL THAT ACCOUNTS FOR TWO FIFTHS OF A MOSTLY-SHARED QUANTITY ACCOUNTS FOR NOTHING OF THE PART THAT IS THIS COSMOLOGY'S*** ***(3) AND THE STEP DOES NOT COMPOSE THE WAY THE CONTRAST DOES.** Product, sum and quadrature predict $\$+0.84\%, \$+1.03\%, \$+1.19\%$ where the realised pair measures $\$-0.014\%$ — **six to nine of the joint's own scatters away, none fitting** — against 'cc66.49's contrast composing multiplicatively, product 7 of 7 $\Rightarrow$ *the two knobs very nearly **cancel** on the step where they **multiply** on the contrast* *Bound:* **NOT that the phase channel is measured to be small** — it is **unresolved**: the trade-off fires, its sign moves with the window, and the honest reading is amplitude-on-the-sign with the share inseparable **NOT that the term mix and the pair are excluded** — they are **not resolved** on the differential estimator, which is a weaker statement than exclusion and is the one the scatter supports **NOT a mechanism** — *the first acoustic cycle is weaker in this cosmology" is a signature, not a cause*, and (4) holds **NOT a chosen aggregation**: the raw band 'std' and the held-period amplitude are **both** carried, as the four bases and two abscissas are **NOT a percentage share on (3)** — the joint's departure is consistent with zero, so residuals are in departure units against its own scatter; ***a percentage of a near-zero measurement would be meaningless, which is this line's own guard about denominators turned on itself*** Nothing SOLVED, nothing RUN; **no corpus edits** *Run:* python3 receipts/P15_CR_cosmology/P15_the_surviving_step_is_amplitude_and_not_phase_and_the_candidate_share

P15R207 P15_no_statistic_this_construction_can_build_resolves_the_two_channels_and_the_phase_step_dies [OK]

*'sec:refit-bound', 'sec:scope' — **no statistic this construction can build resolves the two channels against the step**: the minimum resolvable share is $\$0.59\%$ – $\$0.75\%$ on every route banked while the channels carry $\$0.35\%$ and $\$0.03\%$; **the phase step dies on a matched-width control**, so the amplitude verdict is complete rather than sign-only; and **the composition cancellation is aggregation-dependent** rather than exact or approximate (node 66's 'r7019' order, three items. (1) ***resolve or exclude the two channels on the differential estimator*** — **not resolved is right and it is not a terminal state: it means the measurement has not yet the power to decide, and power is a thing that can be measured and sometimes improved**>, with **if the answer is that nothing available reduces it enough, THAT is 'PO-56's terminal exit arriving — a demonstration and not a shrug**>; (2) ***the phase, against the comb, by your own prescription*** — **it also tests (1)'s premise from the other side**>; (3) ***is the cancellation exact or approximate*** — **an exact cancellation of two large opposite departures is either a coincidence at the sizes their profiles happen to solve, or a CONSTRAINT**>; (4) nothing else. Guards: an identity is not a fit; **a band narrower than the period it measures makes its own statistic phase-dependent**>; a percentage of a near-zero measurement is not a share; ****not resolved" is not "excluded" — and it is also not a finish***; and a share measured against a mostly-shared quantity is not a share of the part that is ours). *Computes:* **THE SEQUENCING**: 'PREDICTION.md' is its own commit ahead of the working script, **defines the resolving ratio before computing it**, names four routes to a smaller scatter and commits to testing each, **names in advance the one it expected most from**, tables the terminal outcome, and names (1)'s own abuse hazard before meeting it ***(1) NOTHING BANKED BRINGS THE FLOOR BELOW WHAT THE CHANNELS CARRY.** The minimum resolvable share $f_{\min} = 2\sigma / d_{\text{arm}}$ runs $\$0.59\%$ to $\$0.75\%$ across **every** route this construction can build — both aggregations, both abscissas, a longer lever arm to $\$q=6.45\%$, and finer bands $\Rightarrow$ ***THE TERM MIX CARRIES $\$0.35\%$ OF THE STEP*

AND THE REALISED PAIR \$0.03\$, AGAINST A FLOOR OF \$0.59\$: THEY CANNOT BE RESOLVED BY ANY STATISTIC THIS CONSTRUCTION CAN BUILD*** *And the reason is what the pre-registration did **not** expect: the held-period aggregation lowers σ by \$2.12\times\$ **exactly** as predicted — and lowers the SIGNAL by \$2.06\times\$ at the same time, so $f_{\min}$ moves only \$0.65\$ to \$0.63\$. **The candidate named in advance as the one expected to help most does not help*** *And the abuse hazard fires before any power claim can be made: **the term mix and the realised pair CHANGE SIGN between the aggregations**, so their departures are not established at all and more power would not decide them — only the window channel keeps its sign on all eight readings* **(2) THE PHASE IS RESOLVED WHERE IT IS NOT NEEDED AND NOT WHERE IT IS.** The long-stretch projection works: over the upper range $\Delta = +0.007368 \pm 0.000974$ rad ($+0.42^\circ$, a 7.6σ determination), the whole range as one stretch agreeing at $+0.007541$. Band 1 reads -0.002440 , $\pm 5.03\sigma$ scatters out on the full-period yardstick** *But that yardstick is wrong and the comparison is not licensed without the control: band 1 is \$0.70\$ of a period, and a projection over a **non-integer** number of periods leaks the baseline, so a narrow stretch is both noisier AND biased. On six stretches of the SAME width the scatter is $3.7\times$ larger* $\Rightarrow$ **BAND 1 SITS \$1.52\sigma\$ SCATTERS OUT, NOT \$5.03\sigma\$**: THE PHASE STEP IS NOT RESOLVED AND ‘cc66.60’s AMPLITUDE VERDICT STANDS AS THE COMPLETE ONE*** **(3) THE CANCELLATION IS NEITHER EXACT NOR APPROXIMATE — IT IS AGGREGATION-DEPENDENT.** The joint vanishes within its own scatter on all four bases of the raw reading (0.24σ – 0.54σ) and on none of the phase-insensitive one (4.16σ – 4.98σ) $\Rightarrow$ **(3) inherits (1)’s answer rather than choosing a word** — the third possibility the pre-registration named — and constraint-versus-coincidence cannot be settled here* *Bound*: **NOT** that the two channels are EXCLUDED** — they are **unresolvable**, which is a statement about what this construction can measure and not about what the channels do **NOT** that the phase difference is zero** — it is $+0.42^\circ$ and resolved at 7.6σ in the upper range; what is unresolved is whether it **steps** at band 1 **NOT** a composition rule** — (3) returns no word at all, by design, because the two aggregations disagree **NOT** an aggregation, basis or abscissa choice**: every reading is carried and none chosen, and **a resolution claim is required to hold on the SAME reading that measured the departure**, which is the hazard this file pre-registered against itself **NOT** a mechanism**, and (4) holds Nothing SOLVED, nothing RUN; **no corpus edits** *Run*: python3 receipts/P15_CR_cosmology/P15_no_statistic_this_construction_can_build_resolves_the_two_channels_and

P15R208 P15_the_likelihoood_sees_the_step_and_separates_the_two_channels_so_the_demonstration_does_not.
[OK]

‘sec:refit-bound’, ‘sec:scope’ — *the likelihood sees the step as a localised contribution to its excess and separates the two channels at band 1 at twenty-five sigma*, so ‘cc66.61’s demonstration covers the STATISTIC family and not the instrument the paper runs beside it, and **PO-56’s amended clause is NOT met**; and **eight of the eleven instruments this row has used band, three do not** (node 66’s ‘r7021’ order, two items, after amending ‘PO-56’s terminal clause to this seat’s narrower sentence. (1) **does the likelihood see the step** — **your floor is proved over every STATISTIC this construction can build, but every one of them bands, and the likelihood does not band**”, with **a demonstration that covers one instrument family and is silent about another the row already uses is not proved over its whole reach, which is your own standard for the word unresolvable**”, and **if the likelihood turns out to be a banded statistic in disguise, that is the answer and it completes the demonstration rather than failing to**; (2) **say whether anything else this row has ever used does not band** — **I do not want to strike on a demonstration with a third instrument outside it**; (3) nothing else, **and do not soften the floor result**. Guards: a narrow-window measurement needs a matched-width control; a reduction in scatter is only a gain if the signal does not fall with it; **unresolvable** is a claim about the instrument and must be proved over its whole reach; **narrow** a terminal clause before taking it; and a departure that changes sign between two legitimate aggregations is not a quantity). *Computes*: **THE SEQUENCING, AND THE HARDEST PART OF IT**: ‘PREDICTION.md’ is its own commit ahead of the working script and **says out loud which facts had already been looked at** — the likelihood’s bin structure, a property of the instrument fixed on disk regardless of any spectrum — **declaring that branch SETTLED rather than tabling it as if open** **(1)(a) THE LIKELIHOOD IS NOT A BANDED STATISTIC IN DISGUISE.** ‘plik_lite’ TT bins at a median \$0.0298\$ in \$q\$ — **one thirty-fourth of a comb period** — with \$24\$ bins inside band 1, and its bin-to-bin correlation is a flat ≈ 0.15 floor rather than a coupling that grows

over a period. *It bins; it does not BAND* **(1)(b)** AND THE STEP IS A LOCALISED CONTRIBUTION TO ITS EXCESS. Band 1's bins carry \$36.4\sigma\$ of arm-versus-control separation on their own where its own bands 2–7 trend predicts \$53–\$71: a departure of \$-0.311\$ to \$-0.489\$ on the four bases at \$2.5–\$3.2\sigma\$ of its own residual — **the same sign as every other instrument in this row, and the first per-band number in it carrying the INSTRUMENT'S own noise rather than an empirical scatter across a noiseless theory spectrum** **(1)(c)** AND IT SEPARATES THE TWO CHANNELS AT BAND 1 AT \$25.1\sigma\$ — the thing no statistic in this row can do — with a smallest detectable share of the band-1 difference of \$0.055 \Rightarrow\$ **SO THE DEMONSTRATION COVERS THE STATISTIC FAMILY AND NOT THE INSTRUMENT THE PAPER RUNS BESIDE IT. 'PO-56's AMENDED CLAUSE IS NOT MET AND THE ROW HAS A MEASUREMENT TO MAKE RATHER THAN AN EXIT TO TAKE** And the two floors are in DIFFERENT UNITS, which the pre-registration required be said before the numbers were in hand: \$0.055\$ is a share of the band-1 DIFFERENCE under real instrument noise and 'cc66.61's \$0.59\$ is a share of the STEP under an empirical scatter of a NOISELESS spectrum. Neither bounds the other **(2) THE SCOPE STATEMENT THE CLAUSE NEEDS.** Of **eleven** instruments this row has made a claim on, **eight BAND** at \$0.70\$ of a comb period; **three do not** — the anchored peak/trough locator (*which makes no amplitude claim at band 1: it locates peaks*), the likelihood, and the refit \$\chi^2\$ that uses its bins \$\Rightarrow\$ **so the likelihood and its refit are the ONLY instruments that both avoid the band-width limit AND make an amplitude claim at band 1**, which is why (1) was the right question and why no third instrument sits outside the demonstration *Bound*: **NOT** that the channels are shown to produce the step — the likelihood can SEPARATE them at band 1, which is a statement about resolving power and not about authorship **NOT** that 'cc66.61's floor is wrong or softened' — it stands exactly as measured over the statistic family; what is added is that the family is not the whole reach **NOT** that the two floors are one number: \$0.055\$ and \$0.59\$ are shares of different quantities under different kinds of uncertainty, and **the only legitimate comparison is whether each instrument can or cannot separate the channels at band 1** — the statistic family cannot, the likelihood can **NOT** a mechanism, an envelope, a basis, an abscissa or an aggregation choice — (3) holds Nothing SOLVED, nothing RUN; **no corpus edits** *Run: python3 receipts/P15_CR_cosmology/P15_the_likelihood_sees_the_step_and_separates_the_two_channels_so_the_de*

P15R209 *P15_the_band_one_departure_is_not_in_the_likelihoods_excess_and_all_three_channels_match_it_in* [OK]

'sec:refit-bound', 'sec:scope' — **band 1 carries under one per cent of the likelihood's excess and its contribution changes SIGN under shape absorption**, so the departure is neither a feature of the residual nor the shape rejection read locally; **'cc66.62' called a separating-power departure a contribution to the excess and that label is corrected here**; and in the metric the step does live in, **all three channels depart the arm's way** (node 66's 'r7023' order, this seat's own redirect taken up, with a distinction placed in front of it. **the step is a two-to-three sigma feature of the likelihood's residual and the twenty-five is the power available to decide between candidates for it; those are not the same number and nothing in the row should ever quote the second where it means the first** **(1)** **score each channel against the step in the likelihood's own metric** — **the same question the banded family could not carry, asked where it can be**, with **the joint sits at 12.82 where the term mix alone sits at 18.64, so the two may partly cancel: measure it, do not read it off**; **(2)** **say whether the lowest band's departure is a distinct feature of the residual or part of the shape rejection** — **this decides what (1)'s answer would mean, and I would rather know which before a share is quoted than after**; **(3)** nothing else, **and 'cc66.61's floor is not revisited**. Guards: an instrument that bins is not necessarily one that bands; **say which facts were in hand before the pre-registration was written**; a floor under noiseless structure and one under instrument noise are not one number; **and separating power is not significance**). *Computes:* **THE SEQUENCING**: 'PREDICTION.md' is its own commit ahead of the working script, **adopts the order's distinction as its own vocabulary** — a table fixing which term means which number and a commitment that no quantity divides one by the other — and **states that (2) is asked FIRST though numbered second**, so the file's structure carries the order's point rather than a sentence **(2) RUN FIRST, AND THE ANSWER IS NEITHER OF THE TWO OUTCOMES TABLED.** Band 1 contributes \$2.6\$ of the \$287\$ the seven bands sum to — **under one per cent** — against a total excess of \$322\$ over all covered bins; absorbing smooth global shape at \$n = 1, 2, 3, 4\$ free coefficients in \$\ln\$ it reads \$+2.6\$, \$-0.5\$, \$+0.3\$, \$+6.6\$, **changing sign**, where bands 2–7 hold to a few per cent \$\Rightarrow\$ **THE DEPARTURE IS NOT**

A DISTINCT FEATURE OF THE RESIDUAL AND IT IS NOT THE SHAPE REJECTION READ LOCALLY — THE SHAPE REJECTION IS BARELY PRESENT THERE AT ALL***, living at bands 4–7 which carry $\$86\backslash\{\}\%$ of the per-band excess **AND THAT FORCES A CORRECTION TO ‘cc66.62’, WHICH IS THIS SEAT’S.** Its (1)**(b)** was headed “the step is a localised contribution to its excess”* and then reported band 1’s **separating power**. ***The number was right and the label was wrong*** $\Rightarrow$ *the likelihood DOES see a band-1 departure in its power to tell models apart; it does NOT carry a band-1 excess — different sentences, run together one revision after the distinction was drawn and one before it bit* ***(1) AND IN THE METRIC THE STEP ACTUALLY LIVES IN, ALL THREE CHANNELS DEPART THE ARM’S WAY.** Against the arm’s $\$-0.311\$$ to $\$-0.489\$$: the **window** channel $\$-0.448\$$ to $\$-0.584\$$, *the same sign and larger*, share $\$1.31\$$; the **term mix** $\$-0.244\$$ to $\$-0.459\$$, share $\$0.86\$$; the **JOINT** $\$-0.100\$$ to $\$-0.343\$$, share $\$0.51\$$ — each with its own bands 2–7 significance, every share a ratio of two significances $\Rightarrow$ ***THE FIRST TIME THIS ROW HAS HAD CANDIDATES THAT DEPART THE SAME WAY AS THE ARM ON AN INSTRUMENT THAT CAN CARRY THE QUESTION*** *And the window channel, which went the WRONG way on the differential estimator, goes the right way here and over-delivers — **a different verdict on a different instrument, reported as that rather than smoothed*** **AND THE CANCELLATION IS MEASURED**: the realised pair delivers $\$34\backslash\{\}\%$ of the closest of product, sum and quadrature, $\$2.4\$$ of its own residual away — *the two knobs partly cancel here as they did on the differential estimator* *Bound:* ***NOT that a candidate produces the step in the sense ‘PO-56’'s strong clause needs*** — (1)’s shares are shares of a **separating-power** departure, and (2) shows that feature carries one per cent of the likelihood’s excess: **a real match in a real metric, and the wrong metric for the clause** **NOT that ‘cc66.62’ measured the wrong thing** — its number stands; its LABEL is corrected **NOT that the likelihood fails to reject this arm** — it rejects it decisively, at bands 4–7 **NOT that the shape absorption shows the departure is spurious** — more freedom always shrinks a residual, so what is read is the RATE against the other bands, and the same absorption is applied to both arms **NOT a new candidate, a mechanism, or any revisiting of ‘cc66.61’'s floor** — (3) holds Nothing SOLVED, nothing RUN; **no corpus edits** *Run:* python3 receipts/P15_CR_cosmology/P15.the.band.one.departure.is.not.in.the.likelihoods.excess.and.a

P15R210 P15.the.term.mix.is.the.first.channel.to.produce.cost.where.the.arm.is.rejected.and.the.excess.
 $\square$

‘sec:refit-bound’, ‘sec:scope’ — *the excess at bands 4–7 is featureless to every smooth shape and yet modulated at the acoustic period***, so ‘cc66.58’'s *featureless** was a property of the *BANDING*; *the term mix is the first channel this row has produced that costs something where the likelihood actually rejects the arm***, though it overshoots by a third and misplaces nearly half of it; and *the cancellation is ABSENT here — the pair adds*** (node 66’s ‘r7025’ order, which took NEITHER of the two readings this seat offered and moved ‘PO-56’'s clause from the structure to the COST. $\Rightarrow$ ***the comparison’s discriminating structure and the data’s rejection live in different bands: the step is the excess’s most prominent feature and very nearly its cheapest”*** (1) ***score the channels at bands 4–7, in the likelihood’s metric, ON THE EXCESS*** — “six sevenths of the cost is there and no candidate has ever been scored against it”*, with the pre-registration to name both the outcome that ends the row and the one that closes it; (2) ***say whether the excess at 4–7 has any structure at all in the likelihood’s metric*** — “the likelihood bins thirty-four times finer, so featureless may be a property of the banding rather than of the excess”*; (3) nothing else, **and ‘cc66.61’'s floor and the band-1 results are finished work**. Guards: a label is a claim; run first what decides what another item means; ***separating power is not significance, and neither is an excess***; **and where a feature is most visible is not where it costs most**). *Computes:* **THE INSTRUMENT IS CORRECTED FIRST, AND THAT IS A CORRECTION TO ‘cc66.63’'s ESTIMATOR AND NOT TO ITS RESULT.** ‘cc66.63’ inverted each band’s covariance block alone and its contributions summed to $\$287\$$ against $\$322\$$; since $\$r.a = r.c - d\$$, the excess is $\$d^{\{T\}}Fd - 2d^{\{T\}}Fr.c\$$, whose per-bin terms sum to it ***identically*** — reproduced to $\$1.7\backslash\{\}\times 10^{-13}\$ \Rightarrow$ and the split is not bookkeeping: the first term is the **separating power** and the second is the only part that knows **where the data sits**, so *‘cc66.63’'s finding is that algebra* bands 4–7 carry $\$87\backslash\{\}\%$ on the exact decomposition against $\$86\backslash\{\}\%$ on the old: ***the location HOLDS*** ***(2) FEATURELESS AND COMBED AT ONCE, WHICH IS NOT A CONTRADICTION.** Across $\$82\$$ bins a constant explains $\$0.0\backslash\{\}\%$ of the scatter, a trend in $\$\ln q\$$ $\$1.6\backslash\{\}\%$, a quadratic $\$2.8\backslash\{\}\%$ — *‘cc66.58’'s verdict survives every smooth shape at the finer scale* **but the acoustic-comb

projection gives \$7.30\$ against a null of \$2.53\$ from \$110\$ wrong periods, of which NOT ONE returns more, and the scan's own maximum sits at period \$1.01\$** $\Rightarrow$ ***SO FEATURELESS WAS A PROPERTY OF THE BANDING*** — *seven numbers cannot see a modulation at the period they are \$0.70\$ wide against* **and the control that makes it a result***: \$d\$ is itself a comb, so the modulation is split — \$6.24\$ in \$-2d^{\wedge}\{T\}Fr_c\$ against \$1.08\$ in \$d^{\wedge}\{T\}Fd\$, ***five sixths from the term that knows where the data sits, so it is a fact about the DATA*** *and the prediction that the quadratic term would enter at period \$1/2\$ did NOT hold cleanly — \$0.57\$ there against \$1.08\$ at \$1.00\$ — reported as it measured rather than quietly dropped* ***(1) THE SHARES ARE LARGE, WHICH IS WHY THEY GET A CONTROL BEFORE A HEADLINE.** At bands 4–7 the **window** scores \$0.14\$, the **term mix** \$1.36\$, the **JOINT** \$1.53\$, stable across \$n=1,2,3,4\$ *but ANY spectrum that is not the control costs something, so a share above one may mean only also rejected and not rejected the same way* $\Rightarrow$ ***so the per-bin PATTERN is compared, not the total*** the **window is ANTI-correlated with the arm at \$r = -0.70\$** — *its cost is not the arm's, it is a DIFFERENT cost* the **term mix matches at \$r = +0.70\$, regression \$0.74\$, \$45\{\}\%\$ left over** the **JOINT matches WORSE than the term mix alone, \$r = +0.46\$** — *adding the window raises the total and DEGRADES the pattern* $\Rightarrow$ ***THE TERM MIX IS THE FIRST CANDIDATE THIS ROW HAS PRODUCED THAT COSTS SOMETHING WHERE THE LIKELIHOOD ACTUALLY REJECTS THE ARM*** — \$1.41\$, \$1.07\$, \$0.76\$ across bands 4, 5 and 7 **AND THE CANCELLATION IS ABSENT, WHICH GOES AGAINST THE STORY THIS ROW WAS BUILDING**: twice elsewhere the pair delivered a fraction of its singles and it was called *beginning to look like a property*; on the excess the singles sum to \$1.4965\$ and the realised pair gives \$1.5305\$ — ***\$102\{\}\%\$: the knobs ADD, and cancellation is a property of the METRIC, not of the pair*** *Bound*: ***NOT that the amended clause is MET*** — a channel producing \$136\{\}\%\$ of the cost with \$70\{\}\%\$ pattern correlation is not *'no quantity'* ***NOT that the carrier is IDENTIFIED*** — a channel misplacing \$45\{\}\%\$ of its cost is not *'the carrier identified'*; **the clause is NEITHER met NOR discharged and it is not rounded either way** **NOT that 'cc66.58' was wrong** — its verdict holds against every smooth shape at \$82\$ bins; what it could not see is a modulation finer than its own bands **NOT that band 6's shares mean anything alone** — the arm is cheapest there (\$14.6\$ against \$80\$, \$80\$, \$123\$), so that denominator is small and is never quoted alone **NOT that the window channel is a small contributor** — it is an ANTI-correlated one, which is a different statement **NOT a new candidate, a mechanism, or any revisiting of 'cc66.61's floor or the band-1 results** — (3) holds Nothing SOLVED, nothing RUN; **no corpus edits** *Run*: python3 receipts/P15_CR_cosmology/P15_the_term_mix_is_the_first_channel_to_produce_cost_where_the_arm_is_rej

P15R211 P15_the_term_mix_does_not_carry_the_modulation_and_it_survives_in_the_part_no_channel_explains

□
*'sec:refit-bound', 'sec:scope' — **the term mix's own cost is NOT combed and the modulation survives in the part it does not explain**, which is 'PO-56's **terminating** row; **the one reading that says otherwise rests on an amplitude that is arithmetic**, gated as such before the run; and **the window is combed in ANTIPHASE on the excess while its spectrum-level modulation is IN PHASE**, so the magnitude composes and the sign does not (node 66's 'r7029' order — *'what joins your two findings is not a sentence, it is one measurement, and it is cheap'*.* ***The gap, which this seat had not closed:*** *'the correlation is measured on per-band shares and the modulation on per-bin structure; a channel can carry four thirds of the cost in exactly the right four bands and be perfectly smooth inside every one of them'* (2) ***three comb projections against the same 110-period null*** — (1) the term mix's own cost, (2) the regression's fitted part, (3) the residual misplaces, **each split by the two terms of the identity, because the self-similarity artefact has to be killed again for the channel*; (3) ***the window's own comb projection and the sign of its phase against the arm's***; (4) nothing else. Guards: no mechanism; no new candidate; 'cc66.61's floor and the band-1 results are finished work; ***and the added guard is this seat's own from 'cc66.64' — A TOTAL IS NOT A MATCH, generalised: a projection amplitude is a total over bins the way the joint was a total over channels***). *Computes*: **THE PRE-REGISTRATION GATED (2)'s AMPLITUDE AS ARITHMETIC BEFORE THE RUN, AND THAT IS WHY THE REVISION HAS AN ANSWER AT ALL.** *A one-coefficient regression's fitted part is a scalar multiple of one of its inputs in EITHER orientation* measured: orientation A returns \$\{\}\beta \{\}\times 7.304 = 5.430\$ and orientation B \$\{\}\gamma \{\}\times 4.238 = 3.404\$, ***both exact to the digit*** $\Rightarrow$ ***so (2) carries nothing its input did not, and since (2) is \$\{\}\gamma \{\}\times\$ (1), (2) is combed if and only if (1) is*** — **the order's fork collapses to one question: is the

term mix's own cost combed? ** (1) IT IS NOT. ** \$4.238\$ against a null maximum of \$4.297\$, **one** period of the \$110\$ returning more ** (3) orientation B — the part of the arm's excess the term mix does NOT explain — \$4.005\$ against a null maximum of \$3.889\$, NONE of the \$110\$ above it, at \$-0.16\$ rad from the arm's own phase: IT CLEARS ** (3) orientation A — the \$45\backslash\{\}\%\$ the channel misplaces — \$1.482\$ against a null maximum of \$3.188\$, with ALL \$110\$ above it: decisively not combed ** $\Rightarrow$ ***THE MODULATION IS IN THE PART NO CHANNEL THIS CONSTRUCTION FIXES ACCOUNTS FOR — (3) COMBED AND (2) NOT, WHICH IS 'PO-56's TERMINATING ROW*** *and the one reading that says DISCHARGES is orientation A taken literally, which rests entirely on the amplitude gated as arithmetic: **strip it and both orientations say the same thing*** **NOT DECISIVE AND NOT REPORTED AS DECISIVE**: *(1) fails by ONE period of \$110\$ and (3) clears by a comparable margin, against a deliberately conservative null-MAXIMUM bar built from correlated periods* ** (3) THE WINDOW IS COMBED, AND IN ANTIPHASE ON THE EXCESS**: \$2.010\$ against a null maximum of \$1.711\$, none above, at \$+3.12\$ rad from the arm's — \$\backslash\{\}\pi\$ to within \$0.02\$, *so it is not a smooth offset* **but one structure read with two signs is NOT established**: *the blunt test fails — \$\backslash\{\}\alpha = -0.059\$ with the residual keeping \$98\backslash\{\}\%\$ of the window's power, the amplitudes missing by a factor of five* *and that blunt test is named in the receipt as THE WRONG INSTRUMENT — a ratio over whole vectors asks whether the window IS the arm scaled, where the question is about each one's MODULATED part, which is 'cc66.60's aggregation error in a new place* $\Rightarrow$ like-for-like, projecting the two spectrum differences: **the window's modulation is \$+0.27\$ rad from the arm's — IN PHASE — at a ratio of \$0.264\$, and \$0.264 \backslash\{\}\times 6.241 = 1.646\$ against a measured \$1.893\$*** $\Rightarrow$ ***THE MAGNITUDE COMPOSES AND THE SIGN DOES NOT: the reversal appears only after the likelihood's own weighting*** *Bound: ***NOT that 'PO-56' is terminated*** — *the measured row IS the terminating one, and placing it is 66's* ***NOT that the exit is decisive*** — *(1) turns on one period of \$110\$; the direction is unambiguous and the margin is thin* ***NOT that orientation A discharges the clause*** — *its (2) is \$\backslash\{\}\beta \backslash\{\}\times\$ the arm's own \$7.30\$ and its (3) is a different object; that exit is the arithmetic talking, and it was gated as such in advance* **NOT that the window and the arm are one structure with two signs** — *the spectrum-level modulations are IN PHASE; only the costs are opposed* **NOT an explanation of the sign flip** — *it is LOCATED, between the spectrum difference and the excess, and naming why would be a mechanism* **NOT a re-derivation of 'cc66.61's floor or the band-1 results** — (4) holds Nothing SOLVED, nothing RUN; **no corpus edits** *Run: python3 receipts/P15_CR.cosmology/P15.the_term_mix_does_not_carry_the_modulation_and_it_survives_in_the_p**

P15R212 *P15_the_resolution_table_eight_of_the_eleven_instruments_cannot_represent_the_comb_period_and*
[OK]

*'sec:refit-bound', 'sec:scope' — **the resolution table 'PO-56' never had: for each of the eleven instruments 'cc66.62' enumerated, the finest period it can resolve (derived from its own geometry), the smallest share it can detect in its own units under its own noise model, and the class of feature invisible to it** — *every banded instrument outputs one number per 0.70 band, a Nyquist period of* \$1.40\$, *so none of the eight can represent a comb-period feature, where the likelihood's bins give* \$0.060\$; **four smallest-share cells are honest blanks** (node 66's 'r7029' redirect, item one: **a result should meet its instrument's limit BEFORE it is stated, not four revisions after** — the band-width limit the row met in four disguises ('cc66.58', 'cc66.60', 'cc66.61', 'cc66.64'), stated once, in advance). *Computes:* the geometry every row is derived from, from the banks on disk (band edges, plik bin widths, grid steps, the extremum spacing), the boxcar transfer each averaging width imposes AT the comb period (\$0.37\$ for a band, \$0.9985\$ for a bin), and the likelihood's per-band floor \$2/\backslash\{\}\sigma_b\$ recomputed under 'COV_TT' (\$0.055\$ at band 1, reproducing 'cc66.62'); every floor it QUOTES is text-gated against the receipt that derived it *Bound:* NOT a verdict on any result of 'cc66's, NOT a re-scoring, NOT any physics, channel or mechanism — it says what each instrument CAN see, not what any DID see; the three no-noise blanks (contrast statistic, 'SRCDEC', projection-width kernel) and the refit's (inputs under '/tmp/n66', absent) are left blank WITH their reasons, because a guessed floor would be worse than none; shares in different units are set side by side and never ranked *Run: python3 receipts/P15_CR.cosmology/P15.the_resolution_table_eight_of_the_eleven_instruments_cannot_represen**

P15R213 *P15_all_three_projections_clear_the_instrument_noise_null_so_the_term_mixs_cost_is_combed_after*
[]

*'sec:refit-bound', 'sec:scope' — **on the null 70 validated, ALL THREE projections clear at \$p*

le 0.0005\$ with none of \$2\{, \}000\$ draws reaching any of them**, so **the term mix's own cost IS combed and 'cc66.65's central reading was WRONG** — wrong because of the bar this seat chose, which it failed by ONE period of \$110\$; and **'cc66.62's scope claim is AMENDED**: the locator LOCATES inside band 1 and MEASURES no height there (node 66's 'r7033' order — **one re-run, and it is not a narrowing: the same three projections against the null 70 validated in the same revision"*. ***70's audit, which this seat asked for one revision earlier:*** *the \$82\$ bins span \$T = 2.78\$ in \$q\$ and hold about \$3.6\$ independent frequencies, \$N_{\{\rm eff\}} = 3.07\$, and \$6\$ of the \$110\$ correlate with the comb above \$0.5\$* $\Rightarrow$ ***"none of 110" was worth roughly ONE IN FOUR*** (1) ***score (1), (2), (3) against \$2\{, \}000\$ 'COV' draws through this seat's own pipeline***, with the two terms of the identity for each; (2) ***70's routed finding against 'cc66.62's scope statement*** — confirm, amend or reject; (3) nothing else. Guards unchanged, **plus the one this seat produced at 'cc66.65' and 66 promoted to standing: AN ARITHMETIC IDENTITY IS NOT A MEASUREMENT, AND THE TIME TO SAY SO IS BEFORE THE RUN**. Computes: **THE INSTRUMENT IS REPRODUCED BEFORE ANYTHING RESTS ON IT**, with 70's own definitions copied rather than re-derived: the arm's \$7.3038\$ against **0 of \$2\{, \}000\$** and a null maximum of \$2.34\$, where 70 reported \$0\$ and \$2.54\$ on another seed *(1) ALL THREE CLEAR*: *(1) the term mix's own cost \$4.238\$** against a null maximum of \$1.874\$; *(2) the arm's excess it does NOT explain \$4.005\$** against \$1.416\$; *(3) the \$45\{\%\}\$ it misplaces \$1.482\$** against \$1.029\$ — *none of \$2\{, \}000\$ reaching any of them* *and the margins are NOT rounded together: (1) and (2) clear by more than double, *(3) by \$1.44\{\times\}\$***, which is stated separately $\Rightarrow$ ***SO (1) CLEARS AND 'cc66.65's CENTRAL READING — "the term mix's own cost is NOT combed" — IS WRONG*** **and the reversal was PRE-REGISTERED in the words used for it*: **a bar worth one in four failing something by one unit is equally capable of passing it** *AND (1)'s CLEARANCE IS NOT THE NOISE-FREE TERM TALKING**, which is the check that makes it a result: *under this null \$d\$ is fixed and only \$r.c\$ moves, so \$d\{T\}Fd\$ has no noise in it to fail* — (1)'s quadratic term is \$0.851\$ against \$0.794\{\pm 0.006\}\$, **reported as no evidence**, while its CROSS term is \$3.399\$ against a null median of \$0.354\$, **0 of \$2\{, \}000\$** $\Rightarrow$ *** (1) clears on the term that knows where the data sits*** *and the held-coefficient variant agrees on both fitted quantities, so none of the clearance is the regression chasing noise* **THE MEASURED ROW IS "BOTH", REPORTED AS SUCH RATHER THAN CHOSEN BETWEEN** — *at this bar the projections no longer separate and the fork as posed does not discriminate* **and the old bar was not merely weak, it was INFLATED*: *its maxima ran \$3.2\$–\$4.3\$ where this one's run \$1.0\$–\$1.9\$, the wrong-period amplitudes carrying the signal itself, leaked* $\Rightarrow$ ***a null built from the same data at neighbouring frequencies is not independent of the feature it is scoring*** *(2) AMENDED, NOT REJECTED*: *the locator's four PEAK anchors sit at \$q = 0.736\$, \$1.778\$, \$2.703\$, \$3.751\$ — **none inside band 1** — but 'C17' states the instrument carries "acoustic peak and trough positions", and **trough 1 sits at \$q = 1.360\$, inside it*** $\Rightarrow$ ***70's factual claim is correct and the peak-only reading would have been a DODGE*** *the qualifier: 'anchored()' returns \$-c_1/2c_0\$, a vertex POSITION, never a height* $\Rightarrow$ **it LOCATES inside band 1 and MEASURES no height there** Bound: ***NOT that 'cc66.65's measurement was wrong*** — *the three amplitudes are unchanged to the digit; **the BAR was wrong and it was this seat's*** **NOT that 'PO-56' discharges*** — (1) clearing reads as DISCHARGES and (2) clears too, which is the order's third line: reported, not chosen between* ***NOT that the projections still separate the channels*** — *at this bar they do not, and that is the finding* **NOT that (1)'s quadratic term is evidence** — *it has no noise in it to fail and is reported as no evidence* **NOT that 70's reading of 'cc66.62' is rejected** — *it is correct on the fact; what is amended is what the claim was implying* **NOT a mechanism, a new candidate, or any revisiting of 'cc66.61's floor or the band-1 results** — (3) holds Nothing SOLVED, nothing RUN; **no corpus edits** Run: python3 receipts/P15_CR.cosmology/P15_all_three_projections_clear_the_instrument_noise_null_so_the_term_mix

P15R214 P15_the_three_instruments_with_no_noise_model_one_can_be_given_a_floor_and_ten_passages_quote.
[OK]

'sec:refit-bound', 'sec:scope' — **the three 'PO-56' instruments that carry no noise model: the contrast statistic NEVER SEES THE DATA as defined (its fitted amplitude cancels in the envelope normalisation, to \$10^{-16}\$), so its numerical floor is the right one for what it says, and its SKY COUNTERPART can be given a floor from the likelihood's own covariance (\$0.018\$ whole-range, \$0.043\$–\$0.086\$ per band); 'SRCDEC' cannot, structurally (only the sum of its terms reaches the sky); the projection-width kernel cannot (it reads no data, and its two anchorings differ twelve-

fold)** — ***and ten passages of ‘P15’ quote a significance or a share that their instrument cannot bear***, one of them a transcription that contradicts the paper nine lines earlier (node 66’s ‘r7033’ order: *“which stated results depend on a floor that does not exist”**) — the four honest blanks of the resolution table, followed to what rests on them). *Computes*: the contrast receipt’s own binned rung rebuilt with its own definitions, the amplitude-invariance of ‘reg’, 2000 draws of ‘COV_TT’ through the statistic whole-range and banded, ‘SRCDEC’-s ten-term closure, the kernel’s two anchorings; every flagged phrase text-gated in ‘CR_cosmology.tex’ and every source receipt gated to draw no noise *Bound*: NOT that any of the ten is wrong about the THEORY — each describes a real difference between noiseless spectra; what is claimed is that a sigma which is not a noise model is not a significance and a share quoted on one anchoring is not the share. No re-scoring, channel, mechanism, or physics; no ‘cc66’ receipt touched; the paper not edited — the passages are routed *Run*: python3 receipts/P15_CR_cosmology/P15_the_three_instruments_with_no_noise_model_one_can_be_giv

P15R215 P15_the_accounting_closes_but_cannot_attribute_because_the_share_is_the_cosine_of_a_phase_offs

□
*‘sec:refit-bound’, ‘sec:scope’ — **the accounting CLOSES exactly and still cannot ATTRIBUTE***: the least-squares share is $\$ \{ \} \text{vert} \{ \} \cos \{ \} \Delta \{ \} \text{rvert} \$$ ***identically***, depending only on the phase offset and not at all on the channel’s amplitude, ***and the window proves it by scoring $\$100 \{ \} \% \$$ in ANTIPHASE***; the other scale is the one (2) invalidates, predicting the window’s cost modulation to $\$13 \{ \} \% \$$ and the term mix’s to $\$116 \{ \} \% \$ \Rightarrow$ ****the third row: no instrument this construction has can attribute the modulation**** (node 66’s ‘r7035’ order, which ***WITHDREW ‘r7033’-s fork as its own defect***: *“I built the fork on a detection test and ‘PO-56’-s clause asks about AUTHORSHIP; every acoustically structured quantity in that decomposition is distinguishable from noise”* $\Rightarrow$ ****a test every candidate passes cannot identify a carrier**** ***THE ACCOUNTING***, which is this seat’s own instrument from ‘cc66.65’ turned on the term mix: (1) the channel’s modulated part against the arm’s — phase offset and amplitude ratio; (2) whether that ratio PREDICTS, as it did for the window; (3) the residue after the channel’s contribution is removed at its measured phase, and whether the shares close to the whole *“an accounting has no third outcome: the shares sum to the whole by construction”**) — ***DISCHARGES on a matched-phase majority, TERMINATES on a minority, TERMINATES on nothing decidable*** Guards: no mechanism; no new candidate; ‘cc66.61’-s floor and the band-1 results finished; ***plus both of ‘cc66.66’-s promoted to the standing set***). *Computes*: ***THE INSTRUMENT IS GATED ON ‘cc66.65’-s OWN WINDOW RESULT FIRST***: phase $\$+0.270 \$$ rad, ratio $\$0.2638 \$$, prediction $\$1.646 \$$ against a measured $\$1.893 \$$ — **three numbers to the digit* ***(1) THE TERM MIX’S SPECTRUM-LEVEL MODULATION IS LARGER THAN THE ARM’S $\$$: $\$+0.383 \$$ rad at a ratio of $\$1.176 \$$, where the window’s was $\$0.264 \$$ ****(2) AND THE RATIO DOES NOT PREDICT, WHICH IS THE HINGE $\$$: $\$1.176 \{ \} \times 6.241 = 7.341 \$$ against a measured $\$3.399 \$$ — ****off by $\$116 \{ \} \% \$$ where the window’s template was off by $\$13 \{ \} \% \$$ **** $\Rightarrow$ **the scale ‘r7035’-s template was built on does NOT carry over to this channel* ***(3) THE VECTOR ACCOUNTING CLOSES EXACTLY on both scales $\$$ — contribution plus residue reconstructs the arm’s own vector to numerical precision, **which the pre-registration made the gate on calling it an accounting at all* **but the two scales give $\$68.3 \{ \} \% \$$ and $\$98.3 \{ \} \% \$$ **** ***AND THE SECOND IS AN IDENTITY, NOT A MEASUREMENT***: in a two-dimensional $\$ \{ \} \cos \{ \} \sin \{ \} \$$ plane $\$ \{ \} \text{vert} \text{kv} \{ \} \text{rvert} = \{ \} \text{vert} \text{v}_a \{ \} \text{rvert} \{ \} \text{vert} \{ \} \cos \{ \} \Delta \{ \} \text{rvert} \$$, so ****the share is $\$ \{ \} \text{vert} \{ \} \cos \{ \} \Delta \{ \} \text{rvert} \$$ EXACTLY**** — term mix $\$ \{ \} \Delta = +0.184 \$$, $\$ \{ \} \text{vert} \{ \} \cos \{ \} \Delta \{ \} \text{rvert} = 0.9832 \$$, share $\$0.9832 \$$; window $\$ \{ \} \Delta = +3.121 \$$, $\$0.9998 \$$, share $\$0.9998 \$ \Rightarrow$ ****it depends ONLY on the phase offset and not at all on the channel’s amplitude: a channel a millionth the size scores the same**** $\Rightarrow$ ****AND THE WINDOW IS THE PROOF RATHER THAN AN ANALOGY — in ANTIPHASE at $\$+3.12 \$$ rad it scores $\$100.0 \{ \} \% \$$ of the authorship, at a scale of $\$-3.633 \$$ that turns its cost UPSIDE DOWN to get there**** **so both scales are out, **each for its own reason and neither failure the other’s***: the spectrum-level ratio by MEASUREMENT ((2), a factor of two), the least-squares projection by ALGEBRA* ***and the two-channel line is printed TO BE DISCOUNTED: two channels span the plane, so together they reconstruct the arm exactly at residue $\$0.000 \$$ — **arithmetic, not attribution, and the same degeneracy one level up**** *Bound*: ****NOT that ‘PO-56’ discharges**** — **a $\$98.3 \{ \} \% \$$ share that is $\$ \{ \} \text{vert} \{ \} \cos \{ \} \Delta \{ \} \text{rvert} \$$ is not a majority of anything* ***NOT that the accounting failed**** — **it closes to numerical precision on both scales; **closing is not attributing**, and that distinction is the result* ***NOT a fourth outcome row**** — **the answer is the third ‘r7035’*

listed, and this seat did not reach past it* **NOT that the term mix is excluded as a carrier** — *it is unattributable on every instrument this construction has, which is a statement about the instruments* **NOT that ‘cc66.66’s clearances are withdrawn** — *they stand; the FORK they were scored against is what 66 withdrew* **NOT a mechanism, a new candidate, or any revisiting of ‘cc66.61’s floor or the band-1 results** Nothing SOLVED, nothing RUN; **no corpus edits** Run: python3 receipts/P15_CR.cosmology/P15.the_accounting_closes_but_cannot_attribute.because.the_share

P15R216 P15_the_null_harness_survives_its_one_assumption_except_for_the_misplaced_part_and_floors_a_ph
[OK]

‘sec:refit-bound’, ‘sec:scope’ — ***the instrument-noise null harness, load-bearing for ‘PO-56’s exit, given one pass: varying the covariance the noise is DRAWN from (estimator fixed) — diagonal, the flat \$0.15\$ floor as a plateau and at lags 1–7, rescaled — the arm and ‘cc66.66’s (a) and (b) clear under every variant, but (c) (the misplaced part) is reached by 26 of 20,000 draws under the lags-1–7 floor, so it is the ONE clearance the assumption decides; its \$1.44\{\}\times\$ is the favourable end of its own seed spread (\$1.10\$–\$1.37\{\}\times\$ over ten seeds); rescaling does not matter (the fitted control’s \$\chi^2/\nu = 0.98\pm 0.10\$, (c) first reached at \$2.5\$); a ratio or phase offset has NO statistical floor at the spectrum level (\$4\{\}\times 10^{-4}\$ rad) and a finite, linear one at the excess (about \$0.05\$ rad)** (node 66’s ‘r7035’ order: ***the null harness is now load-bearing for this row’s exit, so it gets one pass of its own***). Computes: the committed audit script run in-process; ‘cc66.66’s multiples reproduced on its own seed; four drawing covariances at 2,000 draws, two pooled at 20,000, ten seeds for the maximum’s spread, a rescale scan, a Rayleigh test, parametric perturbation about the data at full and half noise, the delta method against it Bound: NOT an accounting: no central value of the term mix’s ratio, phase or share is computed into the record. No channel, mechanism, re-scoring or physics; no verdict on ‘cc66’s results — (c)’s dependence and the seed spread are routed; no ‘cc66’ receipt touched Run: python3 receipts/P15_CR.cosmology/P15.the_null_harness_survives_its_one_assumption_except_for_the_misplaced*

P15R217 P15_the_retention_is_the_combs_average_over_the_kernels_own_k-acceptance_and_the-law_has_no-fi
[OK]

‘sec:refit-bound’ — ***THE RETENTION IS THE COMB AVERAGED OVER THE KERNEL’S OWN \$k\$-ACCEPTANCE, AND THE LAW HAS NO FITTED COEFFICIENT***: for a standing oscillation the line-of-sight integral factorises exactly, \$\Delta_{\ell}(k) = \cos(k r_s^*) k^{\frac{1-n_s}{2}} G_{-}(\ell(k)\$, ***so the comb reaches the transfer undamped and only the sum over \$k\$ at fixed \$\ell\$ can touch it*** — and \$A_{\ell} = \int W e^{2ikr_s^*} r_{vert} \int W\$ with \$W = G_{\ell}^2 / dk/k\$ ***predicts the ABSOLUTE amplitude on both arms, worst band \$6.7\{\}\%\$, six of seven inside the instrument’s gate tolerance of \$5\{\}\%\$ (FIVE of seven inside the \$3.74\{\}\%\$ it measured at the ONE injected phase — re-pinned r7055 on node 70’s floor audit, which also shows that with the instrument’s own error divided out all seven hold inside \$3.74\{\}\%\$)*** \$\Rightarrow\$ **the arm’s acceptance is \$13.1\{\}\%\$ narrower, against ‘r6919’s independently measured \$12.8\{\}\%\$ in \$\mathrm{d}r_s/\mathrm{d}\chi\$** (node 66’s ‘r7039’ order, which ***LIFTED the ‘no mechanism’ guard*** with what replaces it stated — **a mechanism must be exhibited on the integral**, ***predict a number not used to find it***, and be ***checked on a configuration it was not fitted on**** and ‘r7043’, which ***composed it with ‘r7041’s convergence order rather than letting either displace the other***: ***a law with no free coefficient that predicts an absolute amplitude is also a convergence test, because an unconverged integral will not reproduce an absolute number it was not fitted to*** *‘r7041’ re-weighted the row so the presumption is the instrument; ***this receipt reads the REPORTED settings only and makes no convergence claim****, which is a separate row). Computes: ***GATE ZERO*** — ***THE INSTRUMENT IS GATED ON A KNOWN INPUT BEFORE ANY MEASUREMENT PRINTS*** — a synthetic comb of amplitude \$0.5000\$ at period \$1.0347\$ recovered to \$0.24\{\}\%\$ in period and \$3.74\{\}\%\$ in amplitude, **and the gate REFUSES to print if it does not** (1) ***\$A_{\ell}\$’s injection-independence CHECKED, not asserted*** — the two injections’ ‘eta’, ‘x0’, ‘vis’, ‘k’, ‘P’ and \$r_s^*\$ byte-equal, **which is what licenses ONE ‘A’ per arm instead of two keys holding identical arrays** (2) ***the factorisation EXACT*** at \$2.7\{\}\times 10^{-15}\$ (control) and \$2.1\{\}\times 10^{-15}\$ (arm) on ***8 multipoles spread across the reported range***, **and \$A_{\ell}\$ RECOMPUTED from ‘vis’, ‘x0’ and ‘k’ reproducing the banked value to \$0.00\$** \$\Rightarrow\$ ***the law is re-derived here and not trusted from its own bank*** (3) the acceptance spans \$5.2226\$ (control) against \$4.5364\$ (arm) of acoustic phase (4) ***the law forward, absolute, both arms, nothing fitted***: \$1.063/1.011/0.990/1.012/1.042/1.016/1.017\$ and

\$1.067/1.015/0.990/1.012/1.044/1.018/1.016\$ (5) ***and the reproduction gate across a CHANGE OF RUN SCHEME*** — \$1.0587\$ unsliced against ‘r6919’s \$1.0587\$ sliced on ‘KBATCH’, \$0.0000\{\}\%\$ apart, **so the agreement covers the scheme and not only the statistic** *Bound: ***NOT that the injection IS the real source**** — **it is the projection’s transfer of a KNOWN input, and over-delivery is sufficiency and not identity** ****NOT a convergence claim**** — **the REPORTED settings only; ‘r7041’s sweep is a separate row and is running** ****NOT an account of why the construction puts its scales and its distances on different rates**** — **‘r6919’s own reserved bound, untouched here** ***NOT a tighter claim than the instrument supports*** — **six of seven bands sit inside its \$3.74\{\}\%\$ accuracy on a known input and no band is quoted tighter than that** **and the two earlier measuring instruments are NAMED in the source rather than deleted: a band std \$46\{\}\%\$ wrong on a known input, and a per-band matched filter selecting a period by maximising amplitude inside a band holding less than one cycle** $\Rightarrow$ ****‘cc66.60’s error a third time, and the first caught BEFORE a number was reported**** *Run: python3 receipts/P15_CR.cosmology/P15_the_retention_is_the_combs_average_over_the_kernels_own_k_acceptance_*

P15R218 *P15_the_laws_six_of_seven_is_five_at_the_quoted_floor_which_is_one_phases_and_with_the_instrument*
[OK]

*‘sec:refit-bound’ — **r7049 $\rightarrow$ 70, the floor under the acceptance law’s test: “six of the seven bands on each arm inside 3.74 per cent” is FIVE of seven on each arm** (the gate counts at 5 per cent while its label names 3.74; the 3.65–4.35 band sits at 4.2 / 4.4) — **and the 3.74 per cent is ONE phase’s error, not the statistic’s floor**:* scanned over phase on each arm’s own envelope, period and law profile the worst band error is 10.2 / 11.0 per cent — ***but the real comb’s phase is gate zero’s to 0.03 rad**, and there the instrument is off by -4.2 / -4.0 per cent in the lowest band and under one per cent in the other six; **divided out, the law holds to 3.4 / 3.6 per cent and all seven bands on both arms land inside 3.74** — the lowest band’s 6.3 / 6.7 per cent deviation being about two thirds instrument. ***“On each arm” is one test**:* the two arms’ deviations correlate at 0.998; within an arm the seven bands are close to independent (*N-eff* 6.9 of 7), and the phase systematic has about 2.4 modes (node 66’s ‘r7049’ order to 70: **how many independent measurements is “six of seven bands”, and does the 3.74 per cent measured on a known injection transfer to the real arm’s bands** — asked of a claim landed one revision earlier, by the line that caught this class at ‘r7033’ and ‘r7035’). *Computes:* the instrument is ‘cc66’s, lifted from its receipt’s source by syntax tree and run unchanged; M1 the literal count from its own ratios; M2 injections on each arm’s own envelope with the law’s own profile, 24 phases plus the real one, and the corrected ratio; M3 400 noise draws through the whole instrument, the phase-error correlation and the between-arm correlation; the paper’s wording REPORTED, never required *Bound:* no verdict on the law’s physics or on ‘cc66’s convergence sweep; no edit to ‘cc66’s receipt and no re-run of its gate zero as a verdict on it; no prose edited; the white noise probes the instrument’s coupling and is not a noise model for the spectra *Run: python3 receipts/P15_CR.cosmology/P15_the_laws_six_of_seven_is_five_at_the_quoted_floor_which_is_one_phases_*

P15R219 *P15_the_phase_systematic_leaves_the_step_standing_and_carries_a_third_of_the_retention_slope.t*
[OK]

*‘sec:refit-bound’ — **r7055 $Q1 \rightarrow$ 70, the phase systematic’s effective count against the slope and the step: the count is not where the cost is** — against a null injection (identical combs on both arms, common phase scanned) both banded statistics have three to three and a half modes across seven bands (step 3.5 / 2.8, slope 3.3 / 3.6), and the slope’s own effective count is 8.9 / 5.1; **the step stands**, its false value at the real phase a quarter to two fifths of it (−0.010 / −0.017 against −0.043), worst 0.019; **but the retention slope carries a third of itself as systematic**:* at the real phase the null returns +0.0048 / +0.0052 on the reported twelve-setting mean against the real +0.0136 (36 / 39 per cent, same direction), +0.0081 on the seven-band setting; the rise survives the subtraction and its size does not. ***The carrier is a phase drift of 0.013–0.042 rad between the two arms’ source combs**, which the partial-cycle band-RMS reads as retention: one comb for both removes it, a flat envelope does not. And the receipt computes +0.01359 $\pm$ 0.00202 where P15 and its docstring carry +0.0139 $\pm$ 0.0021* (node 66’s ‘r7055’ order $Q1$ to 70: **report the phase systematic’s effective count for the retention slope and the excess’s step specifically, and if unchanged say so** — the order’s own scope kept: the banded statistics’ error structure, not the likelihood). *Computes:* both statistics (‘band_excess’, ‘retained’) and ‘cc66’s period fit lifted from their receipts by syntax tree and run unchanged, each gated to reproduce its receipt’s printed values on the real banks; null injections on every bank each reads,

24 common phases, pre-registered amplitude 0.5 and the banks' own as a declared sensitivity; N_eff, the slope's own count, the false step and slope at the real phase; the D_l / source split and a comb x envelope decomposition of the source side *Bound*: nothing about the likelihood ('r7033's split stands); no edit to either receipt and no prose edited; a null injection measures the statistic's response and does not say what the arms' real retention difference is *Run*: python3 receipts/P15_CR_cosmology/P15_the_phase_systematic_leaves_the_step_standing_and_carries_a_third_of_

P15R220 P15_the_acceptance_does_not_move_under_refinement_and_three_of_the_twelve_axes_could_not_have_ [OK]

'sec:refit-bound' — *THE KERNEL'S \$k\$-ACCEPTANCE DOES NOT MOVE UNDER ANY REFINEMENT THAT CAN MOVE IT, AND THREE OF THE TWELVE AXIS-ARM PAIRS COULD NOT HAVE MOVED IT AT ALL***: across twelve settings varied one at a time on both arms, the WORST SINGLE MULTIPOLE excursion in A_{ℓ} on any of the nine axes that move an input is 0.0082% — *73 times inside \$r6911\$'s 0.6% floor, and 41163 times inside it on the arm's $k_{\max}$ axis over a near-doubling of $k_{\max}$* ⇒ *and the arm-to-control acceptance narrowing is 13.03% at all twelve settings, spread 0.0048% percentage points, against \$r6919\$'s independent $d_{r-s} \wedge d_{\chi}$ reading of 12.8%* *BUT THREE PAIRS ARE INERT BY CONSTRUCTION AND ARE NOT REPORTED AS CONVERGED***: 'NK' on the arm, whose ladder is $\sqrt{L(L+2)}$, \$stretch out to 'KMAXL' so 'NK' is a decimation cap never reached — 1452 modes at 'base', 'nk15' and 'nk20' alike, *byte-identical inputs and $\max \Delta_{\ell}$ rvert=0 exactly at the spectrum***, where the CONTROL moves 2547 to 3822 to 5094 and its spectra differ outright — and 'LSTEP' on BOTH arms, since A_{ℓ} is read at the same multipoles at every setting by construction (node 66's 'r7049', offering and not directing: *" A_{ℓ} is a sharper probe of the same thing and it is now free... and A_{ℓ} carries NO FITTED AMPLITUDE to absorb the truncation, where a height ratio does"* — taken up because 'GRIDSAVE' made it cost 1.45 s per configuration and no re-run). *Computes: GATE ZERO* — *THE INERT TEST MUST DISCRIMINATE BEFORE ANY A_{ℓ} IS READ***: it is required to fire on exactly the three claimed pairs and stay silent on the other nine, *because a test that answers the same way everywhere is not a test* the inert claim carried as a *BYTE claim***, sha256 of k , η , x_0 , vis — *and run the other way on the nine, which must each move an input* A_{ℓ} *recomputed from the banked background* at 8 multipoles on four configurations, reproducing the bank at $0.00e+00$ the *worst single multipole* printed rather than the mean over the range, *because a mean can hide a moving tail* scope gated rather than asserted, with the pre-registered criteria printed beside every axis unaltered *Bound*: *NOT 'r7041's sweep and no substitute for it* — *the sweep asks what the RETENTION and the peak heights do, measured on spectra; this asks what the kernel's \$k\$-acceptance does, computed from the background, and a converged acceptance with an unconverged retention would itself be a finding***, which is why the two are reported apart *NOT a convergence claim for the row* — *nine of twelve axes read inside the floor is not the sweep's verdict, and the criteria are carried unaltered: a sequence that has not turned over is not converged whatever its last step, and a two-point axis cannot turn over* nothing about which cosmology is right *Run*: python3 receipts/P15_CR_cosmology/P15_the_acceptance_does_not_move_under_refinement_and_three_of_the_twelve

P3R12 P03_acceleration_is_slice_curvature [OK]

sec:curvature · rem:twocritical · the bend (on ANY member of the energy family (E cancels: $(dr/d\tau)^2 = E^2 - f$, and E is a constant of the motion) $d^2r/d\tau^2 = -f'/2 = r \cdot K_G$ identically, so THE SIGN OF THE SLICE'S GAUSSIAN CURVATURE IS THE SIGN OF THE COMOVING ACCELERATION — and the flat locus is the deceleration-to-acceleration turnover, which on Narai is the seam and in standard terms is $\rho_m = 2 \rho_{\Lambda}$ ($\csc^2 w = 2$ $\Rightarrow \sinh w = 1/\sqrt{2}$, the seam's phase). A recent cosmological epoch: 7.06 Gyr at $H_0=73$, 7.65 at 67.4, preceding matter-Lambda equality [borrowed from P3 · P7 · P8]). *Computes*: the identity asserted; the K_G zero solved and matched to $(M \alpha^2)^{1/3}$; $\csc^2 w = 2$ $\Rightarrow \sinh w = 1/\sqrt{2}$ proved by algebra after simplify() failed on the closed forms; epochs at both H_0 *Bound*: bound: identities on the Narai $E=1$ worldline; no causal claim between seam and turnover — they are one locus; dating inherits H_0 *Run*: python3 receipts/P03.SdS_slicing/P03_acceleration_is_slice_curvature.py

P15R42 BRANCHPT_transmission_character [OK]

rem:phase-open (BRANCHPT — the transmission character of the BRANCH POINT $r=0$, on its own terms. WHY (r2154). P15 1.525 says "The cosmogenesis branch point, BEING the degenerate

Nariai horizon, is a faithful scale-free transmitter”, and prop:transmission argues from the tortoise integral at a DOUBLE ROOT ($p=2$, $\kappa=0$). **PART 2, from the receipt-vs-sentence audit: the PEAK-POSITION EXCLUSION, which is what P15 actually cites this file for and which the file did not compute** — the collapse leg’s own conformal time gives $\eta_{\text{bp}} \sim 5e3\text{--}1e4$ Mpc, so $r_s^{\text{eff}} = r_s + \eta_{\text{bp}}/\sqrt{3} = 3.0\text{--}5.9e3$ Mpc, and reproducing $L_A = 301.8$ would demand $D = 2.9\text{--}5.7e5$ Mpc against the actual $1.4e4$, a factor of **21-41**. *PART 1 shows the crossing ADDS no divergent phase; PART 2 shows an inherited phase cannot survive. The paper’s sentence needs the second.* [borrowed from P15 (+P7)]. *Computes:* runs clean; registered from its own docstring and a live run *Bound:* description is the receipt’s own wording, condensed; not independently re-derived here *Run:* python3 receipts/P15_CR_cosmology/BRANCHPT_transmission_character.py

H1_the_low_multipole_deficit_is_two_effects_and_the_ladder_imprint_dies_where_the_transfer_is_narrow [OK]

corpus integrity (**THE HARMONIC-ANALYSIS BAKE — second of the four fields ‘L-272’'s re-survey left outstanding, thrown r3166.** **BOUNCED, and largely:** the field’s first question is why a closed- S^3 source is projected through FLAT spherical Bessel functions, and ‘P15’ answers it in its own text — the distance slicing is flat, so only the source modes carry the closed- S^3 quantization — while its measure $\$w_L=(L+1)/(L(L+2))\$$ is derived twice, as degeneracy over per-mode power and as $\$d\{\ln k_L/dL\$,$ both agreeing to machine precision. **BIT:** the deficit reported as one geometric effect splits exactly into a **FLOOR** (modes below $L_{\text{=}}2$ removed) and a **LADDER COARSENESS**. At $\ell=5\text{--}6$ the second contributes $\$+0.38\$$ against a floor of $\$0.27\text{--}\$0.53\$$ — comparable, and in the opposite direction — and it is what sets the recovery multipole the paper quotes ($\ell=8$ with it, $\ell=10$ without). Under $\pm 2\%$ in r_0 the floor moves $\$-2.4\%$ to $\$-6.2\%$ and the full result $\$+27.8\%$ to $\$-43.3\%$: **the location is the floor and is robust as claimed; the depth is the ladder and is volatile**, which gives the paper’s own qualitative split a mechanism. **AND A SELF-WAIVED GATE BECOMES A BOUND:** ‘P15’ records that the ladder “samples the projection below the rate the instrument’s own aliasing gate demands, and that gate waives itself on the claim that the ladder is physical.” The imprint dies at $\ell \leq k_{2D} \cdot C_e^3 \cdot \sigma$; to reach the first acoustic peak the transfer would need to draw power over a factor of nine in k . **Safe with a wide margin, by measurement.** [borrowed from —]). *Computes:* COMPUTES: the spherical-Bessel completeness identity $\sum_{\ell}(2\ell+1)j_{\ell}(x)^2=1$ to ten figures and the exact plateau $\int j_{\ell}^2 d\ln x=1/(2(\ell(\ell+1)))$ reproduced on the fixed grid to six, both **before anything is used**, the measure against $d\{\ln k_L/dL\}$ and against degeneracy-over-power at five L ; the paper’s own D_C/r_0 to 0 limit; the floor/discreteness decomposition across $\ell=2\text{--}12$; each half’s response to $\pm 2\%$ in r_0 ; the recovery multipole with and without the discreteness; and the imprint against transfer width at four σ , with the scaling rule checked against all four rather than extrapolated (15 checks). *Bound:* NOT-A-PAPER-CLAIM — corpus integrity; no paper edited. **NOT claimed:** that the deficit is wrong — every number touched is reproduced or confirmed, the paper’s own limit included; that these are predictions about the sky — the decomposition is the pure Sachs–Wolfe limit while the paper’s depths come from a genuine Boltzmann transfer it says are milder, and the two are not compared; that the real transfer’s width is measured — σ is a Gaussian-in- k stand-in and measuring $\Delta_{\ell}(k)$ is the owed next step; that the aliasing gate should stop waiving — only that the waiver now has a margin; that the low- ℓ oscillation is derived rather than measured. *Run:* python3 receipts/L274_the_harmonic_bake/H1_the_low_multipole_deficit_is_two_effects_and_the_ladder_imprint_

Appendix L The Knowledge Ledgers

Each claim marked ^L in the text rests on a field bake or the figure–theorem bake recorded in the named ledger, which ships with this work and carries the probes, the receipts, and the three registers kept apart — what bit, what bounced, and where the boundary is. A ledger is working apparatus, not a publication, and is cited here rather than in the bibliography. This appendix is generated from the ledger index, not maintained by hand.

- L9** CONVEXITY_OPTIMISATION_LEDGER.md [field bake]
The convexity / optimisation field-bake ledger — what bit, what bounced, and the boundary. One of the three fields listed but never thrown (the overnight order: convexity $\times 143$, constraint $\times 141$). ‘OWED’ 622
- L23** OPTICS_LENSING_LEDGER.md [field bake]
observational optics and lensing against CR — confirmations, and the dimension clause they forced
- L19** SPECTRAL_THEORY_LEDGER.md [field bake]
The spectral-theory field bake — what bit, what bounced, and the boundary. Tier B’s largest never-thrown field ($\times 189$ on the reach measure), verified as NOT covered by the harmonic ledger, which mentions spectral, self-adjoint and deficiency zero times
- L21** INFORMATION_THEORY_LEDGER.md [field bake]
The information-theory field-bake ledger — what bit, what bounced, and where the boundary is
- L22** NUMERICAL_ANALYSIS_LEDGER.md [field bake]
The numerical-analysis field-bake ledger — what bit, what bounced, and where the boundary is
- L14** INTEGRABLE_SYSTEMS_LEDGER.md [field bake]
The integrable-systems field-bake ledger — what bit, what bounced, and where the boundary is

References

- [1] D. Janzen, *A curious normalization of the Λ CDM linear growth factor*, Res. Notes AAS (2025).
- [2] D. Janzen, *A Critical Look at the Standard Cosmological Picture*, FQXi essay contest (2012); arXiv:1301.5980.
- [3] D. Janzen, *General relativity’s constraint algebra as the symmetric-space structure of a de Sitter substrate: the action Lie algebroid of the symmetry-reducible sector, and the problem of time’s “wrong sign” as the substrate’s coset signature*, companion paper (P12).
- [4] D. Janzen, *The event horizon is a metric singularity: a missing definition in general relativity, and the black-hole problems it dissolves*, companion paper (P1).
- [5] D. Janzen, *The de Sitter substrate and its slicing curve: horizons as turning points, and de Sitter and Schwarzschild as two readings of one slicing*, companion paper (P3).
- [6] D. Janzen, *The Schwarzschild–de Sitter description groupoid: generators, relations, and Schwarzschild as the asymmetric realisation*, companion paper (P5).
- [7] D. Janzen, *Covariance of geometries over the de Sitter substrate: the slicing operator, the vacuum kernel, and matter as the bend of the cut*, companion paper (P8).
- [8] D. Janzen, *The range of the de Sitter slicing operator: surjectivity onto the symmetry-reducible sector of general relativity, the Kerr–NUT–(A)dS vacuum kernel, and the wall of inhomogeneity*, companion paper (P9).
- [9] D. Janzen, *Collapsed matter must become a universe: the necessary and sufficient augmentation of general relativity into a description of structural existence, proven for gravitational collapse of any symmetry*, companion paper (P7).
- [10] D. Janzen, *Why the cut bends: the dynamics of the de Sitter cut, the confined gravitational wave, the generative boundary of the slicing operator, and chirality as the turning of the polarization plane*, companion paper (P11).

- [11] D. Janzen, *The modern parallax: the redshift-isotropy floor, the empirical forcing of cosmic time and uniform expansion, and the measured resolution of the relativity of simultaneity*, companion paper (P4).
- [12] D. Janzen, *The shadow of existence: scientific theory-choice as an empirically grounded discipline, calibrated on the historical record and on a live programme*, companion paper (P6).
- [13] V. Pavlidou and T. N. Tomaras, *Where the world stands still: turnaround as a strong test of Λ CDM cosmology*, JCAP **09** (2014) 020.
- [14] D. Janzen, *On the ontological foundations of Cosmological Relativity*.
- [15] D. Janzen, *A critical look at the standard cosmological picture*, in *Questioning the Foundations of Physics: Which of Our Fundamental Assumptions Are Wrong?*, Springer (2015) 103–130.
- [16] D. Janzen, *A Solution to the Cosmological Problem of Relativity Theory*, PhD thesis, University of Saskatchewan (2012).
- [17] D. Janzen, *Reached through the imaginary, real by construction: the maximally symmetric substrate as the geometric–ontological core of Cosmological Relativity*, companion paper (P17).
- [18] D. Janzen, *Cosmological Relativity: what the construction delivers, what it declines, and where its edge is*, companion paper (P18).
- [19] D. Janzen, *Cosmogenesis: the Big Bang as a synthesis of Cosmological Relativity’s deductively forced consequences, and the primordial light-element abundances it produces*, companion paper (P16).
- [20] D. Janzen, *The fermion sector of Cosmological Relativity: three chiral generations from the maximally-symmetric slicing structure*, companion paper (P14).
- [21] R. M. Wald, *Asymptotic behavior of homogeneous cosmological models in the presence of a positive cosmological constant*, Phys. Rev. D **28** (1983) 2118.
- [22] S. Alam et al. (BOSS Collaboration), *The clustering of galaxies in the completed SDSS-III Baryon Oscillation Spectroscopic Survey: cosmological analysis of the DR12 galaxy sample*, Mon. Not. R. Astron. Soc. **470** (2017) 2617.
- [23] DESI Collaboration, *DESI DR2 Results II: Measurements of Baryon Acoustic Oscillations and Cosmological Constraints*, arXiv:2503.14738 (2025).
- [24] Planck Collaboration (N. Aghanim et al.), *Planck 2018 results. VI. Cosmological parameters*, Astron. Astrophys. **641** (2020) A6.
- [25] A. G. Riess et al., *A comprehensive measurement of the local value of the Hubble constant with $1 \text{ km s}^{-1} \text{ Mpc}^{-1}$ uncertainty from the Hubble Space Telescope and the SH0ES team*, Astrophys. J. Lett. **934** (2022) L7.
- [26] M. Moresco et al., *A 6% measurement of the Hubble parameter at $z \sim 0.45$: direct evidence of the epoch of cosmic re-acceleration*, J. Cosmol. Astropart. Phys. **05** (2016) 014.
- [27] J. Silk, *Cosmic black-body radiation and galaxy formation*, Astrophys. J. **151** (1968) 459.
- [28] R. K. Sachs and A. M. Wolfe, *Perturbations of a cosmological model and angular variations of the microwave background*, Astrophys. J. **147** (1967) 73.
- [29] P. Ginsparg and M. J. Perry, *Semiclassical perdurance of de Sitter space*, Nucl. Phys. B **222** (1983) 245.
- [30] G. Lemaître, *Cosmological Application of Relativity*, Rev. Mod. Phys. **21** (1949) 357.
- [31] E. R. Harrison, *Fluctuations at the threshold of classical cosmology*, Phys. Rev. D **1** (1970) 2726.
- [32] Ya. B. Zel’dovich, *A hypothesis, unifying the structure and the entropy of the Universe*, Mon. Not. R. Astron. Soc. **160** (1972) 1P.
- [33] G. W. Gibbons and S. W. Hawking, *Cosmological event horizons, thermodynamics, and particle creation*, Phys. Rev. D **15** (1977) 2738.
- [34] A. S. Eddington, *The Expanding Universe*, Cambridge University Press (1933).

- [35] D. Janzen, *The canonical problem of time as a category error: an empirically forced cosmic time, deparametrization, the dissolution of frozen dynamics, and a graviton quantization the de Sitter horizon closes without a free parameter—the seam where $\hbar$ enters gravity—in Cosmological Relativity*, companion paper (P10).
- [36] D. Janzen, *The Schwarzschild and de Sitter circle: the intrinsic geometry of one homogeneous ring—the event horizon and the curvature singularity at $r = 0$ its two poles, run through by a single continuation*, companion paper (P2).
- [37] H. Nariai, *On a new cosmological solution of Einstein's field equations of gravitation*, Sci. Rep. Tôhoku Univ. Ser. I **35** (1951) 62; reprinted in Gen. Rel. Grav. **31** (1999) 963.
- [38] P. J. E. Peebles, *Recombination of the primeval plasma*, Astrophys. J. **153** (1968) 1.